

INVITATION FOR BIDS
LETTING OF January 24, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on January 24, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

201 TOSTON STRUCTURES (US-287) NHIP-NHPBIP 8-4(66)86 CONTRACT NO. 03119

Grade, gravel, plant mix surf., drainage, 350' continuous welded steel plate girder bridge over MRL train tracks, 661' continuous welded steel plate girder bridge over the Missouri river, signing and pvmt. mkg. on the Toston Structures (US - 287) project in Broadwater County. The project is on US 287/State Route N-8 beginning at RP 85.9 and proceeds south to the project end at RP 89.3.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRVL, PMS, G'RAIL, DRNG, SIGN, ELECT & 2 STL			
GIRDER STR			
103000000	TRAINING PROGRAM	2,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	100,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
105080115	FINISH GRADE CONTROL	114,750.000	CRFT
105080200	BRIDGE SURVEY	1.000	LS
107000060	NOXIOUS WEED CONTROL	5,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	175,182.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	240,568.000	CUYD
203020380	SPECIAL EMBANKMENT	218,460.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	22,496.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
209010100	STRUCTURE EXCAVATION TYPE 1	523.000	CUYD
209010125	STRUCTURE EXCAVATION TYPE 2	3,870.000	CUYD
209010150	SHORING AND CRIBS	1.000	LS
209010160	TEMPORARY SHORING	1.000	LS
210020170	TEST TRAILER-TRANSPORT, SETUP	86.000	MILE
212000000	OBLITERATE ROADWAY	36.000	STA
301020252	BRIDGE END BACKFILL-TYPE 1	4,710.000	CUYD
301020268	TRAFFIC GRAVEL	789.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	50,996.000	CUYD
301020450	SPECIAL BACKFILL	3,134.000	CUYD
301020526	TOP SURFACING GR 3B	703.000	CUYD
301020625	AGGREGATE TREATMENT	152,852.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	39,828.000	TON
401020300	HYDRATED LIME	558.000	TON
402020095	ASPHALT CEMENT PG 70-28	2,231.100	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	15,866.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	284.900	TON
409000000	FINAL SWEEP AND BROOM	8.800	CRMI
409000010	COVER-TYPE 1	159,368.000	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	5.500	MILE
411011135	RUMBLE STRIPS	7.000	MILE
551020030	CONCRETE-CLASS GENERAL	44.600	CUYD
551020035	CONCRETE-CLASS STRUCTURE	2,502.100	CUYD
551020107	CONCRETE-CLASS DECK	1,855.800	CUYD
551020130	CONCRETE-SEAL	1,116.900	CUYD
552010140	TRANSVERSE DECK GROOVING	6,945.000	SQYD
552011010	EXPANSION JOINT STRIP SEAL	299.800	LNFT
552020000	ARCHITECTURAL TREATMENT	851.000	SQYD
555010100	REINFORCING STEEL	338,536.000	LB
555010200	REINFORCING STEEL-EPOXY COATED	618,281.000	LB
555010400	REINFORCING STEEL-SEISMIC	26,024.000	LB
556010011	STRUCTURAL STEEL - GIRDER	1.000	LS
559010202	RE-DRIVE TEST PILE	6.000	EACH
559040035	DYNAMIC LOAD TEST	9.000	EACH
559050103	FURN STEEL PIPE PILE 16 X 1/2 IN	2,782.400	LNFT
559050110	FURN STEEL PIPE PILE 20 X 1/2 IN	6,104.000	LNFT
559060103	DRIVE STEEL PIPE PILE 16 X 1/2	2,676.000	LNFT
559060110	DRIVE STEEL PIPE PILE 20 X 1/2	5,816.000	LNFT

559060200	PILE CUTTING SHOE	144.000	EACH
559060350	PILE CONICAL DRIVING POINT	64.000	EACH
563000040	POLYMER OVERLAY	7,241.800	SQYD
563000100	PREPARE DECK	7,241.800	SQYD
565000010	ELASTOMERIC BEARING DEVICES	63.000	EACH
603000050	GRANULAR BEDDING MATERIAL	505.000	CUYD
603000060	FOUNDATION MATERIAL	691.000	CUYD
603010040	DRAINAGE PIPE 18 IN	840.000	LNFT
603010048	DRAINAGE PIPE 24 IN	754.000	LNFT
603010284	DRAINAGE PIPE 30 IN IRR	98.000	LNFT
603012530	RCP 18 IN	772.000	LNFT
603012555	RCP 24 IN	360.000	LNFT
603012847	RCP IRR 18 IN	86.000	LNFT
603012892	RCP IRR 24 IN	404.000	LNFT
603013300	REIN CONC BOX 19 X 6	162.000	LNFT
603013342	REIN CONC BOX 10 X 8	140.000	LNFT
603013367	REIN CONC BOX 8 X 7	396.000	LNFT
603013453	PIPE-PVC 18 IN	560.000	LNFT
603587020	REMOVE PIPE CULVERT	1,510.000	LNFT
604010213	INLET DROP-TYPE 5	5.000	EACH
604010538	COMB 72 IN T3 MH-T 5 DROP INL	1.000	EACH
605000030	BARRIER RAIL-CAST IN PLACE-BR	3,587.000	LNFT
606010330	MGS GUARDRAIL	2,039.900	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	8.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	8.000	EACH
606010347	MGS LONG SPAN GRDL/LONG POSTS	50.000	LNFT
606010385	REMOVE GUARDRAIL	3,659.800	LNFT
607100009	FENCE - WILDLIFE FRIENDLY FW	2,458.000	LNFT
607100013	FENCE - WILDLIFE	8,154.000	LNFT
607100014	FENCE - PANEL/SINGLE - WILDLIFE	40.000	EACH
607100015	FENCE - PANEL/DOUBLE - WILDLIFE	11.000	EACH
607100017	WILDLIFE FENCE PANEL-SPECIAL DESIGN	12.000	EACH
607100020	WILDLIFE JUMPOUT	8.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	3,211.000	LNFT
607100149	FARM FENCE-TYPE F3W-32 IN WW	1,180.000	LNFT
607100229	FARM FENCE-TYPE F4W	3,336.000	LNFT
607100259	FARM FENCE-TYPE F5W	604.000	LNFT
607100291	FARM FENCE-TYPE F6W	3,373.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	53.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	28.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	88.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	184.000	LNFT
608010125	DETEC WARNING DEVICES-TYPE 1	3.600	SQYD
609010013	PIN DOWN CURB	275.000	EACH
609010112	CURB 4 IN-CONCRETE	746.000	LNFT
610100101	SEEDING AREA NO 1	75.800	ACRE
610100102	SEEDING AREA NO 2	4.800	ACRE
610100103	SEEDING AREA NO 3	16.400	ACRE
610100326	FERTILIZING AREA NO 1	75.800	ACRE
610100555	CONDITION SEEDBED SURFACE	97.000	ACRE
610100560	RIPRAP REVEGETATION	691.000	SQYD
610100566	EROSION CONTROL BLANKET-SHORT-TERM	51.000	SQYD
611010012	CATTLE GUARD 12 FT-LIGHT DUTY (3.6 M)	1.000	EACH
611010200	REMOVE CATTLE GUARD	1.000	EACH
612020000	ANTI-GRAFFITI COATING	358.000	SQYD
613100030	RIPRAP-CLASS 1 RANDOM	63.000	CUYD
613100040	RIPRAP-CLASS 2 RANDOM	2,350.000	CUYD
613100080	RIPRAP-INFILL	123.000	CUYD
613300060	BANK PROTECTION-TYPE 4	42.000	CUYD
613520000	BLOCK MATTRESS	109.000	SQYD
615010730	IRRIGATION DITCH	110.000	LNFT
616323110	CONDUIT-STEEL 1 IN RIGID	137.000	LNFT
616343914	CONDUIT-PLASTIC 1 1/2 IN	94.000	LNFT
616783006	PULL BOX-COMPOSITE TYPE 1	1.000	EACH
617000000	FOUNDATION-CONCRETE	2.000	CUYD
617000050	POLES-TREATED WOOD CLASS 4	20.000	LNFT
617000110	REVISE WEATHER MONITORING SYSTEM	1.000	LS

617123112	CONDUCTOR-COPPER AWG12-600V	783.000	LNFT
617303302	UNDERPASS LUMINAIRE LED	4.000	EACH
617333120	SERV ASSEMB-20 AMP	1.000	EACH
617333130	SERV ASSEMB-30 AMP	1.000	EACH
617343100	ENCLOSURE - NEMA TYPE 3R	2.000	EACH
617523010	SOL SIG-TRAF 1 COLOR-1 WAY 12	4.000	EACH
617673200	SIG STANDARD TYPE 1-200	4.000	EACH
617763700	ELECTRIC WILDLIFE DETERRENT MAT SYSTEM	2.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	500,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618110010	INSTALL, REMOVE CAMERA SYSTEM	1.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	58.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	51.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	386.700	SQFT
619010200	RESET SIGNS	8.000	EACH
619010210	RESET SIGNS-GUIDE	4.000	EACH
619010230	REMOVE SIGN	44.000	EACH
619010240	REMOVE SIGN-GUIDE	5.000	EACH
619010310	POSTS-STEEL U SIGN	240.000	LB
619010480	POLES-TREATED WOOD 4 IN	612.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	190.000	LNFT
619011010	DELINEATOR DES A	109.000	EACH
619011040	DELINEATOR DES D	26.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	28.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	62.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	18.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	41.000	GAL
620012950	TEMPORARY STRIPING	14.000	MILE
620013000	STRIPING-WHITE PAINT	374.000	GAL
620013955	REMOVE PAVEMENT MARKINGS	2,086.000	LNFT
620013960	STRIPING-WHITE EPOXY	248.000	GAL
620014000	STRIPING-YELLOW PAINT	388.000	GAL
620014960	STRIPING-YELLOW EPOXY	258.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	4,268.000	SQYD
622011084	GEOTEXTILE STABILIZATION	214,706.000	SQYD
623000155	MAILBOX	11.000	EACH
699010025	WEATHER TOWER	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 7668001

202 US 2 - POPLAR NH-HSIP 1-10(76)612 CONTRACT NO. 06119

Grade, gravel, plant mix surfacing, roundabouts, curb and gutter, sidewalk, storm drain, electrical, and other improvements on the US 2 - Poplar project located in Roosevelt County. The project is located on US Highway 2 in Poplar beginning at RP 611.5 and extends east 1.7 miles to RP 613.2. This project is located entirely within the Fort Peck Indian Reservation.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADING, GRAVEL, PMS OVERLAY, ROUNDABOUTS, CURB & GUTTER			
103000000	TRAINING PROGRAM	1,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	75,000.000	UNIT
104030045	MISCELLANEOUS ITEMS-EACH	2.000	EACH
105080115	FINISH GRADE CONTROL	18,350.000	CRFT

107000060	NOXIOUS WEED CONTROL	1,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
201311000	REMOVE TREES	2.000	EACH
203020100	EXCAVATION-UNCLASSIFIED	11,100.000	CUYD
203020225	EXCAVATION-STREET	28,415.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	6,809.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	7,911.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	45.000	MILE
301020268	TRAFFIC GRAVEL	1,500.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	9,451.000	CUYD
301020348	DRAIN AGGREGATE	704.000	CUYD
302000000	PAVEMENT PULVERIZATION	19,673.000	SQYD
304010000	PORTLAND CEMENT	553.600	TON
304010002	BLOTTER MATERIAL	36,434.000	SQYD
304010005	BASE-CEMENT TREATED	8,220.000	CUYD
304010012	BASE-CEMENT TREATED-PULVERIZED	15,296.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	11,556.000	TON
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	4,472.000	TON
401020300	HYDRATED LIME	162.000	TON
402020095	ASPHALT CEMENT PG 70-28	578.700	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	7,426.000	GAL
402020360	EMULSIFIED ASPHALT CRS-2	31.100	TON
411010000	COLD MILLING	21,922.000	SQYD
501010119	PORT CEM CONC PAVE 7 IN COLORED	1,294.000	SQYD
501010125	PORT CEM CONC PAVE 9 IN	6,472.000	SQYD
501010126	PORT CEM CONC PAVE 9 IN COLORED	994.000	SQYD
551020030	CONCRETE-CLASS GENERAL	4.000	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	4.000	CUYD
603010040	DRAINAGE PIPE 18 IN	926.000	LNFT
603010048	DRAINAGE PIPE 24 IN	582.000	LNFT
603010064	DRAINAGE PIPE 42 IN	258.000	LNFT
603012705	RCP 48 IN	236.000	LNFT
603013207	RCPA 28 IN	198.000	LNFT
603013414	PIPE-CORR POLYETHYLENE 4 IN	986.000	LNFT
603014242	ADJUST VALVE BOX	16.000	EACH
603017040	STORM DRAIN PIPE-12 IN	3,630.100	LNFT
603017045	STORM DRAIN PIPE-15 IN	7.800	LNFT
603017050	STORM DRAIN PIPE-18 IN	742.600	LNFT
603587020	REMOVE PIPE CULVERT	1,577.600	LNFT
603587030	REMOVE STORM DRAIN	12.000	LNFT
604000100	ADJUST MANHOLE	10.000	EACH
604000140	REMOVE DROP INLET	3.000	EACH
604010045	MANHOLE-48 IN TYPE 3	1.000	EACH
604010212	INLET DROP-TYPE 4	18.000	EACH
604010221	INLET DROP-TYPE 1	5.000	EACH
604010265	INLET FRAME AND GRATE-REPLACE	8.000	EACH
604010533	COMB 48 IN T3 MH-T1 DROP INL	9.000	EACH
604010534	COMB 48 IN T3 MH-T4 DROP INL	20.000	EACH
604010710	MODIFY MANHOLE	1.000	EACH
606400140	REMOVE BOLLARD	3.000	EACH
607150131	RESET GATE	1.000	EACH
608000020	SIDEWALK DRAIN	1.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	3,654.800	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	909.900	SQYD
608010061	SIDEWALK-REINFORCED 7 IN	403.900	SQYD
608010090	CONCRETE 3 IN	4,416.700	SQYD
608010110	CONCRETE 6 IN	539.000	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	165.400	SQYD
609010030	CURB-CONC MEDIAN TYPE A	198.800	LNFT
609010121	CURB-SPECIAL DESIGN	5,892.300	LNFT
609010160	GUTTER-CONC VALLEY	151.000	SQYD
609010200	CURB AND GUTTER-CONC	18,073.800	LNFT
610010100	TOPSOIL	200.000	CUYD
610100101	SEEDING AREA NO 1	17.000	ACRE

610100326	FERTILIZING AREA NO 1	17.000	ACRE
610100555	CONDITION SEEDBED SURFACE	17.000	ACRE
610100625	LANDSCAPING	1.000	LS
613100030	RIPRAP-CLASS 1 RANDOM	175.700	CUYD
615010580	TRASH GUARD	4.000	EACH
616343914	CONDUIT-PLASTIC 1 1/2 IN	8,850.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	325.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	200.000	LNFT
616343931	CONDUIT-PLASTIC 4 IN	200.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	27.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	4.000	EACH
617000000	FOUNDATION-CONCRETE	28.200	CUYD
617033214	CABLE-COPPER 3AWG14-600V	400.000	LNFT
617033514	CABLE-COPPER 9AWG14-600V	1,000.000	LNFT
617033814	CABLE-COPPER 16AWG14-600V	600.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	24,100.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	900.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	40.000	EACH
617233030	CONTROLLER-CAB PEDESTAL TYPE P	1.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	40.000	EACH
617333000	SERV ASSEMBLY-MODIFY	2.000	EACH
617333120	SERV ASSEMB-20 AMP	2.000	EACH
617483110	SIG-TRAF 1 COL-1 WAY 12	2.000	EACH
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	12.000	EACH
617553020	SIG-PEDESTRIAN TYPE 2	8.000	EACH
617573070	RECTANGULAR RAPID FLASHING BEACON	3.000	EACH
617583000	SCHOOL CROSSING BEACON	1.000	EACH
617605081	CONTLR/TRAF-ACTUAT TYPE 8-A	1.000	EACH
617673080	SIG STANDARD TYPE 1-80	7.000	EACH
617673100	SIG STANDARD TYPE 1-100	4.000	EACH
617673200	SIG STANDARD TYPE 1-200	11.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	4.000	EACH
617764010	REMOTE CAMERA SYSTEM	1.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	16.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	700,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	30.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	310.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	998.400	SQFT
619010200	RESET SIGNS	1.000	EACH
619010230	REMOVE SIGN	118.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010310	POSTS-STEEL U SIGN	40.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	194.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	7,295.000	LB
619010480	POLES-TREATED WOOD 4 IN	82.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	16.000	LNFT
619010640	BARRICADES-TYPE B(3)	16.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7 (S100X11)	2.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	11.000	EACH
619011179	DELINEATOR-FLEX SURF MTD WH	27.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	51.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	203.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	43.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	17.000	GAL
620011325	STRIPING-4 IN WHITE-HIGH PERF TAPE	1,675.000	LNFT
620011330	STRIPING-4 IN YELLOW-HIGH PERF TAPE	1,788.000	LNFT
620011335	STRIPING-6 IN WHITE-HIGH PERF TAPE	1,354.000	LNFT
620011340	STRIPING-6 IN YELLOW-HIGH PERF TAPE	1,322.000	LNFT
620011345	STRIPING-8 IN WHITE-HIGH PERF TAPE	540.000	LNFT
620011350	STRIPING-12 IN WHITE-HIGH PERF TAPE	131.000	LNFT
620011355	WORDS & SYMBOLS-WHITE-HIGH PERF TAPE	123.000	SQFT
620011360	WORDS & SYMBOLS-YELLOW-HIGH PERF TAPE	96.000	SQFT
620012950	TEMPORARY STRIPING	3.400	MILE
620013960	STRIPING-WHITE EPOXY	103.000	GAL
620013970	STRIPE GROOVING	6,810.000	LNFT
620013975	STRIPE GROOVING	219.000	SQFT

620014960	STRIPING-YELLOW EPOXY	92.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	2,623.000	SQYD
622011084	GEOTEXTILE STABILIZATION	11,912.000	SQYD
622011175	EDGE DRAIN	2,484.000	LNFT

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 8167000

203 TWO DOT - WEST STPP 14-3(26)83 CONTRACT NO. 04119

Reconstruction of the existing roadway on the Two Dot-West project located in Wheatland County. Work includes: grading, gravel, PMS overlay, drainage, fencing, rumble strips, seal & cover and pavement markings. The project begins at RP 82.9 and extends east approximately 5.2 miles along State Primary Route 14/US 12 to RP 88.0.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADING, GRAVEL, PMS OVERLAY, DRAINAGE			
103000000	TRAINING PROGRAM	1,000.000	HR
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
105080115	FINISH GRADE CONTROL	56,400.000	CRFT
107000060	NOXIOUS WEED CONTROL	2,500.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	137,526.000	CUYD
203020175	EXCAVATION-UNCLASS CHANNEL	13,465.000	CUYD
203020200	EXCAVATION-UNCLASS BORROW	170,855.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	29,320.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	26,013.000	CUYD
203080112	WETLAND SOIL-SALVAGE AND PLACE	763.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
208010486	STREAMBED MATERIAL	26.000	CUYD
210020170	TEST TRAILER-TRANSPORT, SETUP	140.000	MILE
301020268	TRAFFIC GRAVEL	15,000.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	14,173.000	CUYD
301020450	SPECIAL BACKFILL	575.000	CUYD
301020465	LOW PERMEABILITY BACKFILL	4,180.000	CUYD
301020625	AGGREGATE TREATMENT	35,101.000	SQYD
304010002	BLOTTER MATERIAL	79,981.000	SQYD
304010005	BASE-CEMENT TREATED	21,974.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	22,346.000	TON
401020300	HYDRATED LIME	313.000	TON
402020092	ASPHALT CEMENT PG 64-28	1,185.200	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	11,295.000	GAL
402020360	EMULSIFIED ASPHALT CRS-2	69.100	TON
402020368	EMULSIFIED ASPHALT CRS-2P	178.800	TON
409000000	FINAL SWEEP AND BROOM	5.200	CRMI
409000010	COVER-TYPE 1	99,503.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	5.100	MILE
411011135	RUMBLE STRIPS	10.300	MILE
551020030	CONCRETE-CLASS GENERAL	71.800	CUYD
603000050	GRANULAR BEDDING MATERIAL	867.000	CUYD
603000060	FOUNDATION MATERIAL	936.000	CUYD
603010040	DRAINAGE PIPE 18 IN	952.000	LNFT
603010048	DRAINAGE PIPE 24 IN	804.000	LNFT

603010066	DRAINAGE PIPE 36 IN	426.000	LNFT
603010068	DRAINAGE PIPE 48 IN	114.000	LNFT
603010072	DRAINAGE PIPE 54 IN	116.000	LNFT
603010179	DRAINAGE PIPE ARCH 57 IN	86.000	LNFT
603010714	CSP 96 IN	98.000	LNFT
603010722	CSP 108 IN	108.000	LNFT
603011900	SSPP 216 IN	172.000	LNFT
603012530	RCP 18 IN	468.000	LNFT
603012555	RCP 24 IN	70.000	LNFT
603013411	PIPE-SW-POLYETHYLENE 18 IN	170.000	LNFT
603424070	REIN CONC BOX 9 X 5	78.000	LNFT
603587020	REMOVE PIPE CULVERT	1,409.700	LNFT
607100152	FARM FENCE-TYPE F3M-32 IN WW	27,913.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	157.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	10.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	200.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	172.000	LNFT
607100551	FENCE-TEMPORARY	3,472.000	LNFT
607100720	DEADMAN	12.000	EACH
607150015	REMOVE FENCE	8,586.000	LNFT
610100101	SEEDING AREA NO 1	30.100	ACRE
610100102	SEEDING AREA NO 2	1.000	ACRE
610100103	SEEDING AREA NO 3	19.400	ACRE
610100326	FERTILIZING AREA NO 1	30.100	ACRE
610100490	TURF REINF MAT-NATURAL FIBER	320.000	SQYD
610100555	CONDITION SEEDBED SURFACE	49.500	ACRE
610100566	EROSION CONTROL BLANKET-SHORT-TERM	4,361.000	SQYD
613100030	RIPRAP-CLASS 1 RANDOM	21.600	CUYD
615010034	REMOVE IRRIGATION STRUCTURE	8.000	EACH
615010035	INLET STRUCTURE	1.000	LS
615010062	IRRIGATION STRUCTURE	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	900,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	84.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	22.800	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	71.800	SQFT
619010210	RESET SIGNS-GUIDE	1.000	EACH
619010230	REMOVE SIGN	40.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010310	POSTS-STEEL U SIGN	174.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	948.000	LB
619010480	POLES-TREATED WOOD 4 IN	150.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	18.000	LNFT
619010724	FRANG SIGN POST BKWY-S5 X 10 (S130X15)	2.000	EACH
619010730	FRANG SIGN POST BKWY-W8 X 18 (W200 X 27)	2.000	EACH
619011010	DELINEATOR DES A	170.000	EACH
619011040	DELINEATOR DES D	4.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620012950	TEMPORARY STRIPING	5.200	MILE
620013000	STRIPING-WHITE PAINT	372.000	GAL
620013960	STRIPING-WHITE EPOXY	248.000	GAL
620014000	STRIPING-YELLOW PAINT	180.000	GAL
620014960	STRIPING-YELLOW EPOXY	120.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	37.000	SQYD
622011084	GEOTEXTILE STABILIZATION	29,678.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 4889001

204 GILDFORD - EAST NH 1-6(124)355 CONTRACT NO. 05119

Plant Mix Overlay, seal & cover, pavement markings and signing on the Gildford - East project in Hill County. The 17.5 mile project is located on US 2 beginning just east of Gildford at RP 354.6 and extending 17.5 miles east to RP 372.1, approximately 9 miles west of Havre.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PMS OVERLAY, SEAL & COVER, SIGNING			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
210020000	GRADER-MOTOR	30.000	HOURL
210020170	TEST TRAILER-TRANSPORT, SETUP	39.000	MILE
401020048	PLANT MIX SURF GR S-1/2 IN	48,745.000	TON
401020300	HYDRATED LIME	682.000	TON
402020092	ASPHALT CEMENT PG 64-28	2,826.800	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	35,606.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	6,371.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	299.500	TON
402020375	EMULSIFIED ASPHALT CHFRS-2P	299.100	TON
409000000	FINAL SWEEP AND BROOM	13.200	CRMI
409000010	COVER-TYPE 1	332,990.000	SQYD
411010000	COLD MILLING	1,538.000	SQYD
411011135	RUMBLE STRIPS	34.400	MILE
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	154.600	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	355.500	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	329.100	SQFT
619010230	REMOVE SIGN	93.000	EACH
619010240	REMOVE SIGN-GUIDE	9.000	EACH
619010310	POSTS-STEEL U SIGN	453.000	LB
619010480	POLES-TREATED WOOD 4 IN	210.000	LNFT
619011010	DELINEATOR DES A	437.000	EACH
619011040	DELINEATOR DES D	40.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	3.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	2.000	GAL
620012950	TEMPORARY STRIPING	35.200	MILE
620013000	STRIPING-WHITE PAINT	1,269.000	GAL
620013960	STRIPING-WHITE EPOXY	846.000	GAL
620014000	STRIPING-YELLOW PAINT	572.000	GAL
620014960	STRIPING-YELLOW EPOXY	381.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%. All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address: <http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 9393000

NH-HSIP 57-7(26)328 - Cold milling, plant mix surfacing, ADA upgrades, electrical and signing improvements on the Towne St-River to Merrill-Glendive project. The project is located on National Highway Route 57 (Towne St) beginning at RP 327.5 (Yellowstone River bridge end) and extends 0.3 miles to RP 327.8, the intersection with Merrill Ave.

STPU 5002(24)- Street excavation, curb and gutter, plant mix surfacing, ADA upgrades and additive alternate for water and sewer improvements on the Meade Avenue-Glendive project. This project is located on State Urban Route 5002(Meade Ave) beginning at the intersection of Towne Street and extends 0.5 miles to the intersection of Slocum Street.

Both projects are within the urban limits of the city of Glendive in Dawson County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - STREET EXCAVATION, PMS OVERLAY, S & C, C & G, SIDEWALK			
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
105080115	FINISH GRADE CONTROL	5,100.000	CRFT
107000020	CONTAMINATED SOIL	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
203020225	EXCAVATION-STREET	3,672.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	2,623.000	CUYD
301020348	DRAIN AGGREGATE	3.400	CUYD
301020625	AGGREGATE TREATMENT	6,727.000	SQYD
401020021	COMMERCIAL MIX-PG 70-28	1,333.000	TON
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	1,681.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,845.000	GAL
411010000	COLD MILLING	10,479.000	SQYD
601011920	INSULATION	659.000	SQFT
603000050	GRANULAR BEDDING MATERIAL	61.000	CUYD
603000078	ADJUST CURB BOX	3.000	EACH
603010020	FILL AND ABANDON PIPE	1.500	CUYD
603012800	RCP IRR 12 IN	467.300	LNFT
603014242	ADJUST VALVE BOX	29.000	EACH
603587030	REMOVE STORM DRAIN	199.300	LNFT
604000100	ADJUST MANHOLE	22.000	EACH
604000140	REMOVE DROP INLET	14.000	EACH
604000160	REMOVE CURB INLET	22.000	EACH
604000190	RESET CURB STOP AND BOX	1.000	EACH
604000200	RESET FIRE HYDRANT	2.000	EACH
604000250	ADJUST FIRE HYDRANT	4.000	EACH
604010045	MANHOLE-48 IN TYPE 3	11.000	EACH
604010210	INLET DROP-TYPE 3	1.000	EACH
604010212	INLET DROP-TYPE 4	39.000	EACH
604010534	COMB 48 IN T3 MH-T4 DROP INL	1.000	EACH
606010028	GUARDRAIL-OPTIONAL TERM SEC TL-2	2.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	81.200	LNFT
606010386	REMOVE AND SALVAGE GUARDRAIL	180.400	LNFT
608000020	SIDEWALK DRAIN	3.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	2,455.900	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	366.500	SQYD
608010090	CONCRETE 3 IN	18.300	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	90.900	SQYD
609010030	CURB-CONC MEDIAN TYPE A	84.600	LNFT
609010200	CURB AND GUTTER-CONC	6,008.800	LNFT
610100559	REVEGETATION	1.000	LS
616323110	CONDUIT-STEEL 1 IN RIGID	10.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	830.000	LNFT
616343924	CONDUIT-PLASTIC 2 1/2 IN	680.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	1,205.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	12.000	EACH

616783008	PULL BOX-COMPOSITE TYPE 3	4.000	EACH
617000000	FOUNDATION-CONCRETE	18.500	CUYD
617000050	POLES-TREATED WOOD CLASS 4	30.000	LNFT
617033114	CABLE-COPPER 2AWG14-600V	3,395.000	LNFT
617033414	CABLE-COPPER 7AWG14-600V	1,985.000	LNFT
617033514	CABLE-COPPER 9AWG14-600V	1,630.000	LNFT
617086919	CABLE-COPPER 6 PAIR AWG 19 COM	970.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	4,410.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	375.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	2,550.000	LNFT
617233030	CONTROLLER-CAB PEDESTAL TYPE P	3.000	EACH
617333198	SERV ASSEMBLY-200 AMP	1.000	EACH
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	30.000	EACH
617553020	SIG-PEDESTRIAN TYPE 2	22.000	EACH
617605081	CONTLR/TRAF-ACTUAT TYPE 8-A	3.000	EACH
617673080	SIG STANDARD TYPE 1-80	16.000	EACH
617673100	SIG STANDARD TYPE 1-100	2.000	EACH
617673120	SIG STANDARD TYPE 1-120	2.000	EACH
617695503	SIG STANDARD TYPE 2-A-500-3	2.000	EACH
617695504	SIG STANDARD TYPE 2-A-500-4	2.000	EACH
617695906	SIG STANDARD TYPE 2-A-900-6	1.000	EACH
617695907	SIG STANDARD TYPE 2-A-900-7	1.000	EACH
617715053	SIG STANDARD TYPE 3-A-500-3	1.000	EACH
617715054	SIG STANDARD TYPE 3-A-500-4	2.000	EACH
617715095	SIG STANDARD TYPE 3-A-900-5	1.000	EACH
617763405	DETECTOR-VIDEO	1.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	8.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617783030	REMOVE AND RESET MISC ELECTRICAL	1.000	LS
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	22.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010086	SIGNS-ALUM REFL SHEET IV	170.500	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	368.700	SQFT
619010230	REMOVE SIGN	73.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	2,492.000	LB
619010480	POLES-TREATED WOOD 4 IN	82.000	LNFT
619011179	DELINEATOR-FLEX SURF MTD WH	2.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	1.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	48.000	GAL
620010310	CURB MARKING-BLUE PAINT	1.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	48.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	62.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	13.000	GAL
620012950	TEMPORARY STRIPING	0.500	MILE
620013000	STRIPING-WHITE PAINT	20.000	GAL
620013960	STRIPING-WHITE EPOXY	26.000	GAL
620014000	STRIPING-YELLOW PAINT	12.000	GAL
620014960	STRIPING-YELLOW EPOXY	16.000	GAL
622011084	GEOTEXTILE STABILIZATION	7,410.000	SQYD
SECTION NO. 0002 - ADDITIVE ALTERNATE AA1 - WATERLINE WITH LIMITED			
ASBESTOS REMOVAL-CHARGE TO 9302 ACCT			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
104030030	MISCELLANEOUS ITEMS-INSTALL	70.000	LNFT
104030065	MISCELLANEOUS ITEMS-LNFT	20.000	LNFT
109200008	MOBILIZATION (ALTERNATE)	1.000	LS
301020450	SPECIAL BACKFILL	3,292.000	CUYD
601012015	TEMPORARY WATER SERVICE	1.000	EACH
603000055	BEDDING MATERIAL	300.000	CUYD
603000076	REMOVE WATER LINE	435.000	LNFT
603000080	REMOVE WATER VALVE BOX	10.000	EACH
603013457	PIPE-PVC 8 IN	1,498.000	LNFT
603013466	PIPE-PVC PRESS 8 IN WATER	263.000	LNFT
603013478	PIPE-PVC PRESS 12 IN WATER	1,475.000	LNFT
603013532	CONNECT TO MAIN	6.000	EACH
603013545	WATER SERVICE CONNECTION	43.000	EACH

603013550	SEWER SERVICE CONNECTION	50.000	EACH
603013553	CONNECT TO EXISTING MANHOLE	1.000	EACH
603013562	CONNECT WATER LINE-6 IN	1.000	EACH
603013828	DUCTILE IRON FITTINGS	1,524.000	LB
603014492	HYDRANT ASSEMBLY	3.000	EACH
603016061	STEEL CASING 12 IN	9.000	LNFT
604000120	REMOVE FIRE HYDRANT	3.000	EACH
604010035	MANHOLE-48 IN TYPE 1	4.000	EACH
615010741	VALVE-GATE 8 IN W/BOX	4.000	EACH
615010749	VALVE-GATE 12 IN W/BOX	2.000	EACH

SECTION NO. 0003 - ADDITIVE ALTERNATE AB1 - WATERLINE WITH FULL ASBESTOS

REMOVAL-CHARGE TO 9302 ACCT

104030010	MISCELLANEOUS WORK	15,000.000	UNIT
104030030	MISCELLANEOUS ITEMS-INSTALL	50.000	LNFT
104030065	MISCELLANEOUS ITEMS-LNFT	20.000	LNFT
109200008	MOBILIZATION (ALTERNATE)	1.000	LS
301020450	SPECIAL BACKFILL	3,280.000	CUYD
601012015	TEMPORARY WATER SERVICE	1.000	EACH
603000055	BEDDING MATERIAL	300.000	CUYD
603000076	REMOVE WATER LINE	1,490.000	LNFT
603000080	REMOVE WATER VALVE BOX	6.000	EACH
603013457	PIPE-PVC 8 IN	1,498.000	LNFT
603013466	PIPE-PVC PRESS 8 IN WATER	263.000	LNFT
603013478	PIPE-PVC PRESS 12 IN WATER	1,455.000	LNFT
603013532	CONNECT TO MAIN	6.000	EACH
603013545	WATER SERVICE CONNECTION	43.000	EACH
603013550	SEWER SERVICE CONNECTION	50.000	EACH
603013553	CONNECT TO EXISTING MANHOLE	1.000	EACH
603013562	CONNECT WATER LINE-6 IN	1.000	EACH
603013828	DUCTILE IRON FITTINGS	1,120.000	LB
603014492	HYDRANT ASSEMBLY	3.000	EACH
603016061	STEEL CASING 12 IN	9.000	LNFT
604000120	REMOVE FIRE HYDRANT	3.000	EACH
604010035	MANHOLE-48 IN TYPE 1	4.000	EACH
615010741	VALVE-GATE 8 IN W/BOX	4.000	EACH
615010749	VALVE-GATE 12 IN W/BOX	2.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.

Uniform No. 9110000, 9042000

206 WHITE SULPHUR SPRINGS - EAST STPP 14-2(39)43 CONTRACT NO. 02119

Plant mix overlay, seal & cover, guardrail, rumble strips, guardrail, signing, bridge rail revision and pvmt mkgs on the White Sulphur Springs - East project in Meagher County. The project is on US 12/P-14 beginning at White Sulphur Springs (RP 42.7) and proceeds northeasterly to Fourmile Creek (RP 49.0).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - PLANT MIX OVERLAY, RUMBLESTRIPS, G'RAIL, SIGNING AND			
PVMT MKGS			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	170.000	MILE
401020045	PLANT MIX SURF GR S-3/4 IN	20,991.000	TON
401020300	HYDRATED LIME	295.000	TON

402020092	ASPHALT CEMENT PG 64-28	1,132.700	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	15,451.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	254.600	TON
409000000	FINAL SWEEP AND BROOM	6.400	CRMI
409000010	COVER-TYPE 1	143,341.000	SQYD
411010000	COLD MILLING	3,322.000	SQYD
411011135	RUMBLE STRIPS	12.500	MILE
557010505	REVISE BRIDGE RAIL-THRIE BEAM	83.580	LNFT
606010135	ANCHOR POST	4.000	EACH
606010330	MGS GUARDRAIL	50.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	4.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.000	EACH
606010385	REMOVE GUARDRAIL	400.000	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	125,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	188.300	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	286.300	SQFT
619010230	REMOVE SIGN	41.000	EACH
619010240	REMOVE SIGN-GUIDE	6.000	EACH
619010310	POSTS-STEEL U SIGN	154.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,269.000	LB
619010480	POLES-TREATED WOOD 4 IN	250.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	92.000	LNFT
619010730	FRANG SIGN POST BKWY-W8 X 18 (W200 X 27	4.000	EACH
619011010	DELINEATOR DES A	214.000	EACH
619011040	DELINEATOR DES D	6.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	1.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620012950	TEMPORARY STRIPING	12.800	MILE
620013000	STRIPING-WHITE PAINT	438.000	GAL
620013960	STRIPING-WHITE EPOXY	283.000	GAL
620014000	STRIPING-YELLOW PAINT	418.000	GAL
620014960	STRIPING-YELLOW EPOXY	271.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 8116000

207 GUARDRAIL UPGRADE-GALLATIN NH-G 50-2(83)56 CONTRACT NO. 01119

Removal of existing guardrail, installation of new guardrail, and stabilization of slopes behind the guardrail on the Guardrail Upgrade-Gallatin project in Gallatin County. The project is located south of Gallatin Gateway along US 191 (also known as the Gallatin Canyon corridor) beginning at Reference Post 56.3 and extending north to Reference Post 67.5.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - EROSION PROTECTION AND GUARDRAIL			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
203020375	EMBANKMENT IN PLACE	185.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	381.000	CUYD
606010150	GUARDRAIL-STL/BR APPR-TY 1	1.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	16.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	29,634.200	LNFT
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	3.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	112.500	LNFT
606010385	REMOVE GUARDRAIL	28,761.000	LNFT

610100480	TURF REINF MAT-SYNTHETIC FIBER	1,845.000	SQYD
610100558	REVEGETATION	3,782.000	SQYD
613100030	RIPRAP-CLASS 1 RANDOM	563.300	CUYD
613100040	RIPRAP-CLASS 2 RANDOM	231.100	CUYD
618030005	TRAFFIC CONTROL DEVICES CB	350,000.000	UNIT
622011043	PERM EROSION CONTROL-HIGH SURV	602.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

Uniform No. 8766000

208 MBTA JOC - BILLINGS DISTRICT STPX STWD(685) CONTRACT NO. JC119

This project involves tree and shrub clearing, removal, and disposal to comply with the Migratory Bird Treaty Act (MBTA), including all associated preparation and traffic control as listed in each Job Order. The tree and shrub clearing, removal and disposal may be located adjacent to NHS Interstate, NHS Non-Interstate, Primary, Secondary, and County or City routes within MDT's Billings District. Job orders may range from small projects of less than one-half acre in size to greater than 20+ acres. Tree/Shrub Clearing, Removal, Disposal requirements may involve State, Federal, Local Government/Agency and private landowner coordination. Specific requirements will be listed with each job order.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - TREE AND SHRUB REMOVAL			
JOC104000	MISCELLANEOUS WORK	5,000.000	UNIT
JOC109000	MOBILIZATION	1.000	LS
JOC202000	SHRUB CLEARING, REMOVAL, DISPOSAL	0.950	ACRE
JOC202050	SHRUB CLEARING, REMOVAL, DISPOSAL	1.000	EACH
JOC610650	TREE REMOVAL-CAT 1	6.000	EACH
JOC610655	TREE REMOVAL-CAT 2	1.000	EACH
JOC610660	TREE REMOVAL-CAT 3	1.000	EACH
JOC610665	TREE REMOVAL-CAT 4	1.000	EACH
JOC618000	TRAFFIC CONTROL DEVICES-CB	20,000.000	UNIT

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.

Uniform No. 9538005

209 SHELBY VIADUCT - BRIDGE REPAIR

STPB 67-1(10)0

CONTRACT NO. 07119

Repair of a growing fatigue crack of an existing structure on the Shelby Viaduct - Bridge Repair project located in Toole County. The project begins at RP 0.08 on State Primary Route 67/MT 67/Oilfield Avenue located within the Shelby city limits.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE REPAIR			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
552010060	REPAIR STRUCTURE	1.000	LS
556010010	STRUCTURAL STEEL - MISC	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.

Uniform No. 9664000

INVITATION FOR BIDS
LETTING OF February 7, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on February 7, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 LOST TRAIL PASS - NORTH NH 7-1(164)0 CONTRACT NO. 01219
 STEVENSVILLE WYE - N & S NH 7-1(157)66
 STEVENSVILLE - SOUTH STPS 269-1(53)18

NH 7-1(164)0 - Cold milling, PMS overlay, guardrail, rumble strips, seal & cover and pavement markings on the Lost Trail Pass-North project located in Ravalli County. The project begins at RP 0.0 and extends north approximately 8.9 miles along National Highway Route 7/US 93 to RP 8.9.

NH 7-1(157)66 - Cold milling, PMS overlay, seal & cover and pavement markings on the Stevensville Wye-N & S project located in Ravalli County. The project begins at RP 65.9 and extends north approximately 2.5 miles along National Highway Route 7/US 93 to RP 68.3.

STPS 269-1(53)18 - Cold milling, PMS overlay, sidewalk/curb, guardrail, electrical, bridge repair, seal & cover and pavement markings on the Stevensville-South project located in Ravalli County. The project begins at RP 18.0 and extends north approximately 3.1 miles along National Highway Route 7/US 93 to RP 21.1.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - COLD MILLING, PMS OVERLAY, SEAL & COVER			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
104030019	RESET MISCELLANEOUS	2.000	EACH
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	200.000	MILE
301020340	CRUSHED AGGREGATE COURSE	30.000	CUYD
301020416	SHOULDER GRAVEL	193.000	CUYD
301020625	AGGREGATE TREATMENT	310.000	SQYD
401020048	PLANT MIX SURF GR S-1/2 IN	36,551.000	TON
401020300	HYDRATED LIME	512.000	TON
402020092	ASPHALT CEMENT PG 64-28	2,119.300	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	15,029.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	27,278.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	676.200	TON
409000000	FINAL SWEEP AND BROOM	0.900	CRMI
409000010	COVER-TYPE 1	275,941.000	SQYD
409000020	COVER-TYPE 2	103,439.000	SQYD
411010000	COLD MILLING	269,100.000	SQYD
411011135	RUMBLE STRIPS	1.600	MILE
552010160	BRIDGE DECK CRACK SEAL	2,710.600	SQYD
557010544	REVISE TIMBER BRIDGE RAIL-THRIE BEAM	172.900	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	2.000	SQYD
603014242	ADJUST VALVE BOX	5.000	EACH
604000100	ADJUST MANHOLE	4.000	EACH
604000260	ADJUST DROP INLET	2.000	EACH
604010184	CONCRETE APRON	2.000	EACH
606010135	ANCHOR POST	4.000	EACH
606010140	GUARDRAIL END SECTION WIDENING	8.000	EACH
606010330	MGS GUARDRAIL	6,576.700	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	8.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.000	EACH
606010385	REMOVE GUARDRAIL	6,422.300	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	4.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	359.400	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	36.300	SQYD
609010200	CURB AND GUTTER-CONC	719.600	LNFT
610100559	REVEGETATION	1.000	LS
617000000	FOUNDATION-CONCRETE	0.500	CUYD
617183056	STANDARD-STL TYPE 10-A-500-6	1.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	1.000	EACH
617781001	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT

618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618190100	TEMPORARY BARRIER RAIL	230.000	LNFT
618190110	RESET TEMP BARRIER RAIL	230.000	LNFT
619010058	SIGNS-ALUM SHEET INCR IV	824.800	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	182.600	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	560.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1,175.400	SQFT
619010230	REMOVE SIGN	206.000	EACH
619010240	REMOVE SIGN-GUIDE	25.000	EACH
619010300	POSTS-TUBULAR STEEL	369.000	LB
619010310	POSTS-STEEL U SIGN	554.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	859.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	619.000	LB
619010480	POLES-TREATED WOOD 4 IN	274.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	226.000	LNFT
619010500	POLES-TREATED WOOD 6 IN	16.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7 (S100X11)	2.000	EACH
619010724	FRANG SIGN POST BKWY-S5 X 10 (S130X15)	4.000	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD (89MM)	2.000	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD (100 MM)	1.000	EACH
619011001	DELINEATOR SNOWPOLE-DES A	124.000	EACH
619011002	DELINEATOR SNOWPOLE-DES F	54.000	EACH
619011004	DELINEATOR SNOWPOLE-DES C	246.000	EACH
619011010	DELINEATOR DES A	197.000	EACH
619011030	DELINEATOR DES C	45.000	EACH
619011040	DELINEATOR DES D	51.000	EACH
619011060	DELINEATOR DES F	44.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	192.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	81.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	15.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	54.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	10.000	GAL
620012950	TEMPORARY STRIPING	32.800	MILE
620013000	STRIPING-WHITE PAINT	1,132.000	GAL
620013960	STRIPING-WHITE EPOXY	795.000	GAL
620014000	STRIPING-YELLOW PAINT	928.000	GAL
620014960	STRIPING-YELLOW EPOXY	629.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.

Uniform No. 9491000, 9301000, 9234000

102 VARNEY BRIDGE - 8 M S ENNIS STPBIP 249-1(11)8 CONTRACT NO. 05219

Bridge removal and replacement with 250' steel through truss bridge, approaches, slope stabilization, riprap and drainage on the Varney Bridge - 8 Miles South of Ennis project in Madison County. The project is located on state route S-249, 8 miles south of Ennis between RP 7.7 and 8.0, more specifically coordinates T7S, R1W, Section 17.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRAVEL, 250' PREFAB STL TRUSS, SIGNING & RIPRAP			
103000000	TRAINING PROGRAM	500.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
105080115	FINISH GRADE CONTROL	4,500.000	CRFT

105080200	BRIDGE SURVEY	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020310	SPECIAL BORROW-NEAT LINE	5,986.000	CUYD
203020375	EMBANKMENT IN PLACE	4,588.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	1,034.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
208010500	BIOENGINEERED BANK	1.000	LS
209010160	TEMPORARY SHORING	1.000	LS
301020254	BRIDGE END BACKFILL-TYPE 3	791.000	CUYD
301020345	CRUSHED AGGREGATE COURSE	1,162.000	TON
301020450	SPECIAL BACKFILL	376.000	CUYD
301020526	TOP SURFACING GR 3B	321.000	CUYD
301020625	AGGREGATE TREATMENT	4,997.000	SQYD
551020030	CONCRETE-CLASS GENERAL	8.400	CUYD
551020035	CONCRETE-CLASS STRUCTURE	100.000	CUYD
551020166	CONCRETE-CLASS DRILLED SHAFT	123.600	CUYD
552010053	BRIDGE SUPERSTRUCTURE	1.000	LS
555010100	REINFORCING STEEL	9,752.000	LB
555010400	REINFORCING STEEL-SEISMIC	27,562.000	LB
557010011	BRIDGE RAIL-W740	516.900	LNFT
557010110	HAND RAIL	516.900	LNFT
558000140	DRILLED SHAFT - 4.0 FT	267.000	LNFT
558001300	TEMP DRILLED SHAFT CASING	267.000	LNFT
558010050	THERMAL INTEGRITY PROFILER	4.000	EACH
603000050	GRANULAR BEDDING MATERIAL	69.000	CUYD
603000060	FOUNDATION MATERIAL	75.000	CUYD
603011150	CSPA 60 IN	58.000	LNFT
603013343	REIN CONC BOX 12 X 4	60.000	LNFT
603587020	REMOVE PIPE CULVERT	40.600	LNFT
606010265	GRD RL-BOX BEAM/BR APP-SEC TYPE 1	4.000	EACH
606010641	GD RL BOX BEAM OPT TERM SEC	4.000	EACH
607000355	FENCE-JACKLEG WIRE	232.000	LNFT
607000360	FENCE-JACKLEG POLE	99.000	LNFT
607100009	FENCE - WILDLIFE FRIENDLY FW	1,724.000	LNFT
607100362	FARM FENCE-PANEL/SINGLE FM	28.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	32.000	LNFT
607100551	FENCE-TEMPORARY	860.000	LNFT
607100720	DEADMAN	2.000	EACH
607150125	RESET FENCE	126.000	LNFT
610010100	TOPSOIL	1,100.000	CUYD
610100101	SEEDING AREA NO 1	1.000	ACRE
610100102	SEEDING AREA NO 2	0.200	ACRE
610100103	SEEDING AREA NO 3	1.000	ACRE
610100326	FERTILIZING AREA NO 1	1.000	ACRE
610100327	FERTILIZING AREA NO 2	0.200	ACRE
610100555	CONDITION SEEDBED SURFACE	1.000	ACRE
610100560	RIPRAP REVEGETATION	663.000	SQYD
610100561	EROSION CONTROL BLANKET-LONG-TERM	731.000	SQYD
610220050	MULCH-COMPOST	1.000	ACRE
611010025	CATTLE GUARD 24 FT-HEAVY DUTY (7.2 M)	1.000	EACH
611010200	REMOVE CATTLE GUARD	1.000	EACH
613100050	RIPRAP-CLASS 3 RANDOM	1,055.400	CUYD
613300050	BANK PROTECTION-TYPE 3	21.200	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
618110000	INSTALL, REMOVE CAMERA SYSTEM	1.000	LS
619010090	SIGNS-ALUM REFL SHEET XI	17.400	SQFT
619010200	RESET SIGNS	1.000	EACH
619010210	RESET SIGNS-GUIDE	2.000	EACH
619010230	REMOVE SIGN	2.000	EACH
619010480	POLES-TREATED WOOD 4 IN	46.000	LNFT
622011043	PERM EROSION CONTROL-HIGH SURV	11,903.000	SQYD
622011172	GEOCOMPOSITE DRAIN	116.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
 Uniform No. 9038000

103 US 2 - COTTONWOOD TO RESERVE NH 1-2(210)123 CONTRACT NO. 04219
US 93 - IDAHO TO GRANDVIEW (KAL) NH 5-3(138)113

NH 1-2(210)123 - Milling, pms overlay, seal & cover, sidewalk, signing and electrical on the US 2-Cottonwood to Reserve project in Flathead County. The project is located just outside of Kalispell Urban limits on US 2 (N-1) (LaSalle Rd.) beginning just north of the intersection with Cottonwood Dr. (RP 123.1) and extending 2.1 miles to approximately 700 feet north of the Mission Mountain Railroad crossing (RP 125.2).

NH 5-3(138)113 - Milling, pms overlay, seal & cover, sidewalk, signing and electrical on the US 93-Idaho to Grandview (Kal) project in Flathead County. The project is located in the City of Kalispell on US 93 (N-5) (Sunset Blvd.) beginning just north of the intersection US 2 at Washington St. (RP 112.5) and extending north 1.9 miles to just past the intersection with Four Mile Dr./Grandview Dr. (RP 114.9).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - COLD MILLING, PMS OVERLAY, SEAL & COVER			
104030010	MISCELLANEOUS WORK	40,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
105080070	MONUMENT BOX	1.000	EACH
109200005	MOBILIZATION	1.000	LS
210020170	TEST TRAILER-TRANSPORT,SETUP	30.000	MILE
301020340	CRUSHED AGGREGATE COURSE	12.000	CUYD
401020048	PLANT MIX SURF GR S-1/2 IN	21,626.000	TON
401020300	HYDRATED LIME	303.000	TON
402020095	ASPHALT CEMENT PG 70-28	1,362.600	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	8,477.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	298.400	TON
409000020	COVER-TYPE 2	166,973.000	SQYD
411010000	COLD MILLING	170,276.000	SQYD
411011135	RUMBLE STRIPS	0.400	MILE
603014242	ADJUST VALVE BOX	25.000	EACH
603014490	FIRE HYDRANT	1.000	EACH
604000100	ADJUST MANHOLE	16.000	EACH
604000120	REMOVE FIRE HYDRANT	1.000	EACH
606010330	MGS GUARDRAIL	1,000.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	2.000	EACH
606010385	REMOVE GUARDRAIL	1,175.000	LNFT
608010020	SIDEWALK-CONCRETE 4 IN	493.700	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	43.900	SQYD
609010200	CURB AND GUTTER-CONC	798.300	LNFT
610100559	REVEGETATION	1.000	LS
616343920	CONDUIT-PLASTIC 2 IN	1,585.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	1,245.000	LNFT
616782999	ADJUST PULL BOX	2.000	EACH
616783007	PULL BOX-COMPOSITE TYPE 2	2.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	4.000	EACH
617000000	FOUNDATION-CONCRETE	8.000	CUYD
617033214	CABLE-COPPER 3AWG14-600V	235.000	LNFT
617033514	CABLE-COPPER 9AWG14-600V	2,020.000	LNFT
617033814	CABLE-COPPER 16AWG14-600V	1,300.000	LNFT

617123106	CONDUCTOR-COPPER AWG6-600V	725.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	750.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	960.000	LNFT
617233030	CONTROLLER-CAB PEDESTAL TYPE P	2.000	EACH
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	4.000	EACH
617553020	SIG-PEDESTRIAN TYPE 2	16.000	EACH
617603120	CABINET CONTROLLER TYPE P	2.000	EACH
617605081	CONTLR/TRAF-ACTUAT TYPE 8-A	2.000	EACH
617673100	SIG STANDARD TYPE 1-100	14.000	EACH
617695908	SIG STANDARD TYPE 2-A-900-8	1.000	EACH
617763410	RADAR VEHICLE DETECTION	5.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	16.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	25.500	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	543.100	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	593.500	SQFT
619010230	REMOVE SIGN	152.000	EACH
619010240	REMOVE SIGN-GUIDE	1.000	EACH
619010300	POSTS-TUBULAR STEEL	114.000	LB
619010310	POSTS-STEEL U SIGN	88.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	4,746.000	LB
619010742	FRANG SIGN POST BKWY-3.5 IN RD (89MM)	1.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	8.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	14.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	362.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	147.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	56.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	97.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	37.000	GAL
620012950	TEMPORARY STRIPING	14.000	MILE
620013000	STRIPING-WHITE PAINT	480.000	GAL
620013960	STRIPING-WHITE EPOXY	321.000	GAL
620014000	STRIPING-YELLOW PAINT	298.000	GAL
620014960	STRIPING-YELLOW EPOXY	199.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9032000, 9031000

104 SF 149 - YORK ROAD ROUNDABOUT HSIP-G 280-1(29)5 CONTRACT NO. 02C18

Installation of a new roundabout on the SF149 - York Road Roundabout project located in Lewis & Clark County. Work includes: grading, PMS overlay, curb/gutter, drainage, guardrail, fencing, electrical, seal & cover and pavement markings. The project is located at the intersection of State Secondary Route 280/York Road and Lake Helena Drive.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - ROUNDABOUT, GRADING, GRAVEL, PMS OVERLAY, DRAINAGE, FENCING, SEAL & COVER AND PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
105080070	MONUMENT BOX	1.000	EACH
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	26,844.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT

301020340	CRUSHED AGGREGATE COURSE	6,107.000	CUYD
301020625	AGGREGATE TREATMENT	10,331.000	SQYD
401020022	COMMERCIAL MIX-PG 64-28	2,639.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,306.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	14.700	TON
409000000	FINAL SWEEP AND BROOM	0.500	CRMI
409000010	COVER-TYPE 1	9,338.000	SQYD
501010125	PORT CEM CONC PAVE 9 IN	1,978.000	SQYD
501010126	PORT CEM CONC PAVE 9 IN COLORED	691.000	SQYD
603000050	GRANULAR BEDDING MATERIAL	107.500	CUYD
603012800	RCP IRR 12 IN	290.100	LNFT
603012847	RCP IRR 18 IN	128.000	LNFT
603012892	RCP IRR 24 IN	423.800	LNFT
603012925	RCP IRR 30 IN	188.000	LNFT
603012975	RCP IRR 48 IN	210.000	LNFT
603587020	REMOVE PIPE CULVERT	301.000	LNFT
604010213	INLET DROP-TYPE 5	9.000	EACH
604010250	INLET CURB-SPECIAL DESIGN	1.000	EACH
604010253	INLET CURB-TYPE A	1.000	EACH
604010255	INLET CURB-TYPE B	1.000	EACH
604010549	COMB 48 IN T3 MH-TB CURB INLET	1.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	2.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	500.000	LNFT
607000004	FENCE-CHAIN LINK	272.000	LNFT
607100229	FARM FENCE-TYPE F4W	2,195.000	LNFT
607100291	FARM FENCE-TYPE F6W	1,048.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	8.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	13.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	32.000	LNFT
607150015	REMOVE FENCE	3,878.000	LNFT
608010113	DECORATIVE CONCRETE - 3 IN	1,866.000	SQYD
609010121	CURB-SPECIAL DESIGN	1,606.400	LNFT
609010200	CURB AND GUTTER-CONC	4,560.100	LNFT
609010215	CURB MEDIAN-SPECIAL DESIGN COLOR	797.000	LNFT
610100557	REVEGETATION	4.400	ACRE
610100560	RIPRAP REVEGETATION	117.000	SQYD
610100563	WEED CONTROL MAT	649.000	SQYD
610100565	EROSION CONTROL BLANKET-HIGH-PERFORM	3,930.000	SQYD
610100625	LANDSCAPING	1.000	LS
610100720	LANDSCAPE ROCK	98.000	CUYD
613100030	RIPRAP-CLASS 1 RANDOM	5.700	CUYD
616343914	CONDUIT-PLASTIC 1 1/2 IN	2,525.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	500.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	7.000	EACH
617000000	FOUNDATION-CONCRETE	8.000	CUYD
617033214	CABLE-COPPER 3AWG14-600V	150.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	6,000.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	2,925.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	14.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	14.000	EACH
617333140	SERV ASSEMB-40 AMP	1.000	EACH
617781001	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	57.600	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	41.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	132.600	SQFT
619010200	RESET SIGNS	2.000	EACH
619010230	REMOVE SIGN	22.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	836.000	LB
619010480	POLES-TREATED WOOD 4 IN	228.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	18.000	LNFT
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	2.000	EACH
619011179	DELINEATOR-FLEX SURF MTD WH	8.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	12.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	94.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	6.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	13.000	GAL

620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	8.000	GAL
620012950	TEMPORARY STRIPING	0.500	MILE
620013000	STRIPING-WHITE PAINT	39.000	GAL
620013960	STRIPING-WHITE EPOXY	26.000	GAL
620014000	STRIPING-YELLOW PAINT	50.000	GAL
620014960	STRIPING-YELLOW EPOXY	34.000	GAL
622011084	GEOTEXTILE STABILIZATION	17,932.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 8935000

105 US-12 EROSION REPAIR - ELLISTON NH 8-1(39)22 CONTRACT NO. 06219

Streambank erosion repair, riprap, grading, guardrail and fencing on the US-12 Erosion Repair-Elliston project in Powell County. The project is located on US Hwy 12/ N-8, 1.0 mile east of Elliston between RP 22.2 and RP 22.5.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - EROSION REPAIR, RIPRAP, GUARDRAIL, FENCING			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
208010500	BIOENGINEERED BANK	1.000	LS
606010041	GUARDRAIL-BOX BEAM/8 FT POST	900.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	4.000	EACH
606010268	GRD RL-BOX BEAM/BR APP-SEC-TYPE 3	4.000	EACH
606010385	REMOVE GUARDRAIL	883.000	LNFT
606010641	GD RL BOX BEAM OPT TERM SEC	4.000	EACH
607100252	FARM FENCE-TYPE F4M	350.000	LNFT
607100385	FARM FENCE-PANEL/DOUBLE FM	4.000	EACH
613100050	RIPRAP-CLASS 3 RANDOM	1,190.000	CUYD
618030005	TRAFFIC CONTROL DEVICES CB	75,000.000	UNIT
622011043	PERM EROSION CONTROL-HIGH SURV	1,070.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 9634000

106 US-89 EROSION REPAIR - EMIGRANT NH 11-1(96)32 CONTRACT NO. 07219

Riprap, geotextile, embankment, and fencing installation on the US-89 Erosion Repair - Emigrant project located in Park County. The project is located adjacent to National Highway Route 11/US-89 beginning north of Emigrant at RP 32.0 and extends northerly approximately 0.3 miles to RP 32.3.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SLOPE FLATTENING, RIPRAP REVETMENT			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
104030013	MISCELLANEOUS ITEMS-HOUR	10.000	HOURL
109200005	MOBILIZATION	1.000	LS
203020375	EMBANKMENT IN PLACE	1,384.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
209010160	TEMPORARY SHORING	1.000	LS
607100149	FARM FENCE-TYPE F3W-32 IN WW	497.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	1.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	4.000	EACH
610100557	REVEGETATION	0.800	ACRE
613100050	RIPRAP-CLASS 3 RANDOM	1,913.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
622011043	PERM EROSION CONTROL-HIGH SURV	1,610.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Butte District Administrator.
 Uniform No. 9673000

107 US 93 & CARTAGE ROAD (MSLA) NH 5-1(69)0 CONTRACT NO. 03219

Traffic signal modifications to include signal, signing and pavement markings on the US 93 & Cartage Road (MSLA) project in Missoula County. The project is on US 93 at the intersection with Cartage Road, northwest of Missoula (RP 0.3).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - TRAFFIC SIGNAL MODIFICATIONS			
104030010	MISCELLANEOUS WORK	2,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
608010020	SIDEWALK-CONCRETE 4 IN	8.600	SQYD
616343920	CONDUIT-PLASTIC 2 IN	20.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	120.000	LNFT
616782999	ADJUST PULL BOX	2.000	EACH
617000000	FOUNDATION-CONCRETE	4.000	CUYD
617033514	CABLE-COPPER 9AWG14-600V	20.000	LNFT
617033814	CABLE-COPPER 16AWG14-600V	480.000	LNFT
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	4.000	EACH
617513125	SIG TRAF 4 COL 1 W 12-12-12-12	3.000	EACH
617533000	SIG-TRAF-BACKPLATE-REFLECTIVE	8.000	EACH
617553020	SIG-PEDESTRIAN TYPE 2	8.000	EACH
617673100	SIG STANDARD TYPE 1-100	1.000	EACH
617695908	SIG STANDARD TYPE 2-A-900-8	1.000	EACH
617763410	RADAR VEHICLE DETECTION	4.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617783030	REMOVE AND RESET MISC ELECTRICAL	1.000	LS
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	8.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010090	SIGNS-ALUM REFL SHEET XI	25.000	SQFT
619010230	REMOVE SIGN	1.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	79.000	LB
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	1.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9033000

INVITATION FOR BIDS
LETTING OF February 21, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on February 21, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

201 WEST LAUREL INTCH - WEST (PHASE 2) IM 90-8(174)432 CONTRACT NO. 13419

Construction of a 242 ft long x 56 ft wide prestressed concrete beam structure over I-90, grading, gravel, plant mix overlay, seal & cover, signing, striping, drainage, fencing and electrical on the West Laurel Interchange-West (Phase 2) project in Yellowstone County.

The project is located southwest of the City of Laurel on Interstate 90 between RP 432.2 and 432.6 and includes work on the new structure, ramps, 19th street from I-90 north to the intersection with Main Street (0.45 miles), Golf Course Road (0.2 miles), Main Street widening (0.4 miles) and a public approach (0.1 miles).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRAVEL, PMS OVERLAY, SIGN, ELECT			
103000000	TRAINING PROGRAM	500.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
201311005	REMOVE TREES	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	28,441.000	CUYD
203020175	EXCAVATION-UNCLASS CHANNEL	1,392.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	14,964.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	4,946.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
209010100	STRUCTURE EXCAVATION TYPE 1	135.000	CUYD
209010160	TEMPORARY SHORING	1.000	LS
212000000	OBLITERATE ROADWAY	6.800	STA
301020252	BRIDGE END BACKFILL-TYPE 1	1,700.000	CUYD
301020268	TRAFFIC GRAVEL	1,000.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	14,097.000	CUYD
301020526	TOP SURFACING GR 3B	920.000	CUYD
301020625	AGGREGATE TREATMENT	45,502.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	13,347.000	TON
401020300	HYDRATED LIME	187.000	TON
402020095	ASPHALT CEMENT PG 70-28	718.100	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	2,210.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	83.300	TON
409000000	FINAL SWEEP AND BROOM	2.000	CRMI
409000020	COVER-TYPE 2	46,600.000	SQYD
411010000	COLD MILLING	5,376.000	SQYD
411011135	RUMBLE STRIPS	0.400	MILE
551020030	CONCRETE-CLASS GENERAL	4.600	CUYD
551020035	CONCRETE-CLASS STRUCTURE	245.600	CUYD
551020107	CONCRETE-CLASS DECK	389.300	CUYD
552020000	ARCHITECTURAL TREATMENT	107.500	SQYD
553010155	PRESTRESSED BEAM-TYPE MTS-54	1,683.500	LNFT
555010100	REINFORCING STEEL	29,033.000	LB
555010200	REINFORCING STEEL-EPOXY COATED	77,820.000	LB
555010400	REINFORCING STEEL-SEISMIC	514.000	LB
559010202	RE-DRIVE TEST PILE	1.000	EACH
559040035	DYNAMIC LOAD TEST	3.000	EACH
559050080	FURN STEEL PILE HP 14 X 89	1,992.000	LNFT
559060081	DRIVE STEEL PILE HP 14 X 89	1,939.000	LNFT
559060300	PILE DRIVING POINT	32.000	EACH
563000040	POLYMER OVERLAY	1,450.000	SQYD
563000100	PREPARE DECK	1,450.000	SQYD
603012530	RCP 18 IN	432.000	LNFT
603012555	RCP 24 IN	58.000	LNFT
603012847	RCP IRR 18 IN	158.000	LNFT
603012892	RCP IRR 24 IN	436.000	LNFT
603012938	RCP IRR 36 IN	148.000	LNFT
603015270	EMBANKMENT PROTECTOR 18 IN	179.000	LNFT

603587020	REMOVE PIPE CULVERT	461.000	LNFT
605000030	BARRIER RAIL-CAST IN PLACE-BR	489.400	LNFT
606010150	GUARDRAIL-STL/BR APPR-TY 1	4.000	EACH
606010330	MGS GUARDRAIL	4,906.100	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	5.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	5.000	EACH
606010385	REMOVE GUARDRAIL	334.000	LNFT
607100148	FARM FENCE-TYPE F2M-39 IN WW	3,833.000	LNFT
607100154	FARM FENCE-TYPE F2M-48 IN WW	1,307.000	LNFT
607100252	FARM FENCE-TYPE F4M	85.000	LNFT
607100362	FARM FENCE-PANEL/SINGLE FM	22.000	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	12.000	EACH
607100440	FARM GATE-METAL-TYPE G-3	92.000	LNFT
609010112	CURB 4 IN-CONCRETE	104.000	LNFT
610100101	SEEDING AREA NO 1	7.000	ACRE
610100102	SEEDING AREA NO 2	0.600	ACRE
610100103	SEEDING AREA NO 3	3.500	ACRE
610100326	FERTILIZING AREA NO 1	7.000	ACRE
610100555	CONDITION SEEDBED SURFACE	10.500	ACRE
610220050	MULCH-COMPOST	0.600	ACRE
613100030	RIPRAP-CLASS 1 RANDOM	16.000	CUYD
613300050	BANK PROTECTION-TYPE 3	6.000	CUYD
613400010	SLOPE PROTECTION-CONCRETE	596.000	SQYD
614100014	DESIGN, CONST RETAINING WALL	20.000	SQYD
615010022	IRRIGATION DIVISION BOX-TYPE 3	3.000	EACH
615010034	REMOVE IRRIGATION STRUCTURE	1.000	EACH
615010580	TRASH GUARD	1.000	EACH
616343914	CONDUIT-PLASTIC 1 1/2 IN	2,355.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	5.000	EACH
617000000	FOUNDATION-CONCRETE	6.300	CUYD
617123108	CONDUCTOR-COPPER AWG8-600V	5,174.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	2,587.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	12.000	EACH
617303225	LUMINAIRE ASSEMBLY-250 W S.V.	12.000	EACH
617333120	SERV ASSEMB-20 AMP	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
618030180	TRAFFIC CONTROL-CROSSOVER	2.000	EACH
618030300	CROSSOVER-MAINTAIN, CLOSE	2.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	1,137.600	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	21.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	118.500	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	272.700	SQFT
619010200	RESET SIGNS	1.000	EACH
619010230	REMOVE SIGN	11.000	EACH
619010240	REMOVE SIGN-GUIDE	5.000	EACH
619010300	POSTS-TUBULAR STEEL	985.000	LB
619010310	POSTS-STEEL U SIGN	144.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	8,176.000	LB
619010480	POLES-TREATED WOOD 4 IN	420.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	110.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7 (S100X11)	8.000	EACH
619010724	FRANG SIGN POST BKWY-S5 X 10 (S130X15)	2.000	EACH
619010726	FRANG SIGN POST BKWY-W4 X 13 (W100X19)	2.000	EACH
619010730	FRANG SIGN POST BKWY-W8 X 18 (W200 X 27)	3.000	EACH
619010732	FRANG SIGN POST BKWY-W8 X 24 (W200X34)	4.000	EACH
619010734	FRANG SIGN POST BKWY-W12 X 30 (W300X43)	3.000	EACH
619010740	FRANG SIGN POST BKWY-3 IN RD (76 MM)	1.000	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD (89MM)	1.000	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD (100 MM)	2.000	EACH
619011010	DELINEATOR DES A	92.000	EACH
619011040	DELINEATOR DES D	10.000	EACH
619011070	DELINEATOR DES G	48.000	EACH
619011080	DELINEATOR DES H	18.000	EACH
619011085	DELINEATOR DES BJ	22.000	EACH
619011087	DELINEATOR DES GJ	19.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	17.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	25.000	GAL

620011260	WORDS AND SYMBOLS-WHITE EPOXY	11.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	15.000	GAL
620013000	STRIPING-WHITE PAINT	136.000	GAL
620013955	REMOVE PAVEMENT MARKINGS	1,040.000	LNFT
620013960	STRIPING-WHITE EPOXY	91.000	GAL
620014000	STRIPING-YELLOW PAINT	120.000	GAL
620014960	STRIPING-YELLOW EPOXY	80.000	GAL
622011084	GEOTEXTILE STABILIZATION	29,885.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	62.000	SQYD
623000155	MAILBOX	3.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator. Uniform No. 5736003

202 DIXON - RAVALLI STPP 6-1(154)109 CONTRACT NO. 02219
NOXON - E & W STPP 6-1(160)15
DIXON - WEST STPP 6-1(156)99
PERMA CANYON - NORTH STPS 382-1(19)6

STPP 6-1(154)109 - Road and bridge deck crack sealing, seal & cover, rumble strips and pavement markings on the Dixon - Ravalli project in Sanders and Lake County. The project is on State Hwy 200, beginning at the junction of West Street (RP 108.5) in Dixon and proceeds east 7.2 miles to approximately 152 feet west of the junction with Hwy 93 junction in Ravalli (RP 116.1). The project is entirely within the Flathead Indian Reservation.

STPP 6-1(156)99 - Road and bridge deck crack sealing, seal & cover, rumble strips and pavement markings on the Dixon - West project in Sanders County. The project is on State Hwy 200, beginning approximately 3.12 miles east of the Secondary Hwy 382 junction near Perma (RP 98.7). It extends easterly 9.8 miles to the intersection of West Street and State Hwy 200 in Dixon (RP 108.5). The project is entirely within the Flathead Indian Reservation.

STPP 6-1(160)15 - Crack sealing, seal & cover, rumble strips and pavement markings on the Noxon - East & West project in Sanders County. The project is on State Hwy 200, beginning in Noxon at RP 14.7 and proceeds south easterly 8.2 miles to RP 22.9.

STPS 382-1(19)6 - Crack sealing, seal & cover and pavement markings on the Perma Canyon - North project in Sanders County. The project is on State Secondary S-382, beginning at RP 5.9 and proceeding north to RP 10.5. The project is entirely within the Flathead Indian Reservation.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - CRACK SEAL, SEAL & COVER, RUMBLE STRIPS AND PVMT MKGS			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
402020320	EMULSIFIED ASPHALT-FOG SEAL	16,938.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	457.300	TON
402020375	EMULSIFIED ASPHALT CHFRS-2P	573.200	TON
403010255	CRACK SEALING	51,281.000	LB
409000000	FINAL SWEEP AND BROOM	17.000	CRMI
409000010	COVER-TYPE 1	554,466.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	16.300	MILE
411011135	RUMBLE STRIPS	41.900	MILE
552010160	BRIDGE DECK CRACK SEAL	2,651.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	160,000.000	UNIT
620010301	CURB MARKING-YELLOW EPOXY	15.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	11.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	5.000	GAL

620011260	WORDS AND SYMBOLS-WHITE EPOXY	13.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	7.000	GAL
620013000	STRIPING-WHITE PAINT	1,098.000	GAL
620013960	STRIPING-WHITE EPOXY	1,464.000	GAL
620014000	STRIPING-YELLOW PAINT	413.000	GAL
620014960	STRIPING-YELLOW EPOXY	552.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.

Uniform No. 9239000, 9235000, 9238000, 9302000

203 MEADOW CREEK - SOUTH STPS 508-1(16)12 CONTRACT NO. 09219

Cold milling, PMS overlay, bridge crack seal, guardrail, seal & cover and pavement markings on the Meadow Creek-South project located in Lincoln County. The project begins at RP 12.4, approximately 12.4 miles north of the junction with National Highway Route 1/US 2, and extends north approximately 5.7 miles along State Secondary Route 508 (Yaak River Rd.) to RP 18.1.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - COLD MILLING, PMS OVERLAY, SEAL & COVER			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	280.000	MILE
401020048	PLANT MIX SURF GR S-1/2 IN	13,094.000	TON
401020300	HYDRATED LIME	183.000	TON
402020089	ASPHALT CEMENT PG 58-28	720.600	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5,105.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	7,507.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	180.300	TON
409000010	COVER-TYPE 1	100,562.000	SQYD
411010000	COLD MILLING	104,803.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	809.000	SQYD
606010140	GUARDRAIL END SECTION WIDENING	20.000	EACH
606010330	MGS GUARDRAIL	1,099.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	20.000	EACH
606010385	REMOVE GUARDRAIL	1,537.500	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	70,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	58.500	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	60.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	78.200	SQFT
619010230	REMOVE SIGN	26.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010310	POSTS-STEEL U SIGN	120.000	LB
619010480	POLES-TREATED WOOD 4 IN	194.000	LNFT
619011010	DELINEATOR DES A	214.000	EACH
619011060	DELINEATOR DES F	68.000	EACH
620012950	TEMPORARY STRIPING	11.400	MILE
620013000	STRIPING-WHITE PAINT	410.000	GAL
620013960	STRIPING-WHITE EPOXY	273.000	GAL
620014000	STRIPING-YELLOW PAINT	269.000	GAL
620014960	STRIPING-YELLOW EPOXY	179.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Missoula District Administrator.
 Uniform No. 9303000

204 HUFFINE LANE/LOVE LANE - W BOZEMAN NH 50-2(81)84 CONTRACT NO. 11219

Reconstruction of the existing intersection on the Huffine Ln/Love Ln - W Bozeman project located in Gallatin County. Work includes: grading, PMS overlay, curb/gutter, drainage, fencing, traffic signals, seal & cover and pavement markings. The project is located at the intersection of Huffine Lane and Love Lane on National Highway Route 50/US 191 at RP 84.0.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RECONSTRUCTION OF THE EXISTING INTERSECTION			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105080115	FINISH GRADE CONTROL	3,450.000	CRFT
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	5,615.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	4,125.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	335.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	1,918.000	CUYD
301020625	AGGREGATE TREATMENT	7,525.000	SQYD
401020021	COMMERCIAL MIX-PG 70-28	1,760.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	737.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	33.500	TON
409000000	FINAL SWEEP AND BROOM	0.800	CRMI
409000020	COVER-TYPE 2	18,725.000	SQYD
603000050	GRANULAR BEDDING MATERIAL	210.000	CUYD
603012800	RCP IRR 12 IN	256.000	LNFT
603012892	RCP IRR 24 IN	677.100	LNFT
603013413	PIPE-CORR POLYETHYLENE DR 8 IN	116.000	LNFT
603587020	REMOVE PIPE CULVERT	235.100	LNFT
604010045	MANHOLE-48 IN TYPE 3	2.000	EACH
604010213	INLET DROP-TYPE 5	4.000	EACH
604010552	COMB 48 IN T3 MH-T5 DROP INL	2.000	EACH
607100259	FARM FENCE-TYPE F5W	443.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	4.000	EACH
607150015	REMOVE FENCE	379.000	LNFT
608010090	CONCRETE 3 IN	6.100	SQYD
609010160	GUTTER-CONC VALLEY	98.700	SQYD
609010200	CURB AND GUTTER-CONC	1,272.300	LNFT
610100101	SEEDING AREA NO 1	1.100	ACRE
610100102	SEEDING AREA NO 2	0.100	ACRE
610100326	FERTILIZING AREA NO 1	1.100	ACRE
610100327	FERTILIZING AREA NO 2	0.100	ACRE
610100555	CONDITION SEEDBED SURFACE	1.100	ACRE
610100566	EROSION CONTROL BLANKET-SHORT-TERM	52.000	SQYD
616343914	CONDUIT-PLASTIC 1 1/2 IN	1,000.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	930.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	150.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	3.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	1.000	EACH
617000000	FOUNDATION-CONCRETE	14.000	CUYD
617033614	CABLE-COPPER 12AWG14-600V	680.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	95.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	2,300.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	3,080.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	7.000	EACH

617233030	CONTROLLER-CAB PEDESTAL TYPE P	1.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	9.000	EACH
617333198	SERV ASSEMBLY-200 AMP	1.000	EACH
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	14.000	EACH
617605081	CONTLR/TRAF-ACTUAT TYPE 8-A	1.000	EACH
617695907	SIG STANDARD TYPE 2-A-900-7	1.000	EACH
617695909	SIG STANDARD TYPE 2-A-900-9	1.000	EACH
617715097	SIG STANDARD TYPE 3-A-900-7	1.000	EACH
617715099	SIG STANDARD TYPE 3-A-900-9	1.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	4.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	70,000.000	UNIT
619010086	SIGNS-ALUM REFL SHEET IV	35.200	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	15.400	SQFT
619010230	REMOVE SIGN	4.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	126.000	LB
619010480	POLES-TREATED WOOD 4 IN	16.000	LNFT
620010301	CURB MARKING-YELLOW EPOXY	10.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	6.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	11.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	5.000	GAL
620012950	TEMPORARY STRIPING	0.200	MILE
620013000	STRIPING-WHITE PAINT	57.000	GAL
620013960	STRIPING-WHITE EPOXY	61.000	GAL
620014000	STRIPING-YELLOW PAINT	36.000	GAL
620014960	STRIPING-YELLOW EPOXY	29.000	GAL
622011084	GEOTEXTILE STABILIZATION	6,237.000	SQYD
623000155	MAILBOX	6.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 8545000

205 BR PRES YELLOWSTONE GARDINER NHPB 11-1(83)0 CONTRACT NO. 10219

Bridge rehab and approaches to include deck repair, milling and overlay, grading and PCCP approaches on the Bridge Preservation Yellowstone Gardiner project in Park County. The project is in Gardiner on US 89/State Rte N-11 at RP 0.16.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BR REHAB, GRADE, GRVL, PCCP, G'RAIL, CURB & PVMT			
MKGS			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
209010160	TEMPORARY SHORING	1.000	LS
301020340	CRUSHED AGGREGATE COURSE	33.000	CUYD
501010200	PCCP-9 IN REINFORCED	129.000	SQYD
552011120	JOINT SEALS-POLYURETHANE	152.000	LNFT
555010200	REINFORCING STEEL-EPOXY COATED	12,130.500	LB
561020110	BRIDGE DECK MILLING	1,550.500	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	28.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	10.000	SQYD
563000000	CONCRETE-CLASS OVERLAY	124.600	CUYD
104030015	REMOVE AND RESET MISC ITEMS	1.000	LS
563000040	POLYMER OVERLAY	1,670.000	SQYD
563000100	PREPARE DECK	1,670.000	SQYD
604010630	DRAINAGE STRUCTURE	1.000	LS

606010370	RESET GUARDRAIL	35.700	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
608010059	SIDEWALK-REINFORCED 4 IN	19.800	SQYD
609010010	CURB-CONCRETE	36.000	LNFT
614010008	RETAINING WALL REPAIR	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
105080115	FINISH GRADE CONTROL	100.000	CRFT
618030080	TRAFFIC CONTROL	1.000	LS
618100000	SINGLE USE SIGNS	224.000	SQFT
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	260.000	DAY
618190100	TEMPORARY BARRIER RAIL	440.000	LNFT
618190110	RESET TEMP BARRIER RAIL	440.000	LNFT
620010301	CURB MARKING-YELLOW EPOXY	14.000	GAL
620013960	STRIPING-WHITE EPOXY	5.000	GAL
620014960	STRIPING-YELLOW EPOXY	10.000	GAL
105080200	BRIDGE SURVEY	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020115	REMOVE DECK	162.300	SQYD
203020225	EXCAVATION-STREET	71.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 8803000

206 S-324 - CLARK CANYON TO GRANT STPS 324-1(9)0 CONTRACT NO. 12219

Seal and cover and pavement markings on the S-324 - Clark Canyon to Grant project. The project is located south of Dillon on State Secondary Route 324 near Clark Canyon Reservoir beginning at RP 0.15 and extends west 13.0 miles to RP 13.2 just west of the town of Grant. The project is located entirely within Beaverhead County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - SEAL AND COVER			
104030010	MISCELLANEOUS WORK	2,500.000	UNIT
109200005	MOBILIZATION	1.000	LS
402020368	EMULSIFIED ASPHALT CRS-2P	316.800	TON
409000000	FINAL SWEEP AND BROOM	13.000	CRMI
409000010	COVER-TYPE 1	176,368.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	40,000.000	UNIT
620013000	STRIPING-WHITE PAINT	478.000	GAL
620013960	STRIPING-WHITE EPOXY	637.000	GAL
620014000	STRIPING-YELLOW PAINT	274.000	GAL
620014960	STRIPING-YELLOW EPOXY	366.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 9305000

INVITATION FOR BIDS
LETTING OF March 14, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on March 14, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 SF 159 BADGER CREEK SOUTH FENCING HSIP 3-4(41)93 CONTRACT NO. 06319

Install cattle guards and fencing on the SF 159 Badger Creek South Fencing project located in Glacier County. The project begins at RP 93.0 and continues southeast along State Primary Route 3/US 89 to RP 100.2. The entire project is located within the Blackfeet Indian Reservation.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - CATTLE GUARDS AND FENCING			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
107100010	CULTURAL RESOURCE PERSON	5.000	DAY
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
607100010	FENCE-WILDLIFE FRIENDLY FW/FM	14,797.000	LNFT
607100229	FARM FENCE-TYPE F4W	57,577.000	LNFT
607100251	FARM FENCE-TYPE F4M-8 FT POST	2,286.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	321.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	49.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	494.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	64.000	LNFT
607100450	FENCE-PEDESTRIAN PASS	14.000	EACH
607100720	DEADMAN	68.000	EACH
611010016	CATTLE GUARD 16 FT-LIGHT DUTY (4.8 M)	8.000	EACH
611010032	CATTLE GUARD 32 FT-HEAVY DUTY (9.8 M)	1.000	EACH
611010200	REMOVE CATTLE GUARD	5.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
 Uniform No. 9090000

102 SF 159 MEAGHER GUARDRAIL SAFETY HSIP-G 60-1(26)12 CONTRACT NO. 04319

Guardrail removal and installation on the SF 159 Meagher Guardrail Safety project in Meagher County. The project is located northeast of White Sulphur Springs on US 89 (King's Hill Scenic Byway) at two locations. Site #1 is between RP 25.1 and RP 26.6. Site #2 is between RP 15.0 and RP 15.6.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GUARDRAIL			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
606010041	GUARDRAIL-BOX BEAM/8 FT POST	3,726.000	LNFT
606010120	REMOVE CABLE GUARDRAIL	713.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	4.000	EACH
606010641	GD RL BOX BEAM OPT TERM SEC	4.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
 Uniform No. 9103000

103 SF 169 GT FALLS SFTY IMPRV HSIP STWD(559) CONTRACT NO. 08319
SF 169 CASCADE CNTY SFTY IMPRV HSIP 7(71)
SF 159 FORT SHAW SFTY IMPRV HSIP 24-4(23)132

HSIP STWD(559) - Signing, Delineation and Flashers on the SF 169 Great Falls Safety Improvement project in Pondera, Teton, Hill and Lewis and Clark Counties. The five locations are:

Site #1 - Teton River crossing on I-90 RP 318.4 to RP 319.0, Site #2 - I-15 Panel Delineation RP 340.4 to 342.8, Site #3 - I-15 Flasher, RP 238.9 to RP 239.4, Site #4 - L-21-627 Hill County Rd, RP 3.2 to RP 4.0, Site #5 - I-15 BNSF River Crossing, RP 341.8 to RP 342.2.

HSIP 7(71) - Delineation and Signing on the SF 169 Cascade County Safety Improvement project at three locations in Cascade County. The three locations are: Site #1 - I-15 South Bound RP 255.7 to RP 256.1, Site #3 U-5215, 13th Street South RP 1.5 to RP 3.8, and Site #4 Mciver Road RP 6.8 to RP 7.4. HSIP 24-4(23)132 - Signing, pavement markings, delineation and rumble strips on the SF 159 Fort Shaw Safety Improvement project in Cascade County. The project is located southwest of Fort Shaw on MT 200/N-24 between RP 132.0 and RP 133.0.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - DELINEATION AND SIGNING			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
411011135	RUMBLE STRIPS	0.300	MILE
616343920	CONDUIT-PLASTIC 2 IN	600.000	LNFT
617000000	FOUNDATION-CONCRETE	14.000	CUYD
617033214	CABLE-COPPER 3AWG14-600V	600.000	LNFT
617483110	SIG-TRAF 1 COL-1 WAY 12	6.000	EACH
617673200	SIG STANDARD TYPE 1-200	15.000	EACH
617740000	ROADWAY TEMPERATURE SENSOR	3.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	50,000.000	UNIT
619010090	SIGNS-ALUM REFL SHEET XI	300.400	SQFT
619010230	REMOVE SIGN	22.000	EACH
619010480	POLES-TREATED WOOD 4 IN	272.000	LNFT
619010800	PANEL DELINEATOR DESIGN A	91.000	EACH
619010825	PANEL DELINEATOR DESIGN G	6.000	EACH
619010830	PANEL DELINEATOR DESIGN H	51.000	EACH
619011010	DELINEATOR DES A	56.000	EACH
619011030	DELINEATOR DES C	68.000	EACH
619011040	DELINEATOR DES D	20.000	EACH
620013955	REMOVE PAVEMENT MARKINGS	1,478.400	LNFT
620013960	STRIPING-WHITE EPOXY	7.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
 Uniform No. 9425000, 9426000, 9098000

104 SF 169 BOZEMAN SAFETY IMPROVEMENTS HSIP 16(122) CONTRACT NO. 07319
 SF 169 BUTTE DISTRICT DELINEATION HSIP STWD(557)
 SF 169 BUTTE DISTRICT SAFETY HSIP STWD(555)
 SF 169 TWIN BRIDGES SAFETY HSIP STWD(537)

HSIP 16(122) - Signing, delineation and pavement markings on the SF 169 Bozeman Safety Improvements project located in Gallatin County at the following 5 locations:

- Loc #1 - State Primary Route 86/Bridger Canyon Road north of Bozeman from RP 28.9 to RP 29.1.
- Loc #2 - Local Road/Penwell Bridge Road northeast of Belgrade from RP 0.5 to RP 4.5.
- Loc #3 - Local Road/Weaver Drive north of Belgrade from RP 2.8 to RP 3.5.
- Loc #4 - Local Road/Cottonwood Road southwest of Bozeman from RP 2.4 to RP 6.0.
- Loc #5 - Local Road/Hyalite Canyon Road south of Bozeman from RP 0.0 to RP 9.95.

HSIP STWD(557) - Delineation on the SF 169 Butte District Delineation project located in Jefferson County at the following 2 locations:Loc #1 - Interstate Route 90/Homestake Pass from RP 234.1 to RP 234.9.

Loc #2 - State Secondary Route 282/Haab Lane south of Montana City from RP 2.2 to RP 3.6.

HSIP STWD(555) - Delineation and signing on the SF 169 Butte District Safety project located in Beaverhead, Deer Lodge and Silver Bow Counties at the following 5 locations:Loc #1 - Interstate Route 15 north of Melrose in Silver Bow County from RP 96.3 to RP 99.3.

Loc #2 - Interstate Route 15 south of Rocker in Silver Bow County from RP 118.2 to RP 118.8.

Loc #3 - Interstate Route 90 south of Warm Springs in Deer Lodge County from RP 205.3 to RP 206.4.

Loc #4 - Interstate Route 15 north of Lima in Beaverhead County from RP 17.4 to RP 23.5.

Loc #5 - Local Road/Little Basin Creek Road south of Butte in Silver Bow County from RP 0.87 to RP 1.37.

HSIP STWD(537) - Delineation on the SF 169 Twin Bridges Safety project located in Madison County at the following 2 locations:Loc #1 - State Primary Route 29/US 287 north of Alder in Madison County from RP 24.5 to RP 25.1.

Loc #2 - National Highway Route 49/MT 41 southwest of Twin Bridges in Madison County from RP 16.5 to RP 19.5.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SIGNING AND DELINEATION ON 4 TIED PROJECTS			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
617000000	FOUNDATION-CONCRETE	1.000	CUYD
617523010	SOL SIG-TRAF 1 COLOR-1 WAY 12	2.000	EACH
617673200	SIG STANDARD TYPE 1-200	2.000	EACH
617763410	RADAR VEHICLE DETECTION	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	25,000.000	UNIT
619010090	SIGNS-ALUM REFL SHEET XI	1,109.500	SQFT
619010230	REMOVE SIGN	35.000	EACH
619010480	POLES-TREATED WOOD 4 IN	1,688.000	LNFT
619010800	PANEL DELINEATOR DESIGN A	190.000	EACH
619010810	PANEL DELINEATOR DESIGN C	38.000	EACH
619010830	PANEL DELINEATOR DESIGN H	161.000	EACH
619011010	DELINEATOR DES A	299.000	EACH
619011030	DELINEATOR DES C	630.000	EACH
619011040	DELINEATOR DES D	8.000	EACH
619011060	DELINEATOR DES F	229.000	EACH
619011080	DELINEATOR DES H	170.000	EACH
619011205	DELINEATION-LINEAR-BARRIER-YELLOW	846.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Butte District Administrator.
 Uniform No. 9428000, 9427000, 9381000, 9429000

105 SF 169 N11 MURPHY INTX HSIP-G 11-1(92)31 CONTRACT NO. 02319

Upgraded warning signs with actuated flashing beacons on the SF 169 N11 Murphy Intersection project in Park County. The project is located in Emigrant at the intersection with US 89/N-11 (RP 31.0) and the Murphy Lane and Story Road approaches

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - FLASHING BEACONS, WARNING SIGNS			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
616343920	CONDUIT-PLASTIC 2 IN	1,635.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	300.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	7.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	1.000	EACH
617000000	FOUNDATION-CONCRETE	6.000	CUYD
617033214	CABLE-COPPER 3AWG14-600V	2,320.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	455.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	1,510.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	2.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	2.000	EACH
617333150	SERV ASSEMB-50 AMP	1.000	EACH
617483110	SIG-TRAF 1 COL-1 WAY 12	10.000	EACH
617673200	SIG STANDARD TYPE 1-200	10.000	EACH
617763101	DETECTOR LOOP	5.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	2.000	EACH
617903100	CONTROL UNIT	1.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010086	SIGNS-ALUM REFL SHEET IV	5.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	112.000	SQFT
619010230	REMOVE SIGN	1.000	EACH
619010300	POSTS-TUBULAR STEEL	111.000	LB
619010480	POLES-TREATED WOOD 4 IN	12.000	LNFT
619010742	FRANG SIGN POST BKWY-3.5 IN RD (89MM)	1.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Butte District Administrator.
 Uniform No. 9382000

106 SF - 169 MT200 SFTY IMPRV HSIP 57-5(52)230 CONTRACT NO. 05319

Signing and delineation on the SF-169 MT200 Safety Improvement project in Garfield and McCone Counties. The project is on MT 200/N-57, approximately 17 miles east of Jordan, beginning at RP 230.2 and proceeding east to the intersection with S-253 (RP 267.5).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SIGNING & DELINEATION			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010058	SIGNS-ALUM SHEET INCR IV	427.500	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	256.900	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	801.400	SQFT
619010230	REMOVE SIGN	141.000	EACH
619010240	REMOVE SIGN-GUIDE	15.000	EACH
619010310	POSTS-STEEL U SIGN	814.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	727.000	LB
619010480	POLES-TREATED WOOD 4 IN	536.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	264.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7 (S100X11)	8.000	EACH
619010800	PANEL DELINEATOR DESIGN A	198.000	EACH
619011010	DELINEATOR DES A	872.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Glendive District Administrator.
 Uniform No. 9189000

INVITATION FOR BIDS
LETTING OF March 28, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on March 28, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

201 27TH ST-1ST AVE S TO AIRPORT NHIP-CMDP 53-1(30)0 CONTRACT NO. 01319

Digout excavation, cold milling, plant mix overlay, sidewalk, curb and gutter, storm drain, signing, lighting, signals, fiber optic cable and other improvements on the 27th St-1st Ave S to Airport project.

The project is located on National Highway Route 53/27th Street beginning at RP 0.0 (I-90 Interchange) and proceeds 3.2 miles to RP 2+1.205 to Airport Road. The project is located within the urban limits of Billings in Yellowstone County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - DIGOUTS, COLD MILL, PMS OVERLAY, STORM DRAIN, ADA UPGRADES			
103000000	TRAINING PROGRAM	500.000	HR
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	100,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	2,240.000	CUYD
203020200	EXCAVATION-UNCLASS BORROW	456.000	CUYD
203020278	EXCAVATION-DIGOUTS	3,208.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	380.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	2,767.000	CUYD
301020348	DRAIN AGGREGATE	22.000	CUYD
301020526	TOP SURFACING GR 3B	26.000	CUYD
301020625	AGGREGATE TREATMENT	4,691.000	SQYD
401020065	PLANT MIX SURF GR S-3/8 IN	18,102.000	TON
401020300	HYDRATED LIME	256.100	TON
402020095	ASPHALT CEMENT PG 70-28	1,125.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	6,529.000	GAL
411010000	COLD MILLING	120,402.000	SQYD
557010105	PEDESTRIAN RAIL	218.500	LNFT
563000100	PREPARE DECK	340.000	SQYD
563000110	WATERPROOF MEMBRANE	340.000	SQYD
603000050	GRANULAR BEDDING MATERIAL	149.000	CUYD
603010025	PLUG ENDS AND ABANDON PIPE	1.000	EACH
603010500	CAP-CONCRETE 7 IN	1.000	EACH
603010510	STEEL PLATE ORIFICE	1.000	EACH
603012820	RCP IRR 15 IN	749.400	LNFT
603012892	RCP IRR 24 IN	68.300	LNFT
603013462	PIPE-PVC 6 IN	56.500	LNFT
603013519	RISER PIPE-PVC PERF 24 IN	5.600	LNFT
603014242	ADJUST VALVE BOX	104.000	EACH
604000100	ADJUST MANHOLE	60.000	EACH
604000140	REMOVE DROP INLET	1.000	EACH
604010045	MANHOLE-48 IN TYPE 3	3.000	EACH
604010184	CONCRETE APRON	4.000	EACH
604010220	INLET DROP-SPECIAL DESIGN	1.000	EACH
604010240	INLET CURB-TYPE 2	6.000	EACH
604010265	INLET FRAME AND GRATE-REPLACE	44.000	EACH
604010532	COMB 48 IN T3 MH-T2 CURB INL	5.000	EACH
606010385	REMOVE GUARDRAIL	115.500	LNFT
607000030	FENCE-CHAIN LINK 4 FT	50.000	LNFT
608010011	SIDEWALK-CONCRETE-HEATED	37.700	SQYD
608010020	SIDEWALK-CONCRETE 4 IN	6,527.300	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	1,660.900	SQYD
608010090	CONCRETE 3 IN	1,296.200	SQYD
608010112	DECORATIVE CONCRETE	93.500	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	205.700	SQYD
609010200	CURB AND GUTTER-CONC	7,449.800	LNFT
610100101	SEEDING AREA NO 1	0.400	ACRE
610100326	FERTILIZING AREA NO 1	0.400	ACRE
610100470	SODDING	104.600	SQYD
610100555	CONDITION SEEDBED SURFACE	0.400	ACRE
610220100	MULCH	0.400	ACRE
613100030	RIPRAP-CLASS 1 RANDOM	163.000	CUYD
614010009	RETAINING WALL	8.000	SQYD

616343914	CONDUIT-PLASTIC 1 1/2 IN	30,400.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	8,650.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	2,800.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	67.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	59.000	EACH
616783009	PULL BOX-COMPOSITE TYPE 4	13.000	EACH
617000000	FOUNDATION-CONCRETE	247.000	CUYD
617033212	CABLE-COPPER 3AWG12-600V	6,800.000	LNFT
617033414	CABLE-COPPER 7AWG14-600V	12,000.000	LNFT
617033614	CABLE-COPPER 12AWG14-600V	3,450.000	LNFT
617033814	CABLE-COPPER 16AWG14-600V	2,750.000	LNFT
617086919	CABLE-COPPER 6 PAIR AWG 19 COM	1,250.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	15,500.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	93,850.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	47,350.000	LNFT
617123112	CONDUCTOR-COPPER AWG12-600V	14,000.000	LNFT
617123181	CONDUCTOR-COPPER 1/0 AWG-600 V	2,050.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	162.000	EACH
617233020	CONTROLLER-CAB PEDESTAL TYPE M	1.000	EACH
617233030	CONTROLLER-CAB PEDESTAL TYPE P	11.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	182.000	EACH
617333198	SERV ASSEMBLY-200 AMP	9.000	EACH
617483110	SIG-TRAF 1 COL-1 WAY 12	6.000	EACH
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	131.000	EACH
617513125	SIG TRAF 4 COL 1 W 12-12-12-12	5.000	EACH
617523127	SIG-TRAF 5 COL-1 W 12-12-12-12	4.000	EACH
617553020	SIG-PEDESTRIAN TYPE 2	86.000	EACH
617605081	CONTLR/TRAF-ACTUAT TYPE 8-A	11.000	EACH
617623270	BATTERY BACKUP SYSTEM	2.000	EACH
617673080	SIG STANDARD TYPE 1-80	42.000	EACH
617673100	SIG STANDARD TYPE 1-100	23.000	EACH
617673140	SIG STANDARD TYPE 1-140	1.000	EACH
617693503	SIG STANDARD TYPE 2-A-500-3	5.000	EACH
617693905	SIG STANDARD TYPE 2-A-900-5	3.000	EACH
617693906	SIG STANDARD TYPE 2-A-900-6	6.000	EACH
617693907	SIG STANDARD TYPE 2-A-900-7	2.000	EACH
617693908	SIG STANDARD TYPE 2-A-900-8	1.000	EACH
617713052	SIG STANDARD TYPE 3-A-500-2	1.000	EACH
617713053	SIG STANDARD TYPE 3-A-500-3	2.000	EACH
617713054	SIG STANDARD TYPE 3-A-500-4	3.000	EACH
617713095	SIG STANDARD TYPE 3-A-900-5	2.000	EACH
617713096	SIG STANDARD TYPE 3-A-900-6	7.000	EACH
617713097	SIG STANDARD TYPE 3-A-900-7	3.000	EACH
617713098	SIG STANDARD TYPE 3-A-900-8	4.000	EACH
617763410	RADAR VEHICLE DETECTION	38.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903100	CONTROL UNIT	1.000	EACH
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	86.000	EACH
617903703	INNERDUCT SDR 13.5-3/4 IN	26,300.000	LNFT
617903706	INNERDUCT SDR 13.5-1 1/2 IN	1,700.000	LNFT
617903752	12 SM FIBER OPTIC CABLE (12 COUNT)	17,700.000	LNFT
617903801	FIBER OPTIC CABLE TESTING	1.000	LS
617903805	FIBER TERM/FUSION SPLICE/PATCH CORDS	100.000	EACH
617903810	FIBER CABLE TERM ENCLOSURES	10.000	EACH
617903820	SIG CABINET INTERFACE SWITCH-FIBER	11.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	500,000.000	UNIT
618100008	TRAFFIC ACTUATED TEMPORARY SIGNALS	1.000	LS
619010058	SIGNS-ALUM SHEET INCR IV	98.300	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	60.900	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	627.800	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1,472.700	SQFT
619010200	RESET SIGNS	8.000	EACH
619010230	REMOVE SIGN	287.000	EACH
619010240	REMOVE SIGN-GUIDE	7.000	EACH
619010300	POSTS-TUBULAR STEEL	257.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	412.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	7,292.000	LB
619010500	POLES-TREATED WOOD 6 IN	16.000	LNFT
619010521	OVERHEAD STR/METAL-CANTILEVER	3.000	EACH
619010526	REMOVE OVERHEAD STR/METAL-CANTILEVER	6.000	EACH
619010720	FRANG SIGN POST BKWY - S3 X 5.7 (S75X8)	4.000	EACH

619010740	FRANG SIGN POST BKWY-3 IN RD (76 MM)	3.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	18.000	EACH
619011179	DELINEATOR-FLEX SURF MTD WH	9.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	21.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	156.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	88.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	117.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	16.000	GAL
620012950	TEMPORARY STRIPING	6.200	MILE
620013000	STRIPING-WHITE PAINT	227.000	GAL
620013960	STRIPING-WHITE EPOXY	302.000	GAL
620014000	STRIPING-YELLOW PAINT	93.000	GAL
620014960	STRIPING-YELLOW EPOXY	124.000	GAL
622010075	GEOGRID - BIAXIAL	4,431.000	SQYD
622011043	PERM EROSION CONTROL-HIGH SURV	419.000	SQYD
622011084	GEOTEXTILE STABILIZATION	4,735.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 7910000

202 JCT MT 217 - SOUTH STPS 343-1(8)22 CONTRACT NO. 14319

Grade, gravel, new asphalt surfacing, drainage, seal and cover, pavement markings, and new signing on the JCT MT 217 - South project located in Toole County. The project is located on Secondary 343, known as the Galata Road, approximately 19 miles north of Galata. The project begins at the intersection with Green Hill School Road, at reference post 32.9, proceeds north and then turns west for a total distance of 10.6 miles, ending at RP 22.2, just west of the intersection with Secondary 217 (Strawberry Road).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - Roadway - grade, gravel, pms			
103000000	TRAINING PROGRAM	500.000	HOURL
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
107000060	NOXIOUS WEED CONTROL	7,350.000	UNIT
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	103,465.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	50,510.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	36,535.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	250.000	MILE
301020340	CRUSHED AGGREGATE COURSE	89,735.000	CUYD
301020450	SPECIAL BACKFILL	480.000	CUYD
301020526	TOP SURFACING GR 3B	518.000	CUYD
301020625	AGGREGATE TREATMENT	196,328.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	35,173.000	TON
401020300	HYDRATED LIME	492.000	TON
402020092	ASPHALT CEMENT PG 64-28	1,895.200	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	19,243.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	300.300	TON
409000000	FINAL SWEEP AND BROOM	10.600	CRMI
409000010	COVER-TYPE 1	166,879.000	SQYD
411010000	COLD MILLING	340.000	SQYD
551020126	CONTROLLED LOW STRENGTH MATL	92.000	CUYD
603010040	DRAINAGE PIPE 18 IN	1,500.000	LNFT
603010048	DRAINAGE PIPE 24 IN	1,058.000	LNFT
603010064	DRAINAGE PIPE 42 IN	140.000	LNFT
603010066	DRAINAGE PIPE 36 IN	262.000	LNFT
603010540	CSP 24 IN	24.000	LNFT

603013210	RCPA 29 IN	124.000	LNFT
603013462	PIPE-PVC 6 IN	112.000	LNFT
603587020	REMOVE PIPE CULVERT	2,272.100	LNFT
607100229	FARM FENCE-TYPE F4W	5,677.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	25.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	1.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	76.000	LNFT
607100551	FENCE-TEMPORARY	2,692.000	LNFT
607100720	DEADMAN	5.000	EACH
610100101	SEEDING AREA NO 1	107.100	ACRE
610100103	SEEDING AREA NO 3	39.700	ACRE
610100326	FERTILIZING AREA NO 1	107.100	ACRE
610100555	CONDITION SEEDBED SURFACE	146.800	ACRE
610100565	EROSION CONTROL BLANKET-HIGH-PERFORM	601.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	325,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	29.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	125.800	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	151.500	SQFT
619010230	REMOVE SIGN	25.000	EACH
619010240	REMOVE SIGN-GUIDE	1.000	EACH
619010310	POSTS-STEEL U SIGN	200.000	LB
619010480	POLES-TREATED WOOD 4 IN	394.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	32.000	LNFT
619011010	DELINEATOR DES A	288.000	EACH
619011040	DELINEATOR DES D	20.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	4.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	3.000	GAL
620012950	TEMPORARY STRIPING	21.200	MILE
620013000	STRIPING-WHITE PAINT	763.000	GAL
620013960	STRIPING-WHITE EPOXY	509.000	GAL
620014000	STRIPING-YELLOW PAINT	97.000	GAL
620014960	STRIPING-YELLOW EPOXY	64.000	GAL
622011084	GEOTEXTILE STABILIZATION	231,463.000	SQYD
623000155	MAILBOX	1.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
 Uniform No. 6165000

203 HYSHAM INTERCHANGE - EAST IM 94-2(38)67 CONTRACT NO. 17319

Cold milling, PMS overlay, multi-plate stockpass, fencing, curb, cattle guards, bridge deck repair, seal & cover and pavement markings on the Hysham Interchange - East project located in Treasure County. The project begins at RP 67.0 and extends northeast and east approximately 11.3 miles along Interstate Route 94 to RP 78.3.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, FILL, OVERLAY, BRIDGE REPAIR			
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
104030065	MISCELLANEOUS ITEMS-LNFT	162.000	LNFT
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	409.700	LNFT
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020000	GRADER-MOTOR	26.000	HOURL
210020170	TEST TRAILER-TRANSPORT, SETUP	166.000	MILE
301020340	CRUSHED AGGREGATE COURSE	195.000	CUYD
301020416	SHOULDER GRAVEL	2,246.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	23,998.000	TON
401020300	HYDRATED LIME	336.000	TON
402020095	ASPHALT CEMENT PG 70-28	1,298.800	TON

402020315	EMULSIFIED ASPHALT-TACK COAT	8,727.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	964.800	TON
409000000	FINAL SWEEP AND BROOM	24.100	CRMI
409000010	COVER-TYPE 1	542,657.000	SQYD
411010000	COLD MILLING	169,085.000	SQYD
551020120	CEMENT GROUT	295.000	CUYD
552010140	TRANSVERSE DECK GROOVING	1,488.800	SQYD
561020110	BRIDGE DECK MILLING	1,553.200	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	236.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	2.000	SQYD
563000000	CONCRETE-CLASS OVERLAY	102.900	CUYD
563000040	POLYMER OVERLAY	2,432.400	SQYD
563000100	PREPARE DECK	2,432.400	SQYD
603016085	CULVERT-LINER CONCRETE	162.000	LNFT
605000040	REVISE CONCRETE BARRIER RAIL-BR	1,853.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	31.000	EACH
606010330	MGS GUARDRAIL	19,412.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	31.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	15.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	18.000	EACH
606010385	REMOVE GUARDRAIL	21,750.000	LNFT
607100152	FARM FENCE-TYPE F3M-32 IN WW	1,131.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	20.000	EACH
609010112	CURB 4 IN-CONCRETE	1,830.000	LNFT
610100557	REVEGETATION	5.200	ACRE
611010030	CATTLE GUARD 30 FT-HEAVY DUTY (9.0 M)	4.000	EACH
611010210	REMOVE AND SALVAGE CATTLE GUARD	4.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
618100000	SINGLE USE SIGNS	268.000	SQFT
618190100	TEMPORARY BARRIER RAIL	2,150.000	LNFT
618190110	RESET TEMP BARRIER RAIL	2,150.000	LNFT
619010058	SIGNS-ALUM SHEET INCR IV	1,650.000	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	88.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	254.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	690.800	SQFT
619010230	REMOVE SIGN	96.000	EACH
619010240	REMOVE SIGN-GUIDE	32.000	EACH
619010300	POSTS-TUBULAR STEEL	451.000	LB
619010310	POSTS-STEEL U SIGN	594.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,518.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	727.000	LB
619010480	POLES-TREATED WOOD 4 IN	62.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	72.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7 (S100X11)	6.000	EACH
619010724	FRANG SIGN POST BKWY-S5 X 10 (S130X15)	2.000	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD (100 MM)	3.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	8.000	EACH
619011010	DELINEATOR DES A	319.000	EACH
619011020	DELINEATOR DES B	35.000	EACH
619011070	DELINEATOR DES G	74.000	EACH
619011080	DELINEATOR DES H	42.000	EACH
619011085	DELINEATOR DES BJ	39.000	EACH
619011087	DELINEATOR DES GJ	61.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	15.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	10.000	GAL
620012950	TEMPORARY STRIPING	22.900	MILE
620013000	STRIPING-WHITE PAINT	1,210.000	GAL
620013960	STRIPING-WHITE EPOXY	807.000	GAL
620014000	STRIPING-YELLOW PAINT	899.000	GAL
620014960	STRIPING-YELLOW EPOXY	600.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
 Uniform No. 9411000

204 **ROBERTS** **MT 28-2(36)81** **CONTRACT NO. 12319**

Grade, gravel, PMS, drainage, fencing, signing and electrical on the Roberts project in Carbon County. The project is on US 212/P-28 within the community of Roberts, beginning at RP 81.3 and proceeding north to RP 82.9.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRVL, PMS, DRAINAGE			
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	44,183.000	CUYD
617033314	CABLE-COPPER 5AWG14-600V	465.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	465.000	LNFT
617333120	SERV ASSEMB-20 AMP	2.000	EACH
617483110	SIG-TRAF 1 COL-1 WAY 12	2.000	EACH
617673200	SIG STANDARD TYPE 1-200	2.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903463	VARIABLE MESSAGE SIGN	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	6.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	87.800	SQFT
203020310	SPECIAL BORROW-NEAT LINE	6,240.000	CUYD
619010086	SIGNS-ALUM REFL SHEET IV	38.200	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	346.900	SQFT
619010200	RESET SIGNS	1.000	EACH
619010230	REMOVE SIGN	34.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010310	POSTS-STEEL U SIGN	80.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	620.000	LB
619010480	POLES-TREATED WOOD 4 IN	410.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	200.000	LNFT
619010724	FRANG SIGN POST BKWY-S5 X 10 (S130X15)	4.000	EACH
203080100	TOPSOIL-SALVAGING AND PLACING	9,418.000	CUYD
619011010	DELINEATOR DES A	50.000	EACH
619011030	DELINEATOR DES C	14.000	EACH
619011040	DELINEATOR DES D	22.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	19.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	10.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	13.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	6.000	GAL
620012950	TEMPORARY STRIPING	3.000	MILE
620013000	STRIPING-WHITE PAINT	138.000	GAL
620013960	STRIPING-WHITE EPOXY	92.000	GAL
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
620014000	STRIPING-YELLOW PAINT	125.000	GAL
620014960	STRIPING-YELLOW EPOXY	83.000	GAL
622011022	SUBSURFACE DRAIN FILTER-HIGH SURV	415.000	SQYD
622011043	PERM EROSION CONTROL-HIGH SURV	945.000	SQYD
622011084	GEOTEXTILE STABILIZATION	7,395.000	SQYD
622011144	GEOMEMBRANE-LIQ/VAPBARRIER HVY	255.000	SQYD
623000155	MAILBOX	11.000	EACH
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	90.000	MILE
212000000	OBLITERATE ROADWAY	3.000	STA
301020268	TRAFFIC GRAVEL	1,869.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	25,724.000	CUYD
301020450	SPECIAL BACKFILL	928.000	CUYD
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
301020625	AGGREGATE TREATMENT	56,688.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	11,417.000	TON
401020300	HYDRATED LIME	160.000	TON
402020092	ASPHALT CEMENT PG 64-28	616.700	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5,886.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	89.200	TON
409000000	FINAL SWEEP AND BROOM	2.600	CRMI
409000020	COVER-TYPE 2	50,151.000	SQYD
411010000	COLD MILLING	1,040.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	1.100	MILE
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS

411011135	RUMBLE STRIPS	2.200	MILE
551020030	CONCRETE-CLASS GENERAL	26.100	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	396.800	CUYD
601010775	WATER SERVICE	2.000	EACH
601011920	INSULATION	16,672.000	SQFT
601012301	RELOCATE WATER METER	6.000	EACH
603000050	GRANULAR BEDDING MATERIAL	141.000	CUYD
603000060	FOUNDATION MATERIAL	242.000	CUYD
603000078	ADJUST CURB BOX	2.000	EACH
603010040	DRAINAGE PIPE 18 IN	1,278.000	LNFT
104030030	MISCELLANEOUS ITEMS-INSTALL	412.000	LNFT
603010048	DRAINAGE PIPE 24 IN	1,492.000	LNFT
603012521	RCP 15 IN	34.000	LNFT
603012530	RCP 18 IN	338.000	LNFT
603012555	RCP 24 IN	510.000	LNFT
603012847	RCP IRR 18 IN	124.000	LNFT
603012892	RCP IRR 24 IN	430.000	LNFT
603012925	RCP IRR 30 IN	86.000	LNFT
603013042	STEEL CASING 16 IN	356.000	LF
603013053	RCP SIPHON 24 IN	82.000	LNFT
603013220	RCPA 44 IN	384.000	LNFT
105080115	FINISH GRADE CONTROL	22,100.000	CRFT
603013394	REIN CONC BOX 14 X 4	114.000	LNFT
603013469	PIPE-PVC PRESS 10 IN WATER	56.400	LNFT
603013490	PIPE-CORR POLYETHYLENE DR 4 IN	360.000	LNFT
603013525	PIPE-PVC CONDUIT 2 IN	94.000	LNFT
603013549	CONNECT TO EXISTING PIPE	2.000	EACH
603013828	DUCTILE IRON FITTINGS	760.000	LB
603014242	ADJUST VALVE BOX	6.000	EACH
603014369	PIPE PLUG	2.000	EACH
603424060	REIN CONC BOX 9 X 4	78.000	LNFT
603587020	REMOVE PIPE CULVERT	2,821.500	LNFT
107000020	CONTAMINATED SOIL	50,000.000	UNIT
604000100	ADJUST MANHOLE	2.000	EACH
604000190	RESET CURB STOP AND BOX	3.000	EACH
604000200	RESET FIRE HYDRANT	1.000	EACH
604000250	ADJUST FIRE HYDRANT	1.000	EACH
606010330	MGS GUARDRAIL	737.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	2.000	EACH
606010338	MGS LONGSPAN GUARDRAIL	62.500	LNFT
607000006	PANEL-SINGLE CHAIN LINK	11.000	EACH
607000008	PANEL-DOUBLE CHAIN LINK	6.000	EACH
607000009	FENCE-CHAIN LINK 5 FT	251.000	LNFT
107000060	NOXIOUS WEED CONTROL	1,150.000	UNIT
607000013	FENCE-CHAIN LINK 3 FT	97.000	LNFT
607000260	GATE-CHAIN LINK	24.000	LNFT
607100008	FENCE-SPECIAL DESIGN	1,830.000	LNFT
607100148	FARM FENCE-TYPE F2M-39 IN WW	4,451.000	LNFT
607100219	FARM FENCE-TYPE F3M	1,887.000	LNFT
607100252	FARM FENCE-TYPE F4M	1,057.000	LNFT
607100281	FARM FENCE-TYPE F5M	8,359.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	128.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	25.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	260.000	LNFT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
607100440	FARM GATE-METAL-TYPE G-3	152.000	LNFT
607100720	DEADMAN	11.000	EACH
607150015	REMOVE FENCE	645.000	LNFT
607150131	RESET GATE	1.000	EACH
610100101	SEEDING AREA NO 1	16.700	ACRE
610100102	SEEDING AREA NO 2	0.300	ACRE
610100103	SEEDING AREA NO 3	7.000	ACRE
610100326	FERTILIZING AREA NO 1	16.700	ACRE
610100555	CONDITION SEEDBED SURFACE	23.700	ACRE
610100560	RIPRAP REVEGETATION	995.000	SQYD
109200005	MOBILIZATION	1.000	LS
610100561	EROSION CONTROL BLANKET-LONG-TERM	11,129.000	SQYD
610220050	MULCH-COMPOST	0.300	ACRE
613100030	RIPRAP-CLASS 1 RANDOM	39.100	CUYD
613100040	RIPRAP-CLASS 2 RANDOM	739.800	CUYD
615010063	IRRIGATION CLEANOUT	1.000	EACH

615010580	TRASH GUARD	2.000	EACH
615010730	IRRIGATION DITCH	483.000	LNFT
616343914	CONDUIT-PLASTIC 1 1/2 IN	465.000	LNFT
616783001	PULL BOX-CONCRETE TYPE 1	4.000	EACH
617000000	FOUNDATION-CONCRETE	1.000	CUYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 4375003

205 BOX ELDER CREEK BRIDGE (MT-13) STPP-STPB 32-1(25)20 CONTRACT NO. 16319

Grading, gravel, pms overlay, pavement markings, drainage, fencing and a 108 ft long prestressed concrete beam structure on the Box Elder Creek Bridge (MT-13) project in the Fort Peck Indian Reservation and Roosevelt County.

The project is 23 miles northeast of Wolf Point on State Route 13 between RP 20.0 to 20.6.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRAVEL. PMS OVERLAY			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
105080115	FINISH GRADE CONTROL	6,052.000	CRFT
105080200	BRIDGE SURVEY	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020040	REMOVE STRUCTURE	1.000	EACH
203020310	SPECIAL BORROW-NEAT LINE	10,530.000	CUYD
203020375	EMBANKMENT IN PLACE	34,566.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	3,525.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	100.000	MILE
301020254	BRIDGE END BACKFILL-TYPE 3	615.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	9,190.000	CUYD
301020625	AGGREGATE TREATMENT	11,600.000	SQYD
401020022	COMMERCIAL MIX-PG 64-28	2,265.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,243.000	GAL
551020035	CONCRETE-CLASS STRUCTURE	66.200	CUYD
551020107	CONCRETE-CLASS DECK	134.200	CUYD
552010140	TRANSVERSE DECK GROOVING	410.000	SQYD
553010155	PRESTRESSED BEAM-TYPE MTS-54	432.000	LNFT
555010100	REINFORCING STEEL	5,672.000	LB
555010200	REINFORCING STEEL-EPOXY COATED	28,642.000	LB
557010011	BRIDGE RAIL-W740	222.700	LNFT
559040035	DYNAMIC LOAD TEST	2.000	EACH
559050103	FURN STEEL PIPE PILE 16 X 1/2 IN	332.000	LNFT
559060103	DRIVE STEEL PIPE PILE 16 X 1/2	320.000	LNFT
559060200	PILE CUTTING SHOE	8.000	EACH
603010040	DRAINAGE PIPE 18 IN	94.000	LNFT
603010048	DRAINAGE PIPE 24 IN	230.000	LNFT
603010056	DRAINAGE PIPE 30 IN	130.000	LNFT
603587020	REMOVE PIPE CULVERT	163.400	LNFT
606010265	GRD RL-BOX BEAM/BR APP-SEC TYPE 1	4.000	EACH
606010385	REMOVE GUARDRAIL	429.600	LNFT
606010641	GD RL BOX BEAM OPT TERM SEC	2.000	EACH
606010670	BOX BEAM DEPART TERM SEC	2.000	EACH
607100229	FARM FENCE-TYPE F4W	2,745.000	LNFT
607100252	FARM FENCE-TYPE F4M	5,415.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	5.000	EACH
607100362	FARM FENCE-PANEL/SINGLE FM	10.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	8.000	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	15.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	16.000	LNFT
609010112	CURB 4 IN-CONCRETE	316.000	LNFT

610100101	SEEDING AREA NO 1	5.400	ACRE
610100102	SEEDING AREA NO 2	0.100	ACRE
610100103	SEEDING AREA NO 3	1.200	ACRE
610100326	FERTILIZING AREA NO 1	5.400	ACRE
610100327	FERTILIZING AREA NO 2	0.100	ACRE
610100555	CONDITION SEEDBED SURFACE	6.600	ACRE
610100560	RIPRAP REVEGETATION	365.000	SQYD
611010300	RESET CATTLE GUARD	1.000	EACH
613100040	RIPRAP-CLASS 2 RANDOM	711.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010230	REMOVE SIGN	8.000	EACH
619011010	DELINEATOR DES A	22.000	EACH
620013960	STRIPING-WHITE EPOXY	29.000	GAL
620014960	STRIPING-YELLOW EPOXY	8.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	1,276.000	SQYD
622011084	GEOTEXTILE STABILIZATION	16,218.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	19,500.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 7954001

206 EXCELSIOR AVE/PARK ST-BUTTE STPU-TA 1899(31) CONTRACT NO. 03319

Mill, fill, digouts, select reconstruction, ADA enhancements, select sidewalk, curb and gutter, and traffic signal replacement or removal, removal and updating of all overhead lighting on W. Park Street, and signing and pavement markings on the Excelsior Ave/Park St-Butte project located in Silver Bow County. The project is located in Butte on West Park Street (U-1804) and on Excelsior Avenue (U-1801). The project limits on W. Park Street are from Western Avenue near the entrance of Montana Tech (Reference Post (RP) 0.77±) to the west side of Montana Street (RP 0.0). The Excelsior Avenue project limits are from Platinum Street (RP 0.48±) to Caledonia Street (RP 1.11±).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - DIGOUT EXC, COLD MILLING, PMS OVERLAY, C & G, SIDEWALK, ELECTRICAL			
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
105070410	PROPERTY SURVEY	1.000	LS
107000020	CONTAMINATED SOIL	5,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020278	EXCAVATION-DIGOUTS	854.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	8.000	MILE
301020340	CRUSHED AGGREGATE COURSE	780.000	CUYD
301020625	AGGREGATE TREATMENT	1,557.000	SQYD
401020055	COMMERCIAL MIX-3/8 IN-PG 64-28	3,950.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,988.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	879.000	GAL
411010000	COLD MILLING	31,869.000	SQYD
551020030	CONCRETE-CLASS GENERAL	16.000	CUYD
603000078	ADJUST CURB BOX	75.000	EACH
603014242	ADJUST VALVE BOX	84.000	EACH
604000100	ADJUST MANHOLE	44.000	EACH
604010184	CONCRETE APRON	51.000	EACH
604010220	INLET DROP-SPECIAL DESIGN	2.000	EACH
604010615	MODIFY DROP INLETS	2.000	EACH
606400120	BOLLARDS	4.000	EACH
606400140	REMOVE BOLLARD	11.000	EACH

608010020	SIDEWALK-CONCRETE 4 IN	4,635.700	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	1,049.800	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	171.700	SQYD
609010200	CURB AND GUTTER-CONC	6,029.700	LNFT
616343914	CONDUIT-PLASTIC 1 1/2 IN	5,700.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	950.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	240.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	15.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	2.000	EACH
617000000	FOUNDATION-CONCRETE	25.000	CUYD
617033414	CABLE-COPPER 7AWG14-600V	250.000	LNFT
617033614	CABLE-COPPER 12AWG14-600V	450.000	LNFT
617033814	CABLE-COPPER 16AWG14-600V	250.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	650.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	21,050.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	4,500.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	19.000	EACH
617233030	CONTROLLER-CAB PEDESTAL TYPE P	1.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	21.000	EACH
617333198	SERV ASSEMBLY-200 AMP	3.000	EACH
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	10.000	EACH
617553020	SIG-PEDESTRIAN TYPE 2	8.000	EACH
617573070	RECTANGULAR RAPID FLASHING BEACON	2.000	EACH
617605081	CONTLR/TRAF-ACTUAT TYPE 8-A	1.000	EACH
617673200	SIG STANDARD TYPE 1-200	3.000	EACH
617693502	SIG STANDARD TYPE 2-A-500-2	2.000	EACH
617715054	SIG STANDARD TYPE 3-A-500-4	1.000	EACH
617715096	SIG STANDARD TYPE 3-A-900-6	1.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	4.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903250	PUSH BUTTON/PEDESTRIAN	4.000	EACH
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	8.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
619010086	SIGNS-ALUM REFL SHEET IV	369.200	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	733.200	SQFT
619010200	RESET SIGNS	9.000	EACH
619010230	REMOVE SIGN	99.000	EACH
619010300	POSTS-TUBULAR STEEL	349.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	6,134.000	LB
619010740	FRANG SIGN POST BKWY-3 IN RD (76 MM)	1.000	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD (89MM)	1.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	7.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	53.000	GAL
620010310	CURB MARKING-BLUE PAINT	1.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	33.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	42.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	2.000	GAL
620012950	TEMPORARY STRIPING	2.690	MILE
620013000	STRIPING-WHITE PAINT	71.000	GAL
620013955	REMOVE PAVEMENT MARKINGS	7,269.000	LNFT
620013960	STRIPING-WHITE EPOXY	95.000	GAL
620014000	STRIPING-YELLOW PAINT	32.000	GAL
620014960	STRIPING-YELLOW EPOXY	43.000	GAL
622011084	GEOTEXTILE STABILIZATION	1,534.000	SQYD
SECTION NO. 0002 - ADDITIVE ALTERNATE AA1 - COLD MILLING, DIGOUTS, PMS OVERLAY			
203020278	EXCAVATION-DIGOUTS	15.000	CUYD
401020055	COMMERCIAL MIX-3/8 IN-PG 64-28	341.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	177.000	GAL
411010000	COLD MILLING	3,536.000	SQYD
603014242	ADJUST VALVE BOX	5.000	EACH
604000100	ADJUST MANHOLE	1.000	EACH
SECTION NO. 0003 - ADDITIVE ALTERNATE AA2 - COLD MILLING, PMS OVERLAY			
401020055	COMMERCIAL MIX-3/8 IN-PG 64-28	611.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	296.000	GAL
411010000	COLD MILLING	5,262.000	SQYD
603014242	ADJUST VALVE BOX	3.000	EACH
604000100	ADJUST MANHOLE	2.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Butte District Administrator.
 Uniform No. 8678000

207 SF 129-SKD TRTMT E MISSOULA HSIP 90-2(143)109 CONTRACT NO. 10319

Bridge deck improvements including Class A Bridge Deck Repair, expansion joint replacement, guard angle removal, thin polymer overlay and signing on the SF 129 - Skid Treatment East Missoula in Missoula County.
 The project is located on Interstate 90 over the Clark Fork River at RP 109.4 (East and Westbound), approximately 1 mile west of the Bonner/MT 200 Interchange.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE DECK TREATMENT, DECK REPAIR, OVERLAY, JOINT			
104030010	MISCELLANEOUS WORK	2,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	383.400	LNFT
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
552010041	REVISE JOINT	135.100	LNFT
552011010	EXPANSION JOINT STRIP SEAL	135.100	LNFT
552011120	JOINT SEALS-POLYURETHANE	131.800	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	37.400	SQYD
563000040	POLYMER OVERLAY	3,090.500	SQYD
563000100	PREPARE DECK	3,090.500	SQYD
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	50,000.000	UNIT
618190100	TEMPORARY BARRIER RAIL	950.000	LNFT
618190110	RESET TEMP BARRIER RAIL	950.000	LNFT
619010090	SIGNS-ALUM REFL SHEET XI	32.000	SQFT
619010230	REMOVE SIGN	2.000	EACH
620012950	TEMPORARY STRIPING	0.200	MILE
620013960	STRIPING-WHITE EPOXY	4.000	GAL
620014960	STRIPING-YELLOW EPOXY	5.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Missoula District Administrator.
 Uniform No. 8061000

208 COLLINS RD INTCH - BRIDGE REPAIR AR 11969 CONTRACT NO. 09319

The Collins Road Interchange-Bridge Repair project consists of removal, disposal and replacement of a damaged north exterior beam and repair of the 4th interior beam and other necessary work on the Collins Road overpass structure. The overpass structure crosses National Highway Interstate Route I-15 at RP 332.1 approximately 40 miles north of Great Falls in Teton County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE REPAIR			
104030010	MISCELLANEOUS WORK	22,000.000	UNIT
104030025	MISCELLANEOUS ITEMS-INSTALL	1.000	EACH
105080200	BRIDGE SURVEY	1.000	LS

109200005	MOBILIZATION	1.000	LS
551020107	CONCRETE-CLASS DECK	30.500	CUYD
552010040	REVISE STRUCTURE	1.000	LS
552010060	REPAIR STRUCTURE	1.000	LS
553010090	PRESTRESSED BEAM-TYPE 4	105.000	LNFT
555010100	REINFORCING STEEL	6,232.000	LB
606010370	RESET GUARDRAIL	110.500	LNFT
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
618190100	TEMPORARY BARRIER RAIL	296.000	LNFT

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9663000

209 7TH AVE NW SIDEWALKS - CHOTEAU TA 50(29) CONTRACT NO. 15319

Sidewalks, curb and gutter and ADA curb ramps on the 7th Avenue Northwest Sidewalks - Choteau project in Teton County. The project is in Choteau on the west side of 7th Avenue NW (L50-657) from the High School at 2nd Street NW (RP 0.19) to 7th Street NW (RP 0.59).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SIDEWALK, C & G AND ADA CURB RAMPS			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020526	TOP SURFACING GR 3B	54.000	CUYD
551020050	CONCRETE-CLASS PAVE	165.700	CUYD
608010020	SIDEWALK-CONCRETE 4 IN	1,052.700	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	195.700	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	10.800	SQYD
609010200	CURB AND GUTTER-CONC	397.400	LNFT
610100559	REVEGETATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
620010301	CURB MARKING-YELLOW EPOXY	1.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9438000

210 GERALDINE - NORTH STPP 80-1(31)24 CONTRACT NO. 13319

Scrub seal, cover and pavement markings on the Geraldine-North project located in Chouteau County. The project begins at RP 24.3 and extends approximately 3.7 miles southeast along State Primary Route 80/MT 80 to RP 28.0.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SCRUB SEAL & COVER			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS

402020320	EMULSIFIED ASPHALT-FOG SEAL	4,741.000	GAL
402020377	SCRUB SEAL EMULSION	112.600	TON
409000010	COVER-TYPE 1	63,603.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	20,000.000	UNIT
620013000	STRIPING-WHITE PAINT	135.000	GAL
620013960	STRIPING-WHITE EPOXY	180.000	GAL
620014000	STRIPING-YELLOW PAINT	39.000	GAL
620014960	STRIPING-YELLOW EPOXY	52.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9593000

211 PATH PAVEMENT PRESERVATION - BOZEMAN TA 1299(51) CONTRACT NO. 11319

Crack filling, minor pavement repair and fog sealing on the Path Pavement Preservation - Bozeman in Gallatin County. The project is located at the following locations:

Path Name	Nearest Urban Rte #	Length of Work (Miles)
Oak St Path	U-1202	0.6
College St. Path	U-1210	1.0
S. 19th Ave. Path	U-1201	0.3
Highland Blvd. Path	U-1215	1.5
Library Path	N/A*	0.4

*Path does not parallel an urban route.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - FOG SEAL, CRACK FILL AND PMS REPAIR			
104030010	MISCELLANEOUS WORK	1,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
402020320	EMULSIFIED ASPHALT-FOG SEAL	2,324.600	GAL
403010257	CRACK FILLING-MASTIC	4,297.000	LB
618030005	TRAFFIC CONTROL DEVICES CB	5,000.000	UNIT

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 9452000

INVITATION FOR BIDS
LETTING OF April 11, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on April 11, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

NHPB 94-5(48)170 - Bridge deck rehabilitation including deck repair, milling, overlay, expansion joints and bridge rail on the Terry-Fallon Area NHS Bridges project in Prairie County.

The project is on Interstate 94 with dual structures at the following locations:

- 1) Powder River (RP 69.8) - 7 miles southwest of Terry
- 2) BN Railroad (RP 185.1) - southwest of Fallon
- 3) Yellowstone River (RP 186.9) - 1 mile northeast of Fallon

STPB STWD(686) - Bridge deck rehabilitation including deck repair, polymer overlay and expansion joints on the Terry-Fallon Area STP Bridges project in Prairie County.

The project includes structures located on Secondary 253 at the Terry Interchange over I-94 (RP 176.5) and O' Fallon Creek on a frontage road approximately 1 mile west of Fallon and north of I-94.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PMS OVERLAY, SEAL & COVER			
103000000	TRAINING PROGRAM	500.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	394.300	LNFT
202020097	REMOVE BRIDGE APPROACH SLAB	6.000	EACH
203020278	EXCAVATION-DIGOUTS	12,066.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	6,882.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	1,000.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	3,897.000	CUYD
301020625	AGGREGATE TREATMENT	6,436.000	SQYD
401020022	COMMERCIAL MIX-PG 64-28	3,127.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,288.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	18.400	TON
409000000	FINAL SWEEP AND BROOM	0.500	CRMI
409000010	COVER-TYPE 1	10,216.000	SQYD
411010000	COLD MILLING	5,336.000	SQYD
501010401	CONCRETE-SHALLOW REPAIR	9.000	SQYD
552010041	REVISE JOINT	283.200	LNFT
552010059	EPOXY INJECTION	22.000	LNFT
552010140	TRANSVERSE DECK GROOVING	17,027.200	SQYD
552011040	REFURBISH EXPANSION JOINT	166.000	LNFT
552011140	RESEAL EXISTING JOINTS	77.900	LNFT
561010525	EXPANSION JOINT-PRECOMPRESSED	272.400	LNFT
561020110	BRIDGE DECK MILLING	17,907.600	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	115.000	SQYD
563000000	CONCRETE-CLASS OVERLAY	1,243.400	CUYD
563000040	POLYMER OVERLAY	2,462.100	SQYD
563000045	POLYMER OVERLAY PRIMER	2,462.100	SQYD
563000100	PREPARE DECK	2,462.100	SQYD
603015270	EMBANKMENT PROTECTOR 18 IN	268.000	LNFT
603587010	REMOVE EMBANKMENT PROTECTOR	28.000	LNFT
605000040	REVISE CONCRETE BARRIER RAIL-BR	7,851.500	LNFT
606010020	GUARDRAIL-TEMPORARY	288.000	LNFT
606010021	TEMP GD RAIL-STL/BR APPR-TY 1	4.000	EACH
606010022	TEMP GD RAIL-STL/BR APPR-TY 3	4.000	EACH
606010024	TEMP OPTIONAL TERM SECT	8.000	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	4,356.000	LNFT
606010268	GRD RL-BOX BEAM/BR APP-SEC-TYPE 3	4.000	EACH
606010325	GRD RL-BOX BEAM TO W-BEAM TRANS	16.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010385	REMOVE GUARDRAIL	6,257.300	LNFT
606010641	GD RL BOX BEAM OPT TERM SEC	15.000	EACH
606010670	BOX BEAM DEPART TERM SEC	2.000	EACH

609010010	CURB-CONCRETE	939.700	LNFT
609010203	REMOVE CURB	892.400	LNFT
610100490	TURF REINF MAT-NATURAL FIBER	254.000	SQYD
613300050	BANK PROTECTION-TYPE 3	32.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	1,000.000	UNIT
618030055	TRAFFIC CONTROL-RAMP CROSSOVER	2.000	EACH
618030080	TRAFFIC CONTROL	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	8.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	4.800	MILE
618030240	RAMP CROSSOVER	2.000	EACH
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	3.000	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	1.000	EACH
618030280	CROSSOVER RECLAMATION	5.000	EACH
619010100	OVERLAY-SHEET ALUM TYPE IV	8.000	SQFT
619010340	POSTS-TUBULAR STEEL-SQ-PERF	39.000	LB
620012950	TEMPORARY STRIPING	1.400	MILE
620013000	STRIPING-WHITE PAINT	62.000	GAL
620013960	STRIPING-WHITE EPOXY	39.000	GAL
620014000	STRIPING-YELLOW PAINT	52.000	GAL
620014960	STRIPING-YELLOW EPOXY	33.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	238.000	SQYD
622011084	GEOTEXTILE STABILIZATION	11,488.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 8127001, 8127002

102 SW OF LODGE GRASS - SW STPS 463-1(7)6 CONTRACT NO. 03419

The SW of Lodge Grass - SW project consists of crack filling, PMS overlay, seal and cover and other miscellaneous improvements. The project is located southwest of Lodge Grass on State Secondary Route 463, beginning at RP 5.7 and extends 8.5 miles to RP 14.2. The project is entirely within the boundaries of the Crow Indian Reservation in Big Horn County.

MANDATORY PRE-BID CONFERENCE

A pre-bid conference will be held at the following time and location:

Monday, March 25, 2019 10:00 a.m.

MDT Billings District Office

424 Morey Street

Billings, MT

The pre-bid conference will have a formal sign-in process that will become the official record of attendance for the purposes of determining eligible bidders.

Attendance at this conference is mandatory for any Contractor to submit a bid as a prime bidder. Contractors who bid as a prime bidder on this project must have at least one full time, permanent employee present. No proxy representatives, such as subcontractors or consultants, meet this requirement. In the event a prime bidder tenders a bid but did not attend the pre-bid conference, the bid will be returned unopened.

Representatives of the Department will be present to describe the project and answer questions. Representatives of the Apsalooke Nation will be invited to the pre-bid conference. The pre-bid conference is for information only. The Department is not bound by any statement or representation concerning conditions or description of the work given by Department employees or agents and the pre-bid conference. The answers to any questions raised are non-binding oral explanations or instructions, and relying on them is solely at the Bidder's risk. Any issues raised at the pre-bid conference must be posted on the Question and Answer Forum to be considered an enforceable provision of the contract to be let. The pre-bid attendee list and contract document clarifications or modifications considered necessary by the Department will be posted to the Question and Answer Forum.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - CRACK FILL, PMS OVERLAY, S & C - 100% CROW INDIAN			
RESERVATION			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
107100010	CULTURAL RESOURCE PERSON	3.000	DAY
109200005	MOBILIZATION	1.000	LS
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020000	GRADER-MOTOR	140.000	HOURL
210020170	TEST TRAILER-TRANSPORT, SETUP	234.000	MILE
301020416	SHOULDER GRAVEL	403.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	13,964.000	TON
401020300	HYDRATED LIME	195.000	TON
402020092	ASPHALT CEMENT PG 64-28	740.600	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	3,460.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	228.800	TON
402020375	EMULSIFIED ASPHALT CHFRS-2P	216.000	TON
403010258	CRACK FILLING-MASTIC	116,647.000	LNFT
409000000	FINAL SWEEP AND BROOM	8.500	CRMI
409000010	COVER-TYPE 1	248,263.000	SQYD
411010000	COLD MILLING	933.000	SQYD
411011120	CENTERLINE RUMBLE STRIPS-TYPE 1	8.500	MILE
610100557	REVEGETATION	2.500	ACRE
618030005	TRAFFIC CONTROL DEVICES CB	125,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	84.000	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	21.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	55.800	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	222.900	SQFT
619010230	REMOVE SIGN	42.000	EACH
619010240	REMOVE SIGN-GUIDE	3.000	EACH
619010310	POSTS-STEEL U SIGN	172.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	697.000	LB
619010480	POLES-TREATED WOOD 4 IN	156.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	28.000	LNFT
619010724	FRANG SIGN POST BKWY-S5 X 10 (S130X15)	2.000	EACH
619010726	FRANG SIGN POST BKWY-W4 X 13 (W100X19)	2.000	EACH
619010800	PANEL DELINEATOR DESIGN A	20.000	EACH
619010820	PANEL DELINEATOR DESIGN F	20.000	EACH
619011010	DELINEATOR DES A	258.000	EACH
619011040	DELINEATOR DES D	6.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620012950	TEMPORARY STRIPING	17.100	MILE
620013000	STRIPING-WHITE PAINT	616.000	GAL
620013960	STRIPING-WHITE EPOXY	410.000	GAL
620014000	STRIPING-YELLOW PAINT	360.000	GAL
620014960	STRIPING-YELLOW EPOXY	160.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 9594000

103 SF 169 OVR HGHT DETECT SYS STPP-HSIP-G 42-3(25)76 CONTRACT NO. 02419

Installation of an over height detection and warning system and signing on the SF 169 Over Height Detection System in Valley County. The project is located in the City of Glasgow

at US 2/N-1 RP 540.88 to RP 541.15, MT 24/P-42 RP 75.84 to RP 75.99 and S-246/6th Street S.RP 0.00 to RP 0.06.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - OVER HEIGHT DETECTION SYSTEM			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
609010013	PIN DOWN CURB	3.000	EACH
616343920	CONDUIT-PLASTIC 2 IN	1,220.000	LNFT
616783006	PULL BOX-COMPOSITE TYPE 1	8.000	EACH
617000000	FOUNDATION-CONCRETE	4.200	CUYD
617000050	POLES-TREATED WOOD CLASS 4	30.000	LNFT
617033310	CABLE-COPPER 4AWG10-600V	1,110.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	950.000	LNFT
617333198	SERV ASSEMBLY-200 AMP	4.000	EACH
617483110	SIG-TRAF 1 COL-1 WAY 12	4.000	EACH
617763401	OVERHEIGHT DETECTOR	4.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	2.000	EACH
617903463	VARIABLE MESSAGE SIGN	4.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010090	SIGNS-ALUM REFL SHEET XI	76.000	SQFT
619010230	REMOVE SIGN	3.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010521	OVERHEAD STR/METAL-CANTILEVER	4.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 9357000

INVITATION FOR BIDS
LETTING OF April 25, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on April 25, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

201 BLUE CREEK ROAD - BILLINGS UPP-STPB 1033(5)
 SOUTH FRONTAGE ROAD-BILLINGS UPP 1011(20)
 GUARDRAIL - SOUTH OF BILLINGS STPS 416-1(16)11

CONTRACT NO. 08419

UPP-STPB 1033(5) - Cold milling, PMS overlay, rumble strips, seal & cover, pavement markings, guardrail, signing and bridge deck repair on the Blue Creek Road - Billings project located in Yellowstone County. The project begins at RP 0.1 on South Billings Blvd (U-1033) and extends approximately 3.2 miles southeast along Blue Creek Road to RP 2.6.

UPP 1011(20) - Cold milling, PMS overlay, seal & cover, pavement markings, guardrail, signing and bridge deck repair on the South Frontage Road-Billings project located in Yellowstone County. The project is located southwest of Billings beginning at the intersection with Mullaney Lane (RP 0.0) to the intersection of Wise Lane and Shiloh Road (RP 3.75).

STPS 416-1(16)11 - PMS shoulder widening and guardrail on the Guardrail-South of Billings project located in Yellowstone County and entirely within the Crow Indian Reservation. The project is located on Secondary 416 beginning at RP 10.5 and extends approximately 2.8 miles east along Blue Creek Road to RP 13.3, intersecting with Secondary 418 (Pryor Creek Road).

MANDATORY PRE-BID CONFERENCE (TRIBAL)

A pre-bid conference will be held at the following time and location:

Friday, April 12, 2019 at 10:00 A.M.

Billings District Conference Room

424 Morey Street, Billings, MT 59101. The pre-bid conference will have a formal sign-in process that will become the official record of attendance for the purposes of determining eligible bidders.

Attendance at this conference is mandatory for any Contractor to submit a bid as a prime bidder. Contractors who bid as a prime bidder on this project must have at least one full time, permanent employee present. No proxy representatives, such as subcontractors or consultants, meet this requirement. In the event a prime bidder tenders a bid but did not attend the pre-bid conference, the bid will be returned unopened.

Representatives of the Department will be present to describe the project and answer questions. Representatives of the Crow Tribe will be invited to the pre-bid conference. The pre-bid conference is for information only. The Department is not bound by any statement or representation concerning conditions or description of the work given by Department employees or agents and the pre-bid conference. The answers to any questions raised are non-binding oral explanations or instructions, and relying on them is solely at the Bidder's risk. Any issues raised at the pre-bid conference must be posted on the Question and Answer Forum to be considered an enforceable provision of the contract to be let. The pre-bid attendee list and contract document clarifications or modifications considered necessary by the Department will be posted to the Question and Answer Forum.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GUARDRAIL, PMS			
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
107100010	CULTURAL RESOURCE PERSON	5.000	DAY
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	71.200	LNFT
202020139	REMOVE ASPHALT FROM DECK	1,446.500	SQYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	1,500.000	UNIT
210020000	GRADER-MOTOR	68.000	HOURL
301020416	SHOULDER GRAVEL	2,898.000	CUYD
301020625	AGGREGATE TREATMENT	2,211.000	SQYD
401020065	PLANT MIX SURF GR S-3/8 IN	10,626.000	TON
401020300	HYDRATED LIME	149.000	TON
402020095	ASPHALT CEMENT PG 70-28	659.300	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	8,161.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	286.400	TON
409000000	FINAL SWEEP AND BROOM	6.900	CRMI
409000020	COVER-TYPE 2	160,903.000	SQYD
411010000	COLD MILLING	74,161.000	SQYD

411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	1.400	MILE
411011135	RUMBLE STRIPS	5.700	MILE
552010805	MODIFY BRIDGE APPROACH SLAB	8.000	EACH
552011030	EXPANSION JOINT-ASPHALT PLUG	28.000	LNFT
552011110	JOINT SEALS-SILICONE	3.800	LNFT
561020110	BRIDGE DECK MILLING	470.400	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	4.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	2.000	SQYD
563000000	CONCRETE-CLASS OVERLAY	39.200	CUYD
563000040	POLYMER OVERLAY	470.400	SQYD
563000100	PREPARE DECK	1,446.500	SQYD
563000110	WATERPROOF MEMBRANE	976.100	SQYD
604000100	ADJUST MANHOLE	10.000	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	412.700	LNFT
605000045	REVISE CONC BARRIER RAIL END-BR	8.000	EACH
606010140	GUARDRAIL END SECTION WIDENING	15.000	EACH
606010330	MGS GUARDRAIL	7,425.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	34.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	3,612.500	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	225.000	LNFT
606010385	REMOVE GUARDRAIL	1,060.000	LNFT
606010386	REMOVE AND SALVAGE GUARDRAIL	3,075.000	LNFT
610100557	REVEGETATION	1.900	ACRE
618030005	TRAFFIC CONTROL DEVICES CB	225,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	5.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	201.300	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	311.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	623.900	SQFT
619010230	REMOVE SIGN	119.000	EACH
619010240	REMOVE SIGN-GUIDE	7.000	EACH
619010310	POSTS-STEEL U SIGN	114.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	58.000	LB
619010480	POLES-TREATED WOOD 4 IN	554.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	32.000	LNFT
619010800	PANEL DELINEATOR DESIGN A	34.000	EACH
619010820	PANEL DELINEATOR DESIGN F	34.000	EACH
619011010	DELINEATOR DES A	206.000	EACH
619011040	DELINEATOR DES D	48.000	EACH
619011060	DELINEATOR DES F	19.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	160.000	EACH
619011165	TOP MTD BARRIER DELIN-DBL FACE-WHITE	4.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	30.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	40.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	17.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	237.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	15.000	GAL
620012950	TEMPORARY STRIPING	8.400	MILE
620013000	STRIPING-WHITE PAINT	441.000	GAL
620013960	STRIPING-WHITE EPOXY	508.000	GAL
620014000	STRIPING-YELLOW PAINT	403.000	GAL
620014960	STRIPING-YELLOW EPOXY	433.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 9503000, 9501000, 9415000

202 MT-43 BRIDGE DECKS STPB STWD(325)

CONTRACT NO. 07419

The MT-43 Bridge Decks project includes rehabilitation of five bridges consisting of deck milling with a deck concrete overlay, replacing expansion joints, repainting bearings, repairs

to substructure concrete and minor approach work. The project is located on State Primary Route 43(P-46) in Beaverhead, Deer Lodge and Silver Bow counties in the Wise River area. The five bridges are located at RP 41.95, RP 57.98, RP 64.99, RP 65.12 and RP 75.06.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - STRUCTURE REHABILITATION - 5 STRUCTURES			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
104030037	MISCELLANEOUS ITEMS-SQYD	25.000	SQYD
104030045	MISCELLANEOUS ITEMS-EACH	3.000	EACH
105080115	FINISH GRADE CONTROL	800.000	CRFT
105080200	BRIDGE SURVEY	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	55.600	LNFT
203020100	EXCAVATION-UNCLASSIFIED	526.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	350.000	CUYD
301020625	AGGREGATE TREATMENT	1,492.000	SQYD
401020055	COMMERCIAL MIX-3/8 IN-PG 64-28	632.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	292.000	GAL
552010043	FRP REINFORCEMENT	1,024.500	SQFT
552010061	EPOXY INJECTION	16.000	GAL
552010140	TRANSVERSE DECK GROOVING	2,114.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	1,156.000	SQYD
552011010	EXPANSION JOINT STRIP SEAL	133.800	LNFT
552011120	JOINT SEALS-POLYURETHANE	244.000	LNFT
555010200	REINFORCING STEEL-EPOXY COATED	1,121.000	LB
556000100	PAINT EXISTING STRUCTURAL STEEL	80.000	SQYD
561010525	EXPANSION JOINT-PRECOMPRESSED	30.200	LNFT
561020110	BRIDGE DECK MILLING	2,272.200	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	70.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	47.000	SQYD
563000000	CONCRETE-CLASS OVERLAY	150.800	CUYD
606010040	GUARDRAIL-STEEL BOX BEAM	594.000	LNFT
606010268	GRD RL-BOX BEAM/BR APP-SEC-TYPE 3	8.000	EACH
606010385	REMOVE GUARDRAIL	600.000	LNFT
606010641	GD RL BOX BEAM OPT TERM SEC	8.000	EACH
606011503	RESET TEMP IMPACT ATTENUATOR	10.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	10.000	EACH
610100557	REVEGETATION	0.200	ACRE
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
618100000	SINGLE USE SIGNS	408.000	SQFT
618190100	TEMPORARY BARRIER RAIL	1,910.000	LNFT
618190110	RESET TEMP BARRIER RAIL	1,910.000	LNFT
620012950	TEMPORARY STRIPING	0.300	MILE
620013000	STRIPING-WHITE PAINT	14.000	GAL
620013960	STRIPING-WHITE EPOXY	20.000	GAL
620014000	STRIPING-YELLOW PAINT	14.000	GAL
620014960	STRIPING-YELLOW EPOXY	20.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	1,468.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%. All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address: <http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator. Uniform No. 8802000

203 SF 159 SANDERS LINCOLN SLP FLT HSIP STWD(439) CONTRACT NO. 04419

Grading, pms overlay, installing panel delineation, standard delineation, guardrail/slope flattening, curve warning signs and an actuated flasher on the SF 159 Sanders Lincoln Slope

Flattening project in Sanders and Lincoln counties.

The project is located NW of Trout Creek on Hwy 200/P-6 between RP 17.9 and RP 18.2 (Site # 1) and 10 miles SE of Troy on Hwy 56/P-56 between RP 26.5 and RP 26.9 (Site #2).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SLOPE FLATTENING, SIGNING, ELECTRICAL			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105080115	FINISH GRADE CONTROL	2,800.000	CRFT
109200005	MOBILIZATION	1.000	LS
203020375	EMBANKMENT IN PLACE	4,230.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	1,601.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	2,016.000	CUYD
301020625	AGGREGATE TREATMENT	11,416.000	SQYD
401020062	COMMERCIAL MIX-1/2 IN-PG 64-28	2,073.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,135.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	763.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	18.200	TON
409000010	COVER-TYPE 1	10,057.000	SQYD
411010000	COLD MILLING	10,045.000	SQYD
603010528	CSP 18 IN	14.000	LNFT
603010540	CSP 24 IN	10.000	LNFT
603587020	REMOVE PIPE CULVERT	4.000	LNFT
606010330	MGS GUARDRAIL	1,462.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	6.000	EACH
610100101	SEEDING AREA NO 1	2.100	ACRE
610100102	SEEDING AREA NO 2	0.300	ACRE
610100326	FERTILIZING AREA NO 1	2.100	ACRE
610100327	FERTILIZING AREA NO 2	0.300	ACRE
610100555	CONDITION SEEDBED SURFACE	2.100	ACRE
610100561	EROSION CONTROL BLANKET-LONG-TERM	1,452.000	SQYD
617000000	FOUNDATION-CONCRETE	1.000	CUYD
617523010	SOL SIG-TRAF 1 COLOR-1 WAY 12	1.000	EACH
617673200	SIG STANDARD TYPE 1-200	1.000	EACH
617763410	RADAR VEHICLE DETECTION	1.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	60,000.000	UNIT
619010090	SIGNS-ALUM REFL SHEET XI	18.000	SQFT
619010200	RESET SIGNS	3.000	EACH
619010490	POLES-TREATED WOOD 5 IN	16.000	LNFT
619010800	PANEL DELINEATOR DESIGN A	54.000	EACH
619011010	DELINEATOR DES A	8.000	EACH
620012950	TEMPORARY STRIPING	0.500	MILE
620013000	STRIPING-WHITE PAINT	37.000	GAL
620013960	STRIPING-WHITE EPOXY	24.000	GAL
620014000	STRIPING-YELLOW PAINT	27.000	GAL
620014960	STRIPING-YELLOW EPOXY	18.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9131000

204 DRAINAGE - 6 M E GLENDIVE STPB 9011(101)

CONTRACT NO. 06419

Remove a 58' timber structure to replace with a 15' x 8' double RCB, grade, grvl, PMS approaches, revegetation and fencing on the Drainage - 6 Miles East Glendive project in Dawson

County.

The project is approximately 6 miles east of Glendive on Frontage Rd 300/Local Rte X-11315 between RP 5.2 and RP 5.3, more specifically T 16 N, R 56 E, SEC 35.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRVL, PMS, REMOVE STRUCTURE, DRAINAGE AND FENCING			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105080115	FINISH GRADE CONTROL	500.000	CRFT
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020375	EMBANKMENT IN PLACE	1,464.000	CUYD
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	270.000	CUYD
301020450	SPECIAL BACKFILL	922.000	CUYD
401020057	COMMERCIAL MIX-3/8 IN-PG 58-28	156.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	83.000	GAL
551020030	CONCRETE-CLASS GENERAL	18.500	CUYD
603000050	GRANULAR BEDDING MATERIAL	115.000	CUYD
603000060	FOUNDATION MATERIAL	231.000	CUYD
603013310	REIN CONC BOX 15 X 8 DBL	87.000	LNFT
607100252	FARM FENCE-TYPE F4M	1,257.300	LNFT
607100362	FARM FENCE-PANEL/SINGLE FM	10.000	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	5.000	EACH
607100551	FENCE-TEMPORARY	1,200.000	LNFT
607100720	DEADMAN	2.000	EACH
610100559	REVEGETATION	1.000	LS
613100030	RIPRAP-CLASS 1 RANDOM	97.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
622011084	GEOTEXTILE STABILIZATION	1,666.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.

Uniform No. 8800000

205 SF 169 HELENA SAFETY IMPROVEMENTS HSIP 25(89) CONTRACT NO. 05419

SF 099 W OF YORK DELINEATION HSIP 280-1(25)12

HSIP 25(89) - Signs, delineation and rumble strips on the SF 169 Helena Safety Improvements project located in Lewis and Clark County at the following locations:

- Loc #1 - Interstate Route 15 from RP 228.2 to RP 228.8;
- Loc #2 - Local Route 25-900/Boulder Ave from RP 1.0 to RP 1.4;
- Loc #3 - Urban Route 5809/State Sec 229/Montana Ave from RP 4.3 to RP 7.4;
- Loc #4 - Urban Route 5829N/Wylie Drive from RP 2.6 to RP 3.3;
- Loc #5 - Local Route 25-602/Birdseye Road from RP 7.7 to RP 8.7;
- Loc #6a - Local Route 25-635/Grizzly Gulch Road from RP 0.0 to RP 0.5;
- Loc #6b - Local Route 25-635/Grizzly Gulch Road from RP 3.45 to RP 4.05.

HSIP 280-1(25)12 - Signing and delineation on the SF 099 W of York Delineation project located in Lewis and Clark County. The project is located on State Secondary Route 280 from RP 12.07 to RP 15.44.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SIGNING AND DELINEATION			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
411011135	RUMBLE STRIPS	1.400	MILE
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010086	SIGNS-ALUM REFL SHEET IV	19.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	994.000	SQFT
619010230	REMOVE SIGN	81.000	EACH
619010240	REMOVE SIGN-GUIDE	1.000	EACH
619010310	POSTS-STEEL U SIGN	200.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	61.000	LB
619010480	POLES-TREATED WOOD 4 IN	1,358.000	LNFT
619010800	PANEL DELINEATOR DESIGN A	147.000	EACH
619010810	PANEL DELINEATOR DESIGN C	74.000	EACH
619010820	PANEL DELINEATOR DESIGN F	37.000	EACH
619011010	DELINEATOR DES A	118.000	EACH
619011030	DELINEATOR DES C	386.000	EACH
619011040	DELINEATOR DES D	42.000	EACH
619011060	DELINEATOR DES F	124.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	150.000	EACH
619011205	DELINEATION-LINEAR-BARRIER-YELLOW	334.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9424000, 7276000

INVITATION FOR BIDS
LETTING OF May 9, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on May 9, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 CLARK CANYON RES - BARRETT'S IM 15-1(122)46 CONTRACT NO. 04519

The Clark Canyon Reservoir-Barretts project consists of cold milling, plant mix bituminous surfacing, seal and cover, guardrail upgrades, structure rehabilitation, signing and other miscellaneous improvements. The project is located on National Highway Interstate Route 15 beginning at RP 45.9 and extends approximately 8.6 miles to RP 54.5. The project is located entirely within Beaverhead County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, FILL, PMS OVERLAY, S & C, G'RAIL			
103000000	TRAINING PROGRAM	500.000	HOURL
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
105080200	BRIDGE SURVEY	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	88.000	LNFT
202020115	REMOVE DECK	1,738.900	SQYD
203020278	EXCAVATION-DIGOUTS	467.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	150.000	MILE
301020340	CRUSHED AGGREGATE COURSE	366.000	CUYD
301020625	AGGREGATE TREATMENT	435.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	30,966.000	TON
401020300	HYDRATED LIME	434.000	TON
402020095	ASPHALT CEMENT PG 70-28	1,670.200	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	11,790.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	11,571.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	488.900	TON
409000000	FINAL SWEEP AND BROOM	17.700	CRMI
409000010	COVER-TYPE 1	271,930.000	SQYD
411010000	COLD MILLING	240,356.000	SQYD
411011135	RUMBLE STRIPS	0.800	MILE
551020107	CONCRETE-CLASS DECK	399.900	CUYD
552010060	REPAIR STRUCTURE	1.000	LS
552010140	TRANSVERSE DECK GROOVING	2,361.200	SQYD
552010160	BRIDGE DECK CRACK SEAL	2,881.700	SQYD
552011010	EXPANSION JOINT STRIP SEAL	46.900	LNFT
552011110	JOINT SEALS-SILICONE	43.300	LNFT
552011120	JOINT SEALS-POLYURETHANE	44.000	LNFT
555010200	REINFORCING STEEL-EPOXY COATED	91,834.400	LB
561010525	EXPANSION JOINT-PRECOMPRESSED	133.400	LNFT
561020110	BRIDGE DECK MILLING	836.800	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	29.700	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	23.500	SQYD
563000000	CONCRETE-CLASS OVERLAY	46.500	CUYD
605000030	BARRIER RAIL-CAST IN PLACE-BR	715.200	LNFT
605000040	REVISE CONCRETE BARRIER RAIL-BR	343.800	LNFT
605000070	REMOVE CONCRETE BARRIER RAIL	8.000	EACH
605000090	CONCRETE BARRIER RAIL	48.000	EACH
606010100	GUARDRAIL-STEEL-ROCKFALL	1,456.200	LNFT
606010117	HIGH-TENSION CABLE RAIL	720.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	76.000	EACH
606010230	GUARDRAIL-STL/BR APPR-TY 3	62.000	EACH
606010330	MGS GUARDRAIL	24,089.300	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	76.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	3.000	EACH
606010385	REMOVE GUARDRAIL	25,919.000	LNFT
606011520	IMPACT ATTENUATOR	1.000	EACH
609010112	CURB 4 IN-CONCRETE	4,837.000	LNFT
610100557	REVEGETATION	1.350	ACRE
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	4.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	18.400	MILE
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	1.000	EACH

618030280	CROSSOVER RECLAMATION	1.000	EACH
618030300	CROSSOVER-MAINTAIN, CLOSE	1.000	EACH
618030310	CROSSOVER-MEDIAN BARRIER RAIL	1.000	EACH
618100000	SINGLE USE SIGNS	224.000	SQFT
619010058	SIGNS-ALUM SHEET INCR IV	993.200	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	32.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	153.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	570.300	SQFT
619010230	REMOVE SIGN	72.000	EACH
619010240	REMOVE SIGN-GUIDE	20.000	EACH
619010300	POSTS-TUBULAR STEEL	410.000	LB
619010310	POSTS-STEEL U SIGN	425.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	124.000	LB
619010480	POLES-TREATED WOOD 4 IN	52.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	60.000	LNFT
619010500	POLES-TREATED WOOD 6 IN	34.000	LNFT
619010740	FRANG SIGN POST BKWY-3 IN RD (76 MM)	1.000	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD (100 MM)	2.000	EACH
619011010	DELINEATOR DES A	316.000	EACH
619011020	DELINEATOR DES B	10.000	EACH
619011040	DELINEATOR DES D	20.000	EACH
619011070	DELINEATOR DES G	21.000	EACH
619011080	DELINEATOR DES H	264.000	EACH
619011085	DELINEATOR DES BJ	14.000	EACH
619011087	DELINEATOR DES GJ	8.000	EACH
619011162	TOP MTD BARRIER DELIN-DBL FACE-YELLOW	20.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	10.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	7.000	GAL
620012950	TEMPORARY STRIPING	19.000	MILE
620013000	STRIPING-WHITE PAINT	883.000	GAL
620013960	STRIPING-WHITE EPOXY	589.000	GAL
620014000	STRIPING-YELLOW PAINT	680.000	GAL
620014960	STRIPING-YELLOW EPOXY	453.000	GAL
622011084	GEOTEXTILE STABILIZATION	567.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
 Uniform No. 8753000

102 SF- 169 VALLEY SPUR INTX IMPRV HSIP 1299(43) CONTRACT NO. 02519

Grade, gravel, PMS, drainage, signals, signing and pavement markings on the SF - 169 Valley Spur Intersection Improvement project in Gallatin County. The project begins on State Route S-235, known as Valley Center Road at RP 4.5 and proceeds east ending at RP 4.6.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRVL. PMS, DRNG, SIGNING & ELECT			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
105080115	FINISH GRADE CONTROL	1,950.000	CRFT
109200005	MOBILIZATION	1.000	LS
202020140	REMOVE BITUMINOUS PAVEMENT	260.000	SQYD
203020100	EXCAVATION-UNCLASSIFIED	8,316.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	5,835.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	634.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	2.000	MILE

301020268	TRAFFIC GRAVEL	1,139.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	2,009.000	CUYD
301020625	AGGREGATE TREATMENT	8,351.000	SQYD
401020021	COMMERCIAL MIX-PG 70-28	2,036.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	816.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	13.400	TON
409000000	FINAL SWEEP AND BROOM	0.200	CRMI
409000020	COVER-TYPE 2	7,510.000	SQYD
551020030	CONCRETE-CLASS GENERAL	0.500	CUYD
603000050	GRANULAR BEDDING MATERIAL	22.000	CUYD
603010048	DRAINAGE PIPE 24 IN	178.000	LNFT
603012530	RCP 18 IN	206.000	LNFT
603013207	RCPA 28 IN	88.500	LNFT
603587020	REMOVE PIPE CULVERT	58.000	LNFT
604010525	COMB 60 IN T3 MH-TA CURB INLET	2.000	EACH
609010200	CURB AND GUTTER-CONC	690.000	LNFT
610100101	SEEDING AREA NO 1	2.600	ACRE
610100326	FERTILIZING AREA NO 1	2.600	ACRE
610100555	CONDITION SEEDBED SURFACE	2.600	ACRE
616343920	CONDUIT-PLASTIC 2 IN	1,090.000	LNFT
616343924	CONDUIT-PLASTIC 2 1/2 IN	120.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	1,090.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	12.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	3.000	EACH
617000000	FOUNDATION-CONCRETE	35.400	CUYD
617033214	CABLE-COPPER 3AWG14-600V	330.000	LNFT
617033313	CABLE-COPPER 4AWG12-600V	400.000	LNFT
617033414	CABLE-COPPER 7AWG14-600V	380.000	LNFT
617033614	CABLE-COPPER 12AWG14-600V	2,230.000	LNFT
617090050	CABLE-COPPER COAXIAL 50 OHM 3/8 IN	120.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	250.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	1,550.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	2,590.000	LNFT
617233030	CONTROLLER-CAB PEDESTAL TYPE P	2.000	EACH
617233040	CONTROLLER-CAB PEDESTAL TYPE D	1.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	4.000	EACH
617333160	SERV ASSEMB-60 AMP	2.000	EACH
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	21.000	EACH
617605081	CONTLR/TRAF-ACTUAT TYPE 8-A	2.000	EACH
617623270	BATTERY BACKUP SYSTEM	1.000	EACH
617673140	SIG STANDARD TYPE 1-140	1.000	EACH
617695525	SIG STANDARD TYPE 2-A-900-0	1.000	EACH
617695905	SIG STANDARD TYPE 2-A-900-5	1.000	EACH
617695906	SIG STANDARD TYPE 2-A-900-6	2.000	EACH
617715096	SIG STANDARD TYPE 3-A-900-6	1.000	EACH
617715098	SIG STANDARD TYPE 3-A-900-8	2.000	EACH
617715100	SIG STANDARD TYPE 3-A-900-0	1.000	EACH
617763410	RADAR VEHICLE DETECTION	4.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	7.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903459	BLANKOUT SIGN	3.000	EACH
617903540	YAGI ANTENNA-TYPE D	1.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	150,000.000	UNIT
619010086	SIGNS-ALUM REFL SHEET IV	40.300	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	120.500	SQFT
619010230	REMOVE SIGN	9.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	58.000	LB
619010480	POLES-TREATED WOOD 4 IN	126.000	LNFT
619011010	DELINEATOR DES A	14.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	21.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	9.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	14.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	6.000	GAL
620012950	TEMPORARY STRIPING	0.500	MILE
620013000	STRIPING-WHITE PAINT	28.000	GAL
620013955	REMOVE PAVEMENT MARKINGS	970.000	LNFT
620013960	STRIPING-WHITE EPOXY	18.000	GAL

620014000	STRIPING-YELLOW PAINT	29.000	GAL
620014960	STRIPING-YELLOW EPOXY	19.000	GAL
622011084	GEOTEXTILE STABILIZATION	13,262.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 9190000

103 BR PRES YELLOWSTONE GARDINER NHPB 11-1(83)0 CONTRACT NO. 05519

Bridge rehab and approaches to include deck repair, milling and overlay, grading and PCCP approaches on the Bridge Preservation Yellowstone Gardiner project in Park County. The project is in Gardiner on US 89/State Rte N-11 at RP 0.16.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE DECK - POLYMER OVERLAY			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
104030015	REMOVE AND RESET MISC ITEMS	1.000	LS
105080115	FINISH GRADE CONTROL	100.000	CRFT
105080200	BRIDGE SURVEY	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020115	REMOVE DECK	162.300	SQYD
203020225	EXCAVATION-STREET	71.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
209010160	TEMPORARY SHORING	1.000	LS
301020340	CRUSHED AGGREGATE COURSE	33.000	CUYD
501010200	PCCP-9 IN REINFORCED	129.000	SQYD
552011120	JOINT SEALS-POLYURETHANE	152.000	LNFT
555010200	REINFORCING STEEL-EPOXY COATED	12,130.500	LB
561020110	BRIDGE DECK MILLING	1,550.500	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	28.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	10.000	SQYD
563000000	CONCRETE-CLASS OVERLAY	124.600	CUYD
563000040	POLYMER OVERLAY	1,670.000	SQYD
563000100	PREPARE DECK	1,670.000	SQYD
604010630	DRAINAGE STRUCTURE	1.000	LS
606010370	RESET GUARDRAIL	35.700	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
608010059	SIDEWALK-REINFORCED 4 IN	19.800	SQYD
609010010	CURB-CONCRETE	36.000	LNFT
614010008	RETAINING WALL REPAIR	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	100,000.000	UNIT
618100000	SINGLE USE SIGNS	224.000	SQFT
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	260.000	DAY
618190100	TEMPORARY BARRIER RAIL	440.000	LNFT
618190110	RESET TEMP BARRIER RAIL	440.000	LNFT
620010301	CURB MARKING-YELLOW EPOXY	14.000	GAL
620013960	STRIPING-WHITE EPOXY	5.000	GAL
620014960	STRIPING-YELLOW EPOXY	5.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 8803000

INVITATION FOR BIDS
LETTING OF June 13, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on June 13, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 KILA-E & W NHIP 1-2(221)106 CONTRACT NO. 08619
 ELK HILL NH 1-1(104)66

NHIP 1-2(221)106 - Milling, tack, pms overlay and full-width seal & cover and fog seal, guardrail and signing on the Kila - East & West project in Flathead County. The 7.2 mile project is located 6 miles southwest of Kalispell on US 2 (N-1) between RP 106.5 and 113.6.

NH 1-1(104)66 - Milling, tack, pms overlay and full-width seal & cover and fog seal, guardrail and signing on the Elk Hill project in Lincoln County. The 3.4 mile project is located 32 miles south and east of Libby on US 2 (N-1) between RP 65.6 and RP 69.0 (East end of Elk Cr Rd grade separation).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - COLD MILL, PMS OVERLAY, S&C, FOG SEAL, GUARDRAIL, SIGNING			
104030010	MISCELLANEOUS WORK	45,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	1,000.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	150.000	MILE
301020416	SHOULDER GRAVEL	445.000	CUYD
401020048	PLANT MIX SURF GR S-1/2 IN	24,528.000	TON
401020300	HYDRATED LIME	344.000	TON
402020092	ASPHALT CEMENT PG 64-28	1,422.900	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	13,273.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	14,588.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	350.100	TON
409000010	COVER-TYPE 1	195,194.000	SQYD
411010000	COLD MILLING	127,029.000	SQYD
411011120	CENTERLINE RUMBLE STRIPS-TYPE 1	7.200	MILE
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	3.500	MILE
411011135	RUMBLE STRIPS	6.700	MILE
557010505	REVISE BRIDGE RAIL-THRIE BEAM	146.330	LNFT
606010140	GUARDRAIL END SECTION WIDENING	20.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	19.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	6,856.300	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	1.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	62.500	LNFT
606010385	REMOVE GUARDRAIL	7,441.000	LNFT
606010386	REMOVE AND SALVAGE GUARDRAIL	50.000	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
609010010	CURB-CONCRETE	990.000	LNFT
610100559	REVEGETATION	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	200,000.000	UNIT
618190100	TEMPORARY BARRIER RAIL	600.000	LNFT
618190110	RESET TEMP BARRIER RAIL	600.000	LNFT
619010058	SIGNS-ALUM SHEET INCR IV	155.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	112.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	464.000	SQFT
619010230	REMOVE SIGN	85.000	EACH
619010240	REMOVE SIGN-GUIDE	7.000	EACH
619010310	POSTS-STEEL U SIGN	234.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,180.000	LB
619010480	POLES-TREATED WOOD 4 IN	1,072.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	28.000	LNFT
619010730	FRANG SIGN POST BKWY-W8 X 18 (W200 X 27	2.000	EACH
619010800	PANEL DELINEATOR DESIGN A	44.000	EACH
619011010	DELINEATOR DES A	358.000	EACH
619011040	DELINEATOR DES D	20.000	EACH
619011060	DELINEATOR DES F	48.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	224.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	10.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	7.000	GAL
620012950	TEMPORARY STRIPING	21.200	MILE

620013000	STRIPING-WHITE PAINT	763.000	GAL
620013960	STRIPING-WHITE EPOXY	509.000	GAL
620014000	STRIPING-YELLOW PAINT	571.000	GAL
620014960	STRIPING-YELLOW EPOXY	380.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9490000, 9489000

102 SNOW FENCE-N OF BIG TIMBER STPP 45-1(28)23 CONTRACT NO. 08219
HOBSON - EAST (SNOW FENCE) NH 57-2(40)59
SNOW FENCE-NORTH OF HARLOWTON NH 63-1(24)0

STPP 45-1(28)23-The Snow Fence-N of Big Timber project consists of snow fence construction and installation at numerous locations from RP 22.6 to RP 42.6 on State Primary Route 45/US 191 between Big Timber and Harlowton. This project is located in both Sweet Grass and Wheatland County.

NH 57-2(40)59-The Hobson - East (Snow Fence) project consists of snow fence construction and installation at numerous locations from RP 58.6 to RP 63.2 on National Highway Route 57/MT 200 near Hobson and extending east. The project is located in Judith Basin County.

NH 63-1(24)0-The Snow Fence-North of Harlowton project consists of snow fence construction and installation, and concrete snow fence salvage between RP 0.4 to RP 3.6 on National Highway Route 63/US 191 near Harlowton and extending northeast. The project is located in Wheatland County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SNOW FENCE			
104030010	MISCELLANEOUS WORK	3,000.000	UNIT
104030065	MISCELLANEOUS ITEMS-LNFT	1,841.000	LNFT
109200005	MOBILIZATION	1.000	LS
607100360	FARM FENCE-PANEL/SINGLE FW	8.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	64.000	LNFT
607100640	SNOW FENCE - 8 FT	20,704.000	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 9413000, 4368002, 9412000

103 SF 169 FLATHEAD CNTY SFTY HSIP STWD(553) CONTRACT NO. 07619
SF 169 RAVALLI CNTY SFTY HSIP 41(80)
SF 169 MINERAL CNTY SFTY IMPRV HSIP STWD(535)
SF 169 MSLA CNTY SFTY IMPRV HSIP 32(107)

HSIP STWD(553) - Signing, delineation, guardrail, and chevrons on the SF 169 Flathead County Safety project in Flathead County. The project consists of the following 12 sites in Kalispell, Whitefish, Columbia Falls, Somers and Libby:

1. Whitefish Stage Road, Kalispell, RP 0.4 to RP 0.7,
2. Blanchard Lake Road, Whitefish, RP 2.4 to RP 3.1,
3. Lower Valley Road, Kalispell, RP 1.9 to 2.4,
4. Lower Valley Road, Kalispell, RP 4.9 to 5.4,

5. Helena Flats Road, Kalispell, RP 0.0 to 6.5,
6. Columbia Falls Stage Road, Columbia Falls, RP 0.0 to 1.1,
7. Rose Crossing, Kalispell, RP 0.2 to RP 1.2,
8. Halfmoon Road/Edgewood Drive, Whitefish, RP 0.1 to RP 7.5,
9. Whalebone Drive, Kalispell, RP 1.2 to 1.9,
10. Somers Road, Somers, RP 0.5 to 1.0,
11. Ashley Lake Road, Kalispell, RP 3.7 to 4.5,
12. Parmentor Creek Road, RP 0.0 to RP 0.3

HSIP 32(107) - Signing and Delineation on the SF 169 Missoula County Safety Improvement project in Missoula County. The project consists of the following 8 sites around Missoula and the Huson area:

HSIP 32(107) - Signing and Delineation on the SF 169 Missoula County Safety Improvement project in Missoula County. The project consists of the following 8 sites around Missoula and the Huson area:

1. Pattee Canyon Road, RP 0.5 to RP 2.2,
2. Pattee Canyon Road, RP 2.3 to RP 3.7,
- 2a. Pattee Canyon Road, RP 4.4 to RP 4.7,
- 2b. Deer Creek Road, RP 5.0 to RP 5.2,
- 2c. Deer Creek Road, RP 5.4 to RP 5.5,
- 2d. Deer Creek Road, RP 5.5 to RP 5.7,
- 2e. Deer Creek Road, RP 5.9 to RP 6.1,
3. Deer Creek Road, RP 8.5 to RP 8.9,
4. Deer Creek Road, RP 9.8 to RP 10.7,
5. Rogers Street/Cemetary Road, RP 0.01 to RP 0.8,
6. Lower Miller Creek Road, RP 0.050 to RP 0.800,
7. Sixmile, RP 5.6 to RP 5.8,
8. Blue Mountain Road, RP 0.2 to RP 0.5.

HSIP 41(80) - Signing and Delineation on the SF 169 Ravalli County Safety project in Ravalli County. The project consists of the following 2 sites:

1. S-473, South of Darby, Install panel delineation RP 5.0 - RP 5.5 and standard delineation RP 0.0 - RP 14.4.
2. West River Road, Hamilton, Replace and install supplemental curve signing RP 1.25 - RP 1.35.

HSIP STWD(535) - Signing and Delineation on the SF 169 Mineral County Safety Improvement project in Mineral County. The project consists of the following 4 sites:

1. I-90, West of Saltese, RP 4.65 to RP 4.75,
2. I-90, SE of Superior, RP 53.0 to 54.0,
3. I-90, West of Alberton, RP 66.0 to 66.2,
- 4a. East Mullan Road, SE of Superior, RP 2.4 to RP 2.6,
- 4b. East Mullan Road, SE of Superior, RP 6.0 to RP 6.2.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SIGNING AND DELINEATION			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	1,000.000	UNIT
606010140	GUARDRAIL END SECTION WIDENING	4.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	4.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	1,450.000	LNFT
606010385	REMOVE GUARDRAIL	87.500	LNFT
618030015	TRAFFIC CONTROL-FIXED	2,000.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010062	SIGNS-ALUM SHEET INCR XI	12.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	2,252.700	SQFT
619010230	REMOVE SIGN	125.000	EACH
619010240	REMOVE SIGN-GUIDE	1.000	EACH
619010300	POSTS-TUBULAR STEEL	266.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	463.000	LB
619010480	POLES-TREATED WOOD 4 IN	3,324.000	LNFT
619010500	POLES-TREATED WOOD 6 IN	58.000	LNFT
619010726	FRANG SIGN POST BKWY-W4 X 13 (W100X19)	2.000	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD (89MM)	2.000	EACH
619010800	PANEL DELINEATOR DESIGN A	40.000	EACH

619011010	DELINEATOR DES A	923.000	EACH
619011030	DELINEATOR DES C	615.000	EACH
619011040	DELINEATOR DES D	98.000	EACH
619011060	DELINEATOR DES F	246.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	179.000	EACH
619011139	DELINEATION-LINEAR-YELLOW-W-BEAM	104.000	EACH
619011205	DELINEATION-LINEAR-BARRIER-YELLOW	212.000	EACH
623000190	RESET MAILBOX	1.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9419000, 9367000, 9366000, 9418000

104 SIDEWALKS PHASE II - CASCADE TA 7(73) CONTRACT NO. 01619

Sidewalks, C & G and ADA curb ramps on the Sidewalks Phase II - Cascade project in Cascade County. The project is located in the southern area of the town of Cascade on portions of Second and Third Street and Third Avenue South for a total of 8 blocks.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SIDEWALKS AND ADA CURB RAMPS			
104030010	MISCELLANEOUS WORK	7,500.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
201311010	REMOVE TREES AND BRUSH	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	29.100	CUYD
301020526	TOP SURFACING GR 3B	71.500	CUYD
401020023	COMMERCIAL MIX-PG 58-28	31.600	TON
557010110	HAND RAIL	31.600	LNFT
608000020	SIDEWALK DRAIN	6.000	EACH
608010016	PEDESTRIAN STAIRWAY	1.000	LS
608010020	SIDEWALK-CONCRETE 4 IN	1,362.100	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	446.100	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	30.700	SQYD
609010013	PIN DOWN CURB	5.000	EACH
609010200	CURB AND GUTTER-CONC	145.000	LNFT
610100470	SODDING	1,553.000	SQYD
610100559	REVEGETATION	1.000	LS
610100625	LANDSCAPING	1.000	LS
614010009	RETAINING WALL	47.000	SQYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9439000

105 O ST - BENNETT ST CONNECTOR - LIVINGSTON TA 7499(16) CONTRACT NO. 02619

Installation of ADA sidewalks, curb/gutter, drainage, fencing and multi-use asphalt path

on the O Street-Bennett Street Connection-Livingston project located in Livingston in Park County. The project begins at RP 55.2 near the intersection of O Street and Park and extends northeast along Park to RP 55.6.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BIKE AND PEDESTRIAN PATH			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
104030070	MISCELLANEOUS ITEMS-REMOVAL	1.000	LS
105080115	FINISH GRADE CONTROL	1,700.000	CRFT
109200005	MOBILIZATION	1.000	LS
201130000	CLEARING AND GRUBBING	1.000	LS
203020310	SPECIAL BORROW-NEAT LINE	1,138.000	CUYD
203020375	EMBANKMENT IN PLACE	2,449.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	548.000	CUYD
401020055	COMMERCIAL MIX-3/8 IN-PG 64-28	275.000	TON
603012540	RCP 18 IN CLASS 4	24.000	LNFT
606400130	REMOVABLE BOLLARD	1.000	EACH
607100116	FARM FENCE-TYPE F1W-39 IN WW	625.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	1.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	3.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	186.900	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	130.500	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	1.300	SQYD
609010200	CURB AND GUTTER-CONC	186.300	LNFT
610100490	TURF REINF MAT-NATURAL FIBER	289.000	SQYD
610100559	REVEGETATION	1.000	LS
617000050	POLES-TREATED WOOD CLASS 4	80.000	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	50,000.000	UNIT
619010086	SIGNS-ALUM REFL SHEET IV	7.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	37.200	SQFT
619010200	RESET SIGNS	2.000	EACH
619010230	REMOVE SIGN	1.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	63.000	LB
620010301	CURB MARKING-YELLOW EPOXY	2.000	GAL
622011084	GEOTEXTILE STABILIZATION	1,535.000	SQYD
623000155	MAILBOX	1.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 9459000

106 BIG COULEE - 5M SW FAIRFIELD STPB 9050 (25) CONTRACT NO. 05619

Remove structure, replace with box culvert, gravel surfacing and fencing on the Big Coulee-5M SW Fairfield project located in Teton County. The project is located at RP 0.3 on Local Route 50-412 (2nd Road SW) 5 miles southwest of Fairfield.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RECONSTRUCTION AND BOX CULVERT			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS

203020100	EXCAVATION-UNCLASSIFIED	581.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
208010486	STREAMBED MATERIAL	40.000	CUYD
301020450	SPECIAL BACKFILL	607.000	CUYD
301020526	TOP SURFACING GR 3B	681.000	CUYD
603000050	GRANULAR BEDDING MATERIAL	50.000	CUYD
603010528	CSP 18 IN	22.000	LNFT
603013349	REIN CONC BOX 20 X 7	54.000	LNFT
607100271	FARM FENCE-TYPE F5W AND F5M	1,218.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	6.000	EACH
607100362	FARM FENCE-PANEL/SINGLE FM	6.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	4.000	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	4.000	EACH
610100559	REVEGETATION	1.000	LS
613100030	RIPRAP-CLASS 1 RANDOM	57.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Great Falls District Administrator.
 Uniform No. 8853000

107 PARK DR/4TH AVE N PED XING - GTF TA 5208(4) CONTRACT NO. 03619

Sidewalk, C & G, pedestrian path, storm drain, trees and sodding on the Park Drive/4th Avenue North Pedestrian Crossing - GTF project in Cascade County.
 The project is located in Great Falls at the junction of Park Drive (U-5208)/2nd Street N (U-5208)/4th Avenue N with an additional shared-use path within Gibson Park.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PEDESTRIAN PATH AND X-ING AND SIDEWALK-STATE			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
201311000	REMOVE TREES	3.000	EACH
203020225	EXCAVATION-STREET	438.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	143.000	CUYD
301020625	AGGREGATE TREATMENT	604.000	SQYD
401020022	COMMERCIAL MIX-PG 64-28	155.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	62.000	GAL
551020126	CONTROLLED LOW STRENGTH MATL	0.600	CUYD
601011920	INSULATION	32.000	SQFT
601012301	RELOCATE WATER METER	1.000	EACH
603010025	PLUG ENDS AND ABANDON PIPE	10.000	EACH
603013452	PIPE-PVC 12 IN	117.900	LNFT
603013457	PIPE-PVC 8 IN	110.400	LNFT
603013459	PIPE-PVC 4 IN	56.000	LNFT
603013462	PIPE-PVC 6 IN	42.000	LNFT
603013553	CONNECT TO EXISTING MANHOLE	1.000	EACH
603014244	RESET VALVE BOX	1.000	EACH
604000140	REMOVE DROP INLET	4.000	EACH
604010125	MANHOLE-SPECIAL DESIGN	2.000	EACH
604010172	REMOVE MANHOLE	1.000	EACH
604010250	INLET CURB-SPECIAL DESIGN	6.000	EACH

608010020	SIDEWALK-CONCRETE 4 IN	400.200	SQYD
608010060	SIDEWALK-REINFORCED 6 IN	76.200	SQYD
608010112	DECORATIVE CONCRETE	37.600	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	18.500	SQYD
609010200	CURB AND GUTTER-CONC	777.500	LNFT
610100470	SODDING	609.200	SQYD
610590028	TREE	5.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010086	SIGNS-ALUM REFL SHEET IV	25.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	84.200	SQFT
619010210	RESET SIGNS-GUIDE	2.000	EACH
619010230	REMOVE SIGN	15.000	EACH
619010300	POSTS-TUBULAR STEEL	1,184.000	LB
620010301	CURB MARKING-YELLOW EPOXY	9.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	8.000	GAL
620012950	TEMPORARY STRIPING	0.100	MILE
620013955	REMOVE PAVEMENT MARKINGS	110.000	LNFT
620013960	STRIPING-WHITE EPOXY	2.000	GAL
620014960	STRIPING-YELLOW EPOXY	3.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 9148000

108 HSIP PROGRAM JOC - MISSOULA HSIP STWD(680) CONTRACT NO. JC519

This project includes the installation of signs, delineation, and solar flashers within MDT's Missoula District. Refer to Exhibit B & C for sites on the initial Job Order #1. Additional sites will be identified in subsequent job orders of this project. These sites may be located on NHS Interstate, NHS Non-Interstate, Primary, Secondary, and County or City routes.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - DELINEATION AND SIGNING			
JOC104000	MISCELLANEOUS WORK	10,000.000	UNIT
JOC107150	CONTAMINATED SOIL	6,000.000	UNIT
JOC109000	MOBILIZATION	1.000	LS
JOC617000	FOUNDATION CONCRETE	0.500	CUYD
JOC617100	SIG STANDARD TYPE 1-200	1.000	EACH
JOC617150	SOLAR SIG-TRAF 1 COLOR-1 WAY 12	1.000	EACH
JOC618150	TRAFFIC CONTROL-LS	1.000	LS
JOC618175	TRAFFIC CONTROL-FIXED	500.000	UNIT
JOC619000	SIGNS-ALUM REFL SHEET IV	100.000	SQFT
JOC619048	SIGNS-ALUM REFL SHEET XI	494.800	SQFT
JOC619050	REMOVE SIGNS	1.000	EACH
JOC619090	POLES TREATED WOOD 4 IN	702.000	LNFT
JOC619095	POLES TREATED WOOD 5 IN	100.000	LNFT
JOC619110	DELINEATOR SNOWPOLE	100.000	EACH
JOC619120	DELINEATOR	2,353.000	EACH
JOC619140	TOP MTD DELIN-SGL	100.000	EACH
JOC619160	TOP MTD DELIN-DBL	100.000	EACH
JOC619350	PANEL DELINEATOR	393.000	EACH
JOC619360	PANEL DELINATOR SNOWPOLE	100.000	EACH
JOC619370	LINEAR DELINEATOR	100.000	EACH
JOC620013	STRIPING-WHITE EPOXY	218.000	GAL
JOC620014	STRIPING-YELLOW EPOXY	71.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9668000

109 SF 159 BIG TIMBER SFTY IMPRV HSIP 298-1(17)0 CONTRACT NO. 09619

Centerline and shoulder epoxy striping, curve signing and delineation on SF 159 Big Timber Safety Improvement project in Sweet Grass County. This project is located on Secondary 298 beginning in Big Timber at the intersection with P-91, known as I-90 Frontage Road, at RP 0.0 and extends south to RP 25.6.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - DELINEATION, PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619011010	DELINEATOR DES A	785.000	EACH
619011040	DELINEATOR DES D	40.000	EACH
619011060	DELINEATOR DES F	445.000	EACH
620011260	WORDS AND SYMBOLS-WHITE EPOXY	35.000	GAL
620013960	STRIPING-WHITE EPOXY	1,257.000	GAL
620014960	STRIPING-YELLOW EPOXY	839.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 9111000

INVITATION FOR BIDS
LETTING OF July 11, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on July 11, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 BAD ROUTE INTERCHANGE - NE IM 94-6(60)193 CONTRACT NO. 01719

Grade, gravel, pms, overlay seal & cover, drainage, guardrail, pavement markings, signing, electrical and bridge deck work on the Bad Route Interchange-NE project in Dawson County.

The 6.5 mile project is located on Interstate 94 between the towns of Fallon and Glendive starting at the Bad Route Creek Int (RP 192.6) and ending near the Cracker Box Int (RP 199.2).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRAVEL, PMS OVERLAY, S & C, GUARDRAIL, SIGNING, ELECTRICAL, BRIDGE			
103000000	TRAINING PROGRAM	1,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
104030060	MISCELLANEOUS ITEMS-CUYD	264.000	CUYD
105080115	FINISH GRADE CONTROL	66,600.000	CRFT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	351.600	LNFT
202020097	REMOVE BRIDGE APPROACH SLAB	4.000	EACH
203020100	EXCAVATION-UNCLASSIFIED	15,811.000	CUYD
203020200	EXCAVATION-UNCLASS BORROW	103,615.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	15,379.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	40,316.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	6,574.000	CUYD
301020416	SHOULDER GRAVEL	14,808.000	CUYD
301020450	SPECIAL BACKFILL	8,970.000	CUYD
301020625	AGGREGATE TREATMENT	27,289.000	SQYD
302000000	PAVEMENT PULVERIZATION	150,261.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	28,918.000	TON
401020300	HYDRATED LIME	405.000	TON
402020095	ASPHALT CEMENT PG 70-28	1,559.700	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	13,326.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	334.300	TON
409000000	FINAL SWEEP AND BROOM	13.200	CRMI
409000010	COVER-TYPE 1	187,493.000	SQYD
411010000	COLD MILLING	19,520.000	SQYD
411011135	RUMBLE STRIPS	25.600	MILE
551020030	CONCRETE-CLASS GENERAL	96.800	CUYD
562000020	CLASS A BRIDGE DECK REPAIR	20.000	SQYD
563000040	POLYMER OVERLAY	1,851.400	SQYD
563000045	POLYMER OVERLAY PRIMER	1,851.400	SQYD
563000100	PREPARE DECK	1,851.400	SQYD
603000050	GRANULAR BEDDING MATERIAL	944.000	CUYD
603000110	CURED IN PLACE PIPE LINER-36 IN	277.000	LNFT
603000121	CURED IN PLACE PIPE LINER-48 IN	278.000	LNFT
603000126	CURED IN PLACE PIPE LINER-54 IN	678.000	LNFT
603000128	CURED IN PLACE PIPE LINER-58 IN	210.000	LNFT
603000131	CURED IN PLACE PIPE LINER-60 IN	296.000	LNFT
603000136	CURED IN PLACE PIPE LINER-72 IN	594.000	LNFT
603010020	FILL AND ABANDON PIPE	123.000	CUYD
603010540	CSP 24 IN	43.700	LNFT
603010574	CSP 36 IN	22.000	LNFT
603010632	CSP 54 IN	62.000	LNFT
603011070	CSPA 57 IN	70.000	LNFT
603012555	RCP 24 IN	184.000	LNFT
603012660	RCP 36 IN	54.000	LNFT
603012670	RCP 42 IN	42.000	LNFT
603012741	RCP 60 IN	58.000	LNFT
603012892	RCP IRR 24 IN	750.000	LNFT
603013203	RCPA 22 IN	90.000	LNFT
603013235	RCPA 58 IN	60.000	LNFT
603013352	REIN CONC BOX 7 X 3	1,602.000	LNFT
603013355	REIN CONC BOX 7 X 6	336.000	LNFT
603015270	EMBANKMENT PROTECTOR 18 IN	570.000	LNFT
603587010	REMOVE EMBANKMENT PROTECTOR	520.400	LNFT
603587020	REMOVE PIPE CULVERT	2,927.100	LNFT

604000140	REMOVE DROP INLET	8.000	EACH
604010270	INLET MEDIAN-TYPE 1	5.000	EACH
604010273	INLET MEDIAN-TYPE 2	5.000	EACH
604010605	DROP INLET-GRATE	2.000	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	927.800	LNFT
606010021	TEMP GD RAIL-STL/BR APPR-TY 1	7.000	EACH
606010023	ONE-WAY DEPART TERM SECTION	10.000	EACH
606010024	TEMP OPTIONAL TERM SECT	17.000	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	4,230.000	LNFT
606010268	GRD RL-BOX BEAM/BR APP-SEC-TYPE 3	9.000	EACH
606010370	RESET GUARDRAIL	3,636.000	LNFT
606010385	REMOVE GUARDRAIL	2,802.500	LNFT
606010641	GD RL BOX BEAM OPT TERM SEC	17.000	EACH
607100152	FARM FENCE-TYPE F3M-32 IN WW	71,127.000	LNFT
607100362	FARM FENCE-PANEL/SINGLE FM	211.000	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	215.000	EACH
607100720	DEADMAN	67.000	EACH
609010112	CURB 4 IN-CONCRETE	394.900	LNFT
609010203	REMOVE CURB	262.500	LNFT
610100101	SEEDING AREA NO 1	93.500	ACRE
610100102	SEEDING AREA NO 2	4.000	ACRE
610100103	SEEDING AREA NO 3	47.200	ACRE
610100555	CONDITION SEEDBED SURFACE	140.700	ACRE
610220100	MULCH	4.000	ACRE
611010025	CATTLE GUARD 24 FT-HEAVY DUTY (7.2 M)	1.000	EACH
611010200	REMOVE CATTLE GUARD	4.000	EACH
613100030	RIPRAP-CLASS 1 RANDOM	292.400	CUYD
613300050	BANK PROTECTION-TYPE 3	20.300	CUYD
616343914	CONDUIT-PLASTIC 1 1/2 IN	8,700.000	LNFT
616783006	PULL BOX-COMPOSITE TYPE 1	27.000	EACH
616783007	PULL BOX-COMPOSITE TYPE 2	1.000	EACH
617033313	CABLE-COPPER 4AWG12-600V	110.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	25,500.000	LNFT
617333198	SERV ASSEMBLY-200 AMP	1.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903100	CONTROL UNIT	2.000	EACH
617903462	CHANGEABLE MESSAGE SIGN	2.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030055	TRAFFIC CONTROL-RAMP CROSSOVER	4.000	EACH
618030080	TRAFFIC CONTROL	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	2.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	15.000	MILE
618030240	RAMP CROSSOVER	4.000	EACH
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	1.000	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	1.000	EACH
618030280	CROSSOVER RECLAMATION	6.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	1,054.300	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	64.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	92.900	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	20.000	SQFT
619010230	REMOVE SIGN	20.000	EACH
619010240	REMOVE SIGN-GUIDE	15.000	EACH
619010310	POSTS-STEEL U SIGN	462.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,405.000	LB
619010730	FRANG SIGN POST BKWY-W8 X 18 (W200 X 27	4.000	EACH
619011010	DELINEATOR DES A	200.000	EACH
619011020	DELINEATOR DES B	8.000	EACH
619011070	DELINEATOR DES G	47.000	EACH
619011080	DELINEATOR DES H	172.000	EACH
619011085	DELINEATOR DES BJ	3.000	EACH
620012950	TEMPORARY STRIPING	19.800	MILE
620013000	STRIPING-WHITE PAINT	630.000	GAL
620013960	STRIPING-WHITE EPOXY	420.000	GAL
620014000	STRIPING-YELLOW PAINT	476.000	GAL
620014960	STRIPING-YELLOW EPOXY	317.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	663.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	38,502.000	SQYD
SECTION NO. 0002 - ALTERNATE AA1- TYPICAL SECTION NO. 1			
301020340	CRUSHED AGGREGATE COURSE	35,276.000	CUYD
301020416	SHOULDER GRAVEL	8,747.000	CUYD
301020625	AGGREGATE TREATMENT	148,583.000	SQYD

401020045	PLANT MIX SURF GR S-3/4 IN	52,251.000	TON
401020300	HYDRATED LIME	732.000	TON
402020095	ASPHALT CEMENT PG 70-28	2,822.500	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	22,303.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	217.100	TON
409000010	COVER-TYPE 1	122,226.000	SQYD
411010000	COLD MILLING	140,312.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	164,223.000	SQYD
SECTION NO. 0003 - ALTERNATE AA2 - TYPICAL SECTION NO. 1			
301020340	CRUSHED AGGREGATE COURSE	36,263.000	CUYD
301020416	SHOULDER GRAVEL	18,654.000	CUYD
301020625	AGGREGATE TREATMENT	153,217.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	24,792.000	TON
401020250	MINERAL FILLER-CIR	176.400	TON
401020300	HYDRATED LIME	347.000	TON
401020325	COLD RECYCLED PLANT MIX	153,217.000	SQYD
402020095	ASPHALT CEMENT PG 70-28	1,338.300	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	30,700.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	217.400	TON
402020476	RECYCLING AGENT CIR-EE	706.900	TON
409000010	COVER-TYPE 1	122,226.000	SQYD
411010000	COLD MILLING	144,025.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	168,569.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 8150000

102 I-94 BRIDGE DECK - 2 M W FORSYTH NHPB 94-3(84)91 CONTRACT NO. 10719

Bridge deck replacement on two existing 4-span bridges over Smith Creek and Smith Creek Road, cold milling, PMS, guardrail replacement, curbing and seeding/revegetation on the I-94 Bridge Deck - 2 Miles West of Forsyth project in Rosebud County. The project is located approximately two miles west of Forsyth on I-94 between RP 92.1 and RP 92.5.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BR DECK REHAB, APPROACHES AND GUARDRAIL			
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
105080115	FINISH GRADE CONTROL	100.000	CRFT
105080200	BRIDGE SURVEY	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020097	REMOVE BRIDGE APPROACH SLAB	2.000	EACH
202020115	REMOVE DECK	2,211.700	SQYD
203020278	EXCAVATION-DIGOUTS	194.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	196.000	CUYD
301020625	AGGREGATE TREATMENT	284.000	SQYD
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	586.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	244.000	GAL
411010000	COLD MILLING	3,604.000	SQYD
411011135	RUMBLE STRIPS	0.400	MILE
551020107	CONCRETE-CLASS DECK	514.300	CUYD
555010200	REINFORCING STEEL-EPOXY COATED	162,458.000	LB
563000040	POLYMER OVERLAY	2,096.700	SQYD
563000100	PREPARE DECK	2,096.700	SQYD
603015270	EMBANKMENT PROTECTOR 18 IN	86.000	LNFT
605000092	36 IN SS CONCRETE BARRIER RAIL-BR	887.800	LNFT
606010041	GUARDRAIL-BOX BEAM/8 FT POST	3,744.000	LNFT
606010268	GRD RL-BOX BEAM/BR APP-SEC-TYPE 3	6.000	EACH
606010386	REMOVE AND SALVAGE GUARDRAIL	3,977.000	LNFT

606010641	GD RL BOX BEAM OPT TERM SEC	4.000	EACH
606010670	BOX BEAM DEPART TERM SEC	2.000	EACH
606011288	RESET BRIDGE APPROACH SECTION	1.000	EACH
606011300	RESET OPTIONAL TERMINAL SECT	1.000	EACH
609010112	CURB 4 IN-CONCRETE	240.000	LNFT
609010203	REMOVE CURB	1,692.000	LNFT
610100480	TURF REINF MAT-SYNTHETIC FIBER	298.000	SQYD
610100557	REVEGETATION	1.800	ACRE
613300050	BANK PROTECTION-TYPE 3	6.000	CUYD
613300060	BANK PROTECTION-TYPE 4	228.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	4.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	3.600	MILE
618030210	CROSSOVER-MAINTAIN, REMOVE	2.000	EACH
618030280	CROSSOVER RECLAMATION	2.000	EACH
619010200	RESET SIGNS	3.000	EACH
619011010	DELINEATOR DES A	10.000	EACH
619011080	DELINEATOR DES H	10.000	EACH
620013000	STRIPING-WHITE PAINT	3.000	GAL
620013960	STRIPING-WHITE EPOXY	4.000	GAL
620014000	STRIPING-YELLOW PAINT	3.000	GAL
620014960	STRIPING-YELLOW EPOXY	4.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	1,361.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	390.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 9681000

103 BLUE CREEK ROAD - BILLINGS UPP-STPB 1033(5) CONTRACT NO. 11719
SOUTH FRONTAGE ROAD-BILLINGS UPP 1011(20)
GUARDRAIL - SOUTH OF BILLINGS STPS 416-1(16)11

UPP-STPB 1033(5) - Cold milling, PMS overlay, rumble strips, seal & cover, pavement markings, guardrail, signing and bridge deck repair on the Blue Creek Road - Billings project located in Yellowstone County. The project begins at RP 0.1 on South Billings Blvd (U-1033) and extends approximately 3.2 miles southeast along Blue Creek Road to RP 2.6.

UPP 1011(20) - Cold milling, PMS overlay, seal & cover, pavement markings, guardrail, signing and bridge deck repair on the South Frontage Road-Billings project located in Yellowstone County. The project is located southwest of Billings beginning at the intersection with Mallowney Lane (RP 0.0) to the intersection of Wise Lane and Shiloh Road (RP 3.75).

STPS 416-1(16)11 - PMS shoulder widening and guardrail on the Guardrail-South of Billings project located in Yellowstone County and entirely within the Crow Indian Reservation. The project is located on Secondary 416 beginning at RP 10.5 and extends approximately 2.8 miles east along Blue Creek Road to RP 13.3, intersecting with Secondary 418 (Pryor Creek Road).

MANDATORY PRE-BID CONFERENCE (TRIBAL)

A pre-bid conference will be held at the following time and location:

Tuesday, June 25, 2019 at 2:00 P.M.

Billings District Conference Room

424 Morey Street, Billings, MT 59101

The pre-bid conference will have a formal sign-in process that will become the official record of attendance for the purposes of determining eligible bidders. Attendance at this conference is mandatory for any Contractor to submit a bid as a prime bidder. Contractors who bid as a prime bidder on this project must have at least one full time, permanent employee present. No proxy representatives, such as subcontractors or consultants, meet this requirement. In the event a prime bidder tenders a bid but did not attend the pre-bid conference, the bid will be returned unopened. Representatives of the Department will be present to describe the project and answer questions. Representatives of the Crow Tribe will be invited to the pre-bid conference. The pre-bid conference is for information only. The Department is not bound by any statement or representation concerning conditions or description of the work given by Department employees or agents and the pre-bid conference. The answers to any questions raised are non-binding oral

explanations or instructions, and relying on them is solely at the Bidder's risk. Any issues raised at the pre-bid conference must be posted on the Question and Answer Forum to be considered an enforceable provision of the contract to be let. The pre-bid attendee list and contract document clarifications or modifications considered necessary by the Department will be posted to the Question and Answer Forum.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GUARDRAIL, PMS			
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
107100010	CULTURAL RESOURCE PERSON	5.000	DAY
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	71.200	LNFT
202020139	REMOVE ASPHALT FROM DECK	1,446.500	SQYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	1,500.000	UNIT
210020000	GRADER-MOTOR	68.000	HOURL
301020416	SHOULDER GRAVEL	2,898.000	CUYD
301020625	AGGREGATE TREATMENT	2,211.000	SQYD
401020065	PLANT MIX SURF GR S-3/8 IN	10,520.000	TON
401020300	HYDRATED LIME	147.000	TON
402020095	ASPHALT CEMENT PG 70-28	652.600	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	7,967.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	286.400	TON
409000000	FINAL SWEEP AND BROOM	6.900	CRMI
409000020	COVER-TYPE 2	160,903.000	SQYD
411010000	COLD MILLING	80,887.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	1.400	MILE
411011135	RUMBLE STRIPS	5.700	MILE
552010805	MODIFY BRIDGE APPROACH SLAB	8.000	EACH
552011030	EXPANSION JOINT-ASPHALT PLUG	28.000	LNFT
552011110	JOINT SEALS-SILICONE	3.800	LNFT
561020110	BRIDGE DECK MILLING	470.400	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	4.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	2.000	SQYD
563000000	CONCRETE-CLASS OVERLAY	39.200	CUYD
563000040	POLYMER OVERLAY	470.400	SQYD
563000100	PREPARE DECK	1,446.500	SQYD
563000110	WATERPROOF MEMBRANE	976.100	SQYD
604000100	ADJUST MANHOLE	10.000	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	412.700	LNFT
605000045	REVISE CONC BARRIER RAIL END-BR	8.000	EACH
606010140	GUARDRAIL END SECTION WIDENING	15.000	EACH
606010330	MGS GUARDRAIL	7,425.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	34.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	3,612.500	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	225.000	LNFT
606010385	REMOVE GUARDRAIL	4,135.000	LNFT
610100557	REVEGETATION	1.900	ACRE
618030005	TRAFFIC CONTROL DEVICES CB	225,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	5.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	201.300	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	337.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	659.000	SQFT
619010230	REMOVE SIGN	128.000	EACH
619010240	REMOVE SIGN-GUIDE	7.000	EACH
619010310	POSTS-STEEL U SIGN	114.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	58.000	LB
619010480	POLES-TREATED WOOD 4 IN	554.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	32.000	LNFT
619010800	PANEL DELINEATOR DESIGN A	34.000	EACH
619010820	PANEL DELINEATOR DESIGN F	34.000	EACH
619011010	DELINEATOR DES A	206.000	EACH
619011040	DELINEATOR DES D	48.000	EACH
619011060	DELINEATOR DES F	19.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	160.000	EACH
619011165	TOP MTD BARRIER DELIN-DBL FACE-WHITE	4.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	39.000	GAL

620011105	WORDS AND SYMBOLS-WHITE PAINT	48.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	17.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	47.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	15.000	GAL
620012950	TEMPORARY STRIPING	8.400	MILE
620013000	STRIPING-WHITE PAINT	465.000	GAL
620013960	STRIPING-WHITE EPOXY	537.000	GAL
620014000	STRIPING-YELLOW PAINT	409.000	GAL
620014960	STRIPING-YELLOW EPOXY	439.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 9503000, 9501000, 9415000

104 FALLON AREA CULVERTS IM 94-5(44)184 CONTRACT NO. 06719

Remove and replace culverts at 5 locations on the Fallon Area Culverts project located in Prairie County. The project begins at RP 184.1 and extends approximately 2 miles northeast along Interstate Route 94 to RP 186.1 near the Fallon Interchange.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - REPLACE CULVERTS			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	850.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
551020030	CONCRETE-CLASS GENERAL	25.800	CUYD
603000060	FOUNDATION MATERIAL	18.000	CUYD
603010020	FILL AND ABANDON PIPE	530.000	CUYD
603015360	CONCRETE CASING-24"	138.000	LNFT
603015370	CONCRETE CASING-36"	672.000	LNFT
603015380	CONCRETE-CASING 60"	536.000	LNFT
603016005	SPECIAL INSTALLATION OF PIPE-CONCRETE	1,316.000	LNFT
603016100	STRUCTURAL CULVERT LINING	452.000	LNFT
603587020	REMOVE PIPE CULVERT	52.000	LNFT
604000140	REMOVE DROP INLET	1.000	EACH
604010273	INLET MEDIAN-TYPE 2	1.000	EACH
610100559	REVEGETATION	1.000	LS
613100030	RIPRAP-CLASS 1 RANDOM	35.500	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
622011043	PERM EROSION CONTROL-HIGH SURV	109.000	SQYD
622011084	GEOTEXTILE STABILIZATION	44.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 9029000

105 BECRAFT LANE SIDEWALK - LOCKWOOD TA 1099(125) CONTRACT NO. 04619

Installation of new sidewalk on the Becraft Lane Sidewalk-Lockwood project located within Lockwood in Yellowstone County. Work includes: gravel, PMS overlay, drainage, fencing, curb/gutter, irrigation and signing. The project begins at the intersection with Old Hardin Road and continues east along Becraft Lane to the intersection with Noblewood Drive.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PEDESTRIAN PATH			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	1,243.000	CUYD
203020200	EXCAVATION-UNCLASS BORROW	375.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	663.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	690.000	CUYD
301020348	DRAIN AGGREGATE	17.600	CUYD
401020022	COMMERCIAL MIX-PG 64-28	74.000	TON
603010528	CSP 18 IN	40.000	LNFT
603010540	CSP 24 IN	40.000	LNFT
603013462	PIPE-PVC 6 IN	80.000	LNFT
603013474	PIPE-PVC 15 IN	999.000	LNFT
603587020	REMOVE PIPE CULVERT	237.700	LNFT
604010265	INLET FRAME AND GRATE-REPLACE	1.000	EACH
607000015	FENCE-CHAIN LINK 3.5 FT	135.000	LNFT
607100153	FARM FENCE-TYPE F3M-39 IN WW	627.600	LNFT
607150125	RESET FENCE	115.000	LNFT
608010050	SIDEWALK-CONCRETE 6 IN	3,337.600	SQYD
608010110	CONCRETE 6 IN	42.000	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	19.000	SQYD
609010160	GUTTER-CONC VALLEY	31.200	SQYD
609010200	CURB AND GUTTER-CONC	66.700	LNFT
610100102	SEEDING AREA NO 2	1.200	ACRE
610100327	FERTILIZING AREA NO 2	1.200	ACRE
610100470	SODDING	447.000	SQYD
610100555	CONDITION SEEDBED SURFACE	1.200	ACRE
610220100	MULCH	1.200	ACRE
614010009	RETAINING WALL	43.300	SQYD
615010150	18 IN IRRIGATION STRUCTURE	10.000	EACH
615010155	24 IN IRRIGATION STRUCTURE	2.000	EACH
615010160	IRRIGATION ACCESS	8.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010062	SIGNS-ALUM SHEET INCR XI	5.200	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	10.000	SQFT
619010200	RESET SIGNS	9.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	63.000	LB
620011260	WORDS AND SYMBOLS-WHITE EPOXY	2.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	255.400	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator. Uniform No. 9158000

106 BOOTLEGGER TRAIL REPAIR ER 225-4(2)53 CONTRACT NO. 04719

Grading, gravel and installation of 3 culverts to repair damaged roadway on the Bootlegger Trail Repair project in Toole County. The project is located approximately 33 miles east of Conrad on Secondary 225 (Bootlegger Trail) between RP 52.6 and 52.8, 1.5 miles south of the intersection with St. Olaf Church Road. The section, township and range is in S34,35, T29N and R3E.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRAVEL, CULVERTS			
104030010	MISCELLANEOUS WORK	1,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020375	EMBANKMENT IN PLACE	4,323.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	462.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020526	TOP SURFACING GR 3B	656.000	CUYD
301020625	AGGREGATE TREATMENT	2,993.000	SQYD
551020030	CONCRETE-CLASS GENERAL	13.600	CUYD
603010040	DRAINAGE PIPE 18 IN	48.000	LNFT
603010048	DRAINAGE PIPE 24 IN	82.000	LNFT
603010068	DRAINAGE PIPE 48 IN	180.000	LNFT
603587020	REMOVE PIPE CULVERT	208.000	LNFT
610100557	REVEGETATION	0.700	ACRE
610100560	RIPRAP REVEGETATION	138.000	SQYD
613100030	RIPRAP-CLASS 1 RANDOM	91.100	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
622011043	PERM EROSION CONTROL-HIGH SURV	138.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	2,803.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.

Uniform No. 9623000

107 US-2 REPAIR - W OF HAVRE ER 1-6(129)376 CONTRACT NO. 05719

Slide and erosion repair on the US-2 Repair - W of Havre project in Hill County. The project is located on US 2/National Hwy 1, west of Havre between RP 375.7 and RP 376.5.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SLIDE & EROSION REPAIR			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
208010486	STREAMBED MATERIAL	477.000	CUYD
208010555	COIR LOGS	72.000	LNFT
301020450	SPECIAL BACKFILL	426.000	CUYD
603000050	GRANULAR BEDDING MATERIAL	29.000	CUYD
607100252	FARM FENCE-TYPE F4M	190.400	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	2.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	2.000	EACH
607100720	DEADMAN	1.000	EACH
610010100	TOPSOIL	131.000	CUYD
610100102	SEEDING AREA NO 2	0.200	ACRE
610100327	FERTILIZING AREA NO 2	0.200	ACRE
610100565	EROSION CONTROL BLANKET-HIGH-PERFORM	735.000	SQYD
610100575	COIR EROSION CONTROL NET	134.000	SQYD
613100040	RIPRAP-CLASS 2 RANDOM	583.000	CUYD
613520010	VEGETATED CONCRETE BLOCK MAT	34.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	15,000.000	UNIT
622011043	PERM EROSION CONTROL-HIGH SURV	912.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the

proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9625000

108 BIKE/PED PATH II HWY 93 - KALISPELL TA 6799(50) CONTRACT NO. 02719

Construct new shared use path on the Bike/Ped Path II Hwy 93-Kalispell project located in Kalispell in Flathead County. The project is located on the west side of Highway 93 near the Kalispell Sports Complex beginning at RP 114.9 and extending north to RP 115.1. Work includes: gravel, PMS overlay, pedestrian rail and signing.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - NEW BIKE/PED PATH			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	711.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	21.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	238.000	CUYD
401020057	COMMERCIAL MIX-3/8 IN-PG 58-28	184.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	57.000	GAL
557010105	PEDESTRIAN RAIL	132.000	LNFT
604000100	ADJUST MANHOLE	1.000	EACH
610100559	REVEGETATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010086	SIGNS-ALUM REFL SHEET IV	2.500	SQFT
619010230	REMOVE SIGN	1.000	EACH
619010310	POSTS-STEEL U SIGN	20.000	LB

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9451000

109 PVMS VEHICLE CERT SITE - HELENA STPX STWD(702) CONTRACT NO. 09719

Mill and fill three 12 foot wide lanes for calibrating certification vehicles to a specified standard for testing purposes. The project is located at the Rocky Mountain Emergency Services site on the Helena Airport property in Lewis and Clark County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL/FILL			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
401020055	COMMERCIAL MIX-3/8 IN-PG 64-28	618.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	252.000	GAL
411010000	COLD MILLING	4,800.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
 Uniform No. 9688000

110 SF 169 LOLO E MSLA SFTY IMPRV HSIP STWD(533) CONTRACT NO. 03719

Signing, rumble strips, delineation, electrical and pavement markings on the SF 169 Lolo E Missoula Safety Improvement project in Missoula County. The project is located at the following three sites:

- 1) North of Lolo, N-7 /US 93, RP 84.0 to 84.8.
- 2) West of Lolo, N-93/US 12, RP 30.0 to RP 32.366.
- 3) City of Missoula, U-8112/East Broadway/Hwy 200, RP 1.65 to RP 1.92.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SIGNING, DELINEATION, STRIPING & ELECTRICAL			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	2.600	MILE
411011135	RUMBLE STRIPS	1.500	MILE
616343920	CONDUIT-PLASTIC 2 IN	855.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	7.000	EACH
617000000	FOUNDATION-CONCRETE	1.500	CUYD
617033214	CABLE-COPPER 3AWG14-600V	900.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	510.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	855.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	1.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	1.000	EACH
617333150	SERV ASSEMB-50 AMP	1.000	EACH
617483110	SIG-TRAF 1 COL-1 WAY 12	2.000	EACH
617673200	SIG STANDARD TYPE 1-200	2.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	1.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010090	SIGNS-ALUM REFL SHEET XI	114.600	SQFT
619010480	POLES-TREATED WOOD 4 IN	98.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	16.000	LNFT
619011010	DELINEATOR DES A	59.000	EACH
619011040	DELINEATOR DES D	16.000	EACH
620013955	REMOVE PAVEMENT MARKINGS	16,364.000	LNFT
620013960	STRIPING-WHITE EPOXY	37.000	GAL
620014960	STRIPING-YELLOW EPOXY	75.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
 Uniform No. 9373000

111 SF 159 S-384 S-401 SFTY IMPRV HSIP STWD(433) CONTRACT NO. 08719

SF 159 BLGS DIST SIGN DELIN HSIP STWD(455)

SF 159 S-419 S-421 SFTY IMPRV HSIP STWD(435)

SF 159 BLGS DIST SFTY IMPRV HSIP STWD(431)

HSIP STWD(433) - Installation new delineation on the SF 159 S-384 S-401 Safety

Improvements project in Bighorn, Treasure and Yellowstone Counties with some work within the Crow Indian Reservation.

Site 1 - Secondary 384, east of Hardin at Junction P-48 between RP 0.0 and RP 56.8, near the I-94 Sarpy Creek Interchange. The first 12.6 miles are located on the Crow Indian Reservation.

Site 2 - Secondary 401, 7 miles north of Laurel beginning at the junction with S-532 between RP 0.0 to RP 2.6.

HSIP STWD (431) - Signing and delineation improvements on the SF 159 Billings District Safety Improvements project in Musselshell, Yellowstone and Big Horn Counties.

Site 1 - Approximately 10 miles southwest of Roundup on Secondary 381 between RP 4.5 and RP 4.8.

Site 2 - Old US Hwy 87 (X-81016), approximately 20 miles southeast of Billings between RP 18.9 and RP 26.2.

HSIP STWD (435) - Signing and delineation on the SF 159 S-419 S-421 Safety Improvements project in Stillwater County.

Site 1 - Secondary 419 beginning 3 miles south of Absarokee at the Junction with State Route 78 between RP 0.0 and RP 20.0.

Site 2 - Secondary 421 southeast of Columbus between RP 0.5 and RP 4.35.

HSIP STWD (455) - Signing and delineation on the SF 159 Billings District Signing Delineation project in Musselshell, Petroleum, Fergus and Treasure Counties.

Site 1 - MT 87 (N-16), south of Roundup near Klein between RP 43.5 and RP 47.8.

Site 2 - MT 200 (N-57), 7 miles west of Mosby between RP 151.4 and 152.0.

Site 3 - MT 81 (P-81), 3 miles west of Denton between RP 10.0 and RP 11.0.

Site 4 - Secondary 311, 8 miles southwest of Hysham between RP 9.7 and RP 10.1.

MANDATORY PRE-BID CONFERENCE (TRIBAL)

A pre-bid conference will be held at the following time and location:

Tuesday, June 25, 2019 at 1:00 p.m.,

Billings District Conference Room

424 Morey St.

Billings, MT 59101

The pre-bid conference will have a formal sign-in process that will become the official record of attendance for the purposes of determining eligible bidders. Attendance at this conference is mandatory for any Contractor to submit a bid as a prime bidder. Contractors who bid as a prime bidder on this project must have at least one full time, permanent employee present. No proxy representatives, such as subcontractors or consultants, meet this requirement. In the event a prime bidder tenders a bid but did not attend the pre-bid conference, the bid will be returned unopened. Representatives of the Department will be present to describe the project and answer questions. Representatives of the Crow Tribe will be invited to the pre-bid conference. The pre-bid conference is for information only. The Department is not bound by any statement or representation concerning conditions or description of the work given by Department employees or agents and the pre-bid conference. The answers to any questions raised are non-binding oral explanations or instructions, and relying on them is solely at the Bidder's risk. Any issues raised at the pre-bid conference must be posted on the Question and Answer Forum to be considered an enforceable provision of the contract to be let. The pre-bid attendee list and contract document clarifications or modifications considered necessary by the Department will be posted to the Question and Answer Forum.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - SIGNING, DELINEATION			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010090	SIGNS-ALUM REFL SHEET XI	290.900	SQFT
619010230	REMOVE SIGN	17.000	EACH
619010480	POLES-TREATED WOOD 4 IN	312.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	122.000	LNFT
619010800	PANEL DELINEATOR DESIGN A	164.000	EACH
619010820	PANEL DELINEATOR DESIGN F	78.000	EACH
619011010	DELINEATOR DES A	2,410.000	EACH
619011040	DELINEATOR DES D	10.000	EACH
619011060	DELINEATOR DES F	370.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	86.000	EACH
619011155	TOP MOUNTED BARRIER WHITE DELINEATOR	4.000	EACH
619011158	TOP MOUNTED W-BEAM WHITE DELINEATOR	2.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
 Uniform No. 9121000, 9119000, 9122000, 9118000

112 COLUMBIA FALLS - DETENTION POND NH 1-2(224)138 CONTRACT NO. 07719

Construct two storm water detention ponds, including grading, fencing and revegetation on the Columbia Falls - Detention Pond project in Flathead County. The project is located off US 2/National Hwy 1, one mile east of Columbia Falls between RP 138.0 and RP 138.5.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADING, FENCING AND REVEGETATION			
104030010	MISCELLANEOUS WORK	8,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020375	EMBANKMENT IN PLACE	351.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
607100259	FARM FENCE-TYPE F5W	20.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	2.000	EACH
607100440	FARM GATE-METAL-TYPE G-3	12.000	LNFT
610100559	REVEGETATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
 Uniform No. 9535000

INVITATION FOR BIDS
LETTING OF August 15, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on August 15, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 ROUSE AVE - BOZEMAN STPIP 86-1(30)0 CONTRACT NO. 06619

The Rouse Ave-Bozeman projects consists of grading, gravel surfacing, plant mix surfacing, curb and gutter, sidewalk, storm drains, city water and sewer utilities, signal and luminaire improvements and other miscellaneous work.

The project is located on Rouse Avenue (State Primary Route 86) beginning at RP 0.0 (Main Street) and extends north to the junction of Oak Street at RP 0.9. The project is located entirely within the urban boundary of Bozeman in Gallatin County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - G, GS, PMS, C & G, SIDEWALK, STORM DRAIN, DRAINAGE,			
ELECTRICAL			
103000000	TRAINING PROGRAM	1,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	100,000.000	UNIT
104030030	MISCELLANEOUS ITEMS-INSTALL	156.000	LNFT
105070410	PROPERTY SURVEY	1.000	LS
105080115	FINISH GRADE CONTROL	12,550.000	CRFT
107000020	CONTAMINATED SOIL	30,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
201110005	CLEARING	0.100	ACRE
201311000	REMOVE TREES	57.000	EACH
202020040	REMOVE STRUCTURE	2.000	EACH
203020225	EXCAVATION-STREET	27,927.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	11,792.000	CUYD
203030117	EXPLORATORY EXCAVATION	200.000	HOURL
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
208010486	STREAMBED MATERIAL	225.000	CUYD
210020170	TEST TRAILER-TRANSPORT, SETUP	164.000	MILE
301020340	CRUSHED AGGREGATE COURSE	7,719.000	CUYD
301020450	SPECIAL BACKFILL	1,700.000	CUYD
301020625	AGGREGATE TREATMENT	31,901.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	6,094.000	TON
401020055	COMMERCIAL MIX-3/8 IN-PG 64-28	1,932.000	TON
401020300	HYDRATED LIME	85.000	TON
402020092	ASPHALT CEMENT PG 64-28	331.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	4,701.000	GAL
555010200	REINFORCING STEEL-EPOXY COATED	2,200.000	LB
557010105	PEDESTRIAN RAIL	140.400	LNFT
557010110	HAND RAIL	25.000	LNFT
601011920	INSULATION	640.000	SQFT
603000050	GRANULAR BEDDING MATERIAL	1,862.000	CUYD
603000065	TRENCH DRAIN	204.000	LNFT
603000075	REMOVE SANITARY SEWER	34.500	LNFT
603000080	REMOVE WATER VALVE BOX	6.000	EACH
603000085	ADJUST WATER MAIN	6.000	EACH
603010020	FILL AND ABANDON PIPE	6.000	CUYD
603010025	PLUG ENDS AND ABANDON PIPE	1.000	EACH
603012800	RCP IRR 12 IN	1,663.100	LNFT
603012847	RCP IRR 18 IN	2,486.100	LNFT
603012892	RCP IRR 24 IN	594.100	LNFT
603012938	RCP IRR 36 IN	118.600	LNFT
603012960	RCP IRR 42 IN	1,161.600	LNFT
603013462	PIPE-PVC 6 IN	113.700	LNFT
603013465	PIPE-PVC PRESS 8 IN SANITARY	30.000	LNFT
603013549	CONNECT TO EXISTING PIPE	11.000	EACH
603013552	CONNECT TO EXISTING INLET	2.000	EACH
603013553	CONNECT TO EXISTING MANHOLE	1.000	EACH
603013580	WATER MAIN CROSSING	15.000	EACH
603014242	ADJUST VALVE BOX	40.000	EACH
603014490	FIRE HYDRANT	6.000	EACH
603587030	REMOVE STORM DRAIN	1,626.400	LNFT
603587035	ABANDON MAIN-STORM	1.000	LS
604000100	ADJUST MANHOLE	18.000	EACH
604000120	REMOVE FIRE HYDRANT	6.000	EACH

604000140	REMOVE DROP INLET	15.000	EACH
604010035	MANHOLE-48 IN TYPE 1	1.000	EACH
604010045	MANHOLE-48 IN TYPE 3	8.000	EACH
604010055	MANHOLE-54 IN TYPE 3	2.000	EACH
604010065	MANHOLE-60 IN TYPE 3	2.000	EACH
604010070	MANHOLE-66 IN TYPE 3	1.000	EACH
604010075	MANHOLE-72 IN TYPE 3	1.000	EACH
604010085	MANHOLE-84 IN TYPE 3	1.000	EACH
604010100	MANHOLE -102 IN TYPE 3	1.000	EACH
604010108	MANHOLE-120 IN TYPE 3	1.000	EACH
604010172	REMOVE MANHOLE	6.000	EACH
604010213	INLET DROP-TYPE 5	4.000	EACH
604010221	INLET DROP-TYPE 1	2.000	EACH
604010222	INLET DROP-TYPE 2	1.000	EACH
604010253	INLET CURB-TYPE A	7.000	EACH
604010255	INLET CURB-TYPE B	25.000	EACH
604010518	COMB 48 IN T3 MH-TA CURB INLET	1.000	EACH
604010524	COMB 66 IN T3 MH-TB CURB INLET	3.000	EACH
604010526	COMB 60 IN T3 MH-TB CURB INLET	1.000	EACH
604010549	COMB 48 IN T3 MH-TB CURB INLET	7.000	EACH
604010552	COMB 48 IN T3 MH-T5 DROP INL	2.000	EACH
604010597	COMB 66 IN T3 MH-T5 DI	3.000	EACH
604020090	HYDRODYNAMIC SEPARATOR	6.000	EACH
605000030	BARRIER RAIL-CAST IN PLACE-BR	27.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	2.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	462.500	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	1.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	3.000	EACH
606010385	REMOVE GUARDRAIL	318.900	LNFT
606400120	BOLLARDS	1.000	EACH
607000004	FENCE-CHAIN LINK	22.600	LNFT
607000030	FENCE-CHAIN LINK 4 FT	932.700	LNFT
607000050	FENCE-CHAIN LINK 6 FT	439.400	LNFT
607000075	FENCE-CHAIN LINK 8 FT	54.500	LNFT
607100389	FENCE-WOOD-2 RAIL	107.000	LNFT
607150125	RESET FENCE	40.200	LNFT
608010020	SIDEWALK-CONCRETE 4 IN	5,450.500	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	1,861.700	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	51.200	SQYD
609010013	PIN DOWN CURB	13.000	EACH
609010160	GUTTER-CONC VALLEY	367.000	SQYD
609010200	CURB AND GUTTER-CONC	10,579.300	LNFT
610010100	TOPSOIL	806.000	CUYD
610100101	SEEDING AREA NO 1	1.500	ACRE
610100326	FERTILIZING AREA NO 1	1.500	ACRE
610100470	SODDING	298.100	SQYD
610100555	CONDITION SEEDBED SURFACE	1.500	ACRE
610100560	RIPRAP REVEGETATION	16.000	SQYD
610590028	TREE	1.000	EACH
613100040	RIPRAP-CLASS 2 RANDOM	289.000	CUYD
613100080	RIPRAP-INFILL	170.000	CUYD
614010009	RETAINING WALL	953.000	SQYD
614010050	REINFORCED CONCRETE RETAINING WALL	930.000	SQFT
615010737	VALVE-GATE 6 IN W/BOX	3.000	EACH
616323114	CONDUIT-STEEL 1 1/2 IN RIGID	20.000	LNFT
616343910	CONDUIT-PLASTIC 1 IN	20.000	LNFT
616343914	CONDUIT-PLASTIC 1 1/2 IN	28.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	804.000	LNFT
616343924	CONDUIT-PLASTIC 2 1/2 IN	236.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	980.000	LNFT
616343931	CONDUIT-PLASTIC 4 IN	190.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	13.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	6.000	EACH
617000000	FOUNDATION-CONCRETE	51.000	CUYD
617000050	POLES-TREATED WOOD CLASS 4	80.000	LNFT
617033214	CABLE-COPPER 3AWG14-600V	70.000	LNFT
617033314	CABLE-COPPER 5AWG14-600V	870.000	LNFT
617033414	CABLE-COPPER 7AWG14-600V	1,850.000	LNFT
617033514	CABLE-COPPER 9AWG14-600V	170.000	LNFT
617033614	CABLE-COPPER 12AWG14-600V	260.000	LNFT
617033814	CABLE-COPPER 16AWG14-600V	1,310.000	LNFT

617086919	CABLE-COPPER 6 PAIR AWG 19 COM	400.000	LNFT
617099055	CABLE-COPPER COAXIAL 50 OHM 1/2 IN	30.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	300.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	1,160.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	2,120.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	1.000	EACH
617233030	CONTROLLER-CAB PEDESTAL TYPE P	3.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	5.000	EACH
617333160	SERV ASSEMB-60 AMP	4.000	EACH
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	19.000	EACH
617513125	SIG TRAF 4 COL 1 W 12-12-12-12	17.000	EACH
617523201	SIG-TRAF 12 IN LED RETROFIT	7.000	EACH
617533000	SIG-TRAF-BACKPLATE-REFLECTIVE	7.000	EACH
617553020	SIG-PEDESTRIAN TYPE 2	32.000	EACH
617573070	RECTANGULAR RAPID FLASHING BEACON	1.000	EACH
617605081	CONTRLR/TRAF-ACTUAT TYPE 8-A	4.000	EACH
617673100	SIG STANDARD TYPE 1-100	20.000	EACH
617673200	SIG STANDARD TYPE 1-200	2.000	EACH
617693504	SIG STANDARD TYPE 2-A-500-4	1.000	EACH
617693905	SIG STANDARD TYPE 2-A-900-5	1.000	EACH
617693906	SIG STANDARD TYPE 2-A-900-6	4.000	EACH
617693907	SIG STANDARD TYPE 2-A-900-7	1.000	EACH
617713054	SIG STANDARD TYPE 3-A-500-4	1.000	EACH
617713095	SIG STANDARD TYPE 3-A-900-5	2.000	EACH
617713097	SIG STANDARD TYPE 3-A-900-7	1.000	EACH
617725601	SIG STANDARD MODIFY	1.000	EACH
617733621	REMOVE AND RESET EXISTING POLE	1.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	15.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	20.000	EACH
617903540	YAGI ANTENNA-TYPE D	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	750,000.000	UNIT
618100005	PORTABLE VARIABLE MESSAGE SIGN	3.000	EACH
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	420.000	DAY
619010086	SIGNS-ALUM REFL SHEET IV	161.100	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	437.400	SQFT
619010200	RESET SIGNS	3.000	EACH
619010230	REMOVE SIGN	69.000	EACH
619010300	POSTS-TUBULAR STEEL	348.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	3,382.000	LB
619010740	FRANG SIGN POST BKWY-3 IN RD (76 MM)	4.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	10.000	EACH
620010300	CURB MARKING-YELLOW PAINT	72.000	GAL
620010301	CURB MARKING-YELLOW EPOXY	100.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	28.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	10.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	20.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	6.000	GAL
620012950	TEMPORARY STRIPING	1.800	MILE
620013000	STRIPING-WHITE PAINT	150.000	GAL
620013960	STRIPING-WHITE EPOXY	93.000	GAL
620014000	STRIPING-YELLOW PAINT	86.000	GAL
620014960	STRIPING-YELLOW EPOXY	65.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	397.000	SQYD
622011084	GEOTEXTILE STABILIZATION	2,613.000	SQYD
623000155	MAILBOX	28.000	EACH
623000190	RESET MAILBOX	3.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 4805

102 MAIN STREET - LEWISTOWN NH 57-3(64)81 CONTRACT NO. 03819
 1ST AVE N - LEWISTOWN NH 43-1(39)0
 TRUCK ROUTE - LEWISTOWN NH 75-1(7)0

NH 57-3(64)81 - Cold milling, PMS overlay, sidewalks, curb/gutter, vault closure, trees, seal & cover and pavement markings on the Main Street-Lewistown project located within the Lewistown city limits in Fergus County. The project begins at RP 81.4 near 15th Ave N and extends approximately 1.8 miles northeast and east along National Highway Route 57/Main Street to RP 83.2 near Marcella Avenue.

NH 75-1(7)0 - Cold milling, PMS overlay, drainage, guardrail, sidewalk, curb/gutter, seal & cover and pavement markings on the Truck Route-Lewistown project located within the Lewistown city limits in Fergus County. The project begins at RP 0.6 and extends approximately 2.3 miles north and east along National Highway Route 75/Truck Route Bypass/6th Ave to RP 2.8 at the intersection with US Hwy 191/1st Ave N.

NH 43-1(39)0 - Cold milling, PMS overlay, bridge repair, drainage, sidewalk, curb/gutter, electrical, seal & cover and pavement markings on the 1st Ave N-Lewistown project located within the Lewistown city limits in Fergus County. The project begins at RP 0.0 at the intersection with Main Street and extends approximately 0.3 miles northwest along 1st Ave N to RP 0.3 at the intersection with US Hwy 191/1st Ave N.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - 3 TIED LEWISTOWN PROJECTS			
104030010	MISCELLANEOUS WORK	60,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
104030045	MISCELLANEOUS ITEMS-EACH	85.000	EACH
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
201311000	REMOVE TREES	33.000	EACH
202020139	REMOVE ASPHALT FROM DECK	189.000	SQYD
203020278	EXCAVATION-DIGOUTS	1,787.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	800.000	CUYD
203020375	EMBANKMENT IN PLACE	175.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	831.000	CUYD
301020625	AGGREGATE TREATMENT	1,710.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	14,114.000	TON
401020300	HYDRATED LIME	197.000	TON
402020095	ASPHALT CEMENT PG 70-28	706.800	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5,697.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	188.500	TON
409000000	FINAL SWEEP AND BROOM	4.400	CRMI
409000020	COVER-TYPE 2	105,465.000	SQYD
411010000	COLD MILLING	106,081.000	SQYD
563000100	PREPARE DECK	189.000	SQYD
563000110	WATERPROOF MEMBRANE	189.000	SQYD
603000050	GRANULAR BEDDING MATERIAL	23.000	CUYD
603013452	PIPE-PVC 12 IN	29.600	LNFT
603013457	PIPE-PVC 8 IN	6.000	LNFT
603013462	PIPE-PVC 6 IN	60.000	LNFT
603014242	ADJUST VALVE BOX	33.000	EACH
603014470	RCP TEE	1.000	EACH
603587030	REMOVE STORM DRAIN	86.000	LNFT
604000100	ADJUST MANHOLE	33.000	EACH
604000140	REMOVE DROP INLET	13.000	EACH
604010213	INLET DROP-TYPE 5	3.000	EACH
604010221	INLET DROP-TYPE 1	10.000	EACH
604010255	INLET CURB-TYPE B	2.000	EACH
604010265	INLET FRAME AND GRATE-REPLACE	2.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	3.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	2,125.000	LNFT
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	312.500	LNFT
606010385	REMOVE GUARDRAIL	2,463.000	LNFT
608000010	TREE GRATE	35.000	EACH
608000020	SIDEWALK DRAIN	5.000	EACH
608000040	VAULT CLOSURE	1.000	LS
608010020	SIDEWALK-CONCRETE 4 IN	4,515.100	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	684.500	SQYD
608010051	SIDEWALK-PATTERNED CONC 4 IN	67.400	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	38.600	SQYD

609010200	CURB AND GUTTER-CONC	5,970.700	LNFT
610100470	SODDING	1,124.000	SQYD
610590028	TREE	35.000	EACH
616343920	CONDUIT-PLASTIC 2 IN	290.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	4.000	EACH
617000000	FOUNDATION-CONCRETE	1.000	CUYD
617033414	CABLE-COPPER 7AWG14-600V	640.000	LNFT
617033514	CABLE-COPPER 9AWG14-600V	310.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	560.000	LNFT
617673080	SIG STANDARD TYPE 1-80	5.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617783030	REMOVE AND RESET MISC ELECTRICAL	1.000	LS
617903510	ELECTRICAL MISCELLANEOUS	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010058	SIGNS-ALUM SHEET INCR IV	257.100	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	32.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	362.500	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	855.200	SQFT
619010230	REMOVE SIGN	116.000	EACH
619010240	REMOVE SIGN-GUIDE	8.000	EACH
619010300	POSTS-TUBULAR STEEL	673.000	LB
619010310	POSTS-STEEL U SIGN	58.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	1,034.000	LB
619010480	POLES-TREATED WOOD 4 IN	182.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	28.000	LNFT
619010740	FRANG SIGN POST BKWY-3 IN RD (76 MM)	2.000	EACH
619011010	DELINEATOR DES A	18.000	EACH
619011040	DELINEATOR DES D	13.000	EACH
619011060	DELINEATOR DES F	51.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	150.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	327.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	136.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	4.000	GAL
620012950	TEMPORARY STRIPING	8.900	MILE
620013000	STRIPING-WHITE PAINT	516.000	GAL
620013960	STRIPING-WHITE EPOXY	229.000	GAL
620014000	STRIPING-YELLOW PAINT	468.000	GAL
620014960	STRIPING-YELLOW EPOXY	203.000	GAL
622011084	GEOTEXTILE STABILIZATION	2,676.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 8990000, 8989000, 8988000

103 LOLO PASS - EAST NH 93-1(19)0 CONTRACT NO. 02819
LOLO HOT SPRINGS - EAST NH 93-1(21)8

NH 93-1(19)0 - The Lolo Pass - East project consists of cold milling, plant mix bituminous surfacing, seal and cover, guardrail and bridge rail upgrades, signing and other miscellaneous improvements. The project is located on National Highway Route 93/US 12 beginning at the Idaho/Montana border at RP 0.0 and extends east 8.3 miles to RP 8.3.

NH 93-1(21)8 - The Lolo Hot Springs - East project consists of cold milling, plant mix bituminous surfacing, seal and cover, guardrail upgrades, signing and other miscellaneous improvements. The project is located on National Highway Route 93/US 12 beginning at RP 8.3 and extends east 7.9 miles to RP 16.2.

Both projects are located in Missoula County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - ROAD WORK - MILL, PMS OVERLAY, S & C			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
202020140	REMOVE BITUMINOUS PAVEMENT	139.000	SQYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	60.000	MILE
301020416	SHOULDER GRAVEL	285.000	CUYD
401020048	PLANT MIX SURF GR S-1/2 IN	23,069.000	TON
401020300	HYDRATED LIME	323.000	TON
402020092	ASPHALT CEMENT PG 64-28	1,340.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	9,320.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	19,955.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	494.400	TON
403010255	CRACK SEALING	2,389.000	LB
409000010	COVER-TYPE 1	274,609.000	SQYD
411010000	COLD MILLING	187,577.000	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	8.300	MILE
557010544	REVISE TIMBER BRIDGE RAIL-THRIE BEAM	387.320	LNFT
605000070	REMOVE CONCRETE BARRIER RAIL	6.000	EACH
606010150	GUARDRAIL-STL/BR APPR-TY 1	6.000	EACH
606010330	MGS GUARDRAIL	3,824.200	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	23.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	87.500	LNFT
606010385	REMOVE GUARDRAIL	5,155.600	LNFT
610100559	REVEGETATION	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	150,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	39.500	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	173.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	64.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	399.800	SQFT
619010200	RESET SIGNS	1.000	EACH
619010230	REMOVE SIGN	64.000	EACH
619010240	REMOVE SIGN-GUIDE	7.000	EACH
619010310	POSTS-STEEL U SIGN	264.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	694.000	LB
619010480	POLES-TREATED WOOD 4 IN	716.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	90.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7 (S100X11)	4.000	EACH
619011010	DELINEATOR DES A	670.000	EACH
619011040	DELINEATOR DES D	14.000	EACH
619011060	DELINEATOR DES F	329.000	EACH
619011200	DELINEATION-LINEAR-BARRIER-WHITE	720.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	8.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	8.000	GAL
620012950	TEMPORARY STRIPING	10.200	MILE
620013000	STRIPING-WHITE PAINT	958.000	GAL
620013960	STRIPING-WHITE EPOXY	782.000	GAL
620014000	STRIPING-YELLOW PAINT	861.000	GAL
620014960	STRIPING-YELLOW EPOXY	653.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9493000, 9494000

INVITATION FOR BIDS
LETTING OF September 5, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on September 5, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 LOHMAN - E & W NHIP 1-7(44)393 CONTRACT NO. 01919

Reconstruction of the existing roadway on the Lohman-E&W project located in Blaine County. Work includes: cold milling, grading, gravel, PMS overlay, replace structures, fencing, drainage, guardrail, seal & cover and pavement markings. The project begins at RP 393.1 and extends approximately 10.4 miles east along National Highway Route 1/US 2 to RP 403.5. The Chinook city limits begin at RP 403.601.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RECONSTRUCTION OF EXISTING ROADWAY AND BRIDGES			
103000000	TRAINING PROGRAM	2,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
104030060	MISCELLANEOUS ITEMS-CUYD	28,765.000	CUYD
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
107000060	NOXIOUS WEED CONTROL	400.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	381,182.000	CUYD
203020175	EXCAVATION-UNCLASS CHANNEL	125.000	CUYD
203020200	EXCAVATION-UNCLASS BORROW	69,291.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	45,747.000	CUYD
203020380	SPECIAL EMBANKMENT	1,119.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	57,184.000	CUYD
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.000	LS
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
208010486	STREAMBED MATERIAL	260.000	CUYD
210020170	TEST TRAILER-TRANSPORT, SETUP	32.000	MILE
301020252	BRIDGE END BACKFILL-TYPE 1	3,317.000	CUYD
301020268	TRAFFIC GRAVEL	9,731.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	48,992.000	CUYD
301020450	SPECIAL BACKFILL	4,990.000	CUYD
301020625	AGGREGATE TREATMENT	142,770.000	SQYD
304010002	BLOTTER MATERIAL	190,227.000	SQYD
304010005	BASE-CEMENT TREATED	51,432.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	82,873.000	TON
401020300	HYDRATED LIME	1,160.000	TON
402020095	ASPHALT CEMENT PG 70-28	4,393.700	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	34,442.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	103.000	GAL
402020360	EMULSIFIED ASPHALT CRS-2	162.300	TON
402020375	EMULSIFIED ASPHALT CHFRS-2P	637.500	TON
409000000	FINAL SWEEP AND BROOM	15.000	CRMI
409000010	COVER-TYPE 1	312,004.000	SQYD
411010000	COLD MILLING	18,498.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	10.200	MILE
411011135	RUMBLE STRIPS	20.400	MILE
551020030	CONCRETE-CLASS GENERAL	47.100	CUYD
551020035	CONCRETE-CLASS STRUCTURE	432.400	CUYD
551020107	CONCRETE-CLASS DECK	584.100	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	45.000	CUYD
552010140	TRANSVERSE DECK GROOVING	1,061.000	SQYD
552011120	JOINT SEALS-POLYURETHANE	137.200	LNFT
553010632	PRESTRESSED GIRDER-SLAB	1,653.500	LNFT
555010100	REINFORCING STEEL	75,171.000	LB
555010200	REINFORCING STEEL-EPOXY COATED	196,892.000	LB
559010202	RE-DRIVE TEST PILE	6.000	EACH
559040025	STATIC LOAD TEST	1.000	EACH
559040035	DYNAMIC LOAD TEST	6.000	EACH
559050103	FURN STEEL PIPE PILE 16 X 1/2 IN	7,873.000	LNFT
559060103	DRIVE STEEL PIPE PILE 16 X 1/2	7,212.000	LNFT
559060200	PILE CUTTING SHOE	2.000	EACH
559060350	PILE CONICAL DRIVING POINT	105.000	EACH

563000100	PREPARE DECK	755.000	SQYD
563000110	WATERPROOF MEMBRANE	755.000	SQYD
603000050	GRANULAR BEDDING MATERIAL	561.000	CUYD
603000055	BEDDING MATERIAL	44.000	CUYD
603000060	FOUNDATION MATERIAL	788.000	CUYD
603010020	FILL AND ABANDON PIPE	24.000	CUYD
603010040	DRAINAGE PIPE 18 IN	484.000	LNFT
603010048	DRAINAGE PIPE 24 IN	764.000	LNFT
603010056	DRAINAGE PIPE 30 IN	210.000	LNFT
603010540	CSP 24 IN	22.000	LNFT
603012555	RCP 24 IN	1,788.000	LNFT
603012660	RCP 36 IN	322.000	LNFT
603012670	RCP 42 IN	578.000	LNFT
603012705	RCP 48 IN	260.000	LNFT
603012725	RCP 54 IN	204.000	LNFT
603012777	RCP 78 IN	102.000	LNFT
603012847	RCP IRR 18 IN	286.000	LNFT
603012892	RCP IRR 24 IN	108.000	LNFT
603012925	RCP IRR 30 IN	194.000	LNFT
603012938	RCP IRR 36 IN	60.400	LNFT
603013045	RCP SIPHON 18 IN	148.000	LNFT
603013226	RCPA 51 IN	146.000	LNFT
603013263	RCPA 88 IN	50.000	LNFT
603013315	REIN CONC BOX 18 X 4	102.000	LNFT
603013331	REIN CONC BOX 8 X 5	158.000	LNFT
603013358	REIN CONC BOX 14 X 6	123.000	LNFT
603013475	PIPE-PVC PRESS 12 IN SANITARY	133.000	LNFT
603013478	PIPE-PVC PRESS 12 IN WATER	189.000	LNFT
603015270	EMBANKMENT PROTECTOR 18 IN	512.000	LNFT
603587020	REMOVE PIPE CULVERT	4,616.700	LNFT
604010045	MANHOLE-48 IN TYPE 3	1.000	EACH
604010055	MANHOLE-54 IN TYPE 3	1.000	EACH
605000030	BARRIER RAIL-CAST IN PLACE-BR	683.800	LNFT
606010330	MGS GUARDRAIL	3,175.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	16.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	112.500	LNFT
606010370	RESET GUARDRAIL	187.500	LNFT
606010385	REMOVE GUARDRAIL	4,452.900	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	36.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	4.000	EACH
607100095	FARM FENCE-TYPE F1W-32 IN WW	4,772.000	LNFT
607100111	FARM FENCE-TYPE F2W-39 IN WW	30.000	LNFT
607100114	FARM FENCE-TYPE F2W-32 IN WW	4,774.000	LNFT
607100229	FARM FENCE-TYPE F4W	7,904.000	LNFT
607100252	FARM FENCE-TYPE F4M	13,942.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	210.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	17.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	140.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	138.000	LNFT
607100551	FENCE-TEMPORARY	1,290.000	LNFT
607100720	DEADMAN	12.000	EACH
609010010	CURB-CONCRETE	813.100	LNFT
610100101	SEEDING AREA NO 1	124.600	ACRE
610100102	SEEDING AREA NO 2	20.000	ACRE
610100103	SEEDING AREA NO 3	36.500	ACRE
610100326	FERTILIZING AREA NO 1	124.600	ACRE
610100490	TURF REINF MAT-NATURAL FIBER	369.000	SQYD
610100555	CONDITION SEEDBED SURFACE	161.100	ACRE
610100560	RIPRAP REVEGETATION	1,164.000	SQYD
610100565	EROSION CONTROL BLANKET-HIGH-PERFORM	9,687.000	SQYD
610100566	EROSION CONTROL BLANKET-SHORT-TERM	850.000	SQYD
610100575	COIR EROSION CONTROL NET	1,060.000	SQYD
610220100	MULCH	20.000	ACRE
610400012	REVEGETATION-STREAMBANK	0.190	ACRE
613100030	RIPRAP-CLASS 1 RANDOM	248.000	CUYD
613100040	RIPRAP-CLASS 2 RANDOM	792.700	CUYD

613300050	BANK PROTECTION-TYPE 3	55.600	CUYD
618030005	TRAFFIC CONTROL DEVICES CB	900,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	112.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	187.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	379.600	SQFT
619010230	REMOVE SIGN	63.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010310	POSTS-STEEL U SIGN	220.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	267.000	LB
619010480	POLES-TREATED WOOD 4 IN	1,010.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	160.000	LNFT
619010724	FRANG SIGN POST BKWY-S5 X 10 (S130X15)	2.000	EACH
619011010	DELINEATOR DES A	243.000	EACH
619011040	DELINEATOR DES D	18.000	EACH
619011070	DELINEATOR DES G	44.000	EACH
619011155	TOP MOUNTED BARRIER WHITE DELINEATOR	4.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	76.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	117.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	50.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	26.000	GAL
620012950	TEMPORARY STRIPING	38.400	MILE
620013000	STRIPING-WHITE PAINT	870.000	GAL
620013960	STRIPING-WHITE EPOXY	580.000	GAL
620014000	STRIPING-YELLOW PAINT	599.000	GAL
620014960	STRIPING-YELLOW EPOXY	399.000	GAL
622010075	GEOGRID - BIAXIAL	16,830.000	SQYD
622011043	PERM EROSION CONTROL-HIGH SURV	1,277.000	SQYD
622011047	GEOSYNTHETIC CLAY LINER	189.000	SQYD
622011084	GEOTEXTILE STABILIZATION	161,882.000	SQYD
623000155	MAILBOX	11.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
 Uniform No. 6281000

102 TERRY-FALLON AREA NHS BRIDGES NHPB 94-5(48)170 CONTRACT NO. 02919
TERRY-FALLON AREA STP BRIDGES STPB STWD(686)

NHPB 94-5(48)170 - Bridge deck rehabilitation including deck repair, milling, overlay, expansion joints and bridge rail on the Terry-Fallon Area NHS Bridges project in Prairie County.

The project is on Interstate 94 with dual structures at the following locations:

- 1) Powder River (RP 69.8) - 7 miles southwest of Terry
- 2) BN Railroad (RP 185.1) - southwest of Fallon
- 3) Yellowstone River (RP 186.9) - 1 mile northeast of Fallon

STPB STWD(686) - Bridge deck rehabilitation including deck repair, polymer overlay and expansion joints on the Terry-Fallon Area STP Bridges project in Prairie County. The project includes structures located on Secondary 253 at the Terry Interchange over I-94 (RP 176.5) and O' Fallon Creek on a frontage road approximately 1 mile west of Fallon and north of I-94.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILLING, PMS OVERLAY, SEAL & COVER			
103000000	TRAINING PROGRAM	500.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	20,000.000	UNIT

109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	394.300	LNFT
202020097	REMOVE BRIDGE APPROACH SLAB	6.000	EACH
203020278	EXCAVATION-DIGOUTS	12,066.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	6,882.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	1,000.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	3,897.000	CUYD
301020625	AGGREGATE TREATMENT	6,436.000	SQYD
401020022	COMMERCIAL MIX-PG 64-28	3,127.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,288.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	18.400	TON
409000000	FINAL SWEEP AND BROOM	0.500	CRMI
409000010	COVER-TYPE 1	10,216.000	SQYD
411010000	COLD MILLING	5,336.000	SQYD
501010401	CONCRETE-SHALLOW REPAIR	9.000	SQYD
552010041	REVISE JOINT	283.200	LNFT
552010059	EPOXY INJECTION	22.000	LNFT
552010140	TRANSVERSE DECK GROOVING	17,027.200	SQYD
552011040	REFURBISH EXPANSION JOINT	166.000	LNFT
552011140	RESEAL EXISTING JOINTS	77.900	LNFT
561010525	EXPANSION JOINT-PRECOMPRESSED	272.400	LNFT
561020110	BRIDGE DECK MILLING	17,907.600	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	115.000	SQYD
563000000	CONCRETE-CLASS OVERLAY	1,243.400	CUYD
563000040	POLYMER OVERLAY	2,462.100	SQYD
563000045	POLYMER OVERLAY PRIMER	2,462.100	SQYD
563000100	PREPARE DECK	2,462.100	SQYD
603015270	EMBANKMENT PROTECTOR 18 IN	268.000	LNFT
603587010	REMOVE EMBANKMENT PROTECTOR	28.000	LNFT
605000040	REVISE CONCRETE BARRIER RAIL-BR	7,851.500	LNFT
606010020	GUARDRAIL-TEMPORARY	288.000	LNFT
606010021	TEMP GD RAIL-STL/BR APPR-TY 1	4.000	EACH
606010022	TEMP GD RAIL-STL/BR APPR-TY 3	4.000	EACH
606010024	TEMP OPTIONAL TERM SECT	8.000	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	4,356.000	LNFT
606010268	GRD RL-BOX BEAM/BR APP-SEC-TYPE 3	4.000	EACH
606010325	GRD RL-BOX BEAM TO W-BEAM TRANS	16.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010385	REMOVE GUARDRAIL	6,257.300	LNFT
606010641	GD RL BOX BEAM OPT TERM SEC	15.000	EACH
606010670	BOX BEAM DEPART TERM SEC	2.000	EACH
609010010	CURB-CONCRETE	939.700	LNFT
609010203	REMOVE CURB	892.400	LNFT
610100490	TURF REINF MAT-NATURAL FIBER	254.000	SQYD
613300050	BANK PROTECTION-TYPE 3	32.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	1,000.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010100	OVERLAY-SHEET ALUM TYPE IV	8.000	SQFT
619010340	POSTS-TUBULAR STEEL-SQ-PERF	39.000	LB
620012950	TEMPORARY STRIPING	1.400	MILE
620013000	STRIPING-WHITE PAINT	62.000	GAL
620013960	STRIPING-WHITE EPOXY	39.000	GAL
620014000	STRIPING-YELLOW PAINT	52.000	GAL
620014960	STRIPING-YELLOW EPOXY	33.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	238.000	SQYD
622011084	GEOTEXTILE STABILIZATION	11,482.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 8127001, 8127002

103 W FORK RD SLIDE REPAIR (S-473) STPS 473-1(11)12 CONTRACT NO. 08919

Slide repair and stabilization to include excavation, specialized blasting, rock scaling and rock bolting on the West Fork Road Slide Repair (S-473) project in Ravalli County. The project is on state route S-473 (West Fork Road), approximately 12 miles southwest of the junction of US 93 and S-473 between RP 12.3 and RP 12.6.

MANDATORY PRE-BID CONFERENCE

A pre-bid conference will be held at the following time and location: **Tuesday, August 20, 2019 at 1:30 PM at the project site.**

The pre-bid conference will have a formal sign-in process that will become the official record of attendance for the purposes of determining eligible bidders.

Attendance at this conference is mandatory for any Contractor to submit a bid as a prime bidder. Contractors who bid as a prime bidder on this project must have at least one full time, permanent employee present. No proxy representatives, such as subcontractors or consultants, meet this requirement. In the event a prime bidder tenders a bid but did not attend the pre-bid conference, the bid will be returned unopened.

Representatives of the Department will be present to describe the project and answer questions. The pre-bid conference is for information only. The Department is not bound by any statement or representation concerning conditions or description of the work given by Department employees or agents and the pre-bid conference. The answers to any questions raised are non-binding oral explanations or instructions, and relying on them is solely at the Bidder's risk. Any issues raised at the pre-bid conference must be posted on the Question and Answer Forum to be considered an enforceable provision of the contract to be let. The pre-bid attendee list and contract document clarifications or modifications considered necessary by the Department will be posted to the Question and Answer Forum.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - EXCAVATION, SCALING AND ROCK BLASTING			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	2,300.000	CUYD
203020360	SCALING	700.000	HOURL
203020450	DRILL BLAST HOLE	1,400.000	LNFT
203030110	ROCK BOLT	600.000	LNFT
204010185	BLASTING CONSULTANT	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
606010097	TEMPORARY ROCKFALL PROTECTION	1.000	LS
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
610100559	REVEGETATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
618190100	TEMPORARY BARRIER RAIL	500.000	LNFT

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.

Uniform No. 9780000

INVITATION FOR BIDS
LETTING OF September 19, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on September 19, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

201 I-15 BRIDGES (RP 234-248) NHPB 15-4(166)234 CONTRACT NO. 04919

Guardrail, barrier rail, curb, pavement markings and deck rehabilitation on the I-15 Bridges (RP 234-248) project in Lewis & Clark and Cascade Counties.

The project is located on Interstate 15 between Craig and Hardy from RP 234.2 to RP 247.3 and includes work on 20 structures.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GUARDRAIL, PAVEMENT MARKINGS, CROSSOVERS			
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	35,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
552010060	REPAIR STRUCTURE	1.000	LS
552010160	BRIDGE DECK CRACK SEAL	23,151.900	SQYD
552010805	MODIFY BRIDGE APPROACH SLAB	26.000	EACH
552011110	JOINT SEALS-SILICONE	3,965.300	LNFT
552011120	JOINT SEALS-POLYURETHANE	719.000	LNFT
552011140	RESEAL EXISTING JOINTS	198.800	LNFT
561010525	EXPANSION JOINT-PRECOMPRESSED	573.100	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	1,033.800	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.000	SQYD
563000040	POLYMER OVERLAY	23,319.900	SQYD
563000100	PREPARE DECK	23,319.900	SQYD
605000040	REVISE CONCRETE BARRIER RAIL-BR	12,701.800	LNFT
605000090	CONCRETE BARRIER RAIL	203.000	EACH
606010330	MGS GUARDRAIL	8,187.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	32.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	40.000	EACH
606010385	REMOVE GUARDRAIL	10,417.200	LNFT
609010010	CURB-CONCRETE	460.000	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
618030180	TRAFFIC CONTROL-CROSSOVER	4.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	6.600	MILE
618030300	CROSSOVER-MAINTAIN, CLOSE	1.000	EACH
618030310	CROSSOVER-MEDIAN BARRIER RAIL	3.000	EACH
618100000	SINGLE USE SIGNS	231.000	SQFT
618190100	TEMPORARY BARRIER RAIL	2,896.500	LNFT
618190110	RESET TEMP BARRIER RAIL	2,896.500	LNFT
620013960	STRIPING-WHITE EPOXY	97.000	GAL
620014960	STRIPING-YELLOW EPOXY	78.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
 Uniform No. 8085004

202 GREAT FALLS SOUTH - URBAN UPP 5299(132) CONTRACT NO. 03919

Plant Mix Overlay, seal & cover, guardrail, signing and pavement markings on the Great Falls South - Urban project in Cascade County. The project is located between RP 3.0 and RP 3.9 on Urban Route U-5215 (13th St. S., 55th Ave. S.) and between RP 3.8 and RP 0.15 on Urban Route U-5207 (Lower River Road).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PMS O'LAY, G'RAIL, S&C, SIGNING AND PVMT MKGS			
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
203030117	EXPLORATORY EXCAVATION	40.000	HOURL
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020000	GRADER-MOTOR	60.000	HOURL
301020416	SHOULDER GRAVEL	453.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	11,019.000	TON
401020300	HYDRATED LIME	154.000	TON
402020092	ASPHALT CEMENT PG 64-28	595.500	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5,253.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	118.200	TON
409000000	FINAL SWEEP AND BROOM	4.700	CRMI
409000010	COVER-TYPE 1	65,619.000	SQYD
411010000	COLD MILLING	10,567.000	SQYD
557010544	REVISE TIMBER BRIDGE RAIL-THRIE BEAM	187.500	LNFT
605000070	REMOVE CONCRETE BARRIER RAIL	163.000	EACH
606010028	GUARDRAIL-OPTIONAL TERM SEC TL-2	18.000	EACH
606010135	ANCHOR POST	8.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	5,937.500	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	5.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	37.500	LNFT
606010385	REMOVE GUARDRAIL	2,469.800	LNFT
606011520	IMPACT ATTENUATOR	1.000	EACH
610100559	REVEGETATION	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	220,000.000	UNIT
619010062	SIGNS-ALUM SHEET INCR XI	24.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	74.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	407.500	SQFT
619010230	REMOVE SIGN	69.000	EACH
619010240	REMOVE SIGN-GUIDE	3.000	EACH
619010480	POLES-TREATED WOOD 4 IN	392.000	LNFT
619010800	PANEL DELINEATOR DESIGN A	25.000	EACH
619011010	DELINEATOR DES A	108.000	EACH
619011040	DELINEATOR DES D	23.000	EACH
619011060	DELINEATOR DES F	24.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	1,016.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	6.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	5.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.000	GAL
620012950	TEMPORARY STRIPING	4.700	MILE
620013000	STRIPING-WHITE PAINT	352.000	GAL
620013960	STRIPING-WHITE EPOXY	235.000	GAL
620014000	STRIPING-YELLOW PAINT	203.000	GAL
620014960	STRIPING-YELLOW EPOXY	135.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 9511000

203 MAIN STREET-SHELBY NH 1-4(49)278
SHELBY - NORTH STPP 67-1(8)0

CONTRACT NO. 05919

NH 1-4(49)278 - Milling, plant mix surfacing, crack seal, seal & cover, curb & gutter, ADA sidewalk upgrades and signing on the Main Street-Shelby project in Toole County. The project is located on US 2 beginning on the west end of Shelby at the intersection with Adams Ave. (RP 278.1) and extends east along Roosevelt and Main Streets to RP 280.0.

STPP 67-1(8)0 - Milling, plant mix surfacing, crack seal, seal & cover, bridge deck repair, guardrail replacement, curb & gutter, ADA sidewalk upgrades and signing on the Shelby-North project in Toole County.

The project is located in Shelby on MT Highway 67 (Oilfield Ave.) between Main Street (RP 0.0) and the Jct. I-15 North Shelby Interchange (RP 1.8).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, FILL, CRACK SEAL, SEAL & COVER, ADA			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
401020021	COMMERCIAL MIX-PG 70-28	2,501.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,302.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	157.600	TON
403010255	CRACK SEALING	5,432.000	LB
409000000	FINAL SWEEP AND BROOM	3.600	CRMI
409000010	COVER-TYPE 1	92,575.000	SQYD
411010000	COLD MILLING	26,032.000	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	68.000	SQYD
563000040	POLYMER OVERLAY	997.500	SQYD
563000045	POLYMER OVERLAY PRIMER	997.500	SQYD
563000100	PREPARE DECK	997.500	SQYD
606010030	GUARDRAIL-STEEL	100.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	2.000	EACH
606010150	GUARDRAIL-STL/BR APPR-TY 1	4.000	EACH
606010385	REMOVE GUARDRAIL	400.000	LNFT
606010642	GUARDRAIL-OPTIONAL TERM SECT	4.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	277.000	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	21.100	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	12.500	SQYD
609010030	CURB-CONC MEDIAN TYPE A	301.000	LNFT
609010200	CURB AND GUTTER-CONC	167.000	LNFT
609010209	REMOVE MEDIAN CURB	182.000	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	95,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	563.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	694.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	984.800	SQFT
619010210	RESET SIGNS-GUIDE	4.000	EACH
619010230	REMOVE SIGN	166.000	EACH
619010240	REMOVE SIGN-GUIDE	10.000	EACH
619010310	POSTS-STEEL U SIGN	22.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	3,648.000	LB
619010480	POLES-TREATED WOOD 4 IN	316.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	80.000	LNFT
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	1.000	EACH
619011010	DELINEATOR DES A	50.000	EACH
619011040	DELINEATOR DES D	12.000	EACH
619011060	DELINEATOR DES F	4.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	77.000	GAL
620010310	CURB MARKING-BLUE PAINT	1.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	53.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	33.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	63.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	44.000	GAL

620012950	TEMPORARY STRIPING	1.500	MILE
620013000	STRIPING-WHITE PAINT	167.000	GAL
620013960	STRIPING-WHITE EPOXY	245.000	GAL
620014000	STRIPING-YELLOW PAINT	125.000	GAL
620014960	STRIPING-YELLOW EPOXY	173.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 9394000, 9396000

204 RR XING - 1ST AVE S - BILLINGS RRP-RRS-STPRR-STPRP 1022(7) CONTRACT NO. 06919

Remove and replace existing Railroad Crossing on the RR Xing-1st Ave S-Billings project located within the city limits of Billings in Yellowstone County. Work includes: cold milling, PMS overlay, sidewalk, curb/gutter, utility adjustments and electrical. Montana Rail Link (MRL) will remove the existing railroad signal, install the new signal and replace the existing crossing surface. The project begins State Avenue at RP 0.8 and continues approximately 0.1 miles northeast along 1st Ave S to RP 0.9.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RAILROAD CROSSING IMPROVEMENTS			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	1,905.000	TON
411010000	COLD MILLING	2,262.000	SQYD
603014242	ADJUST VALVE BOX	3.000	EACH
604000100	ADJUST MANHOLE	3.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	133.100	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	11.300	SQYD
609010010	CURB-CONCRETE	50.000	LNFT
609010200	CURB AND GUTTER-CONC	254.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	350.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	180.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	7.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	3.000	EACH
617033214	CABLE-COPPER 3AWG14-600V	800.000	LNFT
617033313	CABLE-COPPER 4AWG12-600V	1,230.000	LNFT
617033314	CABLE-COPPER 5AWG14-600V	1,520.000	LNFT
617033414	CABLE-COPPER 7AWG14-600V	480.000	LNFT
617033514	CABLE-COPPER 9AWG14-600V	190.000	LNFT
617033614	CABLE-COPPER 12AWG14-600V	390.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	620.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	2,940.000	LNFT
617333000	SERV ASSEMBLY-MODIFY	1.000	EACH
617503130	SIG-TRAF 3 COL-1 WAY 12-12-12	2.000	EACH
617533000	SIG-TRAF-BACKPLATE-REFLECTIVE	18.000	EACH
617553020	SIG-PEDESTRIAN TYPE 2	4.000	EACH
617605081	CONTLR/TRAF-ACTUAT TYPE 8-A	1.000	EACH
617623270	BATTERY BACKUP SYSTEM	1.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	4.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	4.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010086	SIGNS-ALUM REFL SHEET IV	20.500	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	141.700	SQFT

619010230	REMOVE SIGN	20.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	160.000	LB
619011177	DELINEATOR-FLEX DRIVABLE WH	3.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	32.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	24.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	21.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	16.000	GAL
620013000	STRIPING-WHITE PAINT	16.000	GAL
620013955	REMOVE PAVEMENT MARKINGS	2,435.000	LNFT
620013960	STRIPING-WHITE EPOXY	21.000	GAL
620014000	STRIPING-YELLOW PAINT	32.000	GAL
620014960	STRIPING-YELLOW EPOXY	11.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 5838000

205 SF 169 BLGS AREA SFTY IMPRV HSIP STWD(565) CONTRACT NO. 07919

This project installs safety improvements at 9 locations in the Billings District.

- Site 1 - King Ave E- Replace existing curve signing on U-1026 (King Ave E) between RP 1.6 and RP 2.17 in Yellowstone County.
- Site 2 - Yellowstone River Rd- Replace chevrons, shoulder stripes, and signing on U-1017 (Yellowstone River Rd) between RP 3.5 and RP 3.68 in Yellowstone County.
- Site 3 - Lake Elmo Drive (N of Billings) - Signing, striping and delineation on Lake Elmo Drive between RP 2.2 and 2.5 in Yellowstone County.
- Site 4 - Cooney Rd (N of Roberts)- Signing and chevrons on Cooney Road between RP 1.5 to RP 1.8 in Carbon County.
- Site 5 - Countryman Creek Rd (SW of Columbus)- Signing between RP 0.6 and RP 0.8 in Stillwater County.
- Site 6 - South Frontage Rd (W of Sugar Ave)- Signing between RP 1.8 and RP 2.1 in Yellowstone County.
- Site 7 - Garden Ave- Corridor wide signing upgrade RP 0.0 to RP 1.4 in Yellowstone County.
- Site 8 - Nahmis Ave (Huntley) - Delineation through entire corridor between RP 0.2 to RP 0.7 in Yellowstone County.
- Site 9 - Story Rd (S Billings) - Signing between RP 0.1 and RP 0.3 in Yellowstone County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SIGNING, DELINEATION AND STRIPING			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010062	SIGNS-ALUM SHEET INCR XI	42.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	123.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	884.200	SQFT
619010230	REMOVE SIGN	94.000	EACH
619010240	REMOVE SIGN-GUIDE	11.000	EACH
619010310	POSTS-STEEL U SIGN	100.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	126.000	LB
619010480	POLES-TREATED WOOD 4 IN	944.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	144.000	LNFT
619011010	DELINEATOR DES A	24.000	EACH
619011030	DELINEATOR DES C	34.000	EACH

619011040	DELINEATOR DES D	14.000	EACH
619011060	DELINEATOR DES F	12.000	EACH
620013960	STRIPING-WHITE EPOXY	28.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 9420000

206 I-15 BRIDGE REPAIR - VAUGHN INTERCHANGE NHPB 3-1(50)0 CONTRACT NO. 09919

Bridge repair on the I-15 Bridge Repair-Vaughn Interchange project located in Cascade County. The project is located on National Highway Route/MT 200/US 89 at RP 0.012.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - EMERGENCY BRIDGE REPAIR			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
104030040	MISCELLANEOUS ITEMS-SQFT	53.900	SQFT
109200005	MOBILIZATION	1.000	LS
552010043	FRP REINFORCEMENT	1,045.000	SQFT
552010045	SUPERSTRUCTURE JACKING	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	35,000.000	UNIT

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9794000

INVITATION FOR BIDS
LETTING OF October 10, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on October 10, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 **ROCK CREEK INTERCHANGE - EAST IM 90-2(155)126 CONTRACT NO. 09A19**
ROCK CREEK INTERCHANGE - WEST IM 90-2(153)119

IM 90-2(155)126 - Milling, tack coat application, new plant mix overlay and a full-width seal and cover and fog seal on the Rock Creek Interchange - East project in Missoula and Granite Counties. Other work includes new pavement markings, signing, delineation, rumble strips and guardrail upgrades. The project is located on Interstate 90, beginning at Rock Creek Interchange (RP 126.4), 5 miles SE of Clinton, and extending east 8.3 miles to RP 134.8.

IM 90-2(153)119 - Milling, tack coat application, new plant mix overlay and a full-width seal and cover and fog seal on the Rock Creek Interchange - West project in Missoula County. Other work includes new pavement markings, signing, delineation, rumble strips, guardrail upgrades and bridge deck crack seal. The project is located on Interstate 90, beginning at RP 119.2, 1.7 miles west of Clinton, and extending east 7.1 miles to Rock Creek Interchange (RP 126.4).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILLING, PMS OVERLAY, SEAL & COVER, GUARDRAIL, SIGNING			
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	100.000	MILE
301020416	SHOULDER GRAVEL	550.000	CUYD
401020048	PLANT MIX SURF GR S-1/2 IN	97,021.000	TON
401020300	HYDRATED LIME	1,358.000	TON
402020095	ASPHALT CEMENT PG 70-28	5,635.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	39,622.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	58,228.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	1,367.400	TON
409000020	COVER-TYPE 2	768,528.000	SQYD
411010000	COLD MILLING	773,714.000	SQYD
411011135	RUMBLE STRIPS	59.000	MILE
552010160	BRIDGE DECK CRACK SEAL	1,229.000	SQYD
606010140	GUARDRAIL END SECTION WIDENING	20.000	EACH
606010150	GUARDRAIL-STL/BR APPR-TY 1	4.000	EACH
606010190	GUARDRAIL-STL/BR APPR-TY 2	4.000	EACH
606010330	MGS GUARDRAIL	17,080.900	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	20.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	15.000	EACH
606010386	REMOVE AND SALVAGE GUARDRAIL	17,832.000	LNFT
610100559	REVEGETATION	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	380,000.000	UNIT
618100000	SINGLE USE SIGNS	128.000	SQFT
619010058	SIGNS-ALUM SHEET INCR IV	3,148.900	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	156.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	673.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1,086.500	SQFT
619010230	REMOVE SIGN	163.000	EACH
619010240	REMOVE SIGN-GUIDE	67.000	EACH
619010300	POSTS-TUBULAR STEEL	285.000	LB
619010310	POSTS-STEEL U SIGN	1,080.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,279.000	LB
619010480	POLES-TREATED WOOD 4 IN	76.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	96.000	LNFT
619010742	FRANG SIGN POST BKWY-3.5 IN RD (89MM)	2.000	EACH
619011010	DELINEATOR DES A	587.000	EACH
619011020	DELINEATOR DES B	84.000	EACH
619011040	DELINEATOR DES D	55.000	EACH
619011070	DELINEATOR DES G	190.000	EACH
619011085	DELINEATOR DES BJ	126.000	EACH
619011087	DELINEATOR DES GJ	106.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	38.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	44.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	73.000	GAL
620012950	TEMPORARY STRIPING	61.600	MILE
620013000	STRIPING-WHITE PAINT	1,676.000	GAL
620013960	STRIPING-WHITE EPOXY	1,073.000	GAL
620014000	STRIPING-YELLOW PAINT	1,248.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9243000, 9224000

102 STEEL BRIDGE REHABILITATION-CORROSION 1 NHPB STWD(349) CONTRACT NO. 14A19

Bridge superstructure rehabilitation including the repair or replacement of fatigued and corrosion prone members on steel superstructures, strengthening of steel members, field painting, and joint replacement and rehabilitation on the Steel Bridge Rehab-Corrosion 1 project.

The project includes 20 bridges located in the Missoula District. 18 bridges are located on I-90 in Mineral and Missoula Counties, one bridge on US-2 (N-1) in Lincoln County, and one bridge on US-93 (N-7) in Ravalli County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - CROSSOVERS, TEMPORARY GUARDRAIL, TRAFFIC CONTROL			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
104030045	MISCELLANEOUS ITEMS-EACH	32.000	EACH
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
552010041	REVISE JOINT	545.100	LNFT
552010045	SUPERSTRUCTURE JACKING	1.000	LS
552010060	REPAIR STRUCTURE	1.000	LS
552011010	EXPANSION JOINT STRIP SEAL	327.800	LNFT
552011140	RESEAL EXISTING JOINTS	207.700	LNFT
556000100	PAINT EXISTING STRUCTURAL STEEL	5,474.000	SQYD
556000110	PAINT STRUCTURE	1.000	LS
556010010	STRUCTURAL STEEL - MISC	1.000	LS
556010110	WELDED STIFFENER REPAIR	29.000	EACH
561010525	EXPANSION JOINT-PRECOMPRESSED	610.400	LNFT
605000070	REMOVE CONCRETE BARRIER RAIL	95.000	EACH
605000090	CONCRETE BARRIER RAIL	95.000	EACH
606010020	GUARDRAIL-TEMPORARY	87.500	LNFT
606010021	TEMP GD RAIL-STL/BR APPR-TY 1	5.000	EACH
606010022	TEMP GD RAIL-STL/BR APPR-TY 3	7.000	EACH
606010024	TEMP OPTIONAL TERM SECT	16.000	EACH
606010120	REMOVE CABLE GUARDRAIL	1,460.000	LNFT
606010130	RESET CABLE GUARDRAIL	1,460.000	LNFT
606011502	RESET IMPACT ATTENUATOR	1.000	EACH
606011504	RESET ONE-WAY DEPART TERM SECT	4.000	EACH
606011510	REMOVE IMPACT ATTENUATOR	1.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	3.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618030055	TRAFFIC CONTROL-RAMP CROSSOVER	5.000	EACH
618030180	TRAFFIC CONTROL-CROSSOVER	4.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	7.600	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	1.000	EACH
618030280	CROSSOVER RECLAMATION	1.000	EACH
618030300	CROSSOVER-MAINTAIN, CLOSE	2.000	EACH
618030310	CROSSOVER-MEDIAN BARRIER RAIL	2.000	EACH
618100000	SINGLE USE SIGNS	64.000	SQFT
618190100	TEMPORARY BARRIER RAIL	200.000	LNFT
618190110	RESET TEMP BARRIER RAIL	200.000	LNFT

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
 Uniform No. 8886000

103 CORRAL CR - 11 M NE CIRCLE STPB 51-2(6)10 CONTRACT NO. 06A19

Bridge replacement and approach work on the Corral Creek-11 M NE Circle project located in Dawson County. Work includes: remove existing structure, new structure, gravel, PMS overlay, guardrail, fencing, seal & cover and pavement markings. The project begins at RP 10.3 and extends northeast approximately 0.4 miles along State Primary Route 51/MT 200 to RP 10.6.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE REPLACEMENT AND APPROACH WORK			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
105080115	FINISH GRADE CONTROL	4,000.000	CRFT
105080200	BRIDGE SURVEY	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020375	EMBANKMENT IN PLACE	15,334.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	2,053.000	CUYD
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.000	LS
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020254	BRIDGE END BACKFILL-TYPE 3	1,296.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	3,582.000	CUYD
301020625	AGGREGATE TREATMENT	7,595.000	SQYD
401020022	COMMERCIAL MIX-PG 64-28	1,591.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	813.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	12.300	TON
409000000	FINAL SWEEP AND BROOM	0.300	CRMI
409000010	COVER-TYPE 1	6,585.000	SQYD
551020035	CONCRETE-CLASS STRUCTURE	70.200	CUYD
551020107	CONCRETE-CLASS DECK	131.100	CUYD
552010140	TRANSVERSE DECK GROOVING	436.300	SQYD
553010155	PRESTRESSED BEAM-TYPE MTS-54	460.000	LNFT
555010100	REINFORCING STEEL	5,836.000	LB
555010200	REINFORCING STEEL-EPOXY COATED	28,446.000	LB
557010013	BRIDGE RAIL-W830	235.200	LNFT
559040035	DYNAMIC LOAD TEST	1.000	EACH
559050103	FURN STEEL PIPE PILE 16 X 1/2 IN	326.000	LNFT
559060103	DRIVE STEEL PIPE PILE 16 X 1/2	312.000	LNFT
559060200	PILE CUTTING SHOE	8.000	EACH
603010025	PLUG ENDS AND ABANDON PIPE	1.000	EACH
603015270	EMBANKMENT PROTECTOR 18 IN	157.000	LNFT
603016003	SPECIAL INSTALLATION OF PIPE	302.000	LNFT
603016056	STEEL CASING 36 IN	312.000	LNFT
606010265	GRD RL-BOX BEAM/BR APP-SEC TYPE 1	4.000	EACH
606010641	GD RL BOX BEAM OPT TERM SEC	4.000	EACH
607100229	FARM FENCE-TYPE F4W	3,145.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	22.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	7.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	32.000	LNFT
607100551	FENCE-TEMPORARY	362.000	LNFT
609010112	CURB 4 IN-CONCRETE	440.000	LNFT
610100101	SEEDING AREA NO 1	2.400	ACRE
610100102	SEEDING AREA NO 2	0.200	ACRE
610100103	SEEDING AREA NO 3	1.400	ACRE
610100326	FERTILIZING AREA NO 1	2.400	ACRE
610100327	FERTILIZING AREA NO 2	0.200	ACRE
610100490	TURF REINF MAT-NATURAL FIBER	956.000	SQYD
610100555	CONDITION SEEDBED SURFACE	3.800	ACRE
610100560	RIPRAP REVEGETATION	861.000	SQYD
610220100	MULCH	0.200	ACRE
613100040	RIPRAP-CLASS 2 RANDOM	726.000	CUYD

613300050	BANK PROTECTION-TYPE 3	12.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010086	SIGNS-ALUM REFL SHEET IV	7.600	SQFT
619010230	REMOVE SIGN	6.000	EACH
619010480	POLES-TREATED WOOD 4 IN	20.000	LNFT
620012950	TEMPORARY STRIPING	0.600	MILE
620013000	STRIPING-WHITE PAINT	4.000	GAL
620013960	STRIPING-WHITE EPOXY	5.000	GAL
620014000	STRIPING-YELLOW PAINT	1.000	GAL
620014960	STRIPING-YELLOW EPOXY	1.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	1,023.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	12,370.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 8801000

104 SEELEY LAKE - URBAN STPP 83-1(39)13 CONTRACT NO. 08A19

The Seeley Lake - Urban project consists of crack sealing, seal and cover, fog seal (shared-use path), pavement markings and signing. The project is located on MT 83/State Primary Route 83 beginning at RP 13.1 and extends 1.7 miles to RP 14.8 in Missoula County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL AND COVER, SIGNING			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
402020320	EMULSIFIED ASPHALT-FOG SEAL	659.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	102.500	TON
403010255	CRACK SEALING	2,598.000	LB
409000000	FINAL SWEEP AND BROOM	1.700	CRMI
409000030	COVER-TYPE 3	46,291.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	82,500.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	20.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	68.200	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	205.500	SQFT
619010230	REMOVE SIGN	26.000	EACH
619010240	REMOVE SIGN-GUIDE	1.000	EACH
619010310	POSTS-STEEL U SIGN	20.000	LB
619010480	POLES-TREATED WOOD 4 IN	184.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	182.000	LNFT
620011105	WORDS AND SYMBOLS-WHITE PAINT	8.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	7.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	11.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	10.000	GAL
620013000	STRIPING-WHITE PAINT	64.000	GAL
620013960	STRIPING-WHITE EPOXY	180.000	GAL
620014000	STRIPING-YELLOW PAINT	91.000	GAL
620014960	STRIPING-YELLOW EPOXY	121.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9499000

105 SF 169 BLGS DISTRICT SFTY IMPRV HSIP STWD(563) CONTRACT NO. 10A19

This project consists of safety improvements at 9 locations in the Billings District:

Site 1 - National Highway Interstate Route I-90 (N of Lodge Grass) at RP 528.5. Installation of a curve warning sign and lineal delineation on the median barrier for the curve at RP 528.5. This site is within the boundaries of the Crow Indian Reservation in Big Horn County.

Site 2 - State Primary Route P-14/US 12 (SW of Roundup) at RP 157.8 to 160.1. Install curve warning signs for the curve at RP 158.7 and standard delineation from RP 157.8 to 160.1. This site is located in Musselshell County.

Site 3 - National Highway Route N-16/US 87 (N of Billings) at RP 23.2 to 30.0 Install shoulder rumble strips from approximately RP 23.2 to RP 30.0 and tie into the existing shoulder rumble strips. The roadway width is 40-feet with 8-foot shoulders. This site begins in Yellowstone County at RP 23.2 and enters Musselshell County at RP 25.2.

Site 4 - National Highway Route N-57/MT-3 (Raynesford) at RP 10.5 Install curve warning signs RP 10.5. This site is located in Judith Basin County.

Site 5 - National Highway Route N-57/US 87/MT 200 (W of Grass Range) at RP 109.4. Install curve warning signs for the curve at RP 109.4. This site is located in Fergus County.

Site 6 - National Highway Route N-57/MT 200 (E of Winnett) at RP 149.3, 151.7 and RP 154.95. Install chevrons through the 3 curves at RP 149.3, 151.7 and 154.95. This site is located in Petroleum County.

Site 7 - National Highway Interstate Route I-94 (W of Pompey's Pillar) at RP 33.55. Install for WB only, linear delineation, panel delineation and double curve warning signs for curve at RP 33.55. This site is located in Yellowstone County.

Site 8 - State Urban Route 1032/Johnson Lane at RP 1.2- Install panel delineation, lineal delineation on the guardrail, arrow boards and new curve signs through the curve at RP 1.2. This site is located within the Billings urban limits in Yellowstone County.

Site 9 - State Route X-56788/Old Highway 312 (NW of Billings) at RP 2.3 to RP 3.1. Install panel delineation from RP 2.3 to 3.1. This site is located in Yellowstone County.

MANDATORY PRE-BID CONFERENCE

A pre-bid conference will be held at the following time and location:

Wednesday, September 25, 2019, 10:00 AM. Billings District Conference Room, 424

Morey St., Billings, MT. The pre-bid conference will have a formal sign-in process that will become the official record of attendance for the purposes of determining eligible bidders. Attendance at this conference is mandatory for any Contractor to submit a bid as a prime bidder. Contractors who bid as a prime bidder on this project must have at least one full time, permanent employee present. No proxy representatives, such as subcontractors or consultants, meet this requirement. In the event a prime bidder tenders a bid but did not attend the pre-bid conference, the bid will be returned unopened.

Representatives of the Department will be present to describe the project and answer questions. Representatives of the Apsaalooke Nation will be invited to the pre-bid conference. The pre-bid conference is for information only. The Department is not bound by any statement or representation concerning conditions or description of the work given by Department employees or agents and the pre-bid conference. The answers to any questions raised are nonbinding oral explanations or instructions, and relying on them is solely at the Bidder's risk. Any issues raised at the pre-bid conference must be posted on the Question and Answer Forum to be considered an enforceable provision of the contract to be let. The pre-bid attendee list and contract document clarifications or modifications considered necessary by the Department will be posted to the Question and Answer Forum.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SIGNING, RUMBLE STRIPS-NON INDIAN RESERVATION			
LOCATIONS			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
411011135	RUMBLE STRIPS	13.400	MILE
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010090	SIGNS-ALUM REFL SHEET XI	410.500	SQFT
619010300	POSTS-TUBULAR STEEL	525.000	LB
619010480	POLES-TREATED WOOD 4 IN	514.000	LNFT
619010744	FRANG SIGN POST BKWY-4 IN RD (100 MM)	2.000	EACH
619010800	PANEL DELINEATOR DESIGN A	42.000	EACH
619010810	PANEL DELINEATOR DESIGN C	11.000	EACH
619010830	PANEL DELINEATOR DESIGN H	7.000	EACH
619011010	DELINEATOR DES A	66.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	170.000	EACH

619011205 DELINEATION-LINEAR-BARRIER-YELLOW

132.000 EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 9423000

INVITATION FOR BIDS
LETTING OF November 14, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on November 14, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 MT 200 - FAIRVIEW NHIP 20-2(32)62 CONTRACT NO. 01B19

The MT 200 - Fairview project consists of upgrades to the ADA facilities, electrical, a new storm drain system, watermain replacement, sidewalk, curb and gutter. This project includes PMBS overlay, major rehab with new PCCP and total reconstruction with new PCCP at various limits of the project. The project is located in Richland County on National Highway Route 20/Montana 200 beginning on the southern side of Fairview at RP 62.1 and extends to RP 63.9.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - G, GS, PCCP, PMBS, C&G, SIDEWALK, STORM DRAIN			
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	65,000.000	UNIT
104030037	MISCELLANEOUS ITEMS-SQYD	30,364.000	SQYD
104030065	MISCELLANEOUS ITEMS-LNFT	55.000	LNFT
105080115	FINISH GRADE CONTROL	13,300.000	CRFT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020353	REMOVE CONCRETE	419.100	SQYD
202020539	REMOVE MISCELLANEOUS ITEMS	2.000	EACH
203020225	EXCAVATION-STREET	8,492.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	130.000	MILE
301020268	TRAFFIC GRAVEL	1,000.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	5,707.000	CUYD
301020450	SPECIAL BACKFILL	1,500.000	CUYD
401020021	COMMERCIAL MIX-PG 70-28	2,572.000	TON
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	2,288.000	TON
401020064	COMMERCIAL PLANT MIX-MISC	1,432.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	3,706.000	GAL
411010000	COLD MILLING	31,997.000	SQYD
501010125	PORT CEM CONC PAVE 9 IN	38,312.400	SQYD
501010415	BOND BREAKER	30,365.000	SQYD
551020030	CONCRETE-CLASS GENERAL	10.400	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	2,246.000	CUYD
601011920	INSULATION	216.000	SQFT
601012015	TEMPORARY WATER SERVICE	1.000	EACH
603000050	GRANULAR BEDDING MATERIAL	1,607.000	CUYD
603000055	BEDDING MATERIAL	125.000	CUYD
603000060	FOUNDATION MATERIAL	161.000	CUYD
603010528	CSP 18 IN	42.600	LNFT
603012800	RCP IRR 12 IN	743.000	LNFT
603012847	RCP IRR 18 IN	1,465.900	LNFT
603012892	RCP IRR 24 IN	1,004.800	LNFT
603012925	RCP IRR 30 IN	871.700	LNFT
603012938	RCP IRR 36 IN	36.600	LNFT
603012960	RCP IRR 42 IN	1,274.600	LNFT
603012975	RCP IRR 48 IN	36.700	LNFT
603013356	REIN CONC BOX 6 X 4	306.000	LNFT
603013461	PIPE-PVC PRESS 6 IN WATER	744.000	LNFT
603013466	PIPE-PVC PRESS 8 IN WATER	1,309.000	LNFT
603013532	CONNECT TO MAIN	9.000	EACH
603013545	WATER SERVICE CONNECTION	28.000	EACH
603013592	WATER SERVICE 4 IN	1.000	EACH
603013828	DUCTILE IRON FITTINGS	815.000	LB
603014242	ADJUST VALVE BOX	13.000	EACH
603014492	HYDRANT ASSEMBLY	6.000	EACH
603016003	SPECIAL INSTALLATION OF PIPE	145.500	LNFT
603016054	STEEL CASING 48 IN	25.600	LNFT
603016060	STEEL CASING 42 IN	212.900	LNFT
603587020	REMOVE PIPE CULVERT	286.300	LNFT
603587030	REMOVE STORM DRAIN	168.600	LNFT
604000120	REMOVE FIRE HYDRANT	4.000	EACH
604000200	RESET FIRE HYDRANT	1.000	EACH

604000250	ADJUST FIRE HYDRANT	4.000	EACH
604010045	MANHOLE-48 IN TYPE 3	7.000	EACH
604010065	MANHOLE-60 IN TYPE 3	6.000	EACH
604010075	MANHOLE-72 IN TYPE 3	8.000	EACH
604010085	MANHOLE-84 IN TYPE 3	1.000	EACH
604010210	INLET DROP-TYPE 3	6.000	EACH
604010214	INLET DROP-TYPE 6	23.000	EACH
604010533	COMB 48 IN T3 MH-T1 DROP INL	9.000	EACH
604010552	COMB 48 IN T3 MH-T5 DROP INL	11.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	2,360.600	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	508.500	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	58.300	SQYD
609010200	CURB AND GUTTER-CONC	4,629.500	LNFT
610100558	REVEGETATION	1,827.000	SQYD
613100040	RIPRAP-CLASS 2 RANDOM	34.800	CUYD
615010580	TRASH GUARD	3.000	EACH
615010737	VALVE-GATE 6 IN W/BOX	7.000	EACH
615010741	VALVE-GATE 8 IN W/BOX	5.000	EACH
616343910	CONDUIT-PLASTIC 1 IN	1,090.000	LNFT
616343930	CONDUIT-PLASTIC 3 IN	270.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	4.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	1.000	EACH
617000000	FOUNDATION-CONCRETE	0.600	CUYD
617000050	POLES-TREATED WOOD CLASS 4	30.000	LNFT
617033414	CABLE-COPPER 7AWG14-600V	865.000	LNFT
617033514	CABLE-COPPER 9AWG14-600V	445.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	2,440.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	1,360.000	LNFT
617233030	CONTROLLER-CAB PEDESTAL TYPE P	1.000	EACH
617333198	SERV ASSEMBLY-200 AMP	1.000	EACH
617533000	SIG-TRAF-BACKPLATE-REFLECTIVE	10.000	EACH
617605081	CONTRLR/TRAF-ACTUAT TYPE 8-A	1.000	EACH
617725601	SIG STANDARD MODIFY	2.000	EACH
617733621	REMOVE AND RESET EXISTING POLE	1.000	EACH
617763500	DETECTOR-RADAR/PRESENCE	4.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	750,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	36.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	321.300	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	690.100	SQFT
619010230	REMOVE SIGN	92.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010300	POSTS-TUBULAR STEEL	156.000	LB
619010310	POSTS-STEEL U SIGN	19.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	169.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	3,156.000	LB
619010480	POLES-TREATED WOOD 4 IN	114.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	212.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7 (S100X11)	2.000	EACH
619010740	FRANG SIGN POST BKWY-3 IN RD (76 MM)	2.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	12.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	32.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	79.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	19.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	52.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	13.000	GAL
620012955	TEMPORARY STRIPING	3,669.000	LNFT
620013000	STRIPING-WHITE PAINT	254.000	GAL
620013960	STRIPING-WHITE EPOXY	169.000	GAL
620014000	STRIPING-YELLOW PAINT	206.000	GAL
620014960	STRIPING-YELLOW EPOXY	137.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	86.000	SQYD
622011084	GEOTEXTILE STABILIZATION	11,831.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Glendive District Administrator.
 Uniform No. 8168000

102 BBP - FIVE MILE ROAD STPU 56(87) CONTRACT NO. 03B19

New and existing road construction including grading, plant mix surfacing, concrete, roundabout intersection, lighting, signing, pavement markings, irrigation and other improvements on the BBP - Five Mile Road project in Yellowstone County.

The 1.4 mile project is located northeast of the Heights area of the City of Billings beginning at the intersection of Mary Street with Five Mile Road and continues north 0.4 miles to an intersection with Dover Road. A new segment of Five Mile Road will be constructed north from Dover Road approximately 1.0 mile to a new roundabout intersection with old Hwy 312 at RP 2.7.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRAVEL, PLANT MIX SURFACING			
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
104030045	MISCELLANEOUS ITEMS-EACH	1.000	EACH
104030065	MISCELLANEOUS ITEMS-LNFT	1,468.000	LNFT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
105080050	MONUMENT AND BOX	3.000	EACH
107000060	NOXIOUS WEED CONTROL	1,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	55,670.000	CUYD
203020200	EXCAVATION-UNCLASS BORROW	12,191.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	2,620.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	8,336.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
212000000	OBLITERATE ROADWAY	3.000	STA
301020268	TRAFFIC GRAVEL	1,659.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	36,969.000	CUYD
301020625	AGGREGATE TREATMENT	56,347.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	18,180.000	TON
401020046	PLANT MIX BIT SURF GR S -MISC	543.000	TON
401020300	HYDRATED LIME	255.000	TON
402020092	ASPHALT CEMENT PG 64-28	982.100	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	8,603.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	3,503.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	83.300	TON
409000000	FINAL SWEEP AND BROOM	1.900	CRMI
409000010	COVER-TYPE 1	46,703.000	SQYD
501010126	PORT CEM CONC PAVE 9 IN COLORED	516.000	SQYD
551020030	CONCRETE-CLASS GENERAL	26.000	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	149.200	CUYD
603000050	GRANULAR BEDDING MATERIAL	840.000	CUYD
603012530	RCP 18 IN	374.000	LNFT
603012555	RCP 24 IN	348.000	LNFT
603012625	RCP 30 IN	160.000	LNFT
603012670	RCP 42 IN	170.000	LNFT
603012847	RCP IRR 18 IN	502.200	LNFT
603012892	RCP IRR 24 IN	871.100	LNFT
603012925	RCP IRR 30 IN	216.500	LNFT
603012938	RCP IRR 36 IN	312.000	LNFT
603013053	RCP SIPHON 24 IN	146.000	LNFT

603013190	RCPA 18 IN	36.000	LNFT
603013452	PIPE-PVC 12 IN	48.000	LNFT
603013457	PIPE-PVC 8 IN	2,021.000	LNFT
603587020	REMOVE PIPE CULVERT	1,003.100	LNFT
604000140	REMOVE DROP INLET	1.000	EACH
604010045	MANHOLE-48 IN TYPE 3	1.000	EACH
604010075	MANHOLE-72 IN TYPE 3	1.000	EACH
604010085	MANHOLE-84 IN TYPE 3	1.000	EACH
604010255	INLET CURB-TYPE B	11.000	EACH
604010274	INLET MEDIAN-TYPE 3	1.000	EACH
607100009	FENCE - WILDLIFE FRIENDLY FW	849.000	LNFT
607100012	FENCE - WILDLIFE FRIENDLY FM	2,914.000	LNFT
607100014	FENCE - PANEL/SINGLE - WILDLIFE	23.000	EACH
607100015	FENCE - PANEL/DOUBLE - WILDLIFE	2.000	EACH
607100161	FARM FENCE-TYPE FM-SMOOTH	206.000	LNFT
607100252	FARM FENCE-TYPE F4M	1,517.000	LNFT
607100281	FARM FENCE-TYPE F5M	4,433.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	45.000	EACH
607100362	FARM FENCE-PANEL/SINGLE FM	6.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	1.000	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	2.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	92.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	92.000	LNFT
607100551	FENCE-TEMPORARY	3,195.000	LNFT
607100720	DEADMAN	4.000	EACH
608010090	CONCRETE 3 IN	1,562.900	SQYD
609010030	CURB-CONC MEDIAN TYPE A	2,570.200	LNFT
609010121	CURB-SPECIAL DESIGN	377.200	LNFT
609010160	GUTTER-CONC VALLEY	22.200	SQYD
609010200	CURB AND GUTTER-CONC	1,728.600	LNFT
609010215	CURB MEDIAN-SPECIAL DESIGN COLOR	371.100	LNFT
610100101	SEEDING AREA NO 1	17.200	ACRE
610100102	SEEDING AREA NO 2	1.900	ACRE
610100103	SEEDING AREA NO 3	7.000	ACRE
610100555	CONDITION SEEDBED SURFACE	24.200	ACRE
610100561	EROSION CONTROL BLANKET-LONG-TERM	9,200.000	SQYD
610100625	LANDSCAPING	1.000	LS
610220100	MULCH	1.900	ACRE
613300050	BANK PROTECTION-TYPE 3	21.700	CUYD
615010034	REMOVE IRRIGATION STRUCTURE	6.000	EACH
615010060	IRRIGATION CANAL GATE-8 IN	2.000	EACH
615010063	IRRIGATION CLEANOUT	3.000	EACH
615010071	IRRIGATION CANAL GATE-12 IN (300 MM)	2.000	EACH
615010580	TRASH GUARD	3.000	EACH
616343914	CONDUIT-PLASTIC 1 1/2 IN	2,305.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	225.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	6.000	EACH
617000000	FOUNDATION-CONCRETE	6.900	CUYD
617033214	CABLE-COPPER 3AWG14-600V	175.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	9,185.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	13.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	13.000	EACH
617333120	SERV ASSEMB-20 AMP	1.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
619010086	SIGNS-ALUM REFL SHEET IV	41.800	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	250.800	SQFT
619010230	REMOVE SIGN	6.000	EACH
619010240	REMOVE SIGN-GUIDE	1.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	488.000	LB
619010480	POLES-TREATED WOOD 4 IN	390.000	LNFT
619011010	DELINEATOR DES A	63.000	EACH
619011040	DELINEATOR DES D	4.000	EACH
619011060	DELINEATOR DES F	14.000	EACH
619011179	DELINEATOR-FLEX SURF MTD WH	8.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	4.000	EACH
619526065	RETRO-REFL STRIP-YL 4X60 (100X1500)	2.000	EACH

620010301	CURB MARKING-YELLOW EPOXY	66.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	91.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	24.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	60.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	16.000	GAL
620012955	TEMPORARY STRIPING	41,162.000	LNFT
620013000	STRIPING-WHITE PAINT	253.000	GAL
620013960	STRIPING-WHITE EPOXY	169.000	GAL
620014000	STRIPING-YELLOW PAINT	283.000	GAL
620014960	STRIPING-YELLOW EPOXY	189.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	82.000	SQYD
622011084	GEOTEXTILE STABILIZATION	3,802.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	74,520.000	SQYD
623000155	MAILBOX	4.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
 Uniform No. 4199002

103 MT-21 BRIDGES (SIMMS-AUGUSTA) STPB-STPX 81022 (3) CONTRACT NO. 19A19

The MT-21 Bridges (Simms-Augusta) project consists of rehabilitation of bridge decks and address safety concerns related to bridge width and guardrail blunt ends. The scope is to repair, widen and overlay the bridge decks and upgrade the bridge rail, or replace bridges with culverts. Road reconstruction is limited to provide room for new guardrail and a modified 30-year bridge end surfacing design.

The project is located on Montana 21 (State X Route 81022) at eight locations between Augusta and Simms beginning at RP 0.8 and extending to RP 20.8 in Cascade and Lewis & Clark Counties.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE APPROACH ROADWAY WORK-42.3% LEWIS AND CLARK/57.7% CASCADE			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020040	REMOVE STRUCTURE	3.000	EACH
202020115	REMOVE DECK	668.300	SQYD
202020139	REMOVE ASPHALT FROM DECK	97.000	SQYD
203020100	EXCAVATION-UNCLASSIFIED	2,870.000	CUYD
203020200	EXCAVATION-UNCLASS BORROW	214.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	1,846.000	CUYD
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.000	LS
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	85.000	MILE
301020340	CRUSHED AGGREGATE COURSE	1,686.000	CUYD
301020625	AGGREGATE TREATMENT	6,477.000	SQYD
401020023	COMMERCIAL MIX-PG 58-28	1,505.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	794.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	10.300	TON
409000000	FINAL SWEEP AND BROOM	0.500	CRMI
409000010	COVER-TYPE 1	5,727.000	SQYD
551020030	CONCRETE-CLASS GENERAL	49.200	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	49.000	CUYD

552010037	REVISE TIMBER BRIDGE SUPERSTRUCTURE	1.000	LS
552010038	REVISE TIMBER BRIDGE SUBSTRUCTURE	1.000	LS
557010546	REVISE TIMBER BRIDGE RAIL-T101	635.400	LNFT
557010547	REVISE BRIDGE RAIL T-101	109.900	LNFT
557010606	REMOVE BRIDGE RAIL	649.500	LNFT
563000100	PREPARE DECK	109.000	SQYD
563000110	WATERPROOF MEMBRANE	109.000	SQYD
603000050	GRANULAR BEDDING MATERIAL	325.000	CUYD
603010080	DRAINAGE PIPE 66 IN	106.000	LNFT
603010192	DRAINAGE PIPE ARCH 73 IN	136.000	LNFT
603010692	CSP 84 IN	144.000	LNFT
603013356	REIN CONC BOX 6 X 4	52.600	LNFT
603587020	REMOVE PIPE CULVERT	66.600	LNFT
606010030	GUARDRAIL-STEEL	25.000	LNFT
606010047	GD RAIL-STL INT RDWY TERM SECT	75.000	LNFT
606010135	ANCHOR POST	16.000	EACH
606010190	GUARDRAIL-STL/BR APPR-TY 2	14.000	EACH
606010642	GUARDRAIL-OPTIONAL TERM SECT	12.000	EACH
606011503	RESET TEMP IMPACT ATTENUATOR	4.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	4.000	EACH
606011549	IMPACT ATTENUATOR-4 BAY	2.000	EACH
607100259	FARM FENCE-TYPE F5W	2,638.100	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	50.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	18.000	EACH
607100440	FARM GATE-METAL-TYPE G-3	16.000	LNFT
607100551	FENCE-TEMPORARY	1,531.000	LNFT
607100720	DEADMAN	12.000	EACH
610010100	TOPSOIL	788.000	CUYD
610100101	SEEDING AREA NO 1	3.200	ACRE
610100102	SEEDING AREA NO 2	0.400	ACRE
610100326	FERTILIZING AREA NO 1	3.200	ACRE
610100327	FERTILIZING AREA NO 2	0.400	ACRE
610100555	CONDITION SEEDBED SURFACE	3.200	ACRE
610100561	EROSION CONTROL BLANKET-LONG-TERM	730.000	SQYD
610100565	EROSION CONTROL BLANKET-HIGH-PERFORM	669.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	285,000.000	UNIT
618100000	SINGLE USE SIGNS	104.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	12.000	SQFT
619010230	REMOVE SIGN	34.000	EACH
619010480	POLES-TREATED WOOD 4 IN	40.000	LNFT
620012955	TEMPORARY STRIPING	1,584.000	LNFT
620013000	STRIPING-WHITE PAINT	17.000	GAL
620013960	STRIPING-WHITE EPOXY	19.000	GAL
620014000	STRIPING-YELLOW PAINT	15.000	GAL
620014960	STRIPING-YELLOW EPOXY	17.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 7938000

104 WEST OF MALTA - WEST NH 1-8(66)459 CONTRACT NO. 02A19

Microsurfacing, seal & cover and pavement markings on the West of Malta - West project in Phillips County. The project is on US 2/National Hwy 1 route between Malta and Dodson, beginning at RP 458.6 and proceeding west to RP 466.7.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MICROSURFACING, SEAL AND COVER AND PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
210020170	TEST TRAILER-TRANSPORT,SETUP	240.000	MILE
401020068	MICROSURFACING AGGREGATE-TYPE 3	3,844.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	12,856.400	GAL
402020337	MICROSURFACING EMULSION	444.200	TON
402020368	EMULSIFIED ASPHALT CRS-2P	254.400	TON
402020380	RUT FILLING	170,849.000	LNFT
409000000	FINAL SWEEP AND BROOM	8.100	CRMI
409000010	COVER-TYPE 1	143,564.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	8.100	MILE
411011135	RUMBLE STRIPS	16.200	MILE
618030005	TRAFFIC CONTROL DEVICES CB	125,000.000	UNIT
619011010	DELINEATOR DES A	302.000	EACH
619011040	DELINEATOR DES D	8.000	EACH
620012955	TEMPORARY STRIPING	45,975.000	LNFT
620013000	STRIPING-WHITE PAINT	298.000	GAL
620013960	STRIPING-WHITE EPOXY	398.000	GAL
620014000	STRIPING-YELLOW PAINT	76.000	GAL
620014960	STRIPING-YELLOW EPOXY	102.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
 Uniform No. 9000000

105 MOUNT HIGHLAND DR - BUTTE UPP 1809(8) CONTRACT NO. 05B19

The Mount Highland Drive-Butte project consists of cold milling, plant mix bituminous surfacing, seal and cover, ADA upgrades, signing and pavement markings and other miscellaneous improvements. The project is located on Mount Highland Drive (State Urban Route 1809) beginning at RP 0.0 (Elizabeth Warren Ave intersection) and extends to RP 1.6 (Continental Drive intersection). The project is located within the urban limits of Butte in Silver Bow County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - COLD MILLING, PMS OVERLAY, ADA UPGRADES			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	32.000	MILE
401020021	COMMERCIAL MIX-PG 70-28	3,746.000	TON
401020255	HIGH TENSILE STRENGTH REINFORCING FIBER	491.700	LB
402020315	EMULSIFIED ASPHALT-TACK COAT	1,963.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	67.800	TON
409000000	FINAL SWEEP AND BROOM	1.600	CRMI
409000010	COVER-TYPE 1	38,082.000	SQYD
411010000	COLD MILLING	39,673.000	SQYD

411011140	TRANSVERSE RUMBLE STRIPS	1.000	LS
603014242	ADJUST VALVE BOX	2.000	EACH
604000100	ADJUST MANHOLE	5.000	EACH
608010050	SIDEWALK-CONCRETE 6 IN	122.300	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	11.600	SQYD
609010200	CURB AND GUTTER-CONC	251.400	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	60,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	120.000	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	63.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	163.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	240.500	SQFT
619010230	REMOVE SIGN	34.000	EACH
619010240	REMOVE SIGN-GUIDE	7.000	EACH
619010310	POSTS-STEEL U SIGN	34.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	351.000	LB
619010480	POLES-TREATED WOOD 4 IN	96.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	84.000	LNFT
619011010	DELINEATOR DES A	57.000	EACH
619011040	DELINEATOR DES D	10.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	12.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	14.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	10.000	GAL
620012955	TEMPORARY STRIPING	16,896.000	LNFT
620013000	STRIPING-WHITE PAINT	124.000	GAL
620013960	STRIPING-WHITE EPOXY	83.000	GAL
620014000	STRIPING-YELLOW PAINT	124.000	GAL
620014960	STRIPING-YELLOW EPOXY	83.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
 Uniform No. 9480000

106 **NO NAME DITCH BR - 4 M SE VALIER STPB 9037(36) CONTRACT NO. 22A19**

This is a bridge replacement project in Pondera County on X-37031 (Blue Sky Road). The project begins at Reference Post 1.3, approximately 200 feet north of the bridge and ends at Reference Post 1.4, approximately 200 feet south of the bridge. The existing 40-foot bridge over the "L" canal will be replaced with either a Reinforced Concrete Box or an Aluminum Arch Culvert.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE REPLACEMENT, CULVERT			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
202020540	REMOVE MISCELLANEOUS ITEMS	1.000	LS
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
301020526	TOP SURFACING GR 3B	696.000	CUYD
610100559	REVEGETATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
SECTION NO. 0002 - ALTERNATE A1, RCB 14 X 17 DBL			
203020100	EXCAVATION-UNCLASSIFIED	1,268.000	CUYD
301020450	SPECIAL BACKFILL	1,099.000	CUYD

603000050	GRANULAR BEDDING MATERIAL	98.000	CUYD
603013306	REIN CONC BOX 14 X 7 DBL	78.000	LNFT
SECTION NO. 0003 - ALTERNATE A2, ALUM BOX CULVERT			
203020100	EXCAVATION-UNCLASSIFIED	1,207.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	1,177.000	CUYD
603000050	GRANULAR BEDDING MATERIAL	102.000	CUYD
603016009	ALUMINUM BOX CULVERT	67.500	LNFT

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Great Falls District Administrator.
 Uniform No. 8866000

107 HARDIN ROAD - BILLINGS UPP 1028(9) CONTRACT NO. 06B19
SHILOH ROAD - BILLINGS UPP 1031(20)
KING AVE E - BILLINGS UPP 1026(3)

UPP 1028(9) - Seal & cover and pavement markings on the Hardin Road-Billings project located within the Billings city limits in Yellowstone County. The project begins at RP 0.1 and extends northeast approximately 2.0 miles along Urban Route 1028/Hardin Road to RP 2.1.

UPP 1031(20) - Seal & cover and pavement markings on the Shiloh Road-Billings project located within the Billings urban limits in Yellowstone County. The project begins at RP 4.7 and extends north approximately 0.7 miles north along Urban Route 1031/Shiloh Road to RP 5.3.

UPP 1026(3) - Seal & cover and pavement markings on the King Ave East-Billings project located within the Billings city limits in Yellowstone County. The project begins at RP 1.7 and extends northeast along Urban Route 1026/King Avenue East to RP 2.2.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - 3 TIED BILLINGS PROJECTS			
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
402020368	EMULSIFIED ASPHALT CRS-2P	105.800	TON
409000000	FINAL SWEEP AND BROOM	4.400	CRMI
409000020	COVER-TYPE 2	59,155.000	SQYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL	1.000	LS
618100001	MOTORCYCLE ADVISORY SIGN	6.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	3.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	19.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	6.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	22.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	7.000	GAL
620013000	STRIPING-WHITE PAINT	127.000	GAL
620013960	STRIPING-WHITE EPOXY	169.000	GAL
620014000	STRIPING-YELLOW PAINT	111.000	GAL
620014960	STRIPING-YELLOW EPOXY	148.000	GAL

INVITATION FOR BIDS
LETTING OF December 12, 2019

Sealed bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, Room 101, 2701 Prospect Ave, Helena, Montana until 9:00 a.m. on December 12, 2019. All bids will then be publicly opened, reviewed for correctness, and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Construction Contracting Bureau. These documents may be requested in electronic form by calling (406)444-6212, 6215 or TTY (406)444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this web site.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Barb Skelton, Chairperson
Montana Transportation Commission

Michael T. Tooley
Director of Transportation

101 WESTBY - WEST STPP 30-1(20)16 CONTRACT NO. 03C19

Reconstruction project, including grading, gravel, pl. mix surf., seal & cover, drainage, signing, pavement markings, ADA, storm drain and water main on the Westby - West project Sheridan County.

The project begins 8.0 miles west of Westby on Primary Route 30/MT 5 at RP 15.6 and extends east approximately 8.5 miles to RP 24.1 at the Montana/North Dakota Border.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GRADE, GRAVEL, PMS OVERLAY, SIGNING			
103000000	TRAINING PROGRAM	1,500.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
105080115	FINISH GRADE CONTROL	91,500.000	CRFT
107000060	NOXIOUS WEED CONTROL	7,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
202020362	ABANDON WELL	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	664,560.000	CUYD
203020225	EXCAVATION-STREET	7,219.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	34,238.000	CUYD
203030117	EXPLORATORY EXCAVATION	8.000	HOURL
203080100	TOPSOIL-SALVAGING AND PLACING	64,792.000	CUYD
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.000	LS
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	240.000	MILE
301020268	TRAFFIC GRAVEL	8,118.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	43,195.000	CUYD
301020625	AGGREGATE TREATMENT	28,261.000	SQYD
304010002	BLOTTER MATERIAL	125,711.000	SQYD
304010005	BASE-CEMENT TREATED	50,361.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	36,554.000	TON
401020046	PLANT MIX BIT SURF GR S -MISC	1,410.000	TON
401020300	HYDRATED LIME	531.000	TON
402020092	ASPHALT CEMENT PG 64-28	1,747.800	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	20,518.000	GAL
402020360	EMULSIFIED ASPHALT CRS-2	108.700	TON
402020368	EMULSIFIED ASPHALT CRS-2P	307.400	TON
409000000	FINAL SWEEP AND BROOM	8.700	CRMI
409000010	COVER-TYPE 1	171,075.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	7.900	MILE
411011135	RUMBLE STRIPS	16.100	MILE
551020030	CONCRETE-CLASS GENERAL	8.000	CUYD
601010060	WATER SERVICE - 1 IN	6.000	EACH
601011920	INSULATION	720.000	SQFT
601012015	TEMPORARY WATER SERVICE	1.000	EACH
601012078	WATER SERVICE 2 IN	2.000	EACH
603000050	GRANULAR BEDDING MATERIAL	142.000	CUYD
603000060	FOUNDATION MATERIAL	231.000	CUYD
603010020	FILL AND ABANDON PIPE	21.000	CUYD
603010040	DRAINAGE PIPE 18 IN	1,536.000	LNFT
603010048	DRAINAGE PIPE 24 IN	754.000	LNFT
603010056	DRAINAGE PIPE 30 IN	1,786.000	LNFT
603010064	DRAINAGE PIPE 42 IN	232.000	LNFT
603010066	DRAINAGE PIPE 36 IN	550.000	LNFT
603010068	DRAINAGE PIPE 48 IN	136.000	LNFT
603010076	DRAINAGE PIPE 60 IN	238.000	LNFT
603012530	RCP 18 IN	484.000	LNFT
603012555	RCP 24 IN	68.000	LNFT
603012892	RCP IRR 24 IN	544.000	LNFT
603012925	RCP IRR 30 IN	196.000	LNFT

603013466	PIPE-PVC PRESS 8 IN WATER	1,584.000	LNFT
603013532	CONNECT TO MAIN	5.000	EACH
603013828	DUCTILE IRON FITTINGS	2,015.000	LB
603014492	HYDRANT ASSEMBLY	5.000	EACH
603016003	SPECIAL INSTALLATION OF PIPE	304.000	LNFT
603016045	STEEL CASING 24 IN	304.000	LNFT
603017040	STORM DRAIN PIPE-12 IN	238.000	LNFT
603017060	STORM DRAIN PIPE-24 IN	1,278.000	LNFT
603587020	REMOVE PIPE CULVERT	3,534.700	LNFT
603587030	REMOVE STORM DRAIN	251.700	LNFT
604000100	ADJUST MANHOLE	4.000	EACH
604000140	REMOVE DROP INLET	6.000	EACH
604010045	MANHOLE-48 IN TYPE 3	2.000	EACH
604010220	INLET DROP-SPECIAL DESIGN	3.000	EACH
604010255	INLET CURB-TYPE B	2.000	EACH
604010510	COMB MANHOLE AND DROP INLET	10.000	EACH
604010549	COMB 48 IN T3 MH-TB CURB INLET	2.000	EACH
607100229	FARM FENCE-TYPE F4W	16,597.000	LNFT
607100252	FARM FENCE-TYPE F4M	40,005.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	231.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	109.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	282.000	LNFT
607100720	DEADMAN	61.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	769.500	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	26.600	SQYD
608010090	CONCRETE 3 IN	26.200	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	28.600	SQYD
609010030	CURB-CONC MEDIAN TYPE A	75.000	LNFT
609010160	GUTTER-CONC VALLEY	774.700	SQYD
609010200	CURB AND GUTTER-CONC	1,822.400	LNFT
610100101	SEEDING AREA NO 1	109.200	ACRE
610100103	SEEDING AREA NO 3	30.700	ACRE
610100490	TURF REINF MAT-NATURAL FIBER	8,920.000	SQYD
610100555	CONDITION SEEDBED SURFACE	139.900	ACRE
613100030	RIPRAP-CLASS 1 RANDOM	42.200	CUYD
615010580	TRASH GUARD	1.000	EACH
615010741	VALVE-GATE 8 IN W/BOX	8.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	750,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	146.300	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	195.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	320.900	SQFT
619010210	RESET SIGNS-GUIDE	3.000	EACH
619010230	REMOVE SIGN	66.000	EACH
619010240	REMOVE SIGN-GUIDE	8.000	EACH
619010310	POSTS-STEEL U SIGN	188.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	590.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	1,188.000	LB
619010480	POLES-TREATED WOOD 4 IN	550.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	48.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7 (S100X11)	2.000	EACH
619010726	FRANG SIGN POST BKWY-W4 X 13 (W100X19)	2.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN (76MM)	2.000	EACH
619011010	DELINEATOR DES A	257.000	EACH
619011040	DELINEATOR DES D	20.000	EACH
619011179	DELINEATOR-FLEX SURF MTD WH	3.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	25.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	26.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	17.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	8.000	GAL
620012955	TEMPORARY STRIPING	94,333.000	LNFT
620013000	STRIPING-WHITE PAINT	616.000	GAL
620013960	STRIPING-WHITE EPOXY	410.000	GAL
620014000	STRIPING-YELLOW PAINT	354.000	GAL
620014960	STRIPING-YELLOW EPOXY	235.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	107.000	SQYD

622011084	GEOTEXTILE STABILIZATION	75,711.000	SQYD
623000180	MAILBOX-LARGE	1.000	EACH
SECTION NO. 0002 - ALTERNATE A1-REINFORCED CONCRETE BOX			
551020030	CONCRETE-CLASS GENERAL	13.600	CUYD
603000050	GRANULAR BEDDING MATERIAL	98.000	CUYD
603000060	FOUNDATION MATERIAL	196.000	CUYD
603013383	REIN CONC BOX 14 X 7	138.000	LNFT
622011084	GEOTEXTILE STABILIZATION	656.000	SQYD
SECTION NO. 0003 - ALTERNATE A2-STEEL STRUCTURAL PLATE PIPE ARCH			
551020030	CONCRETE-CLASS GENERAL	18.000	CUYD
603000050	GRANULAR BEDDING MATERIAL	275.000	CUYD
603000060	FOUNDATION MATERIAL	171.000	CUYD
603012265	SSPPA 15 FT 10 IN	116.000	LNFT
622011084	GEOTEXTILE STABILIZATION	574.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Glendive District Administrator.
 Uniform No. 7953000

102 HIGGINS AVE BRIDGE REHAB - MISSOULA STPB 8113(9) CONTRACT NO. 04B19

Bridge rehab and widening on the Higgins Ave Bridge Rehab-Missoula project located within the city limits of Missoula in Missoula County. Work includes: grading, cold milling, PMS overlay, pedestrian and safety rail, drainage, sidewalks, curb/gutter and electrical. The project is located on Urban Route 8113/Higgins Avenue beginning at RP 0.06, north the intersection with 4th Street, extending over the Clark Fork River to RP 0.33, south of the intersection with Front Street.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE REHAB AND WIDENING			
103000000	TRAINING PROGRAM	1,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	75,000.000	UNIT
104030045	MISCELLANEOUS ITEMS-EACH	2.000	EACH
104030065	MISCELLANEOUS ITEMS-LNFT	99.300	LNFT
104030070	MISCELLANEOUS ITEMS-REMOVAL	1.000	LS
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
202020115	REMOVE DECK	5,842.800	SQYD
202020140	REMOVE BITUMINOUS PAVEMENT	4,304.000	SQYD
203020200	EXCAVATION-UNCLASS BORROW	163.000	CUYD
203020225	EXCAVATION-STREET	556.000	CUYD
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
209010160	TEMPORARY SHORING	1.000	LS
301020340	CRUSHED AGGREGATE COURSE	255.000	CUYD
301020625	AGGREGATE TREATMENT	1,196.000	SQYD
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	998.000	TON
401020063	COMMERCIAL MIX-1/2 IN-PG 70-28	235.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	250.000	GAL
411010000	COLD MILLING	2,255.000	SQYD
551020035	CONCRETE-CLASS STRUCTURE	175.000	CUYD
551020104	CONCRETE CLASS-UHPC	24.300	CUYD
551020107	CONCRETE-CLASS DECK	1,730.500	CUYD
551020166	CONCRETE-CLASS DRILLED SHAFT	111.800	CUYD
552010042	FRP DECK PANELS	6,272.000	SQFT

552010045	SUPERSTRUCTURE JACKING	1.000	LS
552010060	REPAIR STRUCTURE	1.000	LS
552010303	CONCRETE STRUCT MODIFICATION	30.500	CUYD
552011000	EXPANSION JOINT	29.800	LNFT
552011010	EXPANSION JOINT STRIP SEAL	207.100	LNFT
553010010	PRESTRESSED BEAM-TYPE A	348.800	LNFT
555010100	REINFORCING STEEL	48,418.800	LB
555010410	REINFORCING STEEL-CR-CLASS 1	474,478.700	LB
556000110	PAINT STRUCTURE	1.000	LS
556010010	STRUCTURAL STEEL - MISC	1.000	LS
556010011	STRUCTURAL STEEL - GIRDER	1.000	LS
557010050	42 IN OPEN RAIL-BR	1,983.100	LNFT
557010055	42 IN OPEN RAIL PARAPET-BR	6.000	EACH
557010105	PEDESTRIAN RAIL	2,053.800	LNFT
557010110	HAND RAIL	482.900	LNFT
558000120	DRILLED SHAFT - 3.0 FT	25.000	LNFT
558000140	DRILLED SHAFT - 4.0 FT	225.000	LNFT
558010050	THERMAL INTEGRITY PROFILER	10.000	EACH
561010525	EXPANSION JOINT-PRECOMPRESSED	304.600	LNFT
563000040	POLYMER OVERLAY	7,015.300	SQYD
563000100	PREPARE DECK	7,015.300	SQYD
565000010	ELASTOMERIC BEARING DEVICES	61.000	EACH
603000050	GRANULAR BEDDING MATERIAL	90.000	CUYD
603000065	TRENCH DRAIN	124.000	LNFT
603012805	RCP IRR 12 IN CLASS 3	216.500	LNFT
603013457	PIPE-PVC 8 IN	265.000	LNFT
603013462	PIPE-PVC 6 IN	59.700	LNFT
603013553	CONNECT TO EXISTING MANHOLE	3.000	EACH
603750300	DRAINAGE-STRUCTURE	1.000	LS
604000100	ADJUST MANHOLE	4.000	EACH
604000260	ADJUST DROP INLET	1.000	EACH
604010045	MANHOLE-48 IN TYPE 3	3.000	EACH
605000010	TEMPORARY CONCRETE BARRIER RAIL	98.000	EACH
605000100	RESET TEMP CONC BARRIER RAIL	98.000	EACH
606010385	REMOVE GUARDRAIL	160.200	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
606011548	IMPACT ATTENUATOR-3 BAY	2.000	EACH
606400120	BOLLARDS	1.000	EACH
606400130	REMOVABLE BOLLARD	1.000	EACH
608010017	PEDESTRIAN STAIRWAY-STEEL	1.000	LS
608010020	SIDEWALK-CONCRETE 4 IN	260.100	SQYD
608010035	SIDEWALK-CONCRETE 4 IN COLORED	328.400	SQYD
608010052	SIDEWALK-CONCRETE 8 IN	244.500	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	4.700	SQYD
609010121	CURB-SPECIAL DESIGN	135.600	LNFT
609010160	GUTTER-CONC VALLEY	15.500	SQYD
609010200	CURB AND GUTTER-CONC	649.300	LNFT
609010209	REMOVE MEDIAN CURB	1,134.000	LNFT
610100559	REVEGETATION	1.000	LS
610100625	LANDSCAPING	1.000	LS
616323120	CONDUIT-STEEL 2 IN RIGID	2,900.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	850.000	LNFT
616723003	JUNCTION BOX	9.000	EACH
616783007	PULL BOX-COMPOSITE TYPE 2	2.000	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	1.000	EACH
617000000	FOUNDATION-CONCRETE	5.600	CUYD
617033212	CABLE-COPPER 3AWG12-600V	750.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	23,825.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	13,775.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	2,800.000	LNFT
617130066	DECORATIVE LUMINAIRE POLE-TYPE 1	27.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	7.000	EACH
617333198	SERV ASSEMBLY-200 AMP	1.000	EACH
617783035	OUTLET RECEPTACLE-120 VOLT	31.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618110000	INSTALL, REMOVE CAMERA SYSTEM	1.000	LS

619010086	SIGNS-ALUM REFL SHEET IV	15.800	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	60.500	SQFT
619010200	RESET SIGNS	1.000	EACH
619010210	RESET SIGNS-GUIDE	1.000	EACH
619010230	REMOVE SIGN	14.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	340.000	LB
620011105	WORDS AND SYMBOLS-WHITE PAINT	29.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	5.000	GAL
620011311	WORDS AND SYMBOLS-GREEN EPOXY	6.000	GAL
620012955	TEMPORARY STRIPING	1,446.500	LNFT
620013000	STRIPING-WHITE PAINT	25.000	GAL
620013960	STRIPING-WHITE EPOXY	34.000	GAL
620014000	STRIPING-YELLOW PAINT	11.000	GAL
620014960	STRIPING-YELLOW EPOXY	15.000	GAL
699010230	SUMP	1.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 8807000

103 SOUTH OF BOULDER - SOUTH STPIP-FLA 399-1(8)10 CONTRACT NO. 01C19

Grade, gravel, plant mix surfacing, S&C, drainage improvements, signing and other improvements on the South of Boulder-South project. The project is located on State Secondary Route 399 (Whitetail Road) and has two segments. The first segment (southern) begins just north of Antelope Road at RP 10.2, extending 9.1 miles to RP 19.3. The second segment (northern) is located closer to Boulder, MT and begins at RP 23.5 and ends at RP 25.0. The first segment will consist of a gravel surface and the second segment will be paved with plant mix surfacing. The project is located in Jefferson County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - G, GS, PLANT MIX BIT SURF, DRAINAGE			
103000000	TRAINING PROGRAM	1,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
105080115	FINISH GRADE CONTROL	110,600.000	CRFT
107000060	NOXIOUS WEED CONTROL	5,000.000	UNIT
107100010	CULTURAL RESOURCE PERSON	10.000	DAY
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	144,200.000	CUYD
203020175	EXCAVATION-UNCLASS CHANNEL	115.000	CUYD
203020200	EXCAVATION-UNCLASS BORROW	134,280.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	1,625.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	21,807.000	CUYD
204010185	BLASTING CONSULTANT	1.000	LS
206000050	DETOUR-MAINTAIN	1.000	LS
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	84.000	MILE
212000000	OBLITERATE ROADWAY	54.000	STA
301020111	SELECT SURFACING	39,580.000	CUYD
301020268	TRAFFIC GRAVEL	538.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	9,833.000	CUYD
301020450	SPECIAL BACKFILL	1,648.000	CUYD
301020465	LOW PERMEABILITY BACKFILL	238.000	CUYD
301020625	AGGREGATE TREATMENT	29,656.000	SQYD
401020062	COMMERCIAL MIX-1/2 IN-PG 64-28	4,722.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	739.000	GAL

402020368	EMULSIFIED ASPHALT CRS-2P	49.200	TON
409000000	FINAL SWEEP AND BROOM	1.800	CRMI
409000010	COVER-TYPE 1	27,348.000	SQYD
551020030	CONCRETE-CLASS GENERAL	7.900	CUYD
603000050	GRANULAR BEDDING MATERIAL	310.000	CUYD
603000060	FOUNDATION MATERIAL	220.000	CUYD
603010040	DRAINAGE PIPE 18 IN	1,636.000	LNFT
603010048	DRAINAGE PIPE 24 IN	1,514.000	LNFT
603010540	CSP 24 IN	316.000	LNFT
603010566	CSP 30 IN	70.000	LNFT
603012530	RCP 18 IN	152.000	LNFT
603012555	RCP 24 IN	172.000	LNFT
603012892	RCP IRR 24 IN	100.000	LNFT
603012925	RCP IRR 30 IN	78.000	LNFT
603013202	RCPA 24 IN	324.000	LNFT
603013212	RCPA 30 IN	120.000	LNFT
603013216	RCPA 36 IN	134.000	LNFT
603013255	RCPA 84 IN	104.000	LNFT
603013378	REIN CONC BOX 14 X 8	102.000	LNFT
603013528	PIPE-PVC CONDUIT 4 IN	184.000	LNFT
603587020	REMOVE PIPE CULVERT	1,222.900	LNFT
603587040	REMOVE AND SALVAGE CULVERT	101.000	LNFT
607000006	PANEL-SINGLE CHAIN LINK	3.000	EACH
607000008	PANEL-DOUBLE CHAIN LINK	2.000	EACH
607000050	FENCE-CHAIN LINK 6 FT	531.000	LNFT
607100008	FENCE-SPECIAL DESIGN	13.000	LNFT
607100114	FARM FENCE-TYPE F2W-32 IN WW	514.000	LNFT
607100149	FARM FENCE-TYPE F3W-32 IN WW	200.000	LNFT
607100229	FARM FENCE-TYPE F4W	85,746.000	LNFT
607100252	FARM FENCE-TYPE F4M	740.000	LNFT
607100259	FARM FENCE-TYPE F5W	7,343.000	LNFT
607100291	FARM FENCE-TYPE F6W	1,313.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	144.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	77.000	EACH
607100390	FENCE-PANEL/SNGL-SPECIAL DESIGN	2.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	592.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	272.000	LNFT
607100551	FENCE-TEMPORARY	7,880.000	LNFT
607100720	DEADMAN	84.000	EACH
610010100	TOPSOIL	5,097.000	CUYD
610100101	SEEDING AREA NO 1	21.900	ACRE
610100102	SEEDING AREA NO 2	2.900	ACRE
610100103	SEEDING AREA NO 3	25.200	ACRE
610100326	FERTILIZING AREA NO 1	21.900	ACRE
610100327	FERTILIZING AREA NO 2	2.900	ACRE
610100555	CONDITION SEEDBED SURFACE	47.100	ACRE
610100565	EROSION CONTROL BLANKET-HIGH-PERFORM	22,427.000	SQYD
610220100	MULCH	3.000	ACRE
611010025	CATTLE GUARD 24 FT-HEAVY DUTY (7.2 M)	2.000	EACH
611010200	REMOVE CATTLE GUARD	4.000	EACH
613100030	RIPRAP-CLASS 1 RANDOM	1,904.600	CUYD
613100080	RIPRAP-INFILL	165.000	CUYD
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	14.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	68.200	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	122.600	SQFT
619010200	RESET SIGNS	1.000	EACH
619010210	RESET SIGNS-GUIDE	9.000	EACH
619010230	REMOVE SIGN	35.000	EACH
619010240	REMOVE SIGN-GUIDE	1.000	EACH
619010310	POSTS-STEEL U SIGN	327.000	LB
619010480	POLES-TREATED WOOD 4 IN	318.000	LNFT
619011010	DELINEATOR DES A	400.000	EACH
619011030	DELINEATOR DES C	58.000	EACH
619011040	DELINEATOR DES D	12.000	EACH
619011060	DELINEATOR DES F	62.000	EACH
620012955	TEMPORARY STRIPING	18,546.000	LNFT

620013000	STRIPING-WHITE PAINT	129.000	GAL
620013960	STRIPING-WHITE EPOXY	86.000	GAL
620014000	STRIPING-YELLOW PAINT	128.000	GAL
620014960	STRIPING-YELLOW EPOXY	85.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	6,926.000	SQYD
622011084	GEOTEXTILE STABILIZATION	3,486.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

Uniform No. 6097000

104 BRADY - N & S (NB) IM 15-6(44)322 CONTRACT NO. 04A19

Cold milling, crack seal, PMS overlay, rumble strips, seal & cover and pavement markings on the Brady-N&S (NB) project located in Pondera and Teton Counties. There is an alternate bid for Hot In-Place Recycle (HIR) or Cold In-Place (CIR). The project begins at RP 322.3 and extends approximately 11.6 miles northwest along Interstate Route 15 to RP 334.3 in the northbound lanes.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - COLD MILLING, CRACK FILL, PMS OVERLAY, RUMBLE STRIPS, SEAL & COVER			
(5% TETON CO. / 95% PONDERA CO.)			
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
210020170	TEST TRAILER-TRANSPORT, SETUP	98.000	MILE
401020048	PLANT MIX SURF GR S-1/2 IN	26,450.000	TON
401020300	HYDRATED LIME	370.000	TON
402020095	ASPHALT CEMENT PG 70-28	1,482.200	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	13,927.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	474.500	TON
403010257	CRACK FILLING-MASTIC	864.000	LB
409000000	FINAL SWEEP AND BROOM	12.300	CRMI
409000020	COVER-TYPE 2	266,908.000	SQYD
411010000	COLD MILLING	7,670.000	SQYD
411011135	RUMBLE STRIPS	23.000	MILE
552010160	BRIDGE DECK CRACK SEAL	939.100	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	8.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	100,000.000	UNIT
619010062	SIGNS-ALUM SHEET INCR XI	53.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	85.500	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	91.500	SQFT
619010230	REMOVE SIGN	25.000	EACH
619010240	REMOVE SIGN-GUIDE	1.000	EACH
619010310	POSTS-STEEL U SIGN	432.000	LB
619010480	POLES-TREATED WOOD 4 IN	30.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	78.000	LNFT
619011010	DELINEATOR DES A	172.000	EACH
619011040	DELINEATOR DES D	10.000	EACH
619011080	DELINEATOR DES H	158.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	1.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	2.000	GAL
620012950	TEMPORARY STRIPING	11.600	MILE
620013000	STRIPING-WHITE PAINT	285.000	GAL
620013960	STRIPING-WHITE EPOXY	379.000	GAL

620014000	STRIPING-YELLOW PAINT	228.000	GAL
620014960	STRIPING-YELLOW EPOXY	304.000	GAL
SECTION NO. 0002 - ALTERNATE 1 - HOT RECYCLE MIX			
401020304	HOT RECYCLED PLANT MIX	196,689.000	SQYD
SECTION NO. 0003 - ALTERNATE 2 - COLD RECYCLE MIX			
401020325	COLD RECYCLED PLANT MIX	196,689.000	SQYD
SECTION NO. 0004 - ALTERNATE 3 - HIGH RAP MIX			
401020045	PLANT MIX SURF GR S-3/4 IN	25,289.000	TON
401020300	HYDRATED LIME	354.000	TON
402020095	ASPHALT CEMENT PG 70-28	1,313.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	9,773.000	GAL
411010000	COLD MILLING	196,689.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9391000

105 HOT SPRINGS - N & S STPP 36-1(33)16 CONTRACT NO. 15A19
TROUT CREEK - SE STPP 6-1(164)30

STPP 36-1(33)16 - Cold milling, PMS overlay, guardrail, rumble strips, seal & cover and pavement markings on the Hot Springs-N&S project located in Sanders County. The project begins at RP 16.2 and extends approximately 5 miles north along State Primary Route 36/MT 28 to RP 21.2. The entire project is located on the Flathead Indian Reservation.

STPP 6-1(164)30 - Crack sealing, guardrail, rumble strips, seal & cover and pavement markings on the Trout Creek-SE project located in Sanders County. The project begins at RP 29.5 and extends approximately 16.8 miles southeast along State Primary Route 6/MT 200 to RP 46.3.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - OVERLAY, SEAL & COVER ON 2 TIED PROJECTS			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	150.000	MILE
301020416	SHOULDER GRAVEL	2,108.000	CUYD
401020046	PLANT MIX BIT SURF GR S -MISC	442.000	TON
401020048	PLANT MIX SURF GR S-1/2 IN	12,265.000	TON
401020300	HYDRATED LIME	178.000	TON
402020092	ASPHALT CEMENT PG 64-28	736.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	4,821.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	25,752.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	613.900	TON
403010255	CRACK SEALING	8,363.000	LB
409000010	COVER-TYPE 1	341,193.000	SQYD
411010000	COLD MILLING	3,273.000	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	21.800	MILE
552010160	BRIDGE DECK CRACK SEAL	1,093.000	SQYD
605000070	REMOVE CONCRETE BARRIER RAIL	6.000	EACH
606010140	GUARDRAIL END SECTION WIDENING	11.000	EACH
606010330	MGS GUARDRAIL	534.300	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	11.000	EACH
606010339	MGS GRDL STIFF 1/4 POST SPACING	175.000	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.000	EACH
606010385	REMOVE GUARDRAIL	1,025.000	LNFT
609010030	CURB-CONC MEDIAN TYPE A	125.000	LNFT

610100559	REVEGETATION	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	150,000.000	UNIT
619010058	SIGNS-ALUM SHEET INCR IV	218.000	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	42.000	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	111.900	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	256.300	SQFT
619010230	REMOVE SIGN	45.000	EACH
619010240	REMOVE SIGN-GUIDE	10.000	EACH
619010310	POSTS-STEEL U SIGN	100.000	LB
619010480	POLES-TREATED WOOD 4 IN	552.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	106.000	LNFT
619011010	DELINEATOR DES A	132.000	EACH
619011040	DELINEATOR DES D	16.000	EACH
620012955	TEMPORARY STRIPING	10,560.000	LNFT
620013000	STRIPING-WHITE PAINT	953.000	GAL
620013960	STRIPING-WHITE EPOXY	1,036.000	GAL
620014000	STRIPING-YELLOW PAINT	393.000	GAL
620014960	STRIPING-YELLOW EPOXY	441.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9497000, 9495000

106 NORTH FORK ROAD (COLUMBIA FALLS) STPS 486-1(9)2 CONTRACT NO. 04C19

Nork Fork Rd (Columbia Falls) project consists of a crack seal, fog seal, and seal and cover with intermittent full width mill and overlay sections (totaling 2.1 miles) on State Secondary Route S-486. Other work includes new pavement markings, signing, and delineation. The project begins on North Fork Rd (State secondary route S-486) at RP 2.2 and extends northeast 10.1 miles to RP 12.4 The project is located in Flathead County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - CRACK SEAL, CENTER LINE RUMBLE STRIPS, FOG SEAL, SEAL & COVER			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
401020048	PLANT MIX SURF GR S-1/2 IN	5,220.000	TON
401020300	HYDRATED LIME	73.000	TON
402020092	ASPHALT CEMENT PG 64-28	302.600	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	2,086.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	13,746.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	333.900	TON
403010255	CRACK SEALING	11,667.000	LB
409000010	COVER-TYPE 1	185,756.000	SQYD
411010000	COLD MILLING	42,436.000	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	9.800	MILE
618030005	TRAFFIC CONTROL DEVICES CB	100,000.000	UNIT
619010086	SIGNS-ALUM REFL SHEET IV	155.200	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	224.700	SQFT
619010230	REMOVE SIGN	53.000	EACH
619010310	POSTS-STEEL U SIGN	215.000	LB
619010480	POLES-TREATED WOOD 4 IN	204.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	16.000	LNFT
619011010	DELINEATOR DES A	376.000	EACH
619011040	DELINEATOR DES D	27.000	EACH
619011060	DELINEATOR DES F	50.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	4.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.000	GAL

620012955	TEMPORARY STRIPING	20,376.000	LNFT
620013000	STRIPING-WHITE PAINT	443.000	GAL
620013960	STRIPING-WHITE EPOXY	492.000	GAL
620014000	STRIPING-YELLOW PAINT	328.000	GAL
620014960	STRIPING-YELLOW EPOXY	363.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Missoula District Administrator.
 Uniform No. 9514000

107 THOMPSON PASS - EAST STPS 471-1(14)10 CONTRACT NO. 02C19
ELMO - WEST STPP 36-2(10)36

STPS 471-1(14)10 - Seal & Cover, Pavement markings on the Thompson Pass - East project located in Sanders County.
 The project is located on Montana Secondary HWY 471(S-471) Idaho/Montana line PR 22 and extends along Montana Secondary HWY 471 to RP 10.

STPP 36-2(10)36 - Seal & Cover, Pavement markings on the Elmo - West project in Flathead and Lake Counties.
 The Project is located on MT-28 west from the town of Elmo (RP 46) and extends along MT 28 to RP 36.1.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & COVER, PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
402020320	EMULSIFIED ASPHALT-FOG SEAL	26,458.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	633.300	TON
403010255	CRACK SEALING	1,209.000	LB
409000010	COVER-TYPE 1	353,138.000	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	22.700	MILE
552010160	BRIDGE DECK CRACK SEAL	881.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	80,000.000	UNIT
620011105	WORDS AND SYMBOLS-WHITE PAINT	1.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620013000	STRIPING-WHITE PAINT	825.000	GAL
620013960	STRIPING-WHITE EPOXY	1,100.000	GAL
620014000	STRIPING-YELLOW PAINT	464.000	GAL
620014960	STRIPING-YELLOW EPOXY	618.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
 This project is under the jurisdiction of the Missoula District Administrator.
 Uniform No. 9513000, 9498000

108 SUPERIOR - SE STPS 257-1(9)0 CONTRACT NO. 05C19
 ALBERTON - EAST STPS 507-1(10)0

STPS 257-1(9)0 - Crack sealing, seal & cover, fog seal and mill/fill, pavement markings and guardrail upgrades on the Superior - Southeast project in Mineral County. The project is located on Secondary 257, beginning just south of the Superior Interchange at RP 0.0 and extends southeast to RP 5.7.

STPS 507-1(10)0 - Crack sealing, seal & cover and pavement markings on the Alberton - East project in Mineral and Missoula counties. The project is located on Secondary 507 beginning west of Alberton at the I-90 Alberton Interchange (RP 0.058) and extends easterly 2.4 miles through Alberton (Railroad Ave./Adams St.) ending just north of the I-90 Petty Creek Interchange (RP 2.476).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, FILL, SEAL & COVER, GUARDRAIL, PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION	1.000	LS
208010200	TEMPORARY EROSION CONTROL	500.000	UNIT
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	511.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	275.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	10,341.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	243.600	TON
403010255	CRACK SEALING	8,939.000	LB
409000010	COVER-TYPE 1	135,675.000	SQYD
411010000	COLD MILLING	5,442.000	SQYD
606010140	GUARDRAIL END SECTION WIDENING	3.000	EACH
606010330	MGS GUARDRAIL	175.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	3.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	3.000	EACH
606010385	REMOVE GUARDRAIL	425.000	LNFT
610100559	REVEGETATION	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	100,000.000	UNIT
620011105	WORDS AND SYMBOLS-WHITE PAINT	3.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.000	GAL
620012955	TEMPORARY STRIPING	3,784.000	LNFT
620013000	STRIPING-WHITE PAINT	297.000	GAL
620013960	STRIPING-WHITE EPOXY	396.000	GAL
620014000	STRIPING-YELLOW PAINT	245.000	GAL
620014960	STRIPING-YELLOW EPOXY	362.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%. All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator. Uniform No. 9512000, 9515000