

INVITATION FOR BIDS  
LETTING OF January 12, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on January 12, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

NHFP 90-4(82)211 - Pavement Preservation project to mill and fill full width the I-90 eastbound and westbound lanes, interchange ramps, crossroads at the Gregson Interchange, Ramsay Interchange and Nissler Junction to a depth of 0.20ft. and replaced with 0.20 ft. plant mix surfacing.

This project will also include a seal and cover, bridge work, MASH compliant guardrail, rumble strips, new cattleguards, pavement markings and updated signing.

The project is located 4.2 miles west of Butte on I-90. The project begins west of the Fairmont Interchange (RP 211.5) and proceeds 8.5 miles east to the Nissler Interchange (219.2).

HSIP STWD (657) - Nissler Interchange - NB to WB loop ramp (121.6 to 121.95): replace existing speed advisory sign with solar powered radar speed feedback sign, install linear delineation on barrier in curve. WB to SB ramp: install chevrons and shoulder rumble strips through curve.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PAVE PRES, MILL FILL			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020140	REMOVE BITUMINOUS PAVEMENT	1,922.000	SQYD
203020278	EXCAVATION-DIGOUTS	4,261.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	3,040.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	23.000	MILE
301020340	CRUSHED AGGREGATE COURSE	780.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	61,685.000	TON
401020300	HYDRATED LIME	864.000	TON
402020095	ASPHALT CEMENT PG 70-28	3,889.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	28,378.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	804.300	TON
409000000	FINAL SWEEP AND BROOM	17.000	CRMI
409000020	COVER-TYPE 2	451,779.000	SQYD
411010000	COLD MILLING	482,374.000	SQYD
411011135	RUMBLE STRIPS	34.290	MILE
501010210	PORT CEM CONC PAVE 10 IN	3,760.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	5,536.000	SQYD
552011140	RESEAL EXISTING JOINTS	32.800	LNFT
557010606	REMOVE BRIDGE RAIL	1,087.900	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	58.500	SQYD
605000000	CONCRETE BARRIER RAIL TRANSITION	1.000	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	1,190.200	LNFT
605000045	REVISE CONC BARRIER RAIL END-BR	8.000	EACH
605000070	REMOVE CONCRETE BARRIER RAIL	169.000	EACH
605000080	TALL CONCRETE BARRIER RAIL	128.000	EACH
605000090	CONCRETE BARRIER RAIL	37.000	EACH
606010140	GUARDRAIL END SECTION WIDENING	30.000	EACH
606010330	MGS GUARDRAIL	22,253.100	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	30.000	EACH
606010339	MGS GRDL STIFF 1/4 POST SPACING	150.000	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	11.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	23.000	EACH
606010385	REMOVE GUARDRAIL	24,225.000	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	8.000	EACH
606011510	REMOVE IMPACT ATTENUATOR	1.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	8.000	EACH
606011520	IMPACT ATTENUATOR	1.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	850.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	5.000	EACH

607100380	FARM FENCE-PANEL/DOUBLE FW	11.000	EACH
609010112	CURB 4 IN-CONCRETE	180.000	LNFT
609010203	REMOVE CURB	30.000	LNFT
611010025	CATTLE GUARD 24 FT-HEAVY DUTY	8.000	EACH
611010200	REMOVE CATTLE GUARD	8.000	EACH
617000000	FOUNDATION-CONCRETE	0.500	CUYD
617673200	SIG STANDARD TYPE 1-200	1.000	EACH
617903461	VEHICLE SPEED FEEDBACK SIGN-SOLAR	1.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	450,000.000	UNIT
618100000	SINGLE USE SIGNS	200.000	SQFT
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	30.000	DAY
618190100	TEMPORARY BARRIER RAIL	2,970.000	LNFT
618190110	RESET TEMP BARRIER RAIL	2,620.000	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	4,198.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1,106.500	SQFT
619010230	REMOVE SIGN	99.000	EACH
619010240	REMOVE SIGN-GUIDE	40.000	EACH
619010300	POSTS-TUBULAR STEEL	1,147.000	LB
619010310	POSTS-STEEL U SIGN	722.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,173.000	LB
619010480	POLES-TREATED WOOD 4 IN	216.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	525.000	LNFT
619010720	FRANG SIGN POST BKWY-S3 X 5.7	2.000	EACH
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD	4.000	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD	4.000	EACH
619010800	PANEL DELINEATOR DESIGN A	13.000	EACH
619010830	PANEL DELINEATOR DESIGN H	13.000	EACH
619011010	DELINEATOR DES A	329.000	EACH
619011020	DELINEATOR DES B	37.000	EACH
619011040	DELINEATOR DES D	16.000	EACH
619011070	DELINEATOR DES G	84.000	EACH
619011085	DELINEATOR DES BJ	67.000	EACH
619011087	DELINEATOR DES GJ	37.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	8.000	GAL
620012955	TEMPORARY STRIPING	64,889.000	LNFT
620013000	STRIPING-WHITE PAINT	852.000	GAL
620013960	STRIPING-WHITE EPOXY	680.000	GAL
620014000	STRIPING-YELLOW PAINT	712.000	GAL
620014960	STRIPING-YELLOW EPOXY	475.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	3,760.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

Uniform No. 9465000, 9652000

## 102 MALTA - SOUTH NH

61-4 (26) 147

CONTRACT NO. 03B22

The Malta - South project is the major rehabilitation of 9.6 miles of US Highway 191 (N-61) in Phillips County. The project begins approximately 9.5 miles south of Malta at Reference Post 147.4, just south of S Alkali Creek Road and extends north for 9.6 miles to the intersection of US 191 and 9th Street at Reference Post 157.0. The roadway surface will be rehabilitated or reconstructed to current design standards, including centerline and shoulder rumble strips, new and lengthened drainage structures, signing, and pavement markings

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
----------	-------------	----------	-------

SECTION NO. 0001 - RD REHAB/RECONST, DRAINAGE, RUMBLE STRIPS, SIGNING,  
PAVEMENT MARKINGS

103000000	TRAINING PROGRAM	1,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
107000060	NOXIOUS WEED CONTROL	10,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020358	ABANDON WELL	2.000	EACH
203020100	EXCAVATION-UNCLASSIFIED	572,900.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	10,516.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	61,785.000	CUYD
204010185	BLASTING CONSULTANT	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	2,000.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	240.000	MILE
301020254	BRIDGE END BACKFILL-TYPE 3	990.000	CUYD
301020450	SPECIAL BACKFILL	4,159.000	CUYD
301020465	LOW PERMEABILITY BACKFILL	235.000	CUYD
302000000	PAVEMENT PULVERIZATION	70,085.000	SQYD
409000000	FINAL SWEEP AND BROOM	9.800	CRMI
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	9.100	MILE
411011135	RUMBLE STRIPS	18.400	MILE
551020030	CONCRETE-CLASS GENERAL	66.800	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	2.000	CUYD
552010160	BRIDGE DECK CRACK SEAL	1,132.000	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	10.000	SQYD
601010770	ADJUST WATER SERVICE LINE	1.000	EACH
601011920	INSULATION	144.000	SQFT
603000050	GRANULAR BEDDING MATERIAL	1,018.000	CUYD
603000060	FOUNDATION MATERIAL	1,033.000	CUYD
603010040	DRAINAGE PIPE 18 IN	1,938.000	LNFT
603010048	DRAINAGE PIPE 24 IN	1,234.000	LNFT
603010056	DRAINAGE PIPE 30 IN	794.000	LNFT
603010064	DRAINAGE PIPE 42 IN	228.000	LNFT
603010066	DRAINAGE PIPE 36 IN	802.000	LNFT
603010068	DRAINAGE PIPE 48 IN	388.000	LNFT
603010072	DRAINAGE PIPE 54 IN	126.000	LNFT
603010076	DRAINAGE PIPE 60 IN	148.000	LNFT
603010080	DRAINAGE PIPE 66 IN	164.000	LNFT
603010084	DRAINAGE PIPE 72 IN	302.000	LNFT
603010088	DRAINAGE PIPE 78 IN	384.000	LNFT
603010714	CSP 96 IN	60.000	LNFT
603010730	CSP 120 IN	90.000	LNFT
603012530	RCP 18 IN	216.000	LNFT
603012555	RCP 24 IN	198.000	LNFT
603012625	RCP 30 IN	278.000	LNFT
603012660	RCP 36 IN	138.000	LNFT
603013212	RCPA 30 IN EQ DIA	124.000	LNFT
603013216	RCPA 36 IN EQ DIA	174.000	LNFT
603013235	RCPA 48 IN EQ DIA	98.000	LNFT
603013263	RCPA 84 IN EQ DIA	32.000	LNFT
603014242	ADJUST VALVE BOX	2.000	EACH
603016050	STEEL CASING 30 IN	88.000	LNFT
603016150	RELAY PIPE CULVERT	30.000	LNFT
603017070	STORM DRAIN PIPE-30 IN	351.600	LNFT
603017085	STORM DRAIN PIPE-42 IN	191.200	LNFT
603587020	REMOVE PIPE CULVERT	3,719.900	LNFT
604000100	ADJUST MANHOLE	3.000	EACH
604000200	RESET FIRE HYDRANT	2.000	EACH
604010306	MANHOLE STRUCTURE BASE 72 IN	1.000	EACH
604010308	MANHOLE STRUCTURE BASE 84 IN (2100 MM)	1.000	EACH
604010358	ADDITIONAL BARREL 84 IN	2.000	LNFT
604010660	MANHOLE LID AND FRAME	2.000	EACH
605000045	REVISE CONC BARRIER RAIL END-BR	4.000	EACH
606010190	GUARDRAIL-STL/BR APPR-TY 2	4.000	EACH

606010330	MGS GUARDRAIL	637.400	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	7.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	40.000	LNFT
606010385	REMOVE GUARDRAIL	1,306.400	LNFT
606011518	TEMPORARY IMPACT ATTENUATOR	4.000	EACH
607000030	FENCE-CHAIN LINK 4 FT	126.000	LNFT
607100010	FENCE-WILDLIFE FRIENDLY FW/FM	21,131.000	LNFT
607100114	FARM FENCE-TYPE F2W-32 IN WW	1,303.000	LNFT
607100147	FARM FENCE-TYPE F2M-32 IN WW	1,436.000	LNFT
607100229	FARM FENCE-TYPE F4W	702.000	LNFT
607100252	FARM FENCE-TYPE F4M	51,785.000	LNFT
607100293	FARM FENCE-TYPE F6M	1,685.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	12.000	EACH
607100362	FARM FENCE-PANEL/SINGLE FM	104.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	8.000	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	231.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	724.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	16.000	LNFT
607100551	FENCE-TEMPORARY	3,202.000	LNFT
607100720	DEADMAN	55.000	EACH
607150131	RESET GATE	3.000	EACH
608000020	SIDEWALK DRAIN	2.000	EACH
608010050	SIDEWALK-CONCRETE 6 IN	494.500	SQYD
608010067	REMOVE SIDEWALK	150.700	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	20.200	SQYD
609010030	CURB-CONC MEDIAN TYPE A	97.000	LNFT
609010160	GUTTER-CONC VALLEY	22.500	SQYD
609010200	CURB AND GUTTER-CONC	710.600	LNFT
609010305	REMOVE CURB AND GUTTER	367.300	LNFT
610100101	SEEDING AREA NO 1	170.500	ACRE
610100103	SEEDING AREA NO 3	16.900	ACRE
610100326	FERTILIZING AREA NO 1	170.500	ACRE
610100470	SODDING	318.000	SQYD
610100490	TURF REINF MAT-NATURAL FIBER	34,110.000	SQYD
610100555	CONDITION SEEDBED SURFACE	170.500	ACRE
610100560	RIPRAP REVEGETATION	541.000	SQYD
611010016	CATTLE GUARD 16 FT-LIGHT DUTY	3.000	EACH
611010025	CATTLE GUARD 24 FT-HEAVY DUTY	1.000	EACH
611010200	REMOVE CATTLE GUARD	4.000	EACH
613100030	RIPRAP-CLASS 1 RANDOM	365.900	CUYD
613100040	RIPRAP-CLASS 2 RANDOM	159.400	CUYD
614010009	RETAINING WALL	13.000	SQYD
615010580	TRASH GUARD	3.000	EACH
617000000	FOUNDATION-CONCRETE	1.000	CUYD
617573070	RECTANGULAR RAPID FLASHING BEACON	2.000	EACH
617673200	SIG STANDARD TYPE 1-200	2.000	EACH
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	750,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618190100	TEMPORARY BARRIER RAIL	530.000	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	182.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	491.100	SQFT
619010180	HISTORICAL MARKER	1.000	EACH
619010230	REMOVE SIGN	76.000	EACH
619010240	REMOVE SIGN-GUIDE	6.000	EACH
619010310	POSTS-STEEL U SIGN	160.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	850.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	399.000	LB
619010480	POLES-TREATED WOOD 4 IN	816.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	64.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	6.000	EACH
619010724	FRANG SIGN POST BKWY-S5 X 10	2.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	2.000	EACH
619011010	DELINEATOR DES A	305.000	EACH
619011040	DELINEATOR DES D	20.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	2.000	GAL

620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	15.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	8.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	10.000	GAL
620012955	TEMPORARY STRIPING	57,546.000	LNFT
620013000	STRIPING-WHITE PAINT	712.000	GAL
620013960	STRIPING-WHITE EPOXY	475.000	GAL
620014000	STRIPING-YELLOW PAINT	319.000	GAL
620014960	STRIPING-YELLOW EPOXY	254.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	541.000	SQYD
622011084	GEOTEXTILE STABILIZATION	19,992.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	161,837.000	SQYD
623000155	MAILBOX	9.000	EACH
SECTION NO. 0002 - ALTERNATE AA1- CRUSHED AGG BASE SURFACING			
301020268	TRAFFIC GRAVEL	9,000.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	124,652.000	CUYD
301020625	AGGREGATE TREATMENT	234,458.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	56,433.000	TON
401020046	PLANT MIX BIT SURF GR S -MISC	2,948.000	TON
401020300	HYDRATED LIME	831.000	TON
402020092	ASPHALT CEMENT PG 64-28	2,886.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	23,854.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	443.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	367.800	TON
409000010	COVER-TYPE 1	207,030.000	SQYD
SECTION NO. 0003 - ALTERNATE AA2 - CEMENT TREATED BASE SURFACING			
301020268	TRAFFIC GRAVEL	9,000.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	69,370.000	CUYD
301020625	AGGREGATE TREATMENT	95,005.000	SQYD
304010002	BLOTTER MATERIAL	143,851.000	SQYD
304010005	BASE-CEMENT TREATED	33,130.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	57,166.000	TON
401020046	PLANT MIX BIT SURF GR S -MISC	2,948.000	TON
401020300	HYDRATED LIME	842.000	TON
402020092	ASPHALT CEMENT PG 64-28	2,922.300	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	24,365.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	443.000	GAL
402020360	EMULSIFIED ASPHALT CRS-2	124.400	TON
402020375	EMULSIFIED ASPHALT CHFRS-2P	367.800	TON
409000010	COVER-TYPE 1	207,030.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator. Uniform No. 7951000

**103 POWER - N&S**

**IM 15-6(46)301**

**CONTRACT NO. 01123**

The Power - N& S project is in Teton County on Interstate 15 (I-15) beginning at RP 301.4, the Cascade/Teton County line, and continuing north 7.8 miles to RP 309.2, approximately 3 miles south of the Dutton Interchange. Mainline will be milled and overlaid full width and new shoulder rumble strips will be cut. The Power Interchange ramps and crossroad will be crack sealed. Everything will be chip sealed.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, OVERLAY, SEAL & COVER			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS

109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	46.000	MILE
401020045	PLANT MIX SURF GR S-3/4 IN	45,242.000	TON
401020300	HYDRATED LIME	633.000	TON
402020095	ASPHALT CEMENT PG 70-28	2,266.400	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	18,002.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	636.600	TON
403010255	CRACK SEALING	466.000	LB
409000000	FINAL SWEEP AND BROOM	16.200	CRMI
409000020	COVER-TYPE 2	356,025.000	SQYD
411010000	COLD MILLING	364,880.000	SQYD
411011135	RUMBLE STRIPS	30.400	MILE
552010160	BRIDGE DECK CRACK SEAL	2,734.700	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	90.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	2.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	200,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620012955	TEMPORARY STRIPING	20,592.000	LNFT
620013000	STRIPING-WHITE PAINT	766.000	GAL
620013960	STRIPING-WHITE EPOXY	516.000	GAL
620014000	STRIPING-YELLOW PAINT	598.000	GAL
620014960	STRIPING-YELLOW EPOXY	401.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 9948000

**104 FALLON - SOUTHWEST**

**CRSII-IM 94-5(46)178**

**CONTRACT NO. 10R22**

Mill & overlay, seal & cover, rumble strips, bridge deck repair, bridge rail, guardrail, signing, & pavement markings on the Fallon - Southwest project.

This project is located on I-94 east bound lanes the project begins at RP 178.0, 1.5± miles east of Terry Exit 176 and ends at to 184.5, 1.0± miles west of Fallon Exit 185.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL & OVERLAY, SEAL & COVER			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	171.600	LNFT
202020139	REMOVE ASPHALT FROM DECK	153.700	SQYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	30.000	MILE
401020045	PLANT MIX SURF GR S-3/4 IN	18,920.000	TON
401020300	HYDRATED LIME	260.000	TON
402020095	ASPHALT CEMENT PG 70-28	948.300	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	7,398.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	248.800	TON
409000000	FINAL SWEEP AND BROOM	6.500	CRMI
409000010	COVER-TYPE 1	139,213.000	SQYD

411010000	COLD MILLING	149,824.000	SQYD
411011135	RUMBLE STRIPS	12.800	MILE
552010041	REVISE JOINT	182.000	LNFT
552010140	TRANSVERSE DECK GROOVING	2,198.800	SQYD
561010525	EXPANSION JOINT-PRECOMPRESSED	305.900	LNFT
561020110	BRIDGE DECK MILLING	2,292.500	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	32.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.000	SQYD
563000010	CONCRETE-CLASS OVERLAY	2,292.500	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.000	UNIT
563000040	POLYMER OVERLAY	1,271.100	SQYD
563000045	POLYMER OVERLAY PRIMER	1,271.100	SQYD
563000100	PREPARE DECK	1,271.100	SQYD
605000040	REVISE CONCRETE BARRIER RAIL-BR	1,557.000	LNFT
606010037	MASH BOX BEAM TERMINAL - MBEAT	22.000	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	3,312.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	10.000	EACH
606010190	GUARDRAIL-STL/BR APPR-TY 2	3.000	EACH
606010325	GRD RL-BOX BEAM TO W-BEAM TRANS	6.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	6.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	8.000	EACH
606010385	REMOVE GUARDRAIL	3,951.000	LNFT
609010203	REMOVE CURB	1,600.000	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	2.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	6.500	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	1.000	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	1.000	EACH
618030280	CROSSOVER RECLAMATION	2.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	142.300	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	113.300	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	94.000	SQFT
619010230	REMOVE SIGN	25.000	EACH
619010240	REMOVE SIGN-GUIDE	3.000	EACH
619010310	POSTS-STEEL U SIGN	504.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	74.000	LB
619011010	DELINEATOR DES A	168.000	EACH
619011020	DELINEATOR DES B	12.000	EACH
619011080	DELINEATOR DES H	168.000	EACH
620012955	TEMPORARY STRIPING	67,253.000	LNFT
620013000	STRIPING-WHITE PAINT	295.000	GAL
620013955	REMOVE PAVEMENT MARKINGS	34,848.000	LNFT
620013960	STRIPING-WHITE EPOXY	417.000	GAL
620014000	STRIPING-YELLOW PAINT	236.000	GAL
620014960	STRIPING-YELLOW EPOXY	314.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator. Uniform No. 9404000

**105 I-94 FARM FENCE - RP 0-78 (D5) IM 94-1 (84) 0 CONTRACT NO. 07123**

Installation of farm and wildlife fencing and cattle guards on the I-94 Farm Fence - RP 0-78 (D5) project in Yellowstone and Treasure Counties. The project begins near Billings on Interstate 94 at the Pinehill Interchange (RP 0.1) and extends northeast 78.3 miles to the Rosebud County line. Cattle Guard replacements are at the Pompey's Pillar Interchange (RP 23.3) and the Sarpy Creek Interchange (RP 72.0).

INVOLVING



ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - INTERSTATE FENCING, CATTLE GUARDS			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
606010370	RESET GUARDRAIL	250.000	LNFT
607100012	FENCE - WILDLIFE FRIENDLY FM	186,332.000	LNFT
607100152	FARM FENCE-TYPE F3M-32 IN WW	85,314.000	LNFT
607100281	FARM FENCE-TYPE F5M	103,891.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	188.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	75.000	EACH
607100390	FENCE-PANEL/SNGL-SPECIAL DESIGN	854.000	EACH
607100395	FENCE-PANEL/DBL-SPECIAL DESIGN	555.000	EACH
607100720	DEADMAN	340.000	EACH
610100559	REVEGETATION	1.000	LS
611010030	CATTLE GUARD 30 FT-HEAVY DUTY	7.000	EACH
611010040	CATTLE GUARD 40 FT-HEAVY DUTY	1.000	EACH
611010210	REMOVE AND SALVAGE CATTLE GUARD	8.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator. Uniform No. 8131003

106 **DEARBORN - N & S** **IM 15-4(172)229** **CONTRACT NO. 28R22**

Crack Seal and Seal & Cover on I-15 in Lewis and Clark and Cascade Counties, beginning at RP 236.8, approximately 0.5 miles north of NBI I00015236+02121 bridge over the Missouri River and extends north 11.1 miles to RP 247.9 approximately 0.5 miles north of the Hardy Creek Interchange. Interchange ramps and crossroads will be included.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & COVER			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
402020375	EMULSIFIED ASPHALT CHFRS-2P	910.800	TON
403010255	CRACK SEALING	69,093.000	LB
409000000	FINAL SWEEP AND BROOM	24.700	CRMI
409000020	COVER-TYPE 2	511,968.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	185,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
620010300	CURB MARKING-YELLOW PAINT	12.000	GAL
620010301	CURB MARKING-YELLOW EPOXY	16.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	115.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	153.000	GAL
620013000	STRIPING-WHITE PAINT	538.000	GAL
620013960	STRIPING-WHITE EPOXY	718.000	GAL
620014000	STRIPING-YELLOW PAINT	491.000	GAL

620014960 STRIPING-YELLOW EPOXY

655.000 GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 9946000

INVITATION FOR BIDS  
LETTING OF February 23, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on February 23, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

NHPB STWD(730) - The I-15 Bridge Rehab - Clancy Area project is a bridge repair and resurfacing project on 9 bridges on I-15 located in the vicinity of Clancy and Montana City. The project involves spot repair, overlays, or replacement of bridge decks. In addition, the bridges will have railing systems updated to meet current bridge railing safety standards and other minor bridge repairs will be included. Crossover construction, guardrail, and surfacing.

NHPB 15-1(128)180 - The I-15 Bridge Rehab - Jefferson City project is a bridge repair and resurfacing project on 3 bridges on I-15 located in the vicinity of Jefferson City. The project involves spot repair and patching at various locations of two stream crossing bridges, and complete replacement of the deck at the Jefferson City Interchange. In addition, the bridges will have railing systems updated to meet current bridge railing safety standards and other minor bridge repairs will be included.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE REHABILITATION			
104030010	MISCELLANEOUS WORK	150,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	319.800	LNFT
202020115	REMOVE DECK	2,108.200	SQYD
203020100	EXCAVATION-UNCLASSIFIED	2,532.000	CUYD
203020185	TEMPORARY CHANNEL DIVERSION	1.000	LS
203020278	EXCAVATION-DIGOUTS	137.000	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
209010160	TEMPORARY SHORING	1.000	LS
301020252	BRIDGE END BACKFILL-TYPE 1	69.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	2,148.000	CUYD
301020625	AGGREGATE TREATMENT	3,346.000	SQYD
401020021	COMMERCIAL MIX-PG 70-28	2,072.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	458.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	14.800	TON
409000000	FINAL SWEEP AND BROOM	0.600	CRMI
409000020	COVER-TYPE 2	8,104.000	SQYD
411010000	COLD MILLING	5,772.000	SQYD
411011135	RUMBLE STRIPS	0.600	MILE
501010401	CONCRETE-SHALLOW REPAIR	1.600	SQYD
551020036	CONCRETE-CLASS STRUCTURE LOW SLUMP	502.900	CUYD
552010043	FRP REINFORCEMENT	98.400	SQFT
552010059	EPOXY INJECTION	34.800	LNFT
552010060	REPAIR STRUCTURE	1.000	LS
552010140	TRANSVERSE DECK GROOVING	3,831.800	SQYD
552011010	EXPANSION JOINT STRIP SEAL	34.600	LNFT
552011030	EXPANSION JOINT-ASPHALT PLUG	175.600	LNFT
552011120	JOINT SEALS-POLYURETHANE	247.300	LNFT
555010200	REINFORCING STEEL-EPOXY COATED	127,396.000	LB
556000100	PAINT EXISTING STRUCTURAL STEEL	0.400	SQYD
561020110	BRIDGE DECK MILLING	2,113.800	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	9.400	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	8.000	SQYD
563000010	CONCRETE-CLASS OVERLAY	2,113.800	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.000	UNIT
563000040	POLYMER OVERLAY	665.000	SQYD
563000045	POLYMER OVERLAY PRIMER	665.000	SQYD
563000100	PREPARE DECK	665.000	SQYD
563000110	WATERPROOF MEMBRANE	34.800	SQYD
603013413	PIPE-CORR POLYETHYLENE DR 8 IN	133.000	LNFT
603015270	EMBANKMENT PROTECTOR 18 IN	528.000	LNFT
603587010	REMOVE EMBANKMENT PROTECTOR	280.000	LNFT

604000270	ADJUST MEDIAN INLET	1.000	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	1,493.400	LNFT
605000093	36 IN SS CONCRETE BARRIER RAIL-BR-CSC	1,117.500	LNFT
606010117	HIGH-TENSION CABLE RAIL	2,161.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	21.000	EACH
606010150	GUARDRAIL-STL/BR APPR-TY 1	6.000	EACH
606010330	MGS GUARDRAIL	2,927.300	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	21.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	38.000	EACH
606010386	REMOVE AND SALVAGE GUARDRAIL	2,880.600	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	8.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	8.000	EACH
607150125	RESET FENCE	40.000	LNFT
609010112	CURB 4 IN-CONCRETE	1,506.300	LNFT
609010200	CURB AND GUTTER-CONC	24.000	LNFT
609010203	REMOVE CURB	1,374.300	LNFT
610100559	REVEGETATION	1.000	LS
610100560	RIPRAP REVEGETATION	6.000	SQYD
613100040	RIPRAP-CLASS 2 RANDOM	39.000	CUYD
613300050	BANK PROTECTION-TYPE 3	21.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	40,000.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	5.000	EACH
618030280	CROSSOVER RECLAMATION	5.000	EACH
618100000	SINGLE USE SIGNS	377.000	SQFT
618190100	TEMPORARY BARRIER RAIL	1,400.000	LNFT
618190110	RESET TEMP BARRIER RAIL	1,400.000	LNFT
620013000	STRIPING-WHITE PAINT	32.000	GAL
620013955	REMOVE PAVEMENT MARKINGS	132,280.000	LNFT
620013960	STRIPING-WHITE EPOXY	353.000	GAL
620014000	STRIPING-YELLOW PAINT	30.000	GAL
620014960	STRIPING-YELLOW EPOXY	285.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	74.000	SQYD
622011084	GEOTEXTILE STABILIZATION	192.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	4,220.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
Uniform No. 9783000, 9782000

**202 CARTER - NORTH & SOUTH**

**CRSII-NH 10-3(22)20**

**CONTRACT NO. 06123**

Milling, PMS overlay, seal and cover, signing and pavement markings on the Carter - North & South project located in Chouteau County. The project begins at RP 20.06 and proceeds northeast along US-87 (N-10) for approximately 9.7 miles traversing through the Town of Carter and ending at RP 29.73.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - COLD MILLING & PMS OVERLAY			
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	48.000	MILE
401020045	PLANT MIX SURF-3/4 IN	25,168.000	TON

401020300	HYDRATED LIME	352.000	TON
402020192	ASPHALT CEMENT PG 58V-34	1,433.100	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	20,524.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	338.600	TON
409000000	FINAL SWEEP AND BROOM	9.700	CRMI
409000010	COVER-TYPE 1	188,401.000	SQYD
411010000	COLD MILLING	203,271.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	9.700	MILE
411011135	RUMBLE STRIPS	19.400	MILE
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	182.500	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	264.900	SQFT
619010230	REMOVE SIGN	44.000	EACH
619010240	REMOVE SIGN-GUIDE	8.000	EACH
619010310	POSTS-STEEL U SIGN	180.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	167.000	LB
619010480	POLES-TREATED WOOD 4 IN	532.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	102.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	8.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	18.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	5.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	12.000	GAL
620012955	TEMPORARY STRIPING	102,708.000	LNFT
620013000	STRIPING-WHITE PAINT	724.000	GAL
620013960	STRIPING-WHITE EPOXY	482.000	GAL
620014000	STRIPING-YELLOW PAINT	372.000	GAL
620014960	STRIPING-YELLOW EPOXY	249.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 9845000

**203 CYR BR REHAB - 3M W ALBERTON STPB 31170(2) CONTRACT NO. 05123**

The Cyr Bridge Rehab - 3M W Alberton project will rehabilitate the existing Cyr bridge, replace the bridge rail, install new approach guardrail, reconstruct the roadway (200 ft. from the west bridge end and 150 ft. from the east bridge end), and construct a historical turnout with a historical marker on the northeast corner of the bridge. The project is located on Fish Creek Rd/Old MT-10 (X-31170) in Mineral County, approximately 3 miles west of Alberton from RP 0.0 to 0.2.

INVOLVING

-----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001 - MAJOR BRIDGE REHAB			
103000000	TRAINING PROGRAM	500.000	HOURL
104030010	MISCELLANEOUS WORK	35,000.000	UNIT
104030035	MISCELLANEOUS ITEMS-REPAIR	1.000	LS
104030037	MISCELLANEOUS ITEMS-SQYD	78.000	SQYD
104030040	MISCELLANEOUS ITEMS-SQFT	25.000	SQFT
104030045	MISCELLANEOUS ITEMS-EACH	1.000	EACH
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020115	REMOVE DECK	28.800	SQYD
203020100	EXCAVATION-UNCLASSIFIED	748.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS

208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	272.000	CUYD
301020625	AGGREGATE TREATMENT	1,155.000	SQYD
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	345.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	174.000	GAL
551020035	CONCRETE-CLASS STRUCTURE	7.100	CUYD
552010060	REPAIR STRUCTURE	1.000	LS
552011010	EXPANSION JOINT STRIP SEAL	52.000	LNFT
555010100	REINFORCING STEEL	236.000	LB
555010200	REINFORCING STEEL-EPOXY COATED	5,402.000	LB
556000110	PAINT STRUCTURE	1.000	LS
556010010	STRUCTURAL STEEL - MISC	1.000	LS
557010110	HAND RAIL	1,062.800	LNFT
557010537	REVISE BRIDGE RAIL-W830	1,074.300	LNFT
557010606	REMOVE BRIDGE RAIL	1,060.700	LNFT
561010525	EXPANSION JOINT-PRECOMPRESSED	57.500	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	50.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	20.000	SQYD
563000040	POLYMER OVERLAY	1,381.300	SQYD
563000045	POLYMER OVERLAY PRIMER	1,381.300	SQYD
563000100	PREPARE DECK	1,381.300	SQYD
606010037	MASH BOX BEAM TERMINAL - MBEAT	4.000	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	54.000	LNFT
606010266	GRD RL-BOX BEAM/BR APP-SEC TYPE 2	4.000	EACH
607100149	FARM FENCE-TYPE F3W-32 IN WW	117.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	1.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	1.000	EACH
610100559	REVEGETATION	1.000	LS
613100030	RIPRAP-CLASS 1 RANDOM	2.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618100005	PORTABLE VARIABLE MESSAGE SIGN	4.000	EACH
619010090	SIGNS-ALUM REFL SHEET XI	16.400	SQFT
619010180	HISTORICAL MARKER	1.000	EACH
619010230	REMOVE SIGN	8.000	EACH
619010480	POLES-TREATED WOOD 4 IN	32.000	LNFT
620013000	STRIPING-WHITE PAINT	2.000	GAL
620013960	STRIPING-WHITE EPOXY	3.000	GAL
620014000	STRIPING-YELLOW PAINT	2.000	GAL
620014960	STRIPING-YELLOW EPOXY	3.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	1,139.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
Uniform No. 9524000

**204 SOUTH OF LIVINGSTON - SOUTH NH 11-1(94)24 CONTRACT NO. 01223**  
Scrub seal and cover, new pavement markings, and upgrades to existing guardrail on the South of Livingston - South project located in Park County. The project begins at RP 23.7 and extends approximately 25.9 miles northeast along National Highway Route 11/US-89 to RP 49.7.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001 - SCRUB SEAL & COVER, GUARDRAIL			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS

208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
402020377	SCRUB SEAL EMULSION	901.700	TON
409000000	FINAL SWEEP AND BROOM	25.600	CRMI
409000010	COVER-TYPE 1	501,543.000	SQYD
606010140	GUARDRAIL END SECTION WIDENING	34.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	34.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	28,562.500	LNFT
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	375.000	LNFT
606010385	REMOVE GUARDRAIL	29,362.500	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
620011105	WORDS AND SYMBOLS-WHITE PAINT	11.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	24.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	13.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	32.000	GAL
620013000	STRIPING-WHITE PAINT	959.000	GAL
620013960	STRIPING-WHITE EPOXY	1,278.000	GAL
620014000	STRIPING-YELLOW PAINT	430.000	GAL
620014960	STRIPING-YELLOW EPOXY	573.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 9476000

**205 BOULDER HILL - GUARDRAIL IM 15-3(97)167 CONTRACT NO. 03123**

The Boulder Hill - Guardrail project is located in Jefferson County on Interstate 15. The project begins approximately 3 miles north of the Boulder Interchange (Exit 164) at RP 167.0 and extends north to RP 175.1, near the Jefferson City Interchange (Exit 176). The project will replace guardrail including terminal sections, bridge approach sections and one-way departure terminal sections. The project will also include roadway delineation.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001 - GUARDRAIL SAFETY IMPROVEMENTS			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
552011120	JOINT SEALS-POLYURETHANE	122.000	LNFT
605000040	REVISE CONCRETE BARRIER RAIL-BR	803.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	19.000	EACH
606010330	MGS GUARDRAIL	46,700.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	19.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	19.000	EACH
606010385	REMOVE GUARDRAIL	48,337.500	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	4.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	4.000	EACH
609010112	CURB 4 IN-CONCRETE	24,153.000	LNFT
609010203	REMOVE CURB	24,153.000	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618190100	TEMPORARY BARRIER RAIL	2,000.000	LNFT
618190110	RESET TEMP BARRIER RAIL	2,000.000	LNFT



619011010	DELINEATOR DES A	359.000	EACH
619011020	DELINEATOR DES B	12.000	EACH
619011080	DELINEATOR DES H	326.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	4,610.000	EACH
619011139	DELINEATION-LINEAR-YELLOW-W-BEAM	3,082.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 9245000

INVITATION FOR BIDS  
LETTING OF March 9, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on March 9, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

NHFP 90-4(82)211 - Pavement Preservation project to mill and fill full width the I-90 eastbound and westbound lanes, interchange ramps, crossroads at the Gregson Interchange, Ramsay Interchange and Nissler Junction to a depth of 0.20ft. and replaced with 0.20 ft. plant mix surfacing.

This project will also include a seal and cover, bridge work, MASH compliant guardrail, rumble strips, new cattleguards, pavement markings and updated signing. The project is located 4.2 miles west of Butte on I-90. The project begins west of the Fairmont Interchange (RP 211.1) and proceeds 8.5 miles east to the Nissler Interchange (219.2).

HSIP STWD (657) - Nissler Interchange - NB to WB loop ramp (121.6 to 121.95): replace existing speed advisory sign with solar powered radar speed feedback sign, install linear delineation on barrier in curve. WB to SB ramp: install chevrons and shoulder rumble strips through curve.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PAVE PRES, MILL FILL			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020278	EXCAVATION-DIGOUTS	2,407.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	1,602.000	CUYD
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	23.000	MILE
301020340	CRUSHED AGGREGATE COURSE	401.000	CUYD
301020416	SHOULDER GRAVEL	53.000	CUYD
401020045	PLANT MIX SURF-3/4 IN	61,528.000	TON
401020300	HYDRATED LIME	861.000	TON
402020095	ASPHALT CEMENT PG 70-28	3,889.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	25,174.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	802.600	TON
409000000	FINAL SWEEP AND BROOM	17.000	CRMI
409000020	COVER-TYPE 2	450,513.000	SQYD
411010000	COLD MILLING	482,374.000	SQYD
411011135	RUMBLE STRIPS	34.290	MILE
501010210	PORT CEM CONC PAVE 10 IN	1,266.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	5,536.000	SQYD
552011140	RESEAL EXISTING JOINTS	32.800	LNFT
557010606	REMOVE BRIDGE RAIL	1,087.900	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	58.500	SQYD
605000000	CONCRETE BARRIER RAIL TRANSITION	1.000	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	1,199.200	LNFT
605000045	REVISE CONC BARRIER RAIL END-BR	8.000	EACH
605000070	REMOVE CONCRETE BARRIER RAIL	169.000	EACH
605000080	TALL CONCRETE BARRIER RAIL	128.000	EACH
605000090	CONCRETE BARRIER RAIL	37.000	EACH
606010140	GUARDRAIL END SECTION WIDENING	30.000	EACH
606010330	MGS GUARDRAIL	22,253.100	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	30.000	EACH
606010339	MGS GRDL STIFF 1/4 POST SPACING	150.000	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	11.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	23.000	EACH
606010385	REMOVE GUARDRAIL	24,225.000	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	9.000	EACH
606011510	REMOVE IMPACT ATTENUATOR	1.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	9.000	EACH
606011520	IMPACT ATTENUATOR	1.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	850.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	5.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	11.000	EACH
609010112	CURB 4 IN-CONCRETE	180.000	LNFT

609010203	REMOVE CURB	30.000	LNFT
610100559	REVEGETATION	1.000	LS
611010025	CATTLE GUARD 24 FT-HEAVY DUTY	8.000	EACH
611010200	REMOVE CATTLE GUARD	8.000	EACH
617000000	FOUNDATION-CONCRETE	0.500	CUYD
617673200	SIG STANDARD TYPE 1-200	1.000	EACH
617903461	VEHICLE SPEED FEEDBACK SIGN-SOLAR	1.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	700,000.000	UNIT
618100000	SINGLE USE SIGNS	200.000	SQFT
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	50.000	DAY
618190100	TEMPORARY BARRIER RAIL	3,540.000	LNFT
618190110	RESET TEMP BARRIER RAIL	3,120.000	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	4,198.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1,106.500	SQFT
619010230	REMOVE SIGN	99.000	EACH
619010240	REMOVE SIGN-GUIDE	40.000	EACH
619010300	POSTS-TUBULAR STEEL	1,147.000	LB
619010310	POSTS-STEEL U SIGN	722.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,173.000	LB
619010480	POLES-TREATED WOOD 4 IN	216.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	525.000	LNFT
619010720	FRANG SIGN POST BKWY-S3 X 5.7	2.000	EACH
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD	4.000	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD	4.000	EACH
619010800	PANEL DELINEATOR DESIGN A	13.000	EACH
619010830	PANEL DELINEATOR DESIGN H	13.000	EACH
619011010	DELINEATOR DES A	329.000	EACH
619011020	DELINEATOR DES B	37.000	EACH
619011040	DELINEATOR DES D	16.000	EACH
619011070	DELINEATOR DES G	84.000	EACH
619011085	DELINEATOR DES BJ	67.000	EACH
619011087	DELINEATOR DES GJ	37.000	EACH
619011205	DELINEATION-LINEAR-BARRIER-YELLOW	232.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	8.000	GAL
620012955	TEMPORARY STRIPING	64,889.000	LNFT
620013000	STRIPING-WHITE PAINT	852.000	GAL
620013960	STRIPING-WHITE EPOXY	680.000	GAL
620014000	STRIPING-YELLOW PAINT	712.000	GAL
620014960	STRIPING-YELLOW EPOXY	475.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	1,746.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

Uniform No. 9465000, 9652000

**102 SF 139 - RACETRACK BRIDGE REMOVAL IM-HSIP 90-4(70)196 CONTRACT NO. 03323**

Remove Structures, grading, gravel, plant mix surfacing, seal & cover, pavement markings and updated signing on the SF 139 - Racetrack Bridge Removal located in Deer Lodge and Powell counties.

The project is located on Interstate Route 90 south of the Racetrack Interchange between Deer Lodge and Warm Springs. The project begins at RP-195.35 and extends east to RP-196.2. The project length is 0.6 miles. The project Reference Posts and stationing run from north to south.

INVOLVING

-----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - STRUCTURE REMOVAL			
103000000	TRAINING PROGRAM	500.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	75,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	266,475.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	45,054.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	7,089.000	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	56.000	MILE
301020340	CRUSHED AGGREGATE COURSE	15,757.000	CUYD
301020450	SPECIAL BACKFILL	20,667.000	CUYD
301020625	AGGREGATE TREATMENT	46,471.000	SQYD
401020045	PLANT MIX SURF-3/4 IN	16,363.000	TON
401020300	HYDRATED LIME	229.000	TON
402020095	ASPHALT CEMENT PG 70-28	850.700	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	6,976.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	68.200	TON
409000000	FINAL SWEEP AND BROOM	1.700	CRMI
409000020	COVER-TYPE 2	38,336.000	SQYD
411011135	RUMBLE STRIPS	3.200	MILE
551020030	CONCRETE-CLASS GENERAL	19.600	CUYD
603000050	GRANULAR BEDDING MATERIAL	549.000	CUYD
603000060	FOUNDATION MATERIAL	704.000	CUYD
603012725	RCP 54 IN	564.000	LNFT
603013361	REIN CONC BOX 8 X 6	318.000	LNFT
603587020	REMOVE PIPE CULVERT	1,387.400	LNFT
606010020	GUARDRAIL-TEMPORARY	1,450.000	LNFT
606010021	TEMP GD RAIL-STL/BR APPR-TY 1	2.000	EACH
606010024	TEMP OPTIONAL TERM SECT	2.000	EACH
606010117	HIGH-TENSION CABLE RAIL	400.000	LNFT
606010330	MGS GUARDRAIL	400.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	2.000	EACH
606010385	REMOVE GUARDRAIL	5,387.500	LNFT
606011300	RESET OPTIONAL TERMINAL SECT	1.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	9,468.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	21.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	24.000	EACH
607100720	DEADMAN	2.000	EACH
610010100	TOPSOIL	2,000.000	CUYD
610100101	SEEDING AREA NO 1	17.700	ACRE
610100103	SEEDING AREA NO 3	6.200	ACRE
610100326	FERTILIZING AREA NO 1	17.700	ACRE
610100555	CONDITION SEEDBED SURFACE	23.900	ACRE
618030015	TRAFFIC CONTROL-FIXED	50,000.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	4.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	4.000	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	1.000	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	1.000	EACH
618030280	CROSSOVER RECLAMATION	2.000	EACH
618100000	SINGLE USE SIGNS	200.000	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	151.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	98.300	SQFT
619010200	RESET SIGNS	1.000	EACH
619010230	REMOVE SIGN	6.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010300	POSTS-TUBULAR STEEL	501.000	LB
619010310	POSTS-STEEL U SIGN	72.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	880.000	LB

619010490	POLES-TREATED WOOD 5 IN	16.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
619010730	FRANG SIGN POST BKWY-W8 X 18	2.000	EACH
619011010	DELINEATOR DES A	24.000	EACH
619011070	DELINEATOR DES G	8.000	EACH
619011080	DELINEATOR DES H	28.000	EACH
620012955	TEMPORARY STRIPING	26,944.000	LNFT
620013000	STRIPING-WHITE PAINT	76.000	GAL
620013960	STRIPING-WHITE EPOXY	51.000	GAL
620014000	STRIPING-YELLOW PAINT	62.000	GAL
620014960	STRIPING-YELLOW EPOXY	41.000	GAL
622011084	GEOTEXTILE STABILIZATION	2,503.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	72,839.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

Uniform No. 8613000

**103 W BROADWAY - OLD HWY 10 (MSLA) NH 132-1(2)0 CONTRACT NO. 09R22  
PATH PRESERVATION - MISSOULA TA 8199(165)**

NH 132-1(2)0 - This resurfacing project on W. Broadway (Old Hwy 10) in Missoula County begins on the south side of the S-474/US Hwy 10 W. intersection and extends southeasterly 5.6 miles to the west side of the Reserve Street interchange. The pavement will be milled and overlaid with new asphalt. Other work includes chip seal, fog seal, guardrail upgrades, inlet adjustment, new signing, and pavement markings.

TA 8199(165) - Crack filling, dig out (tree root removal), surfacing, and fog seal over the entire length of the path. The project is located on the Northside Greenway Path that runs parallel to the railroad tracks on the northside of Missoula.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - OVERLAY, CHIP SEAL, GUARDRAIL, SIGNING, PAVEMENT MARKINGS, & PATH PRESERVATION			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020278	EXCAVATION-DIGOUTS	459.000	CUYD
203020375	EMBANKMENT IN PLACE	305.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010015	AQUATIC RESOURCE MONITOR	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	126.000	CUYD
301020416	SHOULDER GRAVEL	80.000	CUYD
401020048	PLANT MIX SURF-1/2 IN	25,962.000	TON
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	76.000	TON
401020300	HYDRATED LIME	363.000	TON
402020192	ASPHALT CEMENT PG 58V-34	1,505.500	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	10,272.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	16,095.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	377.700	TON
403010255	CRACK SEALING	314.000	LB
409000020	COVER-TYPE 2	211,518.000	SQYD
411010000	COLD MILLING	205,234.000	SQYD
603014242	ADJUST VALVE BOX	12.000	EACH
604000100	ADJUST MANHOLE	1.000	EACH

604000260	ADJUST DROP INLET	8.000	EACH
605000070	REMOVE CONCRETE BARRIER RAIL	18.000	EACH
605000090	CONCRETE BARRIER RAIL	12.000	EACH
606010150	GUARDRAIL-STL/BR APPR-TY 1	4.000	EACH
606010330	MGS GUARDRAIL	665.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	5.000	EACH
606010385	REMOVE GUARDRAIL	528.100	LNFT
609010010	CURB-CONCRETE	72.000	LNFT
610100559	REVEGETATION	1.000	LS
617533000	SIG-TRAF-BACKPLATE-REFLECTIVE	34.000	EACH
617763510	DETECTOR-RADAR/ADVANCE	3.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	275,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	684.900	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	911.700	SQFT
619010230	REMOVE SIGN	79.000	EACH
619010240	REMOVE SIGN-GUIDE	30.000	EACH
619010310	POSTS-STEEL U SIGN	134.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	2,169.000	LB
619010480	POLES-TREATED WOOD 4 IN	482.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	462.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	14.000	EACH
619010724	FRANG SIGN POST BKWY-S5 X 10	4.000	EACH
619011010	DELINEATOR DES A	124.000	EACH
619011040	DELINEATOR DES D	48.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	14.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	24.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	78.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	44.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	51.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	30.000	GAL
620012955	TEMPORARY STRIPING	118,014.000	LNFT
620013000	STRIPING-WHITE PAINT	880.000	GAL
620013960	STRIPING-WHITE EPOXY	586.000	GAL
620014000	STRIPING-YELLOW PAINT	560.000	GAL
620014960	STRIPING-YELLOW EPOXY	373.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

[http://www.mdt.mt.gov/business/contracting/under the "Advertised Bid Packages" link.](http://www.mdt.mt.gov/business/contracting/under%20the%20Advertised%20Bid%20Packages%20link)

This project is under the jurisdiction of the Missoula District Administrator. Uniform No. 9863000, 10086000

**104 THOMPSON FALLS - URBAN STPP 6-1(172)50 CONTRACT NO. 01323**

Milling and overlay and seal and cover on the Thompson Falls - Urban project located in Sanders County. Additional work will include approach chip sealing, new pavement markings, signing, delineation, luminaire replacements, and ADA upgrades. The project begins at RP 50.2 and extends southeasterly through the town of Thompson Falls for approximately 1.3 miles ending at RP 51.5.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL & FILL, SEAL & COVER, ADA UPGRADES			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS

208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	216.000	MILE
301020340	CRUSHED AGGREGATE COURSE	84.000	CUYD
301020625	AGGREGATE TREATMENT	1,530.000	SQYD
401020064	COMMERCIAL PLANT MIX-MISC	307.000	TON
401020162	COMMERCIAL MIX-1/2 IN-PG 58V-34	2,653.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,132.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	76.000	TON
409000000	FINAL SWEEP AND BROOM	1.300	CRMI
409000030	COVER-TYPE 3	34,387.000	SQYD
411010000	COLD MILLING	20,749.000	SQYD
603014242	ADJUST VALVE BOX	11.000	EACH
604000260	ADJUST DROP INLET	12.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	1,111.000	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	433.900	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	52.600	SQYD
609010200	CURB AND GUTTER-CONC	2,169.200	LNFT
610100559	REVEGETATION	1.000	LS
616343914	CONDUIT-PLASTIC 1 1/2 IN	95.000	LNFT
616782999	ADJUST PULL BOX	3.000	EACH
616783006	PULL BOX-COMPOSITE TYPE 1	3.000	EACH
617000000	FOUNDATION-CONCRETE	1.160	CUYD
617123106	CONDUCTOR-COPPER AWG6-600V	172.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	273.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	2.000	EACH
617303800	RESET LUMINAIRE ASSEMBLY	1.000	LS
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
619010090	SIGNS-ALUM REFL SHEET XI	512.800	SQFT
619010230	REMOVE SIGN	58.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	2,455.300	LB
619010480	POLES-TREATED WOOD 4 IN	88.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	64.000	LNFT
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	4.000	EACH
619011010	DELINEATOR DES A	19.000	EACH
619011040	DELINEATOR DES D	10.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	24.000	GAL
620010310	CURB MARKING-BLUE PAINT	2.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	30.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	22.000	GAL
620012955	TEMPORARY STRIPING	11,272.000	LNFT
620013000	STRIPING-WHITE PAINT	78.000	GAL
620013960	STRIPING-WHITE EPOXY	69.000	GAL
620014000	STRIPING-YELLOW PAINT	44.000	GAL
620014960	STRIPING-YELLOW EPOXY	39.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
Uniform No. 9708000

**105 SF 189 93 N RUMBLE STRIPS HSIP 5-1(83)7 CONTRACT NO. 02323**

SF 189 93 N Rumble Strips project located in Missoula and Lake Counties. Install new rumble strips at various locations on US 93. Install shoulder rumble strips where not currently present from RP 6.5 to RP 45.7 and the curve near RP 70. This project is located entirely within the Flathead Indian Reservation.



INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RUMBLE STRIPS			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
411011135	RUMBLE STRIPS	20.200	MILE
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
620013960	STRIPING-WHITE EPOXY	1,296.000	GAL
620014960	STRIPING-YELLOW EPOXY	146.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
Uniform No. 9892000

INVITATION FOR BIDS  
LETTING OF April 6, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on April 6, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

Roadside safety enhancements include installations of advance warning signs with flashing beacons, road closure gates, electronic variable message signs (VMS), guardrail to shield the VMS structures, and upgrading wind speed gauge on the I-90 Incident Management project located in Broadwater, Gallatin, Park, Sweet Grass, Stillwater, and Yellowstone Counties.

This project begins just east of the Three Forks Interchange at RP 273.7 and extends 182.3 miles east past the Johnson Lane Interchange near Billings at RP 456.0.

## INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GUARDRAIL, SIGNING, ELECTRICAL			
Billing District 53% Butte District 47%			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
107000020	CONTAMINATED SOIL	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
551020030	CONCRETE-CLASS GENERAL	3.000	CUYD
606010150	GUARDRAIL-STL/BR APPR-TY 1	1.000	EACH
606010330	MGS GUARDRAIL	3,700.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	16.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	16.000	EACH
606010385	REMOVE GUARDRAIL	50.000	LNFT
616323114	CONDUIT-STEEL 1 1/2 IN RIGID	210.000	LNFT
616343914	CONDUIT-PLASTIC 1 1/2 IN	1,450.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	20,312.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	110.000	EACH
617000000	FOUNDATION-CONCRETE	68.000	CUYD
617000050	POLES-TREATED WOOD CLASS 4	450.000	LNFT
617000060	GATE-ROAD CLOSURE	34.000	EACH
617033214	CABLE-COPPER 3AWG14-600V	628.000	LNFT
617033314	CABLE-COPPER 5AWG14-600V	21,760.000	LNFT
617123104	CONDUCTOR-COPPER AWG4-600V	10,219.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	9,860.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	48,258.000	LNFT
617303300	HIGH EFFICACY LUMINAIRE LED	34.000	EACH
617333000	SERV ASSEMBLY-MODIFY	1.000	EACH
617333100	SERV ASSEMBLY	24.000	EACH
617483110	SIG-TRAF 1 COL-1 WAY 12	37.000	EACH
617523010	SOL SIG-TRAF 1 COLOR-1 WAY 12	48.000	EACH
617673200	SIG STANDARD TYPE 1-200	24.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903459	BLANKOUT SIGN	1.000	EACH
617903475	VARIABLE MESSAGE SIGN COLOR-HALF	5.000	EACH
617903480	VARIABLE MESSAGE SIGN COLOR-FULL	12.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
619010062	SIGNS-ALUM SHEET INCR XI	1,199.700	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	321.400	SQFT
619010320	POSTS-STEEL STRUCTURAL SIGN	11,121.000	LB
619010510	OVERHEAD STRUCTURE/METAL	7.000	EACH
619010521	OVERHEAD STR/METAL-CANTILEVER	6.000	EACH
619010726	FRANG SIGN POST BKWY-W4 X 13	30.000	EACH
619010730	FRANG SIGN POST BKWY-W8 X 18	18.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
 Uniform No. 9856000

**102 SWAN LAKE STPP 83-2(25)71 CONTRACT NO. 01423**

The Swan Lake project is located in Lake County on Highway 83 (P-83) from RP 70.5 to 77.6. The project will include an asphalt mill and overlay, seal and cover, and fog seal. In addition, new pavement markings, signing, delineation, sinusoidal rumble strips, and guardrail upgrades will be included.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, FILL, SEAL & COVER, GUARDRAIL UPGRADES			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010015	AQUATIC RESOURCE MONITOR	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	80.000	MILE
401020048	PLANT MIX SURF-1/2 IN	12,409.000	TON
401020300	HYDRATED LIME	174.000	TON
402020192	ASPHALT CEMENT PG 58V-34	706.100	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	4,896.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	8,093.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	193.200	TON
409000010	COVER-TYPE 1	107,838.000	SQYD
411010000	COLD MILLING	100,184.000	SQYD
411011145	SINUSOIDAL RUMBLE STRIPS	5.200	MILE
606010140	GUARDRAIL END SECTION WIDENING	21.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	21.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	15,450.000	LNFT
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	1.000	EACH
606010386	REMOVE AND SALVAGE GUARDRAIL	16,509.700	LNFT
610100559	REVEGETATION	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	400,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	80.000	DAY
619010062	SIGNS-ALUM SHEET INCR XI	90.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	753.400	SQFT
619010200	RESET SIGNS	5.000	EACH
619010230	REMOVE SIGN	105.000	EACH
619010240	REMOVE SIGN-GUIDE	4.000	EACH
619010310	POSTS-STEEL U SIGN	379.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	155.800	LB
619010480	POLES-TREATED WOOD 4 IN	1,066.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	146.000	LNFT
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	2.000	EACH
619011010	DELINEATOR DES A	225.000	EACH
619011030	DELINEATOR DES C	68.000	EACH
619011040	DELINEATOR DES D	4.000	EACH
619011060	DELINEATOR DES F	215.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	4.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	2.000	GAL
620012955	TEMPORARY STRIPING	67,955.000	LNFT
620013000	STRIPING-WHITE PAINT	528.000	GAL
620013960	STRIPING-WHITE EPOXY	352.000	GAL
620014000	STRIPING-YELLOW PAINT	494.000	GAL
620014960	STRIPING-YELLOW EPOXY	329.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
 Uniform No. 9869000

**103 KALISPELL URBAN PAVE PRES UPP 6799(60) CONTRACT NO. 03423**

This project is located in Flathead County and includes multiple locations within the Kalispell area. The work on E. Reserve Dr. (RP 0.009 to RP 0.998), W. Evergreen Dr. (RP 0.728 to RP 1.437), Airport Rd. (RP 11.368 to RP 12.115), Conrad Dr. (RP 1.496 to RP 1.554), and Woodland Park Dr. (RP 0.002 to RP 0.410) includes milling out the existing roadway surface, applying a plant mix overlay and finishing with a seal & cover. The work on 7th Ave. E. / Whitefish Stage (RP 0.010 to RP 2.559) and Woodland Ave. (RP 0.005 to RP 1.082) includes a seal and cover only. This project will receive new pavement markings and the manholes and valve boxes that are located within the milling area will receive concrete collars.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - COLD MILL, OVERLAY, SEAL & COVER			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105080112	ADJUST MONUMENT BOX	2.000	EACH
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010015	AQUATIC RESOURCE MONITOR	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	2.000	MILE
401020048	PLANT MIX SURF-1/2 IN	5,299.000	TON
401020300	HYDRATED LIME	74.000	TON
620014960	STRIPING-YELLOW EPOXY	268.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
 Uniform No. 10217000

**104 SE OF MILES CITY - SOUTH NH 23-1(38)28 CONTRACT NO. 22R22**

Resurfacing, rumble strips, striping, and signing on the SE of Miles City - South project.

This project is located on Montana Highway Route 59 (National Highway Route 23) in Custer County. NH-23 is classified as a principal arterial route. The project begins approximately 27.5 miles south of Miles City, at RP 27.8 and extends 5.4 miles south to RP 33.2.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RESURFACING			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT

210020170	TEST TRAILER-TRANSPORT, SETUP	1.000	MILE
401020045	PLANT MIX SURF-3/4 IN	14,600.000	TON
401020046	PLANT MIX BIT SURF-MISC	210.000	TON
401020300	HYDRATED LIME	207.000	TON
402020095	ASPHALT CEMENT PG 70-28	712.200	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5,742.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	192.400	TON
409000000	FINAL SWEEP AND BROOM	5.400	CRMI
409000010	COVER-TYPE 1	108,541.000	SQYD
411010000	COLD MILLING	112,325.000	SQYD
411011135	RUMBLE STRIPS	10.800	MILE
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	73.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	76.900	SQFT
619010230	REMOVE SIGN	14.000	EACH
619010240	REMOVE SIGN-GUIDE	4.000	EACH
619010310	POSTS-STEEL U SIGN	120.000	LB
619010480	POLES-TREATED WOOD 4 IN	122.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	140.000	LNFT
619011010	DELINEATOR DES A	150.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
620012955	TEMPORARY STRIPING	56,664.000	LNFT
620013000	STRIPING-WHITE PAINT	392.000	GAL
620013960	STRIPING-WHITE EPOXY	261.000	GAL
620014000	STRIPING-YELLOW PAINT	66.000	GAL
620014960	STRIPING-YELLOW EPOXY	44.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.  
Uniform No. 9582000

INVITATION FOR BIDS  
LETTING OF April 27, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on April 27, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

The Buxton - North & South project is located on Interstate Route 15 (I-15) in Silver Bow County. The project begins south of the Buxton Interchange at RP 115.9 and proceeds 5 miles north to end at the Rarus Bridge near the I-90 Nissler Interchange at RP 120.9. Works includes seal and cover, culvert replacement, guardrail upgrades, bridge work, cattle guards, and pavement markings.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & COVER, CULVERT REPLACEMENT			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
104030070	MISCELLANEOUS ITEMS-REMOVAL	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	166.000	LNFT
202020097	REMOVE BRIDGE APPROACH SLAB	4.000	EACH
202020140	REMOVE BITUMINOUS PAVEMENT	272.000	SQYD
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	483.000	CUYD
301020450	SPECIAL BACKFILL	6,932.000	CUYD
301020625	AGGREGATE TREATMENT	2,044.000	SQYD
401020021	COMMERCIAL MIX-PG 70-28	1,909.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	797.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	5,879.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	294.100	TON
409000000	FINAL SWEEP AND BROOM	9.800	CRMI
409000020	COVER-TYPE 2	163,610.000	SQYD
411010000	COLD MILLING	4,666.000	SQYD
411011135	RUMBLE STRIPS	0.600	MILE
551020030	CONCRETE-CLASS GENERAL	13.800	CUYD
552010140	TRANSVERSE DECK GROOVING	1,126.400	SQYD
552010160	BRIDGE DECK CRACK SEAL	4,968.100	SQYD
556000100	PAINT EXISTING STRUCTURAL STEEL	364.200	SQYD
561010525	EXPANSION JOINT-PRECOMPRESSED	214.000	LNFT
561020110	BRIDGE DECK MILLING	1,175.800	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	16.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.000	SQYD
563000010	CONCRETE-CLASS OVERLAY	1,175.800	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.000	UNIT
603000050	GRANULAR BEDDING MATERIAL	124.000	CUYD
603000060	FOUNDATION MATERIAL	247.000	CUYD
603013371	REIN CONC BOX 9 X 9	234.000	LNFT
603587020	REMOVE PIPE CULVERT	218.000	LNFT
605000040	REVISE CONCRETE BARRIER RAIL-BR	522.000	LNFT
605000045	REVISE CONC BARRIER RAIL END-BR	8.000	EACH
606010020	GUARDRAIL-TEMPORARY	1,600.000	LNFT
606010022	TEMP GD RAIL-STL/BR APPR-TY 3	5.000	EACH
606010024	TEMP OPTIONAL TERM SECT	16.000	EACH
606010117	HIGH-TENSION CABLE RAIL	1,879.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	46.000	EACH
606010330	MGS GUARDRAIL	6,100.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	33.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	5,563.000	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010370	RESET GUARDRAIL	646.000	LNFT
606010385	REMOVE GUARDRAIL	11,130.300	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	1,075.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	20.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	6.000	EACH
609010112	CURB 4 IN-CONCRETE	670.000	LNFT
609010203	REMOVE CURB	520.000	LNFT



610100559	REVEGETATION	1.000	LS
611010022	CATTLE GUARD 20 FT-HEAVY DUTY	1.000	EACH
611010025	CATTLE GUARD 24 FT-HEAVY DUTY	6.000	EACH
611010200	REMOVE CATTLE GUARD	7.000	EACH
618030015	TRAFFIC CONTROL-FIXED	10,000.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	12.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	6.000	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	2.000	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	4.000	EACH
618030280	CROSSOVER RECLAMATION	6.000	EACH
618100000	SINGLE USE SIGNS	240.000	SQFT
618190100	TEMPORARY BARRIER RAIL	300.000	LNFT
618190110	RESET TEMP BARRIER RAIL	300.000	LNFT
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	16.000	GAL
620012955	TEMPORARY STRIPING	15,442.000	LNFT
620013000	STRIPING-WHITE PAINT	282.000	GAL
620013960	STRIPING-WHITE EPOXY	376.000	GAL
620014000	STRIPING-YELLOW PAINT	208.000	GAL
620014960	STRIPING-YELLOW EPOXY	277.000	GAL
622011084	GEOTEXTILE STABILIZATION	310.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
Uniform No. 9462000

**202 JCT S279 - WEST (MT 200) NH 24-3(69)76 CONTRACT NO. 05423**  
**LINCOLN - E&W NH 24-3(73)65**

NH 24-3(69)76 - The JCT S-279 West (MT-200) project is in Lewis and Clark County on MT 200 beginning at RP 75+0.751 (accumulated miles 76.486) and ending at RP 83+0.132 (accumulated miles 83.839), approximately 3.5 miles east of the unincorporated town of Lincoln. This project proposes a 0.15' centerline trench mill/fill, full width crack seal and seal and cover with new pavement markings, and bridge deck seal. Centerline rumble strips will be re-milled.

NH 24-3(73)65 - The Lincoln - E&W project is in Lewis and Clark County on MT 200 beginning at RP 65+0.450 (accumulated miles 66.193) and ending at RP 75+0.751 (accumulated miles 76.486). This project proposes a 0.15' centerline trench mill/fill, full width crack seal and seal and cover with new pavement markings. Centerline rumble strips will be re-milled.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & COVER, PAVEMENT MARKINGS, RUMBLE STRIPS			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	176.000	MILE
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	1,804.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	857.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	26,129.000	GAL

402020375	EMULSIFIED ASPHALT CHFRS-2P	629.800	TON
402020450	VOID REDUCING ASPHALT MEMBRANE	85,661.000	LNFT
403010255	CRACK SEALING	39,672.000	LB
409000010	COVER-TYPE 1	353,783.000	SQYD
411010000	COLD MILLING	19,028.000	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	2.300	MILE
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	13.900	MILE
411011135	RUMBLE STRIPS	17.000	MILE
552010160	BRIDGE DECK CRACK SEAL	1,440.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	7.000	GAL
620012955	TEMPORARY STRIPING	108,640.000	LNFT
620013000	STRIPING-WHITE PAINT	1,282.000	GAL
620013960	STRIPING-WHITE EPOXY	857.000	GAL
620014000	STRIPING-YELLOW PAINT	522.000	GAL
620014960	STRIPING-YELLOW EPOXY	349.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 9953000, 9960000

**203 DUPUYER - SOUTHEAST**

**STPP 3-3(37)71**

**CONTRACT NO. 06423**

Full width mill/fill, seal, and cover, signing and pavement markings. Existing rumble strips will be re-milled.

The Dupuyer - Southeast project is in Pondera County on Hwy 89 beginning at RP 70.45 and ending at RP 74.92.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL/FILL, SEAL & COVER, SIGNING, AND PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	85.000	MILE
401020045	PLANT MIX SURF-3/4 IN	9,837.000	TON
401020300	HYDRATED LIME	138.000	TON
402020192	ASPHALT CEMENT PG 58V-34	510.900	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5,118.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	7,428.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	174.200	TON
409000010	COVER-TYPE 1	97,993.000	SQYD
411010000	COLD MILLING	103,292.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	4.400	MILE
411011135	RUMBLE STRIPS	8.800	MILE
552010160	BRIDGE DECK CRACK SEAL	744.200	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	160,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010088	SIGNS-ALUM REFL SHEET IX	104.200	SQFT
619010230	REMOVE SIGN	13.000	EACH
619010310	POSTS-STEEL U SIGN	83.000	LB

619010480	POLES-TREATED WOOD 4 IN	48.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	66.000	LNFT
619011010	DELINEATOR DES A	159.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
619011060	DELINEATOR DES F	13.000	EACH
620012955	TEMPORARY STRIPING	46,584.000	LNFT
620013000	STRIPING-WHITE PAINT	330.000	GAL
620013960	STRIPING-WHITE EPOXY	220.000	GAL
620014000	STRIPING-YELLOW PAINT	316.000	GAL
620014960	STRIPING-YELLOW EPOXY	165.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 9957000

INVITATION FOR BIDS  
LETTING OF May 18, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on May 18, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

101 CHOTEAU - NORTH STPP-FLA 3-2(99)43 CONTRACT NO. 01523

Earthwork, surfacing, drainage, pavement markings, signing, and horizontal and vertical alignment shifts and seal and cover on the Choteau - North project in Teton County.

The project begins approximately 0.7 miles northwest of the Choteau city limits at RP 42.6 and proceeds northwest along U.S. Highway 89 for approximately 6.9 miles ending at RP 49.6, approximately 5.4 miles southeast of Bynum.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RECONSTRUCTION, GRADING			
103000000	TRAINING PROGRAM	500.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	100,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	224,116.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	48,691.000	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
208010486	STREAMBED MATERIAL	27.000	CUYD
208010500	BIOENGINEERED BANK	1.000	LS
210020170	TEST TRAILER-TRANSPORT, SETUP	180.000	MILE
301020268	TRAFFIC GRAVEL	3,221.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	56,546.000	CUYD
301020450	SPECIAL BACKFILL	2,400.000	CUYD
301020465	LOW PERMEABILITY BACKFILL	937.000	CUYD
301020625	AGGREGATE TREATMENT	162,381.000	SQYD
401020045	PLANT MIX SURF-3/4 IN	27,998.000	TON
401020046	PLANT MIX BIT SURF-MISC	1,290.000	TON
401020300	HYDRATED LIME	410.000	TON
402020192	ASPHALT CEMENT PG 58V-34	1,574.800	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	17,570.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	243.200	TON
409000000	FINAL SWEEP AND BROOM	6.900	CRMI
409000010	COVER-TYPE 1	135,314.000	SQYD
411010000	COLD MILLING	1,081.000	SQYD
411011145	SINUSOIDAL RUMBLE STRIPS	20.500	MILE
551020030	CONCRETE-CLASS GENERAL	53.600	CUYD
603000050	GRANULAR BEDDING MATERIAL	298.000	CUYD
603000060	FOUNDATION MATERIAL	104.000	CUYD
603010040	DRAINAGE PIPE 18 IN	2,190.000	LNFT
603010048	DRAINAGE PIPE 24 IN	340.000	LNFT
603010068	DRAINAGE PIPE 48 IN	152.000	LNFT
603010518	CSP 15 IN	2.000	LNFT
603012530	RCP 18 IN	58.000	LNFT
603012555	RCP 24 IN	116.000	LNFT
603012847	RCP IRR 18 IN	98.000	LNFT
603013060	RCP SIPHON 30 IN	78.000	LNFT
603013212	RCPA 30 IN EQ DIA	86.000	LNFT
603013216	RCPA 36 IN EQ DIA	158.000	LNFT
603013343	REIN CONC BOX 12 X 4	210.000	LNFT
603013350	REIN CONC BOX 6 X 3	186.000	LNFT
603013355	REIN CONC BOX 7 X 6	114.000	LNFT
603013356	REIN CONC BOX 6 X 4	78.000	LNFT
603587020	REMOVE PIPE CULVERT	2,179.600	LNFT
607100009	FENCE - WILDLIFE FRIENDLY FW	12,677.100	LNFT
607100012	FENCE - WILDLIFE FRIENDLY FM	872.300	LNFT
607100202	FARM FENCE-TYPE F3W	1,615.600	LNFT
607100229	FARM FENCE-TYPE F4W	11,323.300	LNFT
607100252	FARM FENCE-TYPE F4M	954.400	LNFT
607100259	FARM FENCE-TYPE F5W	25,537.900	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	269.000	EACH
607100362	FARM FENCE-PANEL/SINGLE FM	5.000	EACH

607100380	FARM FENCE-PANEL/DOUBLE FW	55.000	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	2.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	336.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	124.000	LNFT
607100551	FENCE-TEMPORARY	12,022.000	LNFT
607100720	DEADMAN	21.000	EACH
610100101	SEEDING AREA NO 1	98.500	ACRE
610100103	SEEDING AREA NO 3	25.800	ACRE
610100490	TURF REINF MAT-NATURAL FIBER	18,751.000	SQYD
610100555	CONDITION SEEDBED SURFACE	125.600	ACRE
611010016	CATTLE GUARD 16 FT-LIGHT DUTY	3.000	EACH
611010020	CATTLE GUARD 20 FT-LIGHT DUTY	1.000	EACH
611010200	REMOVE CATTLE GUARD	2.000	EACH
613100030	RIPRAP-CLASS 1 RANDOM	26.000	CUYD
613100040	RIPRAP-CLASS 2 RANDOM	35.000	CUYD
615010034	REMOVE IRRIGATION STRUCTURE	3.000	EACH
615010225	SLIDEGATE	2.000	EACH
615010580	TRASH GUARD	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	750,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	30.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	362.400	SQFT
619010180	HISTORICAL MARKER	2.000	EACH
619010230	REMOVE SIGN	94.000	EACH
619010240	REMOVE SIGN-GUIDE	3.000	EACH
619010310	POSTS-STEEL U SIGN	140.000	LB
619010480	POLES-TREATED WOOD 4 IN	522.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	96.000	LNFT
619011010	DELINEATOR DES A	226.000	EACH
619011040	DELINEATOR DES D	18.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	6.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.000	GAL
620012955	TEMPORARY STRIPING	72,864.000	LNFT
620013000	STRIPING-WHITE PAINT	442.000	GAL
620013960	STRIPING-WHITE EPOXY	295.000	GAL
620014000	STRIPING-YELLOW PAINT	84.000	GAL
620014960	STRIPING-YELLOW EPOXY	56.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	130.000	SQYD
622011084	GEOTEXTILE STABILIZATION	363.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	167,732.000	SQYD
623000155	MAILBOX	16.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
 Uniform No. 8965000

**102 NORTH OF BENCHLAND - NORTH STPS 207-1(2)5 CONTRACT NO. 04523**

Gravel resurfacing and gravel overlay on the North of Benchland - North project located in Fergus and Judith Basin Counties. The project begins approximately 5 miles north of Highway 87 at RP 4.97 and extends approximately 16.9 miles north along Secondary 207 (Benchland Road) to the Denton town limits at RP 21.83.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001 - GRAVEL RESURFACING			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
109200005	MOBILIZATION	1.000	LS

208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020000	GRADER-MOTOR	103.000	HOURL
210020160	MISCELLANEOUS EQUIPMENT	59.000	HOURL
301020525	TOP SURFACING GR 3B	81,781.000	TON
301020625	AGGREGATE TREATMENT	291,345.000	SQYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
 Uniform No. 10205000

**103 FOUR CORNERS - EAST NH 50-2(89)82 CONTRACT NO. 05523**

Mill and overlay, crack seal, seal and cover, digouts, bridge deck repair, and pavement marking upgrades on the Four Corners - East project in Gallatin County.

The project is located on US-191 (Huffine Lane and W. Main Street) west of Bozeman beginning near the junction of MT-85 (Jackrabbit Lane), RP 81.9 extending east 6.3 miles near the junction of 19th Avenue at RP 88.0.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001 - COLD MILLING, PMS SURFACING, SEAL & COVER			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020278	EXCAVATION-DIGOUTS	610.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	466.000	CUYD
401020021	COMMERCIAL MIX-PG 70-28	4,444.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,747.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	3,349.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	435.200	TON
403010255	CRACK SEALING	20,433.000	LB
403010257	CRACK FILLING-MASTIC	5,647.000	LB
409000000	FINAL SWEEP AND BROOM	12.600	CRMI
409000020	COVER-TYPE 2	243,590.000	SQYD
411010000	COLD MILLING	29,556.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	310.000	SQYD
603014242	ADJUST VALVE BOX	2.000	EACH
604000100	ADJUST MANHOLE	5.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	200,000.000	UNIT
620010301	CURB MARKING-YELLOW EPOXY	105.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	138.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	165.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	2.000	GAL
620012955	TEMPORARY STRIPING	109,575.000	LNFT
620013000	STRIPING-WHITE PAINT	339.000	GAL
620013957	THERMOPLASTIC TREATMENT	1.000	LS
620013960	STRIPING-WHITE EPOXY	453.000	GAL
620014000	STRIPING-YELLOW PAINT	261.000	GAL
620014960	STRIPING-YELLOW EPOXY	348.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	1,076.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 9473000

**104 ELM STREET - ANACONDA STPU 0203(2) CONTRACT NO. 02523**

The Elm Street - Anaconda project located on urban route (U 203, Elm street) within the city of Anaconda in Deer Lodge County. The project begins at 7th Street West (RP 0.0) Intersection and extends north 0.4 miles to the West Commercial Avenue intersection (RP 0.4). Work includes milling, new asphalt pavement, chip sealing and pavement markings.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, PMS OVERLAY, ADA UPGRADES			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	30.000	MILE
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	1,258.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	494.000	GAL
411010000	COLD MILLING	9,764.000	SQYD
603014242	ADJUST VALVE BOX	13.000	EACH
604000100	ADJUST MANHOLE	4.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	236.000	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	20.000	SQYD
609010200	CURB AND GUTTER-CONC	270.800	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	80,000.000	UNIT
620010301	CURB MARKING-YELLOW EPOXY	24.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	5.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	7.000	GAL
620013000	STRIPING-WHITE PAINT	12.000	GAL
620013960	STRIPING-WHITE EPOXY	17.000	GAL
620014000	STRIPING-YELLOW PAINT	12.000	GAL
620014960	STRIPING-YELLOW EPOXY	17.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 9829000

**105 PATH PRESERVATION - BROADUS TA 38(17) CONTRACT NO. 03523**  
**PATH PRESERVATION - MILES CITY TA 8099(16)**

TA 38(17) - Crack seal treatment, overlay, and fog seal of the Powder River shared-use path on the Path Preservation - Broadus project located in Powder River County. The total length of the project is approximately 1.3 miles divided into two sections with the first section along Highway 212 entering into the west end of Broadus (up to the sidewalk west of Jensen Avenue), and the second section running along Park Avenue from Cottonwood Street to the end of the path near the Powder River Bridge. Both sections will receive a crack seal treatment and a thin pavement overlay, with the exception of the section from South Street to Airport Road which will receive crack seal treatment.



TA 8099(16) - Crack seal repair, overlay, and fog seal of the Custer County Fairgrounds Trail on the Path Preservation - Miles City project located in Custer County. The total length of the project is approximately 1.0 miles and includes both "on-system" and "off-system" portions. The "on-system" portion begins near the Tongue River bridge on Main Street and continues southwest along Main Street to the intersection of Garryowen Road and Main Street. The "off-system" portion begins at the intersection of Main Street and Garryowen Road and continues southeast along Garryowen Road, to the intersection of Garryowen Road and Pacific Avenue. The "off-system" portion then follows Pacific Avenue northeast to the Tongue River bridge located on Pacific Avenue.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BIKE/PED FACILITIES			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
202020140	REMOVE BITUMINOUS PAVEMENT	15.400	SQYD
203020278	EXCAVATION-DIGOUTS	4.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020000	GRADER-MOTOR	12.000	HOURL
301020340	CRUSHED AGGREGATE COURSE	3.000	CUYD
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	600.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	423.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	952.000	GAL
403010255	CRACK SEALING	456.000	LB
403010257	CRACK FILLING-MASTIC	1,484.000	LB
411010000	COLD MILLING	197.000	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	34.100	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	11.200	SQYD
609010200	CURB AND GUTTER-CONC	25.000	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	16.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%. All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator. Uniform No. 10084000, 10085000

INVITATION FOR BIDS  
LETTING OF June 29, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on June 29, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

201 SF 169 S-288 CURVES HSIP-STPB 288-1(11)2 CONTRACT NO. 05623

Grading, gravel surfacing, plant mix bituminous surfacing, seal and cover, irrigation and drainage improvements, bridge replacements, rumble strips, signing and pavement markings on the SF 169 S288 Curves project located in Gallatin County. The project is located on State Secondary Route 288 between Manhattan and Churchill and includes two separate locations. Site 1 begins at RP 4.5 and extends southeast to RP 4.8. Site 2 begins at RP 2.3 and extends south to RP 2.8. Total project length is approximately 0.8 miles.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - ROADWAY & SAFETY IMPROVEMENTS			
104030010	MISCELLANEOUS WORK	35,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
201311000	REMOVE TREES	2.000	EACH
202020041	REMOVE STRUCTURE	1.000	LS
203020310	SPECIAL BORROW-NEAT LINE	4,561.000	CUYD
203020375	EMBANKMENT IN PLACE	22,343.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	4,609.000	CUYD
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.000	LS
206000050	DETOUR-MAINTAIN	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	25.000	MILE
301020340	CRUSHED AGGREGATE COURSE	5,523.000	CUYD
301020450	SPECIAL BACKFILL	3,446.000	CUYD
301020465	LOW PERMEABILITY BACKFILL	81.400	CUYD
301020625	AGGREGATE TREATMENT	20,115.000	SQYD
401020064	COMMERCIAL PLANT MIX-MISC	158.000	TON
401020122	COMMERCIAL MIX-PG 58V-34	4,379.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,907.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	29.400	TON
409000000	FINAL SWEEP AND BROOM	0.800	CRMI
409000010	COVER-TYPE 1	16,314.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	0.800	MILE
411011135	RUMBLE STRIPS	1.600	MILE
551020030	CONCRETE-CLASS GENERAL	16.700	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	105.000	CUYD
603000050	GRANULAR BEDDING MATERIAL	114.000	CUYD
603012892	RCP IRR 24 IN	206.000	LNFT
603012938	RCP IRR 36 IN	108.000	LNFT
603013302	REIN CONC BOX 24 X 9	96.000	LNFT
603013303	REIN CONC BOX 20 X 8	110.000	LNFT
603587020	REMOVE PIPE CULVERT	327.000	LNFT
606010385	REMOVE GUARDRAIL	281.600	LNFT
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
607100111	FARM FENCE-TYPE F2W-39 IN WW	1,041.000	LNFT
607100229	FARM FENCE-TYPE F4W	1,506.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	10.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	5.000	EACH
607100391	FENCE-WOOD-4 RAIL	146.000	LNFT
607100430	FARM GATE-WIRE-TYPE G-2	48.000	LNFT
610100101	SEEDING AREA NO 1	5.800	ACRE
610100103	SEEDING AREA NO 3	2.900	ACRE
610100326	FERTILIZING AREA NO 1	5.800	ACRE
610100555	CONDITION SEEDBED SURFACE	8.700	ACRE
610100561	EROSION CONTROL BLANKET-LONG-TERM	2,852.000	SQYD
613100090	CULVERT INFILL	171.800	CUYD
618030005	TRAFFIC CONTROL DEVICES CB	200,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	24.000	DAY
618190100	TEMPORARY BARRIER RAIL	90.000	LNFT
619010090	SIGNS-ALUM REFL SHEET XI	116.400	SQFT
619010230	REMOVE SIGN	15.000	EACH

619010480	POLES-TREATED WOOD 4 IN	180.000	LNFT
619010810	PANEL DELINEATOR DESIGN C	28.000	EACH
619010820	PANEL DELINEATOR DESIGN F	12.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620012955	TEMPORARY STRIPING	9,281.000	LNFT
620013000	STRIPING-WHITE PAINT	72.000	GAL
620013960	STRIPING-WHITE EPOXY	48.000	GAL
620014000	STRIPING-YELLOW PAINT	64.000	GAL
620014960	STRIPING-YELLOW EPOXY	42.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	14,882.000	SQYD
623000155	MAILBOX	3.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
Uniform No. 9380000

**202 BIG MOUNTAIN ROAD STPS 487-1(17)4 CONTRACT NO. 01623**

The Big Mountain Road project is located in Flathead County on Big Mountain Road (S-487) from RP 4.0 to 6.6. The project will be a plant mix overlay with a seal and cover and fog seal. Other work will include: two proposed sections of digouts, connection milling, shoulder taper milling in curbed sections, limited curb replacement, new pavement markings, signing, delineation, and the replacement of existing guardrail.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - OVERLAY, SEAL & COVER, AND DIGOUTS			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
203020278	EXCAVATION-DIGOUTS	6,210.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	2,617.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	2,028.000	CUYD
301020416	SHOULDER GRAVEL	442.000	CUYD
301020625	AGGREGATE TREATMENT	9,077.000	SQYD
401020046	PLANT MIX BIT SURF-MISC	25.000	TON
401020048	PLANT MIX SURF-1/2 IN	7,895.000	TON
401020300	HYDRATED LIME	111.000	TON
402020192	ASPHALT CEMENT PG 58V-34	420.200	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	4,050.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	4,497.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	133.500	TON
409000030	COVER-TYPE 3	60,433.000	SQYD
411010000	COLD MILLING	4,411.000	SQYD
603013490	PIPE-CORR POLYETHYLENE DR 4 IN	1,915.000	LNFT
604000100	ADJUST MANHOLE	2.000	EACH
606010330	MGS GUARDRAIL	9,837.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	14.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	8.000	EACH
606010385	REMOVE GUARDRAIL	10,379.800	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	4.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	4.000	EACH
609010112	CURB 4 IN-CONCRETE	860.000	LNFT
610100559	REVEGETATION	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT

618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	40.000	DAY
618190100	TEMPORARY BARRIER RAIL	1,920.000	LNFT
618190110	RESET TEMP BARRIER RAIL	1,920.000	LNFT
619010090	SIGNS-ALUM REFL SHEET XI	461.700	SQFT
619010230	REMOVE SIGN	47.000	EACH
619010310	POSTS-STEEL U SIGN	54.000	LB
619010480	POLES-TREATED WOOD 4 IN	364.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	72.000	LNFT
619011002	DELINEATOR SNOWPOLE-DES F	12.000	EACH
619011010	DELINEATOR DES A	50.000	EACH
619011030	DELINEATOR DES C	123.000	EACH
619011040	DELINEATOR DES D	8.000	EACH
619011060	DELINEATOR DES F	101.000	EACH
620012955	TEMPORARY STRIPING	27,582.000	LNFT
620013000	STRIPING-WHITE PAINT	190.000	GAL
620013960	STRIPING-WHITE EPOXY	127.000	GAL
620014000	STRIPING-YELLOW PAINT	190.000	GAL
620014960	STRIPING-YELLOW EPOXY	127.000	GAL
622011022	SUBSURFACE DRAIN FILTER-HIGH SURV	15,597.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
 Uniform No. 9940000

**203 JCT US 2 - SOUTH (S-417) STPS 417-1(3)0 CONTRACT NO. 04623  
 CONRAD - WEST STPS 534-1(8)23**

STPS 417-1(3)0 - Located in Pondera & Toole Counties, the JCT US 2 - South (S-417) project proposes a full width scrub seal, upgraded signage, new pavement markings and Class A bridge deck repair for Secondary Highway 417 (F Bridge Road) along the entire length of the roadway. Beginning at RP 0.0, the project continues north 16.5 miles to RP 16.5.

STPS 534-1(8)23 - Located in Pondera County, the Conrad - West project proposes a full width scrub seal with new pavement markings and signage on Secondary Highway 534 (Conrad-Dupuyer Rd/4th Avenue South) for the paved portion of the roadway. Beginning at RP 23.4, the project continues northwest for 4.5 miles to RP 27.8.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001 - SCRUB SEAL			
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
402020320	EMULSIFIED ASPHALT-FOG SEAL	24,523.000	GAL
402020377	SCRUB SEAL EMULSION	584.800	TON
409000010	COVER-TYPE 1	325,382.000	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	45.000	SQYD
563000040	POLYMER OVERLAY	1,315.000	SQYD
563000045	POLYMER OVERLAY PRIMER	1,315.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	225,000.000	UNIT
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	6.000	DAY
619010062	SIGNS-ALUM SHEET INCR XI	49.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1,017.100	SQFT

619010200	RESET SIGNS	2.000	EACH
619010230	REMOVE SIGN	143.000	EACH
619010240	REMOVE SIGN-GUIDE	9.000	EACH
619010310	POSTS-STEEL U SIGN	401.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	200.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	1,442.000	LB
619010480	POLES-TREATED WOOD 4 IN	1,106.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	238.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	9.000	EACH
619011010	DELINEATOR DES A	660.000	EACH
619011030	DELINEATOR DES C	6.000	EACH
619011040	DELINEATOR DES D	36.000	EACH
619011060	DELINEATOR DES F	200.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	74.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	15.000	GAL
620013000	STRIPING-WHITE PAINT	766.000	GAL
620013960	STRIPING-WHITE EPOXY	1,018.000	GAL
620014000	STRIPING-YELLOW PAINT	377.000	GAL
620014960	STRIPING-YELLOW EPOXY	502.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
 Uniform No. 10289000, 10287000

**204 JCT MT 44 - NORTHWEST (US-89) STPP 3-3(39)84 CONTRACT NO. 03623**

Scrub seal, and pavement markings on the JCT MT 44 - Northwest (US-89) project located in Pondera and Glacier Counties. A portion of this project is located on the Blackfeet Indian reservation.

This project is located on Hwy 89(P-3) beginning at mile marker 83.6 and extending north to mile marker 101.0.

**MANDATORY PRE-BID CONFERENCE**

A pre-bid conference will be held at the following time and location:

**Tuesday, June 20, 2023 at 10:00 am, This will be a Zoom meeting. The Zoom links will be posted to the Q&A forum.**

The pre-bid conference will have a formal sign-in process that will become the official record of attendance for the purposes of determining eligible bidders.

Attendance at this conference is mandatory for any Contractor to submit a bid as a prime bidder. Contractors who bid as a prime bidder on this project must have at least one full time, permanent employee present. No proxy representatives, such as subcontractors or consultants, meet this requirement. In the event a prime bidder tenders a bid but did not attend the pre-bid conference, the bid will be non-responsive.

Representatives of the Department will be present to describe the project and answer questions. Representatives of the Blackfeet Tribe will be invited to the pre-bid conference. The pre-bid conference is for information only. The Department is not bound by any statement or representation concerning conditions or description of the work given by Department employees or agents and the pre-bid conference. The answers to any questions raised are non-binding oral explanations or instructions and relying on them is solely at the Bidder's risk. Any issues raised at the pre-bid conference must be posted on the Question and Answer Forum to be considered an enforceable provision of the contract to be let. The pre-bid attendee list and contract document clarifications or modifications considered necessary by the Department will be posted to the Question and Answer Forum.

INVOLVING

-----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
----------	-------------	----------	-------

SECTION NO. 0001 - SCRUB SEAL, CHIP SEAL, PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	40,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
402020320	EMULSIFIED ASPHALT-FOG SEAL	26,601.000	GAL
402020377	SCRUB SEAL EMULSION	634.100	TON
409000010	COVER-TYPE 1	356,209.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	713.900	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	135,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	2.000	GAL
620013000	STRIPING-WHITE PAINT	631.000	GAL
620013960	STRIPING-WHITE EPOXY	841.000	GAL
620014000	STRIPING-YELLOW PAINT	224.000	GAL
620014960	STRIPING-YELLOW EPOXY	299.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 9958000

**205 MT-141 CULVERT - NORTH OF AVON STPP 41-1(32)2 CONTRACT NO. EX123**

Replacement of two structurally deficient culverts with one State Furnished reinforced concrete box culvert at the Sixmile Creek drainage on the MT-141 Culvert - North of Avon project in Powell County. The road will be reconstructed across the culverts. In addition, signing, delineation, pavement markings, and revegetation will be included. The project is located approximately 3 miles north of Avon, from RP 3.0 to 3.2.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - REMOVE & REPLACE CULVERTS			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
104030030	MISCELLANEOUS ITEMS-INSTALL	108.000	LNFT
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	11,251.000	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
209010160	TEMPORARY SHORING	1.000	LS
301020268	TRAFFIC GRAVEL	730.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	930.000	CUYD
301020450	SPECIAL BACKFILL	5,839.000	CUYD
301020625	AGGREGATE TREATMENT	8,480.000	SQYD
401020064	COMMERCIAL PLANT MIX-MISC	35.000	TON
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	741.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	367.000	GAL
551020030	CONCRETE-CLASS GENERAL	8.600	CUYD
603000050	GRANULAR BEDDING MATERIAL	88.000	CUYD
603000060	FOUNDATION MATERIAL	176.000	CUYD
606011503	RESET TEMP IMPACT ATTENUATOR	6.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
610100559	REVEGETATION	1.000	LS
613100090	CULVERT INFILL	32.000	CUYD

618030005	TRAFFIC CONTROL DEVICES CB	200,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	40.000	DAY
618190100	TEMPORARY BARRIER RAIL	1,000.000	LNFT
618190110	RESET TEMP BARRIER RAIL	3,000.000	LNFT
619010090	SIGNS-ALUM REFL SHEET XI	30.400	SQFT
619010200	RESET SIGNS	1.000	EACH
619010230	REMOVE SIGN	5.000	EACH
619010310	POSTS-STEEL U SIGN	38.000	LB
619010480	POLES-TREATED WOOD 4 IN	42.000	LNFT
619010820	PANEL DELINEATOR DESIGN F	17.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
620012955	TEMPORARY STRIPING	2,000.000	LNFT
620013000	STRIPING-WHITE PAINT	10.000	GAL
620013960	STRIPING-WHITE EPOXY	13.000	GAL
620014000	STRIPING-YELLOW PAINT	11.000	GAL
620014960	STRIPING-YELLOW EPOXY	14.000	GAL
622011084	GEOTEXTILE STABILIZATION	560.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
This project is under the jurisdiction of the Butte District Administrator.  
Uniform No. 10334000



INVITATION FOR BIDS  
LETTING OF July 20, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on July 20, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

Roadside safety enhancements include installations of advance warning signs with flashing beacons, road closure gates, electronic variable message signs (VMS), guardrail to shield the VMS structures, and upgrading wind speed gauge on the I-90 Incident Management project located in Broadwater, Gallatin, Park, Sweet Grass, Stillwater, and Yellowstone Counties.

This project begins just east of the Three Forks Interchange at RP 273.7 and extends 182.3 miles east past the Johnson Lane Interchange near Billings at RP 456.0.

## INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GUARDRAIL, SIGNING, ELECTRICAL			
Billing District 53% Butte District 47%			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
107000020	CONTAMINATED SOIL	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
551020030	CONCRETE-CLASS GENERAL	3.000	CUYD
606010150	GUARDRAIL-STL/BR APPR-TY 1	1.000	EACH
606010330	MGS GUARDRAIL	3,700.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	16.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	16.000	EACH
606010385	REMOVE GUARDRAIL	50.000	LNFT
616323114	CONDUIT-STEEL 1 1/2 IN RIGID	210.000	LNFT
616343914	CONDUIT-PLASTIC 1 1/2 IN	1,450.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	20,312.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	110.000	EACH
617000000	FOUNDATION-CONCRETE	68.000	CUYD
617000050	POLES-TREATED WOOD CLASS 4	450.000	LNFT
617000060	GATE-ROAD CLOSURE	34.000	EACH
617033214	CABLE-COPPER 3AWG14-600V	628.000	LNFT
617033314	CABLE-COPPER 5AWG14-600V	21,760.000	LNFT
617123104	CONDUCTOR-COPPER AWG4-600V	10,219.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	9,860.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	48,258.000	LNFT
617303300	HIGH EFFICACY LUMINAIRE LED	34.000	EACH
617333000	SERV ASSEMBLY-MODIFY	1.000	EACH
617333100	SERV ASSEMBLY	24.000	EACH
617483110	SIG-TRAF 1 COL-1 WAY 12	37.000	EACH
617523010	SOL SIG-TRAF 1 COLOR-1 WAY 12	48.000	EACH
617673200	SIG STANDARD TYPE 1-200	24.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903459	BLANKOUT SIGN	1.000	EACH
617903475	VARIABLE MESSAGE SIGN COLOR-HALF	5.000	EACH
617903480	VARIABLE MESSAGE SIGN COLOR-FULL	12.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
619010062	SIGNS-ALUM SHEET INCR XI	1,199.700	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	321.400	SQFT
619010320	POSTS-STEEL STRUCTURAL SIGN	11,121.000	LB
619010510	OVERHEAD STRUCTURE/METAL	7.000	EACH
619010521	OVERHEAD STR/METAL-CANTILEVER	6.000	EACH
619010726	FRANG SIGN POST BKWY-W4 X 13	30.000	EACH
619010730	FRANG SIGN POST BKWY-W8 X 18	18.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
Uniform No. 9856000

**102 BROWNING - NORTH STPS 464-1(19)0 CONTRACT NO. 04723**  
Scrub seal, bridge deck repair and overlay, guardrail replacement, and signing on the Browning - North project located in Glacier County. The project begins at reference post 0.0 and extends approximately 33.64 miles north along Secondary 464 to reference post 33.64. The project is located entirely on the Blackfeet Indian Reservation.

**MANDATORY PRE-BID CONFERENCE**

A pre-bid conference will be held at the following time and location:

**Thursday, July 13, 2023 at 10:00am.**

**This will be a Zoom meeting.** The Zoom links will be posted to the Q&A forum.

The pre-bid conference will have a formal sign-in process that will become the official record of attendance for the purposes of determining eligible bidders.

Attendance at this conference is mandatory for any Contractor to submit a bid as a prime bidder. Contractors who bid as a prime bidder on this project must have at least one full time, permanent employee present. No proxy representatives, such as subcontractors or consultants, meet this requirement. In the event a prime bidder tenders a bid but did not attend the pre-bid conference, the bid will be non-responsive.

Representatives of the Department will be present to describe the project and answer questions. Representatives of the Blackfeet Tribe will be invited to the pre-bid conference. The pre-bid conference is for information only. The Department is not bound by any statement or representation concerning conditions or description of the work given by Department employees or agents and the pre-bid conference. The answers to any questions raised are non-binding oral explanations or instructions and relying on them is solely at the Bidder's risk. Any issues raised at the pre-bid conference must be posted on the Question and Answer Forum to be considered an enforceable provision of the contract to be let. The pre-bid attendee list and contract document clarifications or modifications considered necessary by the Department will be posted to the Question and Answer Forum.

**INVOLVING**

-----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001 - SCRUB SEAL & BRIDGE DECK REPAIR			
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	280.000	MILE
402020320	EMULSIFIED ASPHALT-FOG SEAL	44,070.000	GAL
402020377	SCRUB SEAL EMULSION	1,028.700	TON
409000010	COVER-TYPE 1	579,652.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	220.000	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	40.000	SQYD
563000040	POLYMER OVERLAY	896.000	SQYD
606010330	MGS GUARDRAIL	1,275.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	2.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	2.000	EACH
606010385	REMOVE GUARDRAIL	1,375.000	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	103.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	2,177.600	SQFT
619010230	REMOVE SIGN	120.000	EACH
619010240	REMOVE SIGN-GUIDE	4.000	EACH

619010310	POSTS-STEEL U SIGN	691.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	1,043.000	LB
619010480	POLES-TREATED WOOD 4 IN	872.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	164.000	LNFT
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	19.000	EACH
619010800	PANEL DELINEATOR DESIGN A	20.000	EACH
619010820	PANEL DELINEATOR DESIGN F	20.000	EACH
619011001	DELINEATOR SNOWPOLE-DES A	15.000	EACH
619011010	DELINEATOR DES A	885.000	EACH
619011040	DELINEATOR DES D	78.000	EACH
619011060	DELINEATOR DES F	10.000	EACH
619011158	TOP MOUNTED W-BEAM WHITE DELINEATOR	102.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	12.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	13.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	1.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	17.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	2.000	GAL
620013000	STRIPING-WHITE PAINT	1,224.000	GAL
620013960	STRIPING-WHITE EPOXY	1,633.000	GAL
620014000	STRIPING-YELLOW PAINT	532.000	GAL
620014960	STRIPING-YELLOW EPOXY	710.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%. All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 10246000

**103 N INTERCHANGE RD - DILLON (N-89) NH 89-1(20)2 CONTRACT NO. 01723**

The North Interchange Rd - Dillon (N-89) project is located in Beaverhead County. Work includes Mill, PMS Overlay, Seal & Cover, Bridge Repair, Guardrail, and Pavement Markings. Works extends .5 miles in a SW direction on N-89 between RP 2.9 to RP 2.5.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, PMS OVERLAY, SEAL & COVER, & BRIDGE REHAB			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	87.500	LNFT
202020097	REMOVE BRIDGE APPROACH SLAB	2.000	EACH
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	130.000	MILE
301020340	CRUSHED AGGREGATE COURSE	156.000	CUYD
401020021	COMMERCIAL MIX-PG 70-28	1,675.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	665.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	19.100	TON
402020377	SCRUB SEAL EMULSION	19.300	TON
409000000	FINAL SWEEP AND BROOM	0.500	CRMI
409000020	COVER-TYPE 2	21,456.000	SQYD
411010000	COLD MILLING	10,947.000	SQYD
552010140	TRANSVERSE DECK GROOVING	1,485.600	SQYD
552010160	BRIDGE DECK CRACK SEAL	1,560.400	SQYD
561020110	BRIDGE DECK MILLING	1,560.400	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.000	SQYD
563000010	CONCRETE-CLASS OVERLAY	1,553.200	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.000	UNIT

605000040	REVISE CONCRETE BARRIER RAIL-BR	647.300	LNFT
606010140	GUARDRAIL END SECTION WIDENING	4.000	EACH
606010330	MGS GUARDRAIL	2,300.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	4.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.000	EACH
606010385	REMOVE GUARDRAIL	2,600.000	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
609010112	CURB 4 IN-CONCRETE	1,102.000	LNFT
609010203	REMOVE CURB	1,062.000	LNFT
610100559	REVEGETATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618100000	SINGLE USE SIGNS	80.000	SQFT
618100008	TRAFFIC ACTUATED TEMPORARY SIGNALS	1.000	LS
618190100	TEMPORARY BARRIER RAIL	490.000	LNFT
618190110	RESET TEMP BARRIER RAIL	490.000	LNFT
620010301	CURB MARKING-YELLOW EPOXY	1.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	8.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	6.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	5.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	4.000	GAL
620012955	TEMPORARY STRIPING	5,956.000	LNFT
620013000	STRIPING-WHITE PAINT	34.000	GAL
620013960	STRIPING-WHITE EPOXY	22.000	GAL
620014000	STRIPING-YELLOW PAINT	38.000	GAL
620014960	STRIPING-YELLOW EPOXY	26.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 9876000

**104 RAYNOLDS PASS - NORTH STPP 13-1(63)0 CONTRACT NO. 02723**

The project is a crack seal, seal and cover located in Madison County on Primary Route 13 (MT-87). The project begins approximately 50 miles southeast of Ennis at the Montana/Idaho Border at RP 0.0 and proceeds north through the junction with US-287 (Raynolds Pass Jct.) towards Ennis, ending at RP 8.8. The project length is 8.8 miles.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001 - CRACK SEAL, SEAL AND COVER			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
402020375	EMULSIFIED ASPHALT CHFRS-2P	321.100	TON
403010255	CRACK SEALING	5,600.000	LB
403010257	CRACK FILLING-MASTIC	1,000.000	LB
409000000	FINAL SWEEP AND BROOM	8.800	CRMI
409000010	COVER-TYPE 1	178,678.000	SQYD
606010140	GUARDRAIL END SECTION WIDENING	2.000	EACH
606010330	MGS GUARDRAIL	550.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	2.000	EACH
606010385	REMOVE GUARDRAIL	650.000	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	100,000.000	UNIT
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL

620011260	WORDS AND SYMBOLS-WHITE EPOXY	2.000	GAL
620013000	STRIPING-WHITE PAINT	307.000	GAL
620013960	STRIPING-WHITE EPOXY	409.000	GAL
620014000	STRIPING-YELLOW PAINT	153.000	GAL
620014960	STRIPING-YELLOW EPOXY	203.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
This project is under the jurisdiction of the Butte District Administrator.  
Uniform No. 10266000

**105 PATH PRESERVATION - BROADUS TA 38(17) CONTRACT NO. 07723**  
**PATH PRESERVATION - MILES CITY TA 8099(16)**

TA 38(17) - Crack seal treatment, overlay, and fog seal of the Powder River shared-use path on the Path Preservation - Broadus project located in Powder River County. The total length of the project is approximately 1.3 miles divided into two sections with the first section along Highway 212 entering into the west end of Broadus (up to the sidewalk west of Jensen Avenue), and the second section running along Park Avenue from Cottonwood Street to the end of the path near the Powder River Bridge. Both sections will receive a crack seal treatment and a thin pavement overlay, with the exception of the section from South Street to Airport Road which will receive crack seal treatment.

TA 8099(16) - Crack seal repair, overlay, and fog seal of the Custer County Fairgrounds Trail on the Path Preservation - Miles City project located in Custer County. The total length of the project is approximately 1.0 miles and includes both "on-system" and "off-system" portions. The "on-system" portion begins near the Tongue River bridge on Main Street and continues southwest along Main Street to the intersection of Garryowen Road and Main Street. The "off-system" portion begins at the intersection of Main Street and Garryowen Road and continues southeast along Garryowen Road, to the intersection of Garryowen Road and Pacific Avenue. The "off-system" portion then follows Pacific Avenue northeast to the Tongue River bridge located on Pacific Avenue.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BIKE/PED FACILITIES			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
202020140	REMOVE BITUMINOUS PAVEMENT	15.400	SQYD
203020278	EXCAVATION-DIGOUTS	4.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020000	GRADER-MOTOR	12.000	HOURL
301020340	CRUSHED AGGREGATE COURSE	3.000	CUYD
401020023	COMMERCIAL MIX-PG 58-28	600.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	423.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	952.000	GAL
403010255	CRACK SEALING	456.000	LB
403010257	CRACK FILLING-MASTIC	1,484.000	LB
411010000	COLD MILLING	197.000	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	34.100	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	11.200	SQYD
609010200	CURB AND GUTTER-CONC	25.000	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	16.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Glendive District Administrator.  
 Uniform No. 10084000, 10085000

106      **SF 179 HELENA INTX SAFETY**                      **HSIP STWD(663)**                      **CONTRACT NO. 03723**  
 Safety improvements on the SF 179 HELENA INTX SAFETY project at 3 sites in the Helena area:

SITE 1: Prospect Avenue (US 12) and Gibbon Intersection (approx. RP 45.55 to RP 45.75 (US 12) within the City of Helena in Lewis and Clark County) - Remove left turn movement, replace left turn bay with raised concrete refuge island. Install ladder-style crosswalk and new pedestrian warning signs for southbound vehicles on Gibbon. Install pedestrian warning signs for eastbound to northbound left-turning vehicles on Prospect (place in raised median).

SITE 2: Lincoln Road (Secondary 453) and Glass Drive Intersection (approx. RP 0.4 to 0.75 (S-453) in Lewis and Clark County) - Install 1-2 luminaires for designation lighting, install northbound/southbound oversized stop signs with "cross traffic does not stop" plaques, add new northbound/southbound stop bars, install eastbound/westbound intersection warning signs with street name plaques.

SITE 3: Lincoln Road (Secondary 453) and Hauser Dam Road Intersection (approx. RP 4.85 to RP 5.12(S-453) in Lewis and Clark County) - ITS solution - Installation of a vehicle activated solar powered sign warning eastbound vehicles about upcoming stop condition. Inlaid thermoplastic warning in roadway, upgrade existing double-sided arrow sign.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SAFETY IMPROVEMENTS			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020140	REMOVE BITUMINOUS PAVEMENT	14.400	SQYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
608010050	SIDEWALK-CONCRETE 6 IN	9.700	SQYD
608010113	DECORATIVE CONCRETE - 3 IN	83.400	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	3.700	SQYD
609010030	CURB-CONC MEDIAN TYPE A	318.600	LNFT
616343920	CONDUIT-PLASTIC 2 IN	750.000	LNFT
616783006	PULL BOX-COMPOSITE TYPE 1	4.000	EACH
616783007	PULL BOX-COMPOSITE TYPE 2	1.000	EACH
617000000	FOUNDATION-CONCRETE	1.200	CUYD
617033214	CABLE-COPPER 3AWG14-600V	700.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	1,500.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	950.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	2.000	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	2.000	EACH
617333100	SERV ASSEMBLY	1.000	EACH
617763410	RADAR VEHICLE DETECTION	1.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	85,000.000	UNIT
619010062	SIGNS-ALUM SHEET INCR XI	31.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	188.900	SQFT
619010230	REMOVE SIGN	5.000	EACH
619010240	REMOVE SIGN-GUIDE	1.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	248.700	LB

619010490	POLES-TREATED WOOD 5 IN	138.000	LNFT
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	5.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	1.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	5.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	16.000	GAL
620013960	STRIPING-WHITE EPOXY	12.000	GAL
620014960	STRIPING-YELLOW EPOXY	8.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 9655000



INVITATION FOR BIDS  
LETTING OF August 10, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on August 10, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

**101 JCT MT 200 - SOUTHEAST STPS 279-1(32)22 CONTRACT NO. 03823**

This project is located in Lewis & Clark County that includes full width scrub seal, upgraded pavement markings and new signage on Secondary 279 heading North between RP 22+0.042 and RP 30+0.444. It also proposes a full width 0.20-ft PMS mill/fill, seal and cover, upgraded pavement markings and new signage between RP 30+0.444 and 38+0.886 to JCT MT 200.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SCRUB SEAL, MILL/FILL, SEAL & COVER, FOG SEAL			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	77.000	MILE
401020048	PLANT MIX SURF-1/2 IN	17,302.000	TON
401020300	HYDRATED LIME	242.000	TON
402020192	ASPHALT CEMENT PG 58V-34	1,022.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	7,064.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	18,354.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	230.100	TON
402020377	SCRUB SEAL EMULSION	211.000	TON
409000030	COVER-TYPE 3	244,660.000	SQYD
411010000	COLD MILLING	141,604.000	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	8.400	MILE
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	112.800	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	2,422.900	SQFT
619010230	REMOVE SIGN	288.000	EACH
619010240	REMOVE SIGN-GUIDE	3.000	EACH
619010310	POSTS-STEEL U SIGN	320.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	620.000	LB
619010480	POLES-TREATED WOOD 4 IN	926.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	122.000	LNFT
619010724	FRANG SIGN POST BKWY-S5 X 10	4.000	EACH
619011010	DELINEATOR DES A	549.000	EACH
619011030	DELINEATOR DES C	384.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
619011060	DELINEATOR DES F	103.000	EACH
620013000	STRIPING-WHITE PAINT	601.000	GAL
620013960	STRIPING-WHITE EPOXY	801.000	GAL
620014000	STRIPING-YELLOW PAINT	402.000	GAL
620014960	STRIPING-YELLOW EPOXY	581.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%. All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 10283000

**102 BOULDER - URBAN STPP 69-1(46)38 CONTRACT NO. 08823**

Cold mill, plant mix surfacing, seal and cover, ADA ramp improvements, raised median modifications, replacement of colored PCCP crosswalks at intersections with PMS, bridge deck repair, signing, and pavement markings on the Boulder - Urban project located in Jefferson County. The project begins at RP 37.5 and extends approximately 1.2 miles north through the town of Boulder, MT along P-69 to RP 38.8.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
----------	-------------	----------	-------

SECTION NO. 0001 - Cold milling, plant mix surfacing, seal & cover			
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
104030037	MISCELLANEOUS ITEMS-SQYD	1,764.000	SQYD
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020353	REMOVE CONCRETE	1,541.000	SQYD
202020539	REMOVE MISCELLANEOUS ITEMS	5.000	EACH
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	65.000	MILE
401020122	COMMERCIAL MIX-PG 58V-34	4,895.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	2,034.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	1,118.200	TON
409000000	FINAL SWEEP AND BROOM	1.200	CRMI
409000010	COVER-TYPE 1	35,706.000	SQYD
411010000	COLD MILLING	35,841.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	783.400	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	4.500	SQYD
603014242	ADJUST VALVE BOX	25.000	EACH
604000100	ADJUST MANHOLE	16.000	EACH
604010184	CONCRETE APRON	20.000	EACH
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	1,484.200	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	23.100	SQYD
608010100	CONCRETE 4 IN	854.500	SQYD
608010110	CONCRETE 6 IN	0.500	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	67.300	SQYD
609010200	CURB AND GUTTER-CONC	1,741.400	LNFT
616343920	CONDUIT-PLASTIC 2 IN	125.000	LNFT
616782999	ADJUST PULL BOX	5.000	EACH
616783007	PULL BOX-COMPOSITE TYPE 2	4.000	EACH
617000000	FOUNDATION-CONCRETE	2.000	CUYD
617033212	CABLE-COPPER 3AWG12-600V	495.000	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	240.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	960.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	145.000	LNFT
617333000	SERV ASSEMBLY-MODIFY	1.000	EACH
617573070	RECTANGULAR RAPID FLASHING BEACON	2.000	EACH
617673200	SIG STANDARD TYPE 1-200	4.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	4.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	180,000.000	UNIT
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	28.000	DAY
618190100	TEMPORARY BARRIER RAIL	550.000	LNFT
618190110	RESET TEMP BARRIER RAIL	550.000	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	66.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	607.100	SQFT
619010230	REMOVE SIGN	68.000	EACH
619010240	REMOVE SIGN-GUIDE	3.000	EACH
619010320	POSTS-STEEL STRUCTURAL SIGN	206.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	759.000	LB
619010480	POLES-TREATED WOOD 4 IN	126.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	10.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	54.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	34.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	10.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	20.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	6.000	GAL
620012955	TEMPORARY STRIPING	8,211.000	LNFT
620013000	STRIPING-WHITE PAINT	90.000	GAL
620013960	STRIPING-WHITE EPOXY	59.000	GAL
620014000	STRIPING-YELLOW PAINT	62.000	GAL
620014960	STRIPING-YELLOW EPOXY	41.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 9742000

**103 TURNBAY - N OF GALLATIN GATEWAY HSIP 50-2(85)77 CONTRACT NO. 07823**

Grade, gravel, plant mix surfacing, and seal and cover on the Turnbay - N of Gallatin Gateway project located in Gallatin County. The project will include widening for the installation of a two-way-left-turn lane (TWLTL), reconstruction of a curve, approach work, box culvert installation, and bridge removal. The project is located along N-50 (US-HWY 191) between RP 76.9 near Gooch Hill Rd. and RP 77.7 near Zachariah Ln.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MAJOR REHAB			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020375	EMBANKMENT IN PLACE	13,715.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	3,530.000	CUYD
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	28.000	MILE
301020268	TRAFFIC GRAVEL	815.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	10,309.000	CUYD
301020450	SPECIAL BACKFILL	330.000	CUYD
301020625	AGGREGATE TREATMENT	24,414.000	SQYD
401020045	PLANT MIX SURF-3/4 IN	7,319.000	TON
401020046	PLANT MIX BIT SURF-MISC	457.000	TON
401020300	HYDRATED LIME	109.000	TON
402020095	ASPHALT CEMENT PG 70-28	406.200	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	3,722.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	52.600	TON
409000000	FINAL SWEEP AND BROOM	0.900	CRMI
409000020	COVER-TYPE 2	29,234.000	SQYD
411010000	COLD MILLING	12,254.000	SQYD
411011135	RUMBLE STRIPS	1.800	MILE
551020030	CONCRETE-CLASS GENERAL	5.800	CUYD
603000050	GRANULAR BEDDING MATERIAL	52.000	CUYD
603000060	FOUNDATION MATERIAL	104.000	CUYD
603010020	FILL AND ABANDON PIPE	7.000	CUYD
603010040	DRAINAGE PIPE 18 IN	444.000	LNFT
603012555	RCP 24 IN	210.000	LNFT
603012660	RCP 36 IN	6.000	LNFT
603013314	REIN CONC BOX 18 X 6	60.000	LNFT
603587020	REMOVE PIPE CULVERT	401.200	LNFT
606010330	MGS GUARDRAIL	762.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	6.000	EACH
606010338	MGS LONGSPAN GUARDRAIL	125.000	LNFT
606010385	REMOVE GUARDRAIL	677.100	LNFT
607100229	FARM FENCE-TYPE F4W	85.000	LNFT
607100259	FARM FENCE-TYPE F5W	204.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	3.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	4.000	EACH
607100551	FENCE-TEMPORARY	258.000	LNFT
610100101	SEEDING AREA NO 1	10.100	ACRE
610100102	SEEDING AREA NO 2	0.100	ACRE
610100103	SEEDING AREA NO 3	3.200	ACRE
610100326	FERTILIZING AREA NO 1	10.100	ACRE
610100327	FERTILIZING AREA NO 2	0.100	ACRE
610100555	CONDITION SEEDBED SURFACE	10.100	ACRE
610220100	MULCH	0.100	ACRE

618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	1.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	57.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	102.600	SQFT
619010230	REMOVE SIGN	9.000	EACH
619010240	REMOVE SIGN-GUIDE	5.000	EACH
619010310	POSTS-STEEL U SIGN	20.000	LB
619010480	POLES-TREATED WOOD 4 IN	204.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	100.000	LNFT
619011010	DELINEATOR DES A	24.000	EACH
619011040	DELINEATOR DES D	8.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	6.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	3.000	GAL
620012955	TEMPORARY STRIPING	9,731.000	LNFT
620013000	STRIPING-WHITE PAINT	54.000	GAL
620013960	STRIPING-WHITE EPOXY	36.000	GAL
620014000	STRIPING-YELLOW PAINT	32.000	GAL
620014960	STRIPING-YELLOW EPOXY	21.000	GAL
622011084	GEOTEXTILE STABILIZATION	338.000	SQYD
623000165	MAILBOX-CLUSTER	4.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
Uniform No. 8998000

**104 TOLUCA - E&W IM 90-9(145)482 CONTRACT NO. 09823**

The Toluca - E & W project is in Big Horn County on Interstate I-90 (US-212/US-87). The project begins approximately 3.2 miles west of the Toluca Interchange (RP 481.0) and ends approximately 0.3 miles east of the Toluca Interchange (RP 486.0). The project is 4.979 miles in length. Work includes crack sealing, leveling, seal and cover, and bridge deck polymer overlay.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PL. MIX. SURF. & SEAL & COVER			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
401020045	PLANT MIX SURF-3/4 IN	7,726.000	TON
401020046	PLANT MIX BIT SURF-MISC	1,521.000	TON
401020300	HYDRATED LIME	129.000	TON
402020095	ASPHALT CEMENT PG 70-28	518.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5,419.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	416.800	TON
403010255	CRACK SEALING	10,817.000	LB
409000000	FINAL SWEEP AND BROOM	10.500	CRMI
409000020	COVER-TYPE 2	234,461.000	SQYD
411010000	COLD MILLING	39,097.000	SQYD
411011135	RUMBLE STRIPS	20.000	MILE
552010160	BRIDGE DECK CRACK SEAL	803.200	SQYD
552011120	JOINT SEALS-POLYURETHANE	166.000	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	1.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	200,000.000	UNIT
620011105	WORDS AND SYMBOLS-WHITE PAINT	6.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.000	GAL
620012955	TEMPORARY STRIPING	105,617.000	LNFT

620013000	STRIPING-WHITE PAINT	396.000	GAL
620013960	STRIPING-WHITE EPOXY	264.000	GAL
620014000	STRIPING-YELLOW PAINT	296.000	GAL
620014960	STRIPING-YELLOW EPOXY	198.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
Uniform No. 10068000

**105 SOUTH OF CHESTER - SOUTH STPS 223-1(10)26 CONTRACT NO. 04823**

Scrub Seal and new pavement markings on South of Chester-South project located in Liberty and Chouteau Counties south of Chester on Secondary 223 (S-223). The project begins at RP 25.4 and extends 22.3 miles to RP 47.7. Bridge deck repair and seal over the Marias River bridge at RP 34.4 is included. Sign faces will be replaced.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SCRUB SEAL, NEW PAVEMENT MARKINGS, BRIDGE DECK REPAIR			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	152.000	MILE
402020377	SCRUB SEAL EMULSION	642.100	TON
409000000	FINAL SWEEP AND BROOM	22.300	CRMI
409000010	COVER-TYPE 1	356,704.000	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	60.000	SQYD
563000040	POLYMER OVERLAY	1,082.400	SQYD
563000045	POLYMER OVERLAY PRIMER	1,082.400	SQYD
563000100	PREPARE DECK	1,082.400	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	150,000.000	UNIT
619010090	SIGNS-ALUM REFL SHEET XI	204.300	SQFT
619010310	POSTS-STEEL U SIGN	20.000	LB
620013000	STRIPING-WHITE PAINT	805.000	GAL
620013960	STRIPING-WHITE EPOXY	1,073.000	GAL
620014000	STRIPING-YELLOW PAINT	276.000	GAL
620014960	STRIPING-YELLOW EPOXY	367.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 10285000

**106 FLY CREEK - 15 MILES WEST HARDIN STPB 81016(7) CONTRACT NO. 06823**

Excavation, bridge scour, sheet pile wall, riprap, and revegetation on the Fly Creek - 15 Miles West Hardin project located in Big Horn County.

This project is located on old Hwy 87, Route X-81016E, approximately 15 miles west of Hardin (RP 29.397).

INVOLVING

-----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE SCOUR			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
104030070	MISCELLANEOUS ITEMS-REMOVAL	1.000	LS
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	2,700.000	CUYD
203020175	EXCAVATION-UNCLASS CHANNEL	600.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
559050141	SHEET PILE WALL	660.000	SQFT
610100559	REVEGETATION	1.000	LS
610100560	RIPRAP REVEGETATION	980.000	SQYD
613100070	RIPRAP-MATRIX	1,440.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
622011043	PERM EROSION CONTROL-HIGH SURV	1,630.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Billings District Administrator.  
 Uniform No. 9791000

**107 VALLEY CENTER/BAXTER LANE - BOZEMAN UPP 1299(59) CONTRACT NO. 01823**

Seal & cover, pavement markings on the Valley Center/Baxter Lane - Bozeman located in Gallatin County.

This project is located on East Valley Road (U-1211) beginning at the intersection of Valley Spur and will extend southwest approximately 1.8 miles to junction with N 19th Avenue. The Baxter Lane (U-1218) portion begins at the intersection of Baxter Lane and North 7th Avenue and will extend northwest along Baxter Lane approximately 1.1 miles to the junction with N 19th Avenue.

INVOLVING

-----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & COVER			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
402020375	EMULSIFIED ASPHALT CHFRS-2P	154.000	TON
403010255	CRACK SEALING	2,100.000	LB
403010257	CRACK FILLING-MASTIC	315.000	LB
409000000	FINAL SWEEP AND BROOM	3.600	CRMI
409000020	COVER-TYPE 2	86,331.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	100,000.000	UNIT
618100005	PORTABLE VARIABLE MESSAGE SIGN	4.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	150.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	45.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	26.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	59.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	34.000	GAL
620013000	STRIPING-WHITE PAINT	137.000	GAL
620013960	STRIPING-WHITE EPOXY	183.000	GAL
620014000	STRIPING-YELLOW PAINT	70.000	GAL
620014960	STRIPING-YELLOW EPOXY	93.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 10250000

**108 SF 189 AIRPORT RD GLENDIVE SFTY HSIP 11(110) CONTRACT NO. 02823**

The SF 189 Airport Rd Glendive Sfty project in Dawson County is to address run off the road cashes along Airport Rd/Dry Creek Rd north of Glendive. This project begins a half mile north of the intersection of Airport Rd/Dry Creek Rd with Alder Ave at RP 0.6+/-, and proceeds north and ends at the Dawson Community Airport RP 3.5+/- for total distance of 2.7 miles. The improvements include tree removal, signing, curve signing, striping, and delineation.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - ROADWAY & ROADSIDE SAFETY IMPROVEMENTS			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
610650035	TREE REMOVAL-CAT 1	169.000	EACH
610650040	TREE REMOVAL-CAT 2	97.000	EACH
610650045	TREE REMOVAL-CAT 3	24.000	EACH
610650050	TREE REMOVAL-CAT 4	27.000	EACH
618030080	TRAFFIC CONTROL-LS	1.000	LS
619010090	SIGNS-ALUM REFL SHEET XI	224.300	SQFT
619010230	REMOVE SIGN	14.000	EACH
619010480	POLES-TREATED WOOD 4 IN	134.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	208.000	LNFT
619011010	DELINEATOR DES A	107.000	EACH
619011030	DELINEATOR DES C	37.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
619011060	DELINEATOR DES F	53.000	EACH
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620013960	STRIPING-WHITE EPOXY	133.000	GAL
620014960	STRIPING-YELLOW EPOXY	203.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.  
 Uniform No. 9904000

**109 ROCK CREEK BRIDGE - ROCKVALE NHPB 4-1(85)42 CONTRACT NO. 05823**

Bridge deck resurfacing, joint repair, and other minor bridge work on the ROCK CREEK BRIDGE - ROCKVALE project located in Carbon County. The Rock Creek Bridge is located along US 310 at RP 42.45 approximately 1/4 mile south of its intersection with US 212 (at Rockvale).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MINOR BRIDGE REHAB			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS



202020058	REMOVE GUARD ANGLE	164.000	LNFT
202020139	REMOVE ASPHALT FROM DECK	598.300	SQYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
401020122	COMMERCIAL MIX-PG 58V-34	83.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	30.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	1.100	TON
409000010	COVER-TYPE 1	595.000	SQYD
552010060	REPAIR STRUCTURE	1.000	LS
552011030	EXPANSION JOINT-ASPHALT PLUG	39.000	LNFT
552011120	JOINT SEALS-POLYURETHANE	5.000	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	10.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.000	SQYD
563000100	PREPARE DECK	598.300	SQYD
563000110	WATERPROOF MEMBRANE	604.400	SQYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
620013000	STRIPING-WHITE PAINT	2.000	GAL
620013960	STRIPING-WHITE EPOXY	2.000	GAL
620014000	STRIPING-YELLOW PAINT	2.000	GAL
620014960	STRIPING-YELLOW EPOXY	2.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
Uniform No. 9685000

INVITATION FOR BIDS  
LETTING OF August 31, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on August 31, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

201 WHEATLAND COUNTY LINE - EAST STPP 14-3(20)77 CONTRACT NO. 17823

Reconstruction of the existing roadway on the Wheatland County Line - East project in Meagher & Wheatland counties. Work includes: grade, gravel, PL mix, installing new drainage structures and bridge replacement. This project begins in Meagher County at RP 77.1 and ends in Wheatland County at RP 82.9 on U.S. Hwy 12 (P-14).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RECONSTRUCTION, PMS, DRAINAGE STRUCTURES, BRIDGE			
REPLACEMENT			
103000000	TRAINING PROGRAM	1,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
104030030	MISCELLANEOUS ITEMS-INSTALL	1,975.000	LNFT
104030065	MISCELLANEOUS ITEMS A-LNFT	2,483.500	LNFT
104030066	MISCELLANEOUS ITEMS B-LNFT	1,327.000	LNFT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000000	CRITICAL PATH SCHEDULE	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	205,016.000	CUYD
203020175	EXCAVATION-UNCLASS CHANNEL	431.000	CUYD
203020200	EXCAVATION-UNCLASS BORROW	13,445.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	146,837.000	CUYD
203020380	SPECIAL EMBANKMENT	28,445.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	30,226.000	CUYD
204010185	BLASTING CONSULTANT	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
208010486	STREAMBED MATERIAL	20.000	CUYD
209010165	TEMPORARY SHORING	203.000	LNFT
210020170	TEST TRAILER-TRANSPORT,SETUP	175.000	MILE
301020252	BRIDGE END BACKFILL-TYPE 1	1,227.000	CUYD
301020268	TRAFFIC GRAVEL	5,500.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	31,793.000	CUYD
301020450	SPECIAL BACKFILL	3,094.000	CUYD
301020453	NON-FROST SUSCEPTIBLE BACKFILL	5,400.000	CUYD
301020625	AGGREGATE TREATMENT	127,233.000	SQYD
401020045	PLANT MIX SURF-3/4 IN	24,489.000	TON
401020046	PLANT MIX BIT SURF-MISC	518.000	TON
401020300	HYDRATED LIME	350.000	TON
402020192	ASPHALT CEMENT PG 58V-34	1,376.800	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	12,453.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	199.600	TON
409000000	FINAL SWEEP AND BROOM	5.800	CRMI
409000010	COVER-TYPE 1	110,762.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	5.800	MILE
411011135	RUMBLE STRIPS	11.300	MILE
551020030	CONCRETE-CLASS GENERAL	35.400	CUYD
551020035	CONCRETE-CLASS STRUCTURE	112.000	CUYD
551020036	CONCRETE-CLASS STRUCTURE LOW SLUMP	115.600	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	338.000	CUYD
552010140	TRANSVERSE DECK GROOVING	361.000	SQYD
553010152	PRESTRESSED BEAM-TYPE MTS-45	475.000	LNFT
555010100	REINFORCING STEEL	19,138.000	LB
555010200	REINFORCING STEEL-EPOXY COATED	25,214.000	LB
557010015	BRIDGE RAIL-W830-CSC	256.880	LNFT
559010202	RE-DRIVE TEST PILE	2.000	EACH
559040035	DYNAMIC LOAD TEST	2.000	EACH
559050117	FURN STEEL PILE-HP	40,719.600	LB
559060115	DRIVE STEEL PILE	414.200	LNFT
559060300	PILE DRIVING POINT	14.000	EACH
603000050	GRANULAR BEDDING MATERIAL	663.000	CUYD
603000060	FOUNDATION MATERIAL	777.000	CUYD
603010040	DRAINAGE PIPE 18 IN	1,434.000	LNFT
603010048	DRAINAGE PIPE 24 IN	140.000	LNFT

603010064	DRAINAGE PIPE 42 IN	224.000	LNFT
603010066	DRAINAGE PIPE 36 IN	134.000	LNFT
603010100	DRAINAGE PIPE 96 IN	210.000	LNFT
603010692	CSP 84 IN	192.000	LNFT
603012530	RCP 18 IN	20.000	LNFT
603012555	RCP 24 IN	106.000	LNFT
603012625	RCP 30 IN	88.000	LNFT
603012660	RCP 36 IN	204.000	LNFT
603012847	RCP IRR 18 IN	6.000	LNFT
603012892	RCP IRR 24 IN	704.000	LNFT
603013190	RCPA 18 IN EQ DIA	36.000	LNFT
603013212	RCPA 30 IN EQ DIA	42.000	LNFT
603013364	REIN CONC BOX 10 X 5	114.000	LNFT
603013402	PIPE-SW-POLYETHYLENE 42 IN	166.000	LNFT
603013452	PIPE-PVC 12 IN	150.000	LNFT
603013462	PIPE-PVC 6 IN	457.000	LNFT
603013470	PIPE-PVC 10 IN	6.000	LNFT
603013478	PIPE-PVC PRESS 12 IN WATER	219.000	LNFT
603015270	EMBANKMENT PROTECTOR 18 IN	114.000	LNFT
603587020	REMOVE PIPE CULVERT	3,405.000	LNFT
604010302	MANHOLE STRUCTURE BASE 48 IN (1220 MM)	2.000	EACH
606010037	MASH BOX BEAM TERMINAL - MBEAT	8.000	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	1,926.000	LNFT
606010266	GRD RL-BOX BEAM/BR APP-SEC TYPE 2	4.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	2,807.000	LNFT
607100149	FARM FENCE-TYPE F3W-32 IN WW	26,214.000	LNFT
607100259	FARM FENCE-TYPE F5W	7,343.000	LNFT
607100281	FARM FENCE-TYPE F5M	19,157.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	200.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	190.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	320.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	216.000	LNFT
607100551	FENCE-TEMPORARY	7,977.000	LNFT
607100720	DEADMAN	20.000	EACH
609010112	CURB 4 IN-CONCRETE	244.000	LNFT
610100101	SEEDING AREA NO 1	74.700	ACRE
610100102	SEEDING AREA NO 2	1.200	ACRE
610100103	SEEDING AREA NO 3	21.500	ACRE
610100326	FERTILIZING AREA NO 1	74.700	ACRE
610100327	FERTILIZING AREA NO 2	1.200	ACRE
610100490	TURF REINF MAT-NATURAL FIBER	1,100.000	SQYD
610100555	CONDITION SEEDBED SURFACE	96.200	ACRE
610100560	RIPRAP REVEGETATION	547.000	SQYD
610220050	MULCH-COMPOST	1.200	ACRE
611010024	CATTLE GUARD 24 FT-LIGHT DUTY	2.000	EACH
611010025	CATTLE GUARD 24 FT-HEAVY DUTY	3.000	EACH
613100040	RIPRAP-CLASS 2 RANDOM	705.000	CUYD
613300050	BANK PROTECTION-TYPE 3	12.000	CUYD
613300065	ROCK FILL	20,875.000	CUYD
615010020	IRRIGATION DIVISION BOX	1.000	EACH
615010022	IRRIGATION DIVISION BOX-TYPE 3	5.000	EACH
615010034	REMOVE IRRIGATION STRUCTURE	12.000	EACH
615010580	TRASH GUARD	3.000	EACH
615010730	IRRIGATION DITCH	1,389.000	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	1,200,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	20.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	84.200	SQFT
619010230	REMOVE SIGN	39.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010310	POSTS-STEEL U SIGN	100.000	LB
619010480	POLES-TREATED WOOD 4 IN	200.000	LNFT
619011010	DELINEATOR DES A	181.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620012955	TEMPORARY STRIPING	61,248.000	LNFT
620013000	STRIPING-WHITE PAINT	398.000	GAL
620013960	STRIPING-WHITE EPOXY	265.000	GAL
620014000	STRIPING-YELLOW PAINT	190.000	GAL
620014960	STRIPING-YELLOW EPOXY	127.000	GAL

622010075	GEOGRID - BIAXIAL	750.000	SQYD
622011043	PERM EROSION CONTROL-HIGH SURV	1,050.000	SQYD
622011084	GEOTEXTILE STABILIZATION	255,137.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
Uniform No. 4889000

**202 SHELBY - SWEETGRASS GUARDRAIL IM-NHPB 15-8(70)354 CONTRACT NO. 16823**

The proposed project is located on Interstate 15 (I-15) in Toole County between RP 354.3 and RP 397.9. The project will replace guardrail and bridge rail, repair and seal bridge decks and upgrade signing. The project passes through the city limits of Shelby and Sunburst. Designated interchange ramps and crossroads will also receive guardrail and bridge treatments.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GUARDRAIL			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
551020107	CONCRETE-CLASS DECK	19.400	CUYD
552010160	BRIDGE DECK CRACK SEAL	14,888.000	SQYD
552011010	EXPANSION JOINT STRIP SEAL	148.400	LNFT
552011120	JOINT SEALS-POLYURETHANE	164.200	LNFT
555010200	REINFORCING STEEL-EPOXY COATED	1,304.000	LB
561010525	EXPANSION JOINT-PRECOMPRESSED	318.000	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	151.200	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	74.900	SQYD
563000040	POLYMER OVERLAY	4,465.000	SQYD
563000045	POLYMER OVERLAY PRIMER	4,465.000	SQYD
563000100	PREPARE DECK	4,465.000	SQYD
605000040	REVISE CONCRETE BARRIER RAIL-BR	6,457.400	LNFT
606010012	GUARDRAIL-STIFFENED	137.500	LNFT
606010037	MASH BOX BEAM TERMINAL - MBEAT	6.000	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	4,572.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	22.000	EACH
606010230	GUARDRAIL-STL/BR APPR-TY 3	13.000	EACH
606010325	GRD RL-BOX BEAM TO W-BEAM TRANS	9.000	EACH
606010330	MGS GUARDRAIL	14,412.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	52.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	26.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	22.000	EACH
606010385	REMOVE GUARDRAIL	22,707.800	LNFT
606010670	BOX BEAM DEPART TERM SEC	3.000	EACH
606011503	RESET TEMP IMPACT ATTENUATOR	18.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	18.000	EACH
609010010	CURB-CONCRETE	1,404.700	LNFT
609010203	REMOVE CURB	1,404.700	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	400,000.000	UNIT
618030180	TRAFFIC CONTROL-CROSSOVER	2.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	1.000	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	2.000	EACH
618030280	CROSSOVER RECLAMATION	2.000	EACH
618100000	SINGLE USE SIGNS	283.000	SQFT
618190100	TEMPORARY BARRIER RAIL	5,620.000	LNFT
618190110	RESET TEMP BARRIER RAIL	5,620.000	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	254.000	SQFT

619010090	SIGNS-ALUM REFL SHEET XI	1,371.900	SQFT
619010230	REMOVE SIGN	112.000	EACH
619010300	POSTS-TUBULAR STEEL	825.000	LB
619010310	POSTS-STEEL U SIGN	38.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,362.000	LB
619010480	POLES-TREATED WOOD 4 IN	74.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	1,006.000	LNFT
619010730	FRANG SIGN POST BKWY-W8 X 18	2.000	EACH
619010732	FRANG SIGN POST BKWY-W8 X 24	2.000	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD	2.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 9966000

**203 SF 169 S-288 CURVES HSIP-STPB 288-1(11)2 CONTRACT NO. 05623R**

Grading, gravel surfacing, plant mix bituminous surfacing, seal and cover, irrigation and drainage improvements, bridge replacements, rumble strips, signing and pavement markings on the SF 169 S288 Curves project located in Gallatin County. The project is located on State Secondary Route 288 between Manhattan and Churchill and includes two separate locations. Site 1 begins at RP 4.5 and extends southeast to RP 4.8. Site 2 begins at RP 2.3 and extends south to RP 2.8. Total project length is approximately 0.8 miles.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - ROADWAY & SAFETY IMPROVEMENTS			
104030010	MISCELLANEOUS WORK	35,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
201311000	REMOVE TREES	2.000	EACH
202020041	REMOVE STRUCTURE	1.000	LS
203020310	SPECIAL BORROW-NEAT LINE	4,561.000	CUYD
203020375	EMBANKMENT IN PLACE	22,343.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	4,609.000	CUYD
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.000	LS
206000050	DETOUR-MAINTAIN	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	25.000	MILE
301020268	TRAFFIC GRAVEL	80.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	5,523.000	CUYD
301020450	SPECIAL BACKFILL	3,446.000	CUYD
301020465	LOW PERMEABILITY BACKFILL	81.400	CUYD
301020625	AGGREGATE TREATMENT	20,115.000	SQYD
401020064	COMMERCIAL PLANT MIX-MISC	158.000	TON
401020122	COMMERCIAL MIX-PG 58V-34	4,379.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,907.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	29.400	TON
409000000	FINAL SWEEP AND BROOM	0.800	CRMI
409000010	COVER-TYPE 1	16,314.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	0.800	MILE
411011135	RUMBLE STRIPS	1.600	MILE
551020030	CONCRETE-CLASS GENERAL	16.700	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	105.000	CUYD
603000050	GRANULAR BEDDING MATERIAL	114.000	CUYD
603012892	RCP IRR 24 IN	206.000	LNFT
603012938	RCP IRR 36 IN	108.000	LNFT
603013302	REIN CONC BOX 24 X 9	96.000	LNFT
603013303	REIN CONC BOX 20 X 8	110.000	LNFT
603587020	REMOVE PIPE CULVERT	327.000	LNFT
606010385	REMOVE GUARDRAIL	281.600	LNFT

606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
607100111	FARM FENCE-TYPE F2W-39 IN WW	1,041.000	LNFT
607100229	FARM FENCE-TYPE F4W	1,506.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	10.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	5.000	EACH
607100391	FENCE-WOOD-4 RAIL	146.000	LNFT
607100430	FARM GATE-WIRE-TYPE G-2	48.000	LNFT
610100101	SEEDING AREA NO 1	5.800	ACRE
610100103	SEEDING AREA NO 3	2.900	ACRE
610100326	FERTILIZING AREA NO 1	5.800	ACRE
610100555	CONDITION SEEDBED SURFACE	8.700	ACRE
610100561	EROSION CONTROL BLANKET-LONG-TERM	2,852.000	SQYD
613100090	CULVERT INFILL	171.800	CUYD
618030005	TRAFFIC CONTROL DEVICES CB	200,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	24.000	DAY
618190100	TEMPORARY BARRIER RAIL	90.000	LNFT
619010090	SIGNS-ALUM REFL SHEET XI	116.400	SQFT
619010230	REMOVE SIGN	15.000	EACH
619010480	POLES-TREATED WOOD 4 IN	180.000	LNFT
619010810	PANEL DELINEATOR DESIGN C	28.000	EACH
619010820	PANEL DELINEATOR DESIGN F	12.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620012955	TEMPORARY STRIPING	9,281.000	LNFT
620013000	STRIPING-WHITE PAINT	72.000	GAL
620013960	STRIPING-WHITE EPOXY	48.000	GAL
620014000	STRIPING-YELLOW PAINT	64.000	GAL
620014960	STRIPING-YELLOW EPOXY	42.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	14,882.000	SQYD
623000155	MAILBOX	3.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
Uniform No. 9380000

**204 VIRGINIA CITY - WEST STPP 29-1(70)14 CONTRACT NO. 15823**

Mill and PMS overlay, underseal, seal and cover, guardrail, rumble strips, pavement markings, delineation, electrical, and signage on the Virginia City - West project located in Madison County. The project begins at RP 19.9 and extends approximately 6.1 miles east along Primary Route 29 (MT-287) to RP 13.8. The project passes through Nevada City and Virginia City and includes pedestrian-friendly enhancements within these towns.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RESURFACING, ASPHALT & ADA IMPROVEMENTS			
104030010	MISCELLANEOUS WORK	35,000.000	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.000	LS
104030037	MISCELLANEOUS ITEMS-SQYD	9,639.000	SQYD
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	172.000	MILE
301020340	CRUSHED AGGREGATE COURSE	624.000	CUYD
301020625	AGGREGATE TREATMENT	7,479.000	SQYD
401020045	PLANT MIX SURF-3/4 IN	16,130.000	TON
401020046	PLANT MIX BIT SURF-MISC	628.000	TON

401020300	HYDRATED LIME	235.000	TON
402020192	ASPHALT CEMENT PG 58V-34	905.800	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	11,223.000	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	154.100	TON
402020375	EMULSIFIED ASPHALT CHFRS-2P	152.600	TON
409000000	FINAL SWEEP AND BROOM	5.500	CRMI
409000010	COVER-TYPE 1	170,174.000	SQYD
411010000	COLD MILLING	91,688.000	SQYD
411011120	CENTERLINE RUMBLE STRIPS-TYPE 1	5.500	MILE
557010544	REVISE TIMBER BRIDGE RAIL-THRIE BEAM	111.300	LNFT
604000100	ADJUST MANHOLE	3.000	EACH
606010140	GUARDRAIL END SECTION WIDENING	4.000	EACH
606010330	MGS GUARDRAIL	12.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	3.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	3.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	68.800	LNFT
606010385	REMOVE GUARDRAIL	330.100	LNFT
608010020	SIDEWALK-CONCRETE 4 IN	45.700	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	8.000	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	5.600	SQYD
609010200	CURB AND GUTTER-CONC	63.100	LNFT
610100559	REVEGETATION	1.000	LS
616343920	CONDUIT-PLASTIC 2 IN	80.000	LNFT
616783006	PULL BOX-COMPOSITE TYPE 1	1.000	EACH
617000000	FOUNDATION-CONCRETE	1.000	CUYD
617123108	CONDUCTOR-COPPER AWG8-600V	280.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	100.000	LNFT
617333100	SERV ASSEMBLY	1.000	EACH
617573070	RECTANGULAR RAPID FLASHING BEACON	1.000	EACH
617673200	SIG STANDARD TYPE 1-200	2.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
619010062	SIGNS-ALUM SHEET INCR XI	78.300	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	724.300	SQFT
619010230	REMOVE SIGN	94.000	EACH
619010240	REMOVE SIGN-GUIDE	3.000	EACH
619010310	POSTS-STEEL U SIGN	208.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	290.000	LB
619010480	POLES-TREATED WOOD 4 IN	962.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	264.000	LNFT
619010724	FRANG SIGN POST BKWY-S5 X 10	2.000	EACH
619010800	PANEL DELINEATOR DESIGN A	437.000	EACH
619010815	PANEL DELINEATOR DESIGN D	12.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	13.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.000	GAL
620012955	TEMPORARY STRIPING	125,532.000	LNFT
620013000	STRIPING-WHITE PAINT	455.000	GAL
620013960	STRIPING-WHITE EPOXY	304.000	GAL
620014000	STRIPING-YELLOW PAINT	402.000	GAL
620014960	STRIPING-YELLOW EPOXY	273.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
Uniform No. 9873000

**205 BUTTE URBAN PAVE PRES UPP 1899(47) CONTRACT NO. 11823**

The Butte Urban Pave Pres project consists of multiple streets in the City of Butte, Silver Bow.

- Excelsior Ave. begins at Platinum St. and ends at Caledonia St. The route length is 0.623 miles and will consist of a chip seal and pavement markings.

- Park St. begins at Montana St. and ends at Mining Museum Rd.at. The route length is 1.128 miles and will consist of a chip seal and pavement markings.



- Shields Ave./ Farrell Street begins approximately 350 ft north of the bridge over the railroad on Shields Ave. and ends just past the Montana Resources railroad crossing near Stuart Ave. The route length is 1.005 miles and will consist of a milling, paving, chip seal, guardrail, and pavement markings.
- Grand Ave begins at Harrison Ave. and ends at Continental Dr. The route length is 1.360 miles and will consist of a chip seal, crack seal and pavement markings.
- Amherst Ave. begins at the intersection of Harrison Ave. and ends at Continental Dr. The route length is 0.988 miles and will consist of a chip seal, crack seal and pavement markings.
- Elizabeth Warren begins at Harrison Ave. and ends at Continental Dr. The route length is 1.385 miles and will consist of a chip seal, crack seal and pavement markings.
- Four Mile Rd. Begins at Harrison Ave. and end ends at Holmes Ave., via Utah Ave., Electric St., and Western Blvd. The route length is 1.811 miles and consists of a chip seal and pavement markings with some milling and paving on Four Mile Rd.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - CRACK SEAL, SEAL & COVER			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	30.000	MILE
401020122	COMMERCIAL MIX-PG 58V-34	3,998.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,611.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	375.400	TON
403010255	CRACK SEALING	3,858.000	LB
403010257	CRACK FILLING-MASTIC	1,158.000	LB
409000000	FINAL SWEEP AND BROOM	8.200	CRMI
409000020	COVER-TYPE 2	217,537.000	SQYD
411010000	COLD MILLING	31,968.000	SQYD
603014242	ADJUST VALVE BOX	6.000	EACH
604000100	ADJUST MANHOLE	4.000	EACH
606010230	GUARDRAIL-STL/BR APPR-TY 3	8.000	EACH
606010330	MGS GUARDRAIL	1,893.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	6.000	EACH
606010385	REMOVE GUARDRAIL	3,049.800	LNFT
609010112	CURB 4 IN-CONCRETE	375.000	LNFT
609010203	REMOVE CURB	929.400	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	170,000.000	UNIT
620010301	CURB MARKING-YELLOW EPOXY	364.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	240.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	6.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	305.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	8.000	GAL
620012955	TEMPORARY STRIPING	11,939.000	LNFT
620013000	STRIPING-WHITE PAINT	335.000	GAL
620013960	STRIPING-WHITE EPOXY	386.000	GAL
620014000	STRIPING-YELLOW PAINT	335.000	GAL
620014960	STRIPING-YELLOW EPOXY	382.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 10251000

206 **NAHMIS AVENUE - HUNTLEY STPP 265-1(2)0 CONTRACT NO. 18823**

This project will resurface about 0.7 of Nahmis Avenue just north of Huntley in Yellowstone County. It will consist of overlaying the existing roadway from RP 0.1 heading North to RP 0.8 with new pavement, upgrading existing signage, and applying new pavement markings

INVOLVING

-----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & OVERLAY			
104030010	MISCELLANEOUS WORK	40,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
203020278	EXCAVATION-DIGOUTS	383.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	269.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020000	GRADER-MOTOR	18.000	HOURL
301020340	CRUSHED AGGREGATE COURSE	87.000	CUYD
401020064	COMMERCIAL PLANT MIX-MISC	166.000	TON
401020122	COMMERCIAL MIX-PG 58V-34	1,729.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	672.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	20.200	TON
402020377	SCRUB SEAL EMULSION	21.900	TON
409000000	FINAL SWEEP AND BROOM	0.700	CRMI
409000010	COVER-TYPE 1	23,592.000	SQYD
411010000	COLD MILLING	3,137.000	SQYD
603014242	ADJUST VALVE BOX	1.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	80,000.000	UNIT
619010062	SIGNS-ALUM SHEET INCR XI	42.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	134.800	SQFT
619010230	REMOVE SIGN	13.000	EACH
619010480	POLES-TREATED WOOD 4 IN	100.000	LNFT
619526065	RETRO-REFL STRIP-YL 4 X 60	1.000	EACH
619526085	RETRO-REFL STRIP-RED 4 X 72	1.000	EACH
619526095	RETRO-REFL STRIP-RED 4 X 48	1.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	3.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	1.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	1.000	GAL
620012955	TEMPORARY STRIPING	7,018.000	LNFT
620013000	STRIPING-WHITE PAINT	24.000	GAL
620013960	STRIPING-WHITE EPOXY	32.000	GAL
620014000	STRIPING-YELLOW PAINT	24.000	GAL
620014960	STRIPING-YELLOW EPOXY	32.000	GAL
622011084	GEOTEXTILE STABILIZATION	474.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.

Uniform No. 10252000

**207 OLD HWY 10 SIDEWALK - ST REGIS TA 31(56) CONTRACT NO. 13823**

Installation of ADA sidewalk and asphalt path, curb ramps, PMS approaches and roadway patching, and curb & gutter on the Old Hwy 10 Sidewalk - St Regis project located in Mineral County. The new sidewalk is located within the community of St. Regis on the north side of Mullan Gulch Road from the St. Regis Community Park to the Tiger Street intersection.

INVOLVING

-----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BIKE/PED FACILITIES			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
201311010	REMOVE TREES AND BRUSH	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	167.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT

301020340	CRUSHED AGGREGATE COURSE	173.000	CUYD
401020057	COMMERCIAL MIX-3/8 IN-PG 58-28	144.000	TON
604010661	CURB INLET FRAME AND GRATE	1.000	EACH
604010662	DROP INLET FRAME AND GRATE	2.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	277.700	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	90.200	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	3.600	SQYD
609010030	CURB-CONC MEDIAN TYPE A	24.000	LNFT
609010200	CURB AND GUTTER-CONC	149.700	LNFT
610100559	REVEGETATION	1.000	LS
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
699010230	SUMP	3.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
 Uniform No. 10100000

INVITATION FOR BIDS  
LETTING OF SEPTEMBER 21, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on . All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION  
Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

101

I-94 BR REHAB - CIRCLE INTCH NHPB 94-1(88)211

CONTRACT NO. 08923

Bridge deck rehabilitation/replacement with road reconstruction on the I-94 Bridge Rehab - Circle Intch project in Dawson County. The project is located west of the City of Glendive on I-94 between RP 211.14 and RP 212.20. Work includes grading, gravel, PCCP surfacing, seal course, bridge deck repair/replacement, and interchange crossovers.

## INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO.	0001 - BRIDGE REHAB & ROAD RECONSTRUCT		
104030010	MISCELLANEOUS WORK	20000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
202020058	REMOVE GUARD ANGLE	163.00	LNFT
202020097	REMOVE BRIDGE APPROACH SLAB	4.00	EACH
202020115	REMOVE DECK	1583.00	SQYD
203020100	EXCAVATION-UNCLASSIFIED	10212.00	CUYD
203020310	SPECIAL BORROW-NEAT LINE	1874.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
301020340	CRUSHED AGGREGATE COURSE	2432.00	CUYD
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	328.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	836.00	GAL
411011135	RUMBLE STRIPS	0.00	MILE
501010120	PORT CEM CONC PAVE 8 IN	8381.00	SQYD
551020036	CONCRETE-CLASS STRUCTURE LOW SLUMP	375.00	CUYD
552010060	REPAIR STRUCTURE	1.00	LS
552010140	TRANSVERSE DECK GROOVING	6246.00	SQYD
552011010	EXPANSION JOINT STRIP SEAL	161.00	LNFT
552011300	SCUPPER	8.00	EACH
555010200	REINFORCING STEEL-EPOXY COATED	114536.00	LB
561010525	EXPANSION JOINT-PRECOMPRESSED	161.00	LNFT
561020110	BRIDGE DECK MILLING	5108.00	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	135.00	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	80.00	SQYD
563000010	CONCRETE-CLASS OVERLAY	5108.00	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.00	UNIT
603015275	EMBANKMENT PROTECTOR 24 IN	57.00	LNFT
603587000	REMOVE EMBANKMENT PROTECTOR	1.00	EACH
604000270	ADJUST MEDIAN INLET	1.00	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	2422.00	LNFT
605000094	42 IN SS CONCRETE BARRIER RAIL-BR	711.00	LNFT
606010330	MGS GUARDRAIL	3100.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	8.00	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	8.00	EACH
606010385	REMOVE GUARDRAIL	3244.00	LNFT
607000006	PANEL-SINGLE CHAIN LINK	4.00	EACH
607000050	FENCE-CHAIN LINK 6 FT	106.00	LNFT
609010112	CURB 4 IN-CONCRETE	60.00	LNFT
610100559	REVEGETATION	1.00	LS
613300050	BANK PROTECTION-TYPE 3	1.00	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
618030180	TRAFFIC CONTROL-CROSSOVER	4.00	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	2.00	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	1.00	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	1.00	EACH
618030280	CROSSOVER RECLAMATION	1.00	EACH
619010062	SIGNS-ALUM SHEET INCR XI	366.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	32.00	SQFT
619010230	REMOVE SIGN	2.00	EACH
619010240	REMOVE SIGN-GUIDE	3.00	EACH
619010300	POSTS-TUBULAR STEEL	328.00	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	2322.00	LB
619010720	FRANG SIGN POST BKWY-S3 X 5.7	2.00	EACH

619010800	PANEL DELINEATOR DESIGN A	14.00	EACH
619010830	PANEL DELINEATOR DESIGN H	14.00	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Glendive District Administrator.  
 Uniform No. 9784000

**102 HARLEM - NORTH (S-241/S-338) STPS STWD(909) CONTRACT NO. 07923**

This project is located in Blaine County. Beginning at Secondary 241, locally known as Lincoln Road, N. Main St, Central Avenue E. and Turner Road, continuing North, and includes Secondary 331, locally known as Hogeland Road. A layer of rejuvenating emulsion and rock chips applied to the existing roadway to help seal the cracks. The entirety of Turner Road (approximately 43 miles) from Harlem to Canada and the entire paved section of Hogeland Road (approximately 15 miles) will receive this treatment. Signing and pavement markings will be replaced and the bridge deck over Woody Island Creek will be resealed.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	- SCRUB SEAL, FOG SEAL		
104030010	MISCELLANEOUS WORK	25000.00	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
402020320	EMULSIFIED ASPHALT-FOG SEAL	67311.00	GAL
402020377	SCRUB SEAL EMULSION	1614.00	TON
409000010	COVER-TYPE 1	897187.00	SQYD
552010160	BRIDGE DECK CRACK SEAL	395.00	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	450000.00	UNIT
619010062	SIGNS-ALUM SHEET INCR XI	292.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1344.00	SQFT
619010230	REMOVE SIGN	224.00	EACH
619010240	REMOVE SIGN-GUIDE	17.00	EACH
619010300	POSTS-TUBULAR STEEL	748.00	LB
619010310	POSTS-STEEL U SIGN	1626.00	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1366.00	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	1549.00	LB
619010480	POLES-TREATED WOOD 4 IN	1406.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	86.00	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	10.00	EACH
619010724	FRANG SIGN POST BKWY-S5 X 10	2.00	EACH
619010740	FRANG SIGN POST BKWY-3 IN RD	2.00	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD	4.00	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD	1.00	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	8.00	EACH
619011010	DELINEATOR DES A	1661.00	EACH
619011040	DELINEATOR DES D	60.00	EACH
619011060	DELINEATOR DES F	41.00	EACH
620011260	WORDS AND SYMBOLS-WHITE EPOXY	3.00	GAL
620013000	STRIPING-WHITE PAINT	2345.00	GAL
620013960	STRIPING-WHITE EPOXY	3127.00	GAL
620014000	STRIPING-YELLOW PAINT	582.00	GAL
620014960	STRIPING-YELLOW EPOXY	1088.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 10288000

**103 JCT SEC 331-NORTH (S-228) STPS 228-1(14)14**

**CONTRACT NO. 01923**

The JCT SEC 331 - North (S-228) project includes Texas underseal, crack seal, mastic seal, seal and cover, and new pavement markings on S-228 (Highwood Road) in Cascade and Chouteau Counties. The project begins at RP 13.7 (JCT of Highwood Road and Belt Creek Road) and proceeds northeast for 15.3 miles to RP 29.1 (JCT of Highwood Road and W Shonkin Road).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 -	OVERLAY, SEAL & COVER, CRACK SEAL		
104030010	MISCELLANEOUS WORK	25000.00	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.00	LS
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	60.00	MILE
401020046	PLANT MIX BIT SURF-MISC	47.00	TON
401020048	PLANT MIX SURF-1/2 IN	10273.00	TON
401020300	HYDRATED LIME	144.00	TON
402020192	ASPHALT CEMENT PG 58V-34	598.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5710.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	634.00	TON
403010255	CRACK SEALING	11527.00	LB
403010257	CRACK FILLING-MASTIC	71525.00	LB
409000000	FINAL SWEEP AND BROOM	15.00	CRMI
409000010	COVER-TYPE 1	355174.00	SQYD
411010000	COLD MILLING	4078.00	SQYD
411011140	TRANSVERSE RUMBLE STRIPS	1.00	LS
552010160	BRIDGE DECK CRACK SEAL	1811.00	SQYD
606010140	GUARDRAIL END SECTION WIDENING	19.00	EACH
606010335	MASH W-BEAM TERMINAL SECTION	19.00	EACH
606010337	MGS GUARDRAIL/LONG POSTS	5421.00	LNFT
606010385	REMOVE GUARDRAIL	6265.00	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	300000.00	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	3.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	1.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.00	GAL
620013000	STRIPING-WHITE PAINT	1025.00	GAL
620013960	STRIPING-WHITE EPOXY	738.00	GAL
620014000	STRIPING-YELLOW PAINT	511.00	GAL
620014960	STRIPING-YELLOW EPOXY	373.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 10245000

**104 MUSSELHELL R - 10M SW MUSLSHLL STPB 9033(37) CONTRACT NO. 02923**

Bridge removal and replacement with approaches, riprap, and drainage on the Musselshell R-10M SW Musselshell project in Musselshell County. The project is located on Goffena Road southwest of Musselshell near RP 182 on US Highway 12, Musselshell County, Montana. The existing truss bridge is condemned.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE REPLACEMENT			
103500005	ESCROW OF BID DOCUMENTS	1.00	LS
104030010	MISCELLANEOUS WORK	10000.00	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.00	LS
105070000	CONTRACTOR SURVEY AND LAYOUT	1.00	LS
108000000	CRITICAL PATH SCHEDULE	1.00	LS
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
202020040	REMOVE STRUCTURE	1.00	EACH
203020310	SPECIAL BORROW-NEAT LINE	1161.00	CUYD
203020375	EMBANKMENT IN PLACE	10644.00	CUYD
203030130	REMOVE UNSTABLE ROCK	150.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	570.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
209010125	STRUCTURE EXCAVATION TYPE 2	127.00	CUYD
301020252	BRIDGE END BACKFILL-TYPE 1	1250.00	CUYD
301020340	CRUSHED AGGREGATE COURSE	709.00	CUYD
301020625	AGGREGATE TREATMENT	2193.00	SQYD
401020122	COMMERCIAL MIX-PG 58V-34	554.00	TON
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	102.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	350.00	GAL
551020035	CONCRETE-CLASS STRUCTURE	241.00	CUYD
551020036	CONCRETE-CLASS STRUCTURE LOW SLUMP	179.00	CUYD
552010140	TRANSVERSE DECK GROOVING	500.00	SQYD
553010157	PRESTRESSED BEAM-TYPE MTS-63	802.00	LNFT
555010100	REINFORCING STEEL	28626.00	LB
555010200	REINFORCING STEEL-EPOXY COATED	36903.00	LB
557010051	42 IN OPEN RAIL-BR-CSC	391.00	LNFT
557010056	42 IN OPEN RAIL PARAPET-BR-CSC	4.00	EACH
559040000	PILE DRILL AND SOCKET	116.00	LNFT
559040035	DYNAMIC LOAD TEST	3.00	EACH
559050115	FURN STEEL PILE-PIPE	67792.00	LB
559060115	DRIVE STEEL PILE	515.00	LNFT
559060200	PILE CUTTING SHOE	17.00	EACH
603010048	DRAINAGE PIPE 24 IN	162.00	LNFT
603015270	EMBANKMENT PROTECTOR 18 IN	62.00	LNFT
603587020	REMOVE PIPE CULVERT	56.00	LNFT
606010028	GUARDRAIL-OPTIONAL TERM SEC TL-2	4.00	EACH
606010330	MGS GUARDRAIL	50.00	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.00	EACH
607100152	FARM FENCE-TYPE F3M-32 IN WW	169.00	LNFT
607100252	FARM FENCE-TYPE F4M	319.00	LNFT
607100281	FARM FENCE-TYPE F5M	103.00	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	13.00	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	5.00	EACH
609010112	CURB 4 IN-CONCRETE	172.00	LNFT
610100101	SEEDING AREA NO 1	0.00	ACRE



610100102	SEEDING AREA NO 2	0.00	ACRE
610100103	SEEDING AREA NO 3	0.00	ACRE
610100555	CONDITION SEEDBED SURFACE	1.00	ACRE
610100560	RIPRAP REVEGETATION	414.00	SQYD
610100561	EROSION CONTROL BLANKET-LONG-TERM	367.00	SQYD
613100040	RIPRAP-CLASS 2 RANDOM	1840.00	CUYD
613300050	BANK PROTECTION-TYPE 3	9.00	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
619010090	SIGNS-ALUM REFL SHEET XI	34.00	SQFT
619010230	REMOVE SIGN	2.00	EACH
619010480	POLES-TREATED WOOD 4 IN	28.00	LNFT
619011040	DELINEATOR DES D	4.00	EACH
622011043	PERM EROSION CONTROL-HIGH SURV	2366.00	SQYD
623000190	RESET MAILBOX	2.00	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
Uniform No. 9777000

#### 105 SALTSE-LOZEAU IM STWD(905)

CONTRACT NO. 03923

The Saltese - Lozeau resurfacing project is on Interstate 90 (I-90) in Mineral County and has two different segments. The first segment begins approximately 1.0 miles east of the Henderson Interchange (Exit 22), at the west end of the bridge over the St. Regis River (RP 23.1), extends easterly for about 4.9 miles, and ends approximately 2.1 miles west of the Two-Mile Road Interchange (Exit 30) (RP 27.9). The second segment begins just east of the Dry Creek Interchange (Exit 43), at the west end of the bridge over the Clark Fork River (RP 43.5), extends easterly for about 10.1 miles, and ends about 1.8 miles west of the Lozeau Interchange (Exit 55) (RP 53.6). Scope includes crack sealing, mastic crack filling, seal & cover, fog seal, rumble strips, new pavement markings, and bridge deck crack sealing.

#### INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SEAL AND COVER & FOG SEAL		
104030010	MISCELLANEOUS WORK	50000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010015	AQUATIC RESOURCE MONITOR	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
402020320	EMULSIFIED ASPHALT-FOG SEAL	39579.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	941.00	TON
403010255	CRACK SEALING	59502.00	LB
409000020	COVER-TYPE 2	530192.00	SQYD
411011135	RUMBLE STRIPS	54.00	MILE
552010160	BRIDGE DECK CRACK SEAL	6049.00	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	300000.00	UNIT
618100000	SINGLE USE SIGNS	168.00	SQFT
618100005	PORTABLE VARIABLE MESSAGE SIGN	4.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	6.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	8.00	GAL
620013000	STRIPING-WHITE PAINT	975.00	GAL
620013960	STRIPING-WHITE EPOXY	1300.00	GAL

620014000	STRIPING-YELLOW PAINT	582.00	GAL
620014960	STRIPING-YELLOW EPOXY	775.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Missoula District Administrator.  
 Uniform No. 10231000

**106 S OF SPANISH CREEK - S (US-191) NH 50-2(87)61 CONTRACT NO. 04923**  
 Mill and overlay, seal and cover, bridge deck crack seal, signing upgrades, and pavement marking upgrades on the S of Spanish Creek - S (US-191) project in Gallatin County. The project is located on US-191 (Gallatin Road) south of Gallatin Gateway beginning at the Gallatin River bridge at RP 61.3 extending north approximately 3.7 miles to RP 65.0 near the junction of Storm Castle Road.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	- MILL, PMS OVERLAY, & SEAL & COVER		
104030010	MISCELLANEOUS WORK	30000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	58.00	MILE
401020045	PLANT MIX SURF-3/4 IN	11782.00	TON
401020300	HYDRATED LIME	165.00	TON
402020095	ASPHALT CEMENT PG 70-28	612.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	6420.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	106.00	TON
409000000	FINAL SWEEP AND BROOM	3.00	CRMI
409000020	COVER-TYPE 2	59324.00	SQYD
411010000	COLD MILLING	64102.00	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	3.00	MILE
552010160	BRIDGE DECK CRACK SEAL	731.00	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	230000.00	UNIT
618100005	PORTABLE VARIABLE MESSAGE SIGN	4.00	EACH
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	40.00	DAY
619010090	SIGNS-ALUM REFL SHEET XI	378.00	SQFT
619010230	REMOVE SIGN	35.00	EACH
619010240	REMOVE SIGN-GUIDE	13.00	EACH
619010310	POSTS-STEEL U SIGN	88.00	LB
619010480	POLES-TREATED WOOD 4 IN	24.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	84.00	LNFT
619011001	DELINEATOR SNOWPOLE-DES A	159.00	EACH
619011002	DELINEATOR SNOWPOLE-DES F	36.00	EACH
619011040	DELINEATOR DES D	10.00	EACH
620012955	TEMPORARY STRIPING	76302.00	LNFT
620013000	STRIPING-WHITE PAINT	262.00	GAL
620013960	STRIPING-WHITE EPOXY	174.00	GAL
620014000	STRIPING-YELLOW PAINT	236.00	GAL
620014960	STRIPING-YELLOW EPOXY	157.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 9472000

**107 YORK ROAD - HELENA (S-280) STPS 280-1(35)2 CONTRACT NO. 05923**  
 The York Road - Helena (S-280) project is a full width scrub seal topped with a 0.15-ft PMS overlay and seal and cover on Secondary 280 between RP 1.0 and RP 4.4 located in Lewis & Clark County. Signing, centerline rumble strips, and pavement markings will be replaced.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SEAL & COVER		
104030010	MISCELLANEOUS WORK	25000.00	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020000	GRADER-MOTOR	10.00	HOURL
210020170	TEST TRAILER-TRANSPORT,SETUP	92.00	MILE
401020048	PLANT MIX SURF-1/2 IN	8471.00	TON
401020300	HYDRATED LIME	97.00	TON
402020192	ASPHALT CEMENT PG 58V-34	440.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	3644.00	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	4438.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	104.00	TON
402020377	SCRUB SEAL EMULSION	108.00	TON
409000000	FINAL SWEEP AND BROOM	3.00	CRMI
409000010	COVER-TYPE 1	117600.00	SQYD
411010000	COLD MILLING	1378.00	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	2.00	MILE
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	1.00	MILE
618030005	TRAFFIC CONTROL DEVICES CB	160000.00	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.00	EACH
619010090	SIGNS-ALUM REFL SHEET XI	316.00	SQFT
619010230	REMOVE SIGN	35.00	EACH
619010300	POSTS-TUBULAR STEEL	220.00	LB
619010310	POSTS-STEEL U SIGN	57.00	LB
619010480	POLES-TREATED WOOD 4 IN	232.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	80.00	LNFT
619010742	FRANG SIGN POST BKWY-3.5 IN RD	2.00	EACH
619011010	DELINEATOR DES A	88.00	EACH
619011040	DELINEATOR DES D	26.00	EACH
619011060	DELINEATOR DES F	9.00	EACH
620013000	STRIPING-WHITE PAINT	93.00	GAL
620013960	STRIPING-WHITE EPOXY	124.00	GAL
620014000	STRIPING-YELLOW PAINT	66.00	GAL
620014960	STRIPING-YELLOW EPOXY	93.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 10284000

**108 SPOKANE CREEK ROAD (S-284) STPS 284-2(22)1**

**CONTRACT NO. 06923**

This project is located on Secondary Highway 284, in Lewis & Clark and Jefferson Counties. This project to scrub seal Spokane Creek Road from the connection at the intersection with Highway 12 and continue North to its intersection with Canyon Ferry Road. The project continues east on Canyon Ferry Road past the S-curves near mile marker 7. The deck of the bridge over the Helena Valley Canal will be sealed. New signing and pavement markings will be included.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 -	SCRUB SEAL, MASTIC FILL/SEAL, FOG SEAL		
104030010	MISCELLANEOUS WORK	25000.00	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
402020320	EMULSIFIED ASPHALT-FOG SEAL	8971.00	GAL
402020377	SCRUB SEAL EMULSION	213.00	TON
403010257	CRACK FILLING-MASTIC	11520.00	LB
409000010	COVER-TYPE 1	118568.00	SQYD
552010160	BRIDGE DECK CRACK SEAL	249.00	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	125000.00	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	3.00	EACH
619010062	SIGNS-ALUM SHEET INCR XI	116.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1005.00	SQFT
619010230	REMOVE SIGN	109.00	EACH
619010240	REMOVE SIGN-GUIDE	4.00	EACH
619010300	POSTS-TUBULAR STEEL	123.00	LB
619010310	POSTS-STEEL U SIGN	90.00	LB
619010480	POLES-TREATED WOOD 4 IN	304.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	188.00	LNFT
619010744	FRANG SIGN POST BKWY-4 IN RD	1.00	EACH
619011010	DELINEATOR DES A	202.00	EACH
619011040	DELINEATOR DES D	36.00	EACH
619011060	DELINEATOR DES F	126.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	5.00	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	4.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	6.00	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	5.00	GAL
620013000	STRIPING-WHITE PAINT	259.00	GAL
620013960	STRIPING-WHITE EPOXY	345.00	GAL
620014000	STRIPING-YELLOW PAINT	179.00	GAL
620014960	STRIPING-YELLOW EPOXY	252.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are %.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.  
Uniform No. 10286000

INVITATION FOR BIDS  
LETTING OF OCTOBER 12, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on . All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION  
Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

New construction of an arterial roadway and bridge structure to include grading, gravel, railroad crossing structure, drainage, plant mix bituminous surfacing, guardrail, signing, pavement markings, and other improvements as part of the BBP - RR O'Pass project in Yellowstone County. The project is located northeast of the city of Billings, Yellowstone County, Montana.

## INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	- NEW CONSTRUCTION - BBP RR O'PASS		
103000000	TRAINING PROGRAM	500.00	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.00	LS
104030010	MISCELLANEOUS WORK	50000.00	UNIT
108000000	CRITICAL PATH SCHEDULE	1.00	LS
109200005	MOBILIZATION	1.00	LS
203020100	EXCAVATION-UNCLASSIFIED	492.00	CUYD
203020200	EXCAVATION-UNCLASS BORROW	84026.00	CUYD
203020310	SPECIAL BORROW-NEAT LINE	99886.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	472.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
209010125	STRUCTURE EXCAVATION TYPE 2	390.00	CUYD
209010150	SHORING AND CRIBS	1.00	LS
209010160	TEMPORARY SHORING	1.00	LS
212000000	OBLITERATE ROADWAY	5.00	STA
301020252	BRIDGE END BACKFILL-TYPE 1	829.00	CUYD
301020268	TRAFFIC GRAVEL	322.00	CUYD
301020340	CRUSHED AGGREGATE COURSE	10374.00	CUYD
301020625	AGGREGATE TREATMENT	12478.00	SQYD
401020045	PLANT MIX SURF-3/4 IN	3623.00	TON
401020046	PLANT MIX BIT SURF-MISC	877.00	TON
401020300	HYDRATED LIME	63.00	TON
402020095	ASPHALT CEMENT PG 70-28	242.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	2102.00	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	777.00	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	18.00	TON
409000000	FINAL SWEEP AND BROOM	0.00	CRMI
409000010	COVER-TYPE 1	10363.00	SQYD
551020035	CONCRETE-CLASS STRUCTURE	709.00	CUYD
551020036	CONCRETE-CLASS STRUCTURE LOW SLUMP	935.00	CUYD
552010140	TRANSVERSE DECK GROOVING	3090.00	SQYD
552010160	BRIDGE DECK CRACK SEAL	3256.00	SQYD
552011020	EXPANSION JOINT-MODULAR	96.00	LNFT
555010100	REINFORCING STEEL	103575.00	LB
555010200	REINFORCING STEEL-EPOXY COATED	321497.00	LB
556010011	STRUCTURAL STEEL - GIRDER	1.00	LS
557010095	GUARD FENCE	1461.00	LNFT
559010202	RE-DRIVE TEST PILE	2.00	EACH
559040035	DYNAMIC LOAD TEST	6.00	EACH
559050117	FURN STEEL PILE-HP	417992.00	LB
559060115	DRIVE STEEL PILE	4549.00	LNFT
559060300	PILE DRIVING POINT	88.00	EACH
565000010	ELASTOMERIC BEARING DEVICES	24.00	EACH
603012530	RCP 18 IN	86.00	LNFT
603012960	RCP IRR 42 IN	202.00	LNFT
603015270	EMBANKMENT PROTECTOR 18 IN	402.00	LNFT
605000093	36 IN SS CONCRETE BARRIER RAIL-BR-CSC	1521.00	LNFT
606010028	GUARDRAIL-OPTIONAL TERM SEC TL-2	4.00	EACH
606010330	MGS GUARDRAIL	875.00	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.00	EACH
607100099	FARM FENCE-TYPE F2W F2M-39 IN WW	2115.00	LNFT
607100252	FARM FENCE-TYPE F4M	1567.00	LNFT
607100362	FARM FENCE-PANEL/SINGLE FM	5.00	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	9.00	EACH
607100440	FARM GATE-METAL-TYPE G-3	16.00	LNFT
607100551	FENCE-TEMPORARY	2131.00	LNFT

607100720	DEADMAN	2.00	EACH
609010112	CURB 4 IN-CONCRETE	389.00	LNFT
610010105	TOPSOIL-PLACE	3315.00	CUYD
610100101	SEEDING AREA NO 1	12.00	ACRE
610100102	SEEDING AREA NO 2	1.00	ACRE
610100103	SEEDING AREA NO 3	1.00	ACRE
610100555	CONDITION SEEDBED SURFACE	13.00	ACRE
610100565	EROSION CONTROL BLANKET-HIGH-PERFORM	58.00	SQYD
610220050	MULCH-COMPOST	1.00	ACRE
613300050	BANK PROTECTION-TYPE 3	15.00	CUYD
613400010	SLOPE PROTECTION-CONCRETE	633.00	SQYD
617000000	FOUNDATION-CONCRETE	0.00	CUYD
617523010	SOL SIG-TRAF 1 COLOR-1 WAY 12	1.00	EACH
617673200	SIG STANDARD TYPE 1-200	1.00	EACH
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
619010062	SIGNS-ALUM SHEET INCR XI	184.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	116.00	SQFT
619010320	POSTS-STEEL STRUCTURAL SIGN	1227.00	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	97.00	LB
619010480	POLES-TREATED WOOD 4 IN	168.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	30.00	LNFT
619010640	BARRICADES-TYPE B(3)	24.00	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	12.00	EACH
619011010	DELINEATOR DES A	15.00	EACH
619011030	DELINEATOR DES C	8.00	EACH
619011040	DELINEATOR DES D	2.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.00	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	1.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.00	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	1.00	GAL
620012955	TEMPORARY STRIPING	2387.00	LNFT
620013000	STRIPING-WHITE PAINT	30.00	GAL
620013960	STRIPING-WHITE EPOXY	20.00	GAL
620014000	STRIPING-YELLOW PAINT	40.00	GAL
620014960	STRIPING-YELLOW EPOXY	26.00	GAL
622010082	GEOGRID - UNIAXIAL	34588.00	SQYD
622011084	GEOTEXTILE STABILIZATION	34423.00	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
Uniform No. 4199005

**102 BOZEMAN-EAST IM 90-6(165)307**

**CONTRACT NO. 04R23**

Mill and overlay, seal and cover, guardrail, bridge rehabilitation, crossovers, rumble strips, pavement markings, delineation, and signing on the Bozeman - East project located in Gallatin County. The project begins at the Rouse Avenue/Montana Rail Link Overpass (RP 307.4) and extends approximately 3.4 miles east along Interstate 90 to the Fort Ellis Overpass (RP 311.0).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	COLD MILL, PLANT MIX-SURF, SEAL & COVER, MINOR BRIDGE REHAB		
104030010	MISCELLANEOUS WORK	30000.00	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.00	LS

104030037	MISCELLANEOUS ITEMS-SQYD	367.00	SQYD
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	20.00	MILE
401020045	PLANT MIX SURF-3/4 IN	21648.00	TON
401020300	HYDRATED LIME	303.00	TON
402020095	ASPHALT CEMENT PG 70-28	1169.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	8782.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	288.00	TON
409000000	FINAL SWEEP AND BROOM	7.00	CRMI
409000020	COVER-TYPE 2	162255.00	SQYD
411010000	COLD MILLING	174542.00	SQYD
411011135	RUMBLE STRIPS	12.00	MILE
552010160	BRIDGE DECK CRACK SEAL	9751.00	SQYD
552011010	EXPANSION JOINT STRIP SEAL	152.00	LNFT
552011120	JOINT SEALS-POLYURETHANE	188.00	LNFT
557010505	REVISE BRIDGE RAIL-THRIE BEAM	2056.00	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	40.00	SQYD
605000040	REVISE CONCRETE BARRIER RAIL-BR	582.00	LNFT
605000045	REVISE CONC BARRIER RAIL END-BR	8.00	EACH
606010020	GUARDRAIL-TEMPORARY	200.00	LNFT
606010022	TEMP GD RAIL-STL/BR APPR-TY 3	2.00	EACH
606010024	TEMP OPTIONAL TERM SECT	6.00	EACH
606010125	REMOVE AND SALVAGE CABLE GUARDRAIL	1774.00	LNFT
606010130	RESET CABLE GUARDRAIL	1774.00	LNFT
606010140	GUARDRAIL END SECTION WIDENING	38.00	EACH
606010330	MGS GUARDRAIL	16825.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	32.00	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	32.00	EACH
606010385	REMOVE GUARDRAIL	18329.00	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	4.00	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	4.00	EACH
607100009	FENCE - WILDLIFE FRIENDLY FW	297.00	LNFT
607100013	FENCE - WILDLIFE	3456.00	LNFT
607100014	FENCE - PANEL/SINGLE - WILDLIFE	7.00	EACH
607100015	FENCE - PANEL/DOUBLE - WILDLIFE	15.00	EACH
607100020	WILDLIFE JUMPOUT	2.00	EACH
607100455	GATE-SPECIAL DESIGN	4.00	LNFT
609010112	CURB 4 IN-CONCRETE	200.00	LNFT
610100559	REVEGETATION	1.00	LS
617000000	FOUNDATION-CONCRETE	11.00	CUYD
618030005	TRAFFIC CONTROL DEVICES CB	80000.00	UNIT
618030180	TRAFFIC CONTROL-CROSSOVER	4.00	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	2.00	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	2.00	EACH
618030280	CROSSOVER RECLAMATION	2.00	EACH
618100000	SINGLE USE SIGNS	471.00	SQFT
618100005	PORTABLE VARIABLE MESSAGE SIGN	4.00	EACH
618190100	TEMPORARY BARRIER RAIL	2610.00	LNFT
618190110	RESET TEMP BARRIER RAIL	2610.00	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	2859.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1130.00	SQFT
619010230	REMOVE SIGN	84.00	EACH
619010240	REMOVE SIGN-GUIDE	32.00	EACH
619010300	POSTS-TUBULAR STEEL	1460.00	LB
619010310	POSTS-STEEL U SIGN	231.00	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	3084.00	LB
619010480	POLES-TREATED WOOD 4 IN	112.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	262.00	LNFT
619010720	FRANG SIGN POST BKWY-S3 X 5.7	4.00	EACH
619010722	FRANG SIGN POST BKWY-S4 X 7.7	6.00	EACH
619010730	FRANG SIGN POST BKWY-W8 X 18	3.00	EACH
619010732	FRANG SIGN POST BKWY-W8 X 24	2.00	EACH
619010740	FRANG SIGN POST BKWY-3 IN RD	6.00	EACH



619010742	FRANG SIGN POST BKWY-3.5 IN RD	6.00	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD	1.00	EACH
619011010	DELINEATOR DES A	146.00	EACH
619011020	DELINEATOR DES B	25.00	EACH
619011040	DELINEATOR DES D	10.00	EACH
619011070	DELINEATOR DES G	55.00	EACH
619011080	DELINEATOR DES H	125.00	EACH
619011085	DELINEATOR DES BJ	63.00	EACH
619011087	DELINEATOR DES GJ	41.00	EACH
620010301	CURB MARKING-YELLOW EPOXY	32.00	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	9.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	6.00	GAL
620012955	TEMPORARY STRIPING	22224.00	LNFT
620013000	STRIPING-WHITE PAINT	408.00	GAL
620013960	STRIPING-WHITE EPOXY	272.00	GAL
620014000	STRIPING-YELLOW PAINT	308.00	GAL
620014960	STRIPING-YELLOW EPOXY	206.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 10001000

**103                    FORSYTH - EAST & WEST STPP 95-1(4)0                    CONTRACT NO. 03A23**

The Forsyth - East & West project is a 1.5-mile-long project along Front Street in Forsyth between the intersection with 18th Avenue at RP 0.1 and the intersection with US Highway 12 at RP 1.6 in Rosebud County. Work includes rehabilitation of the existing plant mix surfacing, overlay, new curb and gutter, drainage and storm drain improvements, Americans with Disabilities Act (ADA) upgrades to sidewalk and curb ramps and upgraded signing and pavement markings.

INVOLVING  
 -----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	GRADE, GRAVEL, PLANT MIX, SEAL & COVER		
103000000	TRAINING PROGRAM	500.00	HOURL
104030010	MISCELLANEOUS WORK	20000.00	UNIT
109200005	MOBILIZATION	1.00	LS
202020353	REMOVE CONCRETE	13.00	SQYD
203020100	EXCAVATION-UNCLASSIFIED	9684.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	1885.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
301020340	CRUSHED AGGREGATE COURSE	431.00	CUYD
301020416	SHOULDER GRAVEL	423.00	CUYD
301020625	AGGREGATE TREATMENT	28285.00	SQYD
302000000	PAVEMENT PULVERIZATION	33640.00	SQYD
401020021	COMMERCIAL MIX-PG 70-28	7512.00	TON
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	2459.00	TON
401020064	COMMERCIAL PLANT MIX-MISC	1035.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5847.00	GAL
411010000	COLD MILLING	862.00	SQYD
601011920	INSULATION	486.00	SQFT
603000078	ADJUST CURB BOX	1.00	EACH
603000085	ADJUST WATER MAIN	1.00	EACH
603010048	DRAINAGE PIPE 24 IN	72.00	LNFT
603012530	RCP 18 IN	130.00	LNFT

603012555	RCP 24 IN	86.00	LNFT
603013190	RCPA 18 IN EQ DIA	42.00	LNFT
603014242	ADJUST VALVE BOX	13.00	EACH
603015270	EMBANKMENT PROTECTOR 18 IN	244.00	LNFT
603016003	SPECIAL INSTALLATION OF PIPE	335.00	LNFT
603016033	STEEL CASING 8 IN	52.00	LNFT
603016056	STEEL CASING 36 IN	343.00	LNFT
603016061	STEEL CASING 12 IN	245.00	LNFT
603017040	STORM DRAIN PIPE-12 IN	376.00	LNFT
603017045	STORM DRAIN PIPE-15 IN	265.00	LNFT
603017050	STORM DRAIN PIPE-18 IN	561.00	LNFT
603017060	STORM DRAIN PIPE-24 IN	4424.00	LNFT
603587010	REMOVE EMBANKMENT PROTECTOR	209.00	LNFT
603587020	REMOVE PIPE CULVERT	258.00	LNFT
603587030	REMOVE STORM DRAIN	841.00	LNFT
604000100	ADJUST MANHOLE	7.00	EACH
604000140	REMOVE DROP INLET	6.00	EACH
604010184	CONCRETE APRON	11.00	EACH
604010300	INLET STRUCTURE BASE 30 IN (760 MM)	1.00	EACH
604010301	INLET STRUCTURE BASE 32 IN (810 MM)	11.00	EACH
604010302	MANHOLE STRUCTURE BASE 48 IN (1220 MM)	8.00	EACH
604010304	MANHOLE STRUCTURE BASE 60 IN	12.00	EACH
604010354	ADDITIONAL BARREL 60 IN	88.00	LNFT
604010660	MANHOLE LID AND FRAME	20.00	EACH
604010662	DROP INLET FRAME AND GRATE	12.00	EACH
606010330	MGS GUARDRAIL	87.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	1.00	EACH
606010385	REMOVE GUARDRAIL	412.00	LNFT
608010020	SIDEWALK-CONCRETE 4 IN	934.00	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	729.00	SQYD
608010110	CONCRETE 6 IN	120.00	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	20.00	SQYD
609010112	CURB 4 IN-CONCRETE	67.00	LNFT
609010160	GUTTER-CONC VALLEY	128.00	SQYD
609010200	CURB AND GUTTER-CONC	4819.00	LNFT
610100101	SEEDING AREA NO 1	5.00	ACRE
610100102	SEEDING AREA NO 2	0.00	ACRE
610100103	SEEDING AREA NO 3	4.00	ACRE
610100126	SEEDING-LAWN	0.00	ACRE
610100323	FERTILIZER-LAWN	0.00	ACRE
610100326	FERTILIZING AREA NO 1	5.00	ACRE
610100327	FERTILIZING AREA NO 2	0.00	ACRE
610100555	CONDITION SEEDBED SURFACE	10.00	ACRE
610220100	MULCH	0.00	ACRE
613520010	VEGETATED CONCRETE BLOCK MAT	13.00	SQYD
615010120	IRRIGATION CANAL GATE-24 IN	1.00	EACH
615010580	TRASH GUARD	3.00	EACH
618030005	TRAFFIC CONTROL DEVICES CB	50000.00	UNIT
619010062	SIGNS-ALUM SHEET INCR XI	15.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	318.00	SQFT
619010200	RESET SIGNS	1.00	EACH
619010230	REMOVE SIGN	53.00	EACH
619010240	REMOVE SIGN-GUIDE	4.00	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	1748.00	LB
619010480	POLES-TREATED WOOD 4 IN	148.00	LNFT
620010301	CURB MARKING-YELLOW EPOXY	20.00	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	4.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	5.00	GAL
620012955	TEMPORARY STRIPING	43723.00	LNFT
620013000	STRIPING-WHITE PAINT	55.00	GAL
620013960	STRIPING-WHITE EPOXY	73.00	GAL
620014000	STRIPING-YELLOW PAINT	55.00	GAL
620014960	STRIPING-YELLOW EPOXY	73.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Glendive District Administrator.  
 Uniform No. 9027000

**104 BR PRES COLUMBUS JOLIET AREA STPB STWD(665) CONTRACT NO. 06R23**

Rehabilitation of four (4) bridges on the Br Pres Columbus Joliet Area project located at four (4) sites near the communities of Joliet (Carbon County), Columbus (Stillwater County), Billings (Yellowstone County), and Huntley (Yellowstone County). The scope of work varies for each structure, but generally involves preservation work including bridge deck milling and overlay work, bridge rail repairs or replacement, pedestrian rail replacement, expansion joint repairs, guard angle removal, roadway approach work, guardrail replacement, barrier end repairs and substructure repair.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE REHAB (4 BRIDGES)			
103500005	ESCROW OF BID DOCUMENTS	1.00	LS
104030010	MISCELLANEOUS WORK	50000.00	UNIT
104030045	MISCELLANEOUS ITEMS-EACH	19.00	EACH
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
202020058	REMOVE GUARD ANGLE	613.00	LNFT
202020097	REMOVE BRIDGE APPROACH SLAB	2.00	EACH
203020100	EXCAVATION-UNCLASSIFIED	1581.00	CUYD
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
209010160	TEMPORARY SHORING	1.00	LS
301020252	BRIDGE END BACKFILL-TYPE 1	606.00	CUYD
301020340	CRUSHED AGGREGATE COURSE	487.00	CUYD
301020625	AGGREGATE TREATMENT	1474.00	SQYD
401020060	COMMERCIAL MIX-3/8 IN-PG 70-28	750.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	273.00	GAL
409000000	FINAL SWEEP AND BROOM	0.00	CRMI
411010000	COLD MILLING	3460.00	SQYD
411011135	RUMBLE STRIPS	0.00	MILE
552010060	REPAIR STRUCTURE	1.00	LS
552010140	TRANSVERSE DECK GROOVING	5955.00	SQYD
552010160	BRIDGE DECK CRACK SEAL	6835.00	SQYD
552010805	MODIFY BRIDGE APPROACH SLAB	2.00	EACH
552011010	EXPANSION JOINT STRIP SEAL	59.00	LNFT
552011040	REFURBISH EXPANSION JOINT	90.00	LNFT
552011120	JOINT SEALS-POLYURETHANE	84.00	LNFT
555010200	REINFORCING STEEL-EPOXY COATED	17929.00	LB
556000100	PAINT EXISTING STRUCTURAL STEEL	20.00	SQYD
557010105	PEDESTRIAN RAIL	869.00	LNFT
557010110	HAND RAIL	865.00	LNFT
557010606	REMOVE BRIDGE RAIL	1738.00	LNFT
561010525	EXPANSION JOINT-PRECOMPRESSED	87.00	LNFT
561020110	BRIDGE DECK MILLING	6278.00	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	130.00	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	45.00	SQYD
563000000	CONCRETE-CLASS OVERLAY	423.00	CUYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.00	UNIT
605000040	REVISE CONCRETE BARRIER RAIL-BR	1197.00	LNFT
605000092	36 IN SS CONCRETE BARRIER RAIL-BR	869.00	LNFT
606010330	MGS GUARDRAIL	256.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	2.00	EACH
606010337	MGS GUARDRAIL/LONG POSTS	625.00	LNFT

606010342	MASH THRIE BEAM BR APPRCH SECTION	6.00	EACH
606010385	REMOVE GUARDRAIL	585.00	LNFT
606011288	RESET BRIDGE APPROACH SECTION	2.00	EACH
606011300	RESET OPTIONAL TERMINAL SECT	2.00	EACH
606011503	RESET TEMP IMPACT ATTENUATOR	8.00	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	8.00	EACH
607150015	REMOVE FENCE	242.00	LNFT
609010112	CURB 4 IN-CONCRETE	180.00	LNFT
610100559	REVEGETATION	1.00	LS
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
618100000	SINGLE USE SIGNS	378.00	SQFT
618100008	TRAFFIC ACTUATED TEMPORARY SIGNALS	1.00	LS
618190100	TEMPORARY BARRIER RAIL	2810.00	LNFT
618190110	RESET TEMP BARRIER RAIL	2810.00	LNFT
619010090	SIGNS-ALUM REFL SHEET XI	21.00	SQFT
619010230	REMOVE SIGN	4.00	EACH
619010310	POSTS-STEEL U SIGN	42.00	LB
619010480	POLES-TREATED WOOD 4 IN	48.00	LNFT
620013000	STRIPING-WHITE PAINT	19.00	GAL
620013960	STRIPING-WHITE EPOXY	25.00	GAL
620014000	STRIPING-YELLOW PAINT	19.00	GAL
620014960	STRIPING-YELLOW EPOXY	25.00	GAL
622011084	GEOTEXTILE STABILIZATION	994.00	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
Uniform No. 9552001

**105 NORTH OF ROCKER INTERCHANGE - NORTH STPS 276-1(13)4 CONTRACT NO. 14823**

Replacement of two bridges with RCB culverts, seal and cover, pavement markings, and signing on the North of Rocker Interchange - North project located in Silver Bow County. The project is located along Secondary Route 276 (Browns Gulch Rd), beginning approximately 3.5 miles north of Rocker at RP 3.7, and extending approximately 0.9 miles northwest to RP 4.6, just west of the Hail Columbia intersection.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	- RECONSTRUCTION		
104030010	MISCELLANEOUS WORK	30000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
202020041	REMOVE STRUCTURE	1.00	LS
203020100	EXCAVATION-UNCLASSIFIED	60445.00	CUYD
203020175	EXCAVATION-UNCLASS CHANNEL	160.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	3787.00	CUYD
204010185	BLASTING CONSULTANT	1.00	LS
204010215	DRILL PRESPLITTING HOLES	7708.00	LNFT
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
208010500	BIOENGINEERED BANK	1.00	LS
210020170	TEST TRAILER-TRANSPORT, SETUP	20.00	MILE
212000000	OBLITERATE ROADWAY	14.00	STA
301020268	TRAFFIC GRAVEL	1831.00	CUYD

301020340	CRUSHED AGGREGATE COURSE	5264.00	CUYD
301020450	SPECIAL BACKFILL	1488.00	CUYD
301020625	AGGREGATE TREATMENT	22357.00	SQYD
401020023	COMMERCIAL MIX-PG 58-28	3506.00	TON
401020064	COMMERCIAL PLANT MIX-MISC	227.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	2002.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	33.00	TON
409000000	FINAL SWEEP AND BROOM	1.00	CRMI
409000010	COVER-TYPE 1	18904.00	SQYD
551020030	CONCRETE-CLASS GENERAL	18.00	CUYD
603000050	GRANULAR BEDDING MATERIAL	124.00	CUYD
603000060	FOUNDATION MATERIAL	250.00	CUYD
603010040	DRAINAGE PIPE 18 IN	232.00	LNFT
603010048	DRAINAGE PIPE 24 IN	536.00	LNFT
603013395	REIN CONC BOX 17 X 7	90.00	LNFT
603013436	REIN CONC BOX 10 X 7	92.00	LNFT
603013459	PIPE-PVC 4 IN	95.00	LNFT
603013462	PIPE-PVC 6 IN	215.00	LNFT
603587020	REMOVE PIPE CULVERT	190.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	4.00	EACH
606010337	MGS GUARDRAIL/LONG POSTS	1025.00	LNFT
607100012	FENCE - WILDLIFE FRIENDLY FM	1514.00	LNFT
607100114	FARM FENCE-TYPE F2W-32 IN WW	810.00	LNFT
607100147	FARM FENCE-TYPE F2M-32 IN WW	4713.00	LNFT
607100259	FARM FENCE-TYPE F5W	3939.00	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	45.00	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	70.00	EACH
607100430	FARM GATE-WIRE-TYPE G-2	150.00	LNFT
607100440	FARM GATE-METAL-TYPE G-3	104.00	LNFT
607100551	FENCE-TEMPORARY	1550.00	LNFT
607100720	DEADMAN	15.00	EACH
610100101	SEEDING AREA NO 1	12.00	ACRE
610100102	SEEDING AREA NO 2	2.00	ACRE
610100103	SEEDING AREA NO 3	7.00	ACRE
610100326	FERTILIZING AREA NO 1	12.00	ACRE
610100327	FERTILIZING AREA NO 2	2.00	ACRE
610100555	CONDITION SEEDBED SURFACE	20.00	ACRE
610220050	MULCH-COMPOST	2.00	ACRE
613100090	CULVERT INFILL	140.00	CUYD
613300065	ROCK FILL	15474.00	CUYD
618030005	TRAFFIC CONTROL DEVICES CB	275000.00	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	1.00	EACH
619010090	SIGNS-ALUM REFL SHEET XI	24.00	SQFT
619010180	HISTORICAL MARKER	2.00	EACH
619010230	REMOVE SIGN	7.00	EACH
619010480	POLES-TREATED WOOD 4 IN	28.00	LNFT
619011010	DELINEATOR DES A	61.00	EACH
619011040	DELINEATOR DES D	2.00	EACH
619011060	DELINEATOR DES F	61.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	4.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.00	GAL
620012955	TEMPORARY STRIPING	10300.00	LNFT
620013000	STRIPING-WHITE PAINT	80.00	GAL
620013960	STRIPING-WHITE EPOXY	21.00	GAL
620014000	STRIPING-YELLOW PAINT	128.00	GAL
620014960	STRIPING-YELLOW EPOXY	42.00	GAL
622011084	GEOTEXTILE STABILIZATION	841.00	SQYD
623000155	MAILBOX	5.00	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

**106 CYR BR REHAB - 3M W ALBERTON STPB 31170(2)  
RRXING - DAIGLE LN RRP-L-RRS 31(46)**

**CONTRACT NO. 01A23**

STPB 31170(2) The Cyr Bridge Rehab - 3M W Alberton project will rehabilitate the existing Cyr bridge, replace the bridge rail, install new approach guardrail, reconstruct the roadway (200 ft. from the west bridge end and 150 ft. from the east bridge end), and construct a historical turnout with a historical marker on the northeast corner of the bridge. The project is located on Fish Creek Rd/Old MT-10 (X-31170) in Mineral County, approximately 3 miles west of Alberton from RP 0.0 to 0.2.

RRP-L-RRS 31(46) The RR Xing - Daigle Ln project will improve the safety at the railroad crossing to include railroad crossing signals and a new crossing surface to allow for two-way travel. The project is located on Daigle Ln (L-31-561N) in Mineral County, approximately 3 miles west of Alberton from RP 0.0 to 0.1.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - CYR BR REHAB & RRXING-DAIGLE LN (TIED)			
103000000	TRAINING PROGRAM	500.00	HOURL
104030010	MISCELLANEOUS WORK	50000.00	UNIT
104030035	MISCELLANEOUS ITEMS-REPAIR	1.00	LS
104030037	MISCELLANEOUS ITEMS-SQYD	250.00	SQYD
104030040	MISCELLANEOUS ITEMS-SQFT	25.00	SQFT
104030045	MISCELLANEOUS ITEMS-EACH	1.00	EACH
104030065	MISCELLANEOUS ITEMS A-LNFT	350.00	LNFT
108000000	CRITICAL PATH SCHEDULE	1.00	LS
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
203020100	EXCAVATION-UNCLASSIFIED	748.00	CUYD
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
301020340	CRUSHED AGGREGATE COURSE	272.00	CUYD
301020625	AGGREGATE TREATMENT	1155.00	SQYD
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	463.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	235.00	GAL
411010000	COLD MILLING	612.00	SQYD
552010060	REPAIR STRUCTURE	1.00	LS
552010160	BRIDGE DECK CRACK SEAL	1381.00	SQYD
555010100	REINFORCING STEEL	236.00	LB
556010010	STRUCTURAL STEEL - MISC	1.00	LS
557010110	HAND RAIL	1062.00	LNFT
557010537	REVISE BRIDGE RAIL-W830	1074.00	LNFT
557010606	REMOVE BRIDGE RAIL	1074.00	LNFT
561010525	EXPANSION JOINT-PRECOMPRESSED	57.00	LNFT
561020110	BRIDGE DECK MILLING	21.00	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	50.00	SQYD
563000010	CONCRETE-CLASS OVERLAY	21.00	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.00	UNIT
606010037	MASH BOX BEAM TERMINAL - MBEAT	4.00	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	54.00	LNFT
606010266	GRD RL-BOX BEAM/BR APP-SEC TYPE 2	4.00	EACH
607100149	FARM FENCE-TYPE F3W-32 IN WW	117.00	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	1.00	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	1.00	EACH
610100559	REVEGETATION	1.00	LS
613100030	RIPRAP-CLASS 1 RANDOM	2.00	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
618100005	PORTABLE VARIABLE MESSAGE SIGN	4.00	EACH
619010090	SIGNS-ALUM REFL SHEET XI	40.00	SQFT

619010180	HISTORICAL MARKER	1.00	EACH
619010230	REMOVE SIGN	12.00	EACH
619010480	POLES-TREATED WOOD 4 IN	86.00	LNFT
619011040	DELINEATOR DES D	4.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.00	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	2.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	3.00	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	3.00	GAL
620013000	STRIPING-WHITE PAINT	2.00	GAL
620013960	STRIPING-WHITE EPOXY	3.00	GAL
620014000	STRIPING-YELLOW PAINT	5.00	GAL
620014960	STRIPING-YELLOW EPOXY	7.00	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	1139.00	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
Uniform No. 9524000, 9209000

**107 HAPPY'S INN - WEST NH 1-1(118)69**

**CONTRACT NO. 05R23**

This pavement preservation project on Highway 2 in Lincoln County near Happy's Inn, starts at reference post 69 and extends east to reference post 76.3. The travel lanes will receive cold milling and plant mix surfacing fill, followed by a full width seal & cover and fog seal. Other work includes rumble strips, new signing and pavement markings.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO.	0001 - SEAL & COVER		
104030010	MISCELLANEOUS WORK	10000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	100.00	MILE
401020048	PLANT MIX SURF-1/2 IN	6236.00	TON
401020300	HYDRATED LIME	87.00	TON
402020192	ASPHALT CEMENT PG 58V-34	381.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	3315.00	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	12690.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	303.00	TON
403010255	CRACK SEALING	3080.00	LB
403010257	CRACK FILLING-MASTIC	2210.00	LB
409000020	COVER-TYPE 2	170733.00	SQYD
411010000	COLD MILLING	64453.00	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	4.00	MILE
411011135	RUMBLE STRIPS	14.00	MILE
552010160	BRIDGE DECK CRACK SEAL	334.00	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	200000.00	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.00	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.00	EACH
619010062	SIGNS-ALUM SHEET INCR XI	150.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	340.00	SQFT
619010200	RESET SIGNS	5.00	EACH
619010230	REMOVE SIGN	49.00	EACH
619010240	REMOVE SIGN-GUIDE	7.00	EACH

619010310	POSTS-STEEL U SIGN	140.00	LB
619010480	POLES-TREATED WOOD 4 IN	450.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	204.00	LNFT
619011010	DELINEATOR DES A	126.00	EACH
619011040	DELINEATOR DES D	44.00	EACH
619011060	DELINEATOR DES F	149.00	EACH
620012955	TEMPORARY STRIPING	38570.00	LNFT
620013000	STRIPING-WHITE PAINT	536.00	GAL
620013960	STRIPING-WHITE EPOXY	357.00	GAL
620014000	STRIPING-YELLOW PAINT	280.00	GAL
620014960	STRIPING-YELLOW EPOXY	187.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
 Uniform No. 10232000

**108 SF 159 NE PARK CITY SHLDR WID HSIP 81015(4) CONTRACT NO. 02623**

Reconstruction of the existing roadway on the SF 159 NE Park City Shldr Wid project located in Yellowstone County. The project is located on State Route X-81015 (Old Highway 10) beginning at RP 3.2 and extends approximately 0.4 miles northeast to RP 3.5. Work includes grading, gravel, plant mix surfacing, irrigation, seal & cover, pavement markings, and signing.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001 - GRADE, GRAVEL, PLANT MIX SURFACING, IRRIGATION, SEAL & COVER, SIGNING, & PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	20000.00	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.00	LS
109200005	MOBILIZATION	1.00	LS
203020375	EMBANKMENT IN PLACE	5610.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	1239.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
301020340	CRUSHED AGGREGATE COURSE	2943.00	CUYD
301020625	AGGREGATE TREATMENT	9544.00	SQYD
401020046	PLANT MIX BIT SURF-MISC	124.00	TON
401020122	COMMERCIAL MIX-PG 58V-34	1896.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	878.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	13.00	TON
409000000	FINAL SWEEP AND BROOM	0.00	CRMI
409000020	COVER-TYPE 2	7684.00	SQYD
603000076	REMOVE WATER LINE	71.00	LNFT
603010025	PLUG ENDS AND ABANDON PIPE	4.00	EACH
603012530	RCP 18 IN	56.00	LNFT
603013190	RCPA 18 IN EQ DIA	52.00	LNFT
603013478	PIPE-PVC PRESS 12 IN WATER	1470.00	LNFT
603587020	REMOVE PIPE CULVERT	115.00	LNFT
604010303	MANHOLE STRUCTURE BASE 36 IN (910 MM)	2.00	EACH
604010353	ADDITIONAL BARREL 36 IN	1.00	LNFT
604010660	MANHOLE LID AND FRAME	2.00	EACH
604100020	AIR RELEASE VALVE ASSEMBLY	1.00	EACH
607100281	FARM FENCE-TYPE F5M	447.00	LNFT
607100362	FARM FENCE-PANEL/SINGLE FM	3.00	EACH
607100440	FARM GATE-METAL-TYPE G-3	32.00	LNFT
610100101	SEEDING AREA NO 1	2.00	ACRE



610100103	SEEDING AREA NO 3	1.00	ACRE
610100326	FERTILIZING AREA NO 1	2.00	ACRE
610100555	CONDITION SEEDBED SURFACE	3.00	ACRE
615010034	REMOVE IRRIGATION STRUCTURE	5.00	EACH
615010748	VALVE-GATE 12 IN	2.00	EACH
615010752	IRR ALFALFA VALVE	1.00	EACH
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
619010090	SIGNS-ALUM REFL SHEET XI	108.00	SQFT
619010230	REMOVE SIGN	10.00	EACH
619010310	POSTS-STEEL U SIGN	19.00	LB
619010480	POLES-TREATED WOOD 4 IN	56.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	84.00	LNFT
619011010	DELINEATOR DES A	20.00	EACH
619011040	DELINEATOR DES D	4.00	EACH
619011060	DELINEATOR DES F	13.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	1.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.00	GAL
620012955	TEMPORARY STRIPING	1974.00	LNFT
620013000	STRIPING-WHITE PAINT	28.00	GAL
620013960	STRIPING-WHITE EPOXY	19.00	GAL
620014000	STRIPING-YELLOW PAINT	28.00	GAL
620014960	STRIPING-YELLOW EPOXY	19.00	GAL
622011084	GEOTEXTILE STABILIZATION	8636.00	SQYD
623000155	MAILBOX	4.00	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator. Uniform No. 9115000

**109 HANGING WOMAN CK - 2M S BIRNEY STPB 9044(33) CONTRACT NO. 02A23**

This project replaces the existing Bridge over Hanging Woman Creek located in Rosebud County on Hanging Woman Creek Road approximately 2 miles south of Birney. The work will involve the construction of a new bridge structure and the reconstruction of the roadway approaching the new structure for 0.1 miles. An on-site, single lane detour bridge will be constructed to maintain traffic while the new structure and roadwork are being constructed.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO.	0001 - BRIDGE		
104030010	MISCELLANEOUS WORK	10000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
202020041	REMOVE STRUCTURE	1.00	LS
203020100	EXCAVATION-UNCLASSIFIED	933.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	100.00	CUYD
206000020	DETOUR-CONSTRUCT, MAINTAIN, REMOVE	1.00	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
301020254	BRIDGE END BACKFILL-TYPE 3	613.00	CUYD
301020526	TOP SURFACING GR 3B	601.00	CUYD
551020035	CONCRETE-CLASS STRUCTURE	39.00	CUYD
553010300	PRESTRESSED BEAM-BULB TEE	340.00	LNFT
555010100	REINFORCING STEEL	5294.00	LB
556010010	STRUCTURAL STEEL - MISC	1.00	LS

557010013	BRIDGE RAIL-W830	142.00	LNFT
559010202	RE-DRIVE TEST PILE	2.00	EACH
559040035	DYNAMIC LOAD TEST	2.00	EACH
559050115	FURN STEEL PILE-PIPE	31747.00	LB
559060115	DRIVE STEEL PILE	365.00	LNFT
559060350	PILE CONICAL DRIVING POINT	10.00	EACH
606010037	MASH BOX BEAM TERMINAL - MBEAT	4.00	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	72.00	LNFT
606010266	GRD RL-BOX BEAM/BR APP-SEC TYPE 2	4.00	EACH
610100101	SEEDING AREA NO 1	0.00	ACRE
610100103	SEEDING AREA NO 3	0.00	ACRE
610100326	FERTILIZING AREA NO 1	0.00	ACRE
610100555	CONDITION SEEDBED SURFACE	0.00	ACRE
610100560	RIPRAP REVEGETATION	305.00	SQYD
613100040	RIPRAP-CLASS 2 RANDOM	312.00	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
619010230	REMOVE SIGN	5.00	EACH
622011043	PERM EROSION CONTROL-HIGH SURV	444.00	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	2468.00	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator. Uniform No. 8877000

**110 ELKHORN ROAD - SOUTH STPP 69-1(42)22 CONTRACT NO. 01R23**

Crack sealing, seal and cover, fog seal, and pavement markings on the Elkhorn Road - South project located in Jefferson County on State Primary Route 69 south of Boulder. The project begins at RP 22.1 and extends 9.3 miles northwest to RP 31.8.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	SEAL & COVER, PAVEMENT MARKINGS		
104030010	MISCELLANEOUS WORK	10000.00	UNIT
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
402020320	EMULSIFIED ASPHALT-FOG SEAL	4063.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	238.00	TON
403010255	CRACK SEALING	35363.00	LB
409000000	FINAL SWEEP AND BROOM	9.00	CRMI
409000010	COVER-TYPE 1	135084.00	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	80000.00	UNIT
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	3.00	GAL
620013000	STRIPING-WHITE PAINT	354.00	GAL
620013960	STRIPING-WHITE EPOXY	470.00	GAL
620014000	STRIPING-YELLOW PAINT	83.00	GAL
620014960	STRIPING-YELLOW EPOXY	108.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Butte District Administrator.  
 Uniform No. 9741000

**111 JCT S-227 & S-228 - WEST NH 60-2(129)87 CONTRACT NO. 02R23**  
 Seal the joints and cracks and finish with epoxy pavement markings on MT-200 / MT-3 / US-87 / US-89 / National Highway Route 60 (N-60) east of Great Falls in Cascade County. The project begins at RP 90.3 and extends 3 miles east to RP 87.3.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RESURFACING, CRACK SEAL, & PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	5000.00	UNIT
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	1.00	UNIT
501000100	PCCP JOINT SEAL	206672.00	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	225000.00	UNIT
620010301	CURB MARKING-YELLOW EPOXY	11.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	10.00	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	111.00	GAL
620013955	REMOVE PAVEMENT MARKINGS	1860.00	LNFT
620013960	STRIPING-WHITE EPOXY	221.00	GAL
620014960	STRIPING-YELLOW EPOXY	302.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.  
 This project is under the jurisdiction of the Great Falls District Administrator.  
 Uniform No. 10313000

INVITATION FOR BIDS  
LETTING OF OCTOBER 26, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on . All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION  
Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

201

SF 169 RIMROCK &amp; 62ND STREET WEST - BILLINGS HSIP 1034(4)

CONTRACT NO. 05723

Reconstruct the existing two-way stop-controlled intersection of 62nd Street West and Rimrock Road located along the northwestern fringe of Billings as a roundabout. Work will extend approximately 600-1000 feet along each leg of the intersection and includes grading, paving, irrigation and drainage, curb and gutter, lighting, signing, and stripping.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO.	0001 - PAVING, GRADING, ROUNDABOUT, SIGNING		
103500005	ESCROW OF BID DOCUMENTS	1.00	LS
104030010	MISCELLANEOUS WORK	40000.00	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.00	LS
105080070	MONUMENT BOX	1.00	EACH
108000000	CRITICAL PATH SCHEDULE	1.00	LS
109200005	MOBILIZATION	1.00	LS
202020140	REMOVE BITUMINOUS PAVEMENT	3121.00	SQYD
202020358	ABANDON WELL	2.00	EACH
203020100	EXCAVATION-UNCLASSIFIED	14198.00	CUYD
203020310	SPECIAL BORROW-NEAT LINE	28133.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	3319.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
301020268	TRAFFIC GRAVEL	544.00	CUYD
301020340	CRUSHED AGGREGATE COURSE	4757.00	CUYD
301020450	SPECIAL BACKFILL	590.00	CUYD
301020465	LOW PERMEABILITY BACKFILL	189.00	CUYD
301020625	AGGREGATE TREATMENT	19743.00	SQYD
401020064	COMMERCIAL PLANT MIX-MISC	90.00	TON
401020122	COMMERCIAL MIX-PG 58V-34	2456.00	TON
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	2419.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	2218.00	GAL
501010125	PORT CEM CONC PAVE 9 IN	69.00	SQYD
501010126	PORT CEM CONC PAVE 9 IN COLORED	401.00	SQYD
551020030	CONCRETE-CLASS GENERAL	5.00	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	7.00	CUYD
601011920	INSULATION	96.00	SQFT
601012070	WATER SERVICE 1 1/2 IN	1.00	EACH
603000050	GRANULAR BEDDING MATERIAL	305.00	CUYD
603000060	FOUNDATION MATERIAL	822.00	CUYD
603000075	REMOVE SANITARY SEWER	45.00	LNFT
603000080	REMOVE WATER VALVE BOX	2.00	EACH
603010020	FILL AND ABANDON PIPE	50.00	CUYD
603012530	RCP 18 IN	234.00	LNFT
603012555	RCP 24 IN	80.00	LNFT
603013202	RCPA 24 IN EQ DIA	138.00	LNFT
603013235	RCPA 48 IN EQ DIA	240.00	LNFT
603013446	PVC TEE ASSEMBLY	1.00	EACH
603013453	PIPE-PVC 18 IN	45.00	LNFT
603013457	PIPE-PVC 8 IN	2802.00	LNFT
603013459	PIPE-PVC 4 IN	80.00	LNFT
603013466	PIPE-PVC PRESS 8 IN WATER	1803.00	LNFT
603013493	PIPE-PVC 24 IN	64.00	LNFT
603013549	CONNECT TO EXISTING PIPE	4.00	EACH
603013655	ENCASEMENT PIPE-15 IN	116.00	LNFT
603014242	ADJUST VALVE BOX	5.00	EACH
603014244	RESET VALVE BOX	1.00	EACH
603014492	HYDRANT ASSEMBLY	1.00	EACH
603017040	STORM DRAIN PIPE-12 IN	148.00	LNFT
603017050	STORM DRAIN PIPE-18 IN	62.00	LNFT
603017070	STORM DRAIN PIPE-30 IN	349.00	LNFT
603587020	REMOVE PIPE CULVERT	1572.00	LNFT
603587040	REMOVE AND SALVAGE CULVERT	531.00	LNFT
604000100	ADJUST MANHOLE	6.00	EACH
604000120	REMOVE FIRE HYDRANT	1.00	EACH

604000250	ADJUST FIRE HYDRANT	1.00	EACH
604010172	REMOVE MANHOLE	1.00	EACH
604010250	INLET CURB-SPECIAL DESIGN	8.00	EACH
604010302	MANHOLE STRUCTURE BASE 48 IN (1220 MM)	3.00	EACH
604010304	MANHOLE STRUCTURE BASE 60 IN	2.00	EACH
604010308	MANHOLE STRUCTURE BASE 84 IN (2100 MM)	1.00	EACH
604010310	MANHOLE STRUCTURE BASE 96 IN	1.00	EACH
604010352	ADDITIONAL BARREL 48 IN	10.00	LNFT
604010354	ADDITIONAL BARREL 60 IN	4.00	LNFT
604010358	ADDITIONAL BARREL 84 IN	7.00	LNFT
604010360	ADDITIONAL BARREL 96 IN	2.00	LNFT
604010660	MANHOLE LID AND FRAME	6.00	EACH
604010661	CURB INLET FRAME AND GRATE	8.00	EACH
604010662	DROP INLET FRAME AND GRATE	1.00	EACH
604100020	AIR RELEASE VALVE ASSEMBLY	1.00	EACH
607100147	FARM FENCE-TYPE F2M-32 IN WW	493.00	LNFT
607100385	FARM FENCE-PANEL/DOUBLE FM	3.00	EACH
607100720	DEADMAN	1.00	EACH
608010020	SIDEWALK-CONCRETE 4 IN	535.00	SQYD
608010090	CONCRETE 3 IN	948.00	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	28.00	SQYD
609010030	CURB-CONC MEDIAN TYPE A	2946.00	LNFT
609010200	CURB AND GUTTER-CONC	2533.00	LNFT
610010100	TOPSOIL	269.00	CUYD
610100101	SEEDING AREA NO 1	5.00	ACRE
610100102	SEEDING AREA NO 2	0.00	ACRE
610100103	SEEDING AREA NO 3	1.00	ACRE
610100326	FERTILIZING AREA NO 1	5.00	ACRE
610100327	FERTILIZING AREA NO 2	0.00	ACRE
610100480	TURF REINF MAT-SYNTHETIC FIBER	53.00	SQYD
610100561	EROSION CONTROL BLANKET-LONG-TERM	490.00	SQYD
610100625	LANDSCAPING	1.00	LS
613100030	RIPRAP-CLASS 1 RANDOM	32.00	CUYD
615010063	IRRIGATION CLEANOUT	12.00	EACH
615010739	VALVE-GATE 8 IN	2.00	EACH
616343914	CONDUIT-PLASTIC 1 1/2 IN	2355.00	LNFT
616343920	CONDUIT-PLASTIC 2 IN	274.00	LNFT
616783006	PULL BOX-COMPOSITE TYPE 1	8.00	EACH
617000000	FOUNDATION-CONCRETE	8.00	CUYD
617000050	POLES-TREATED WOOD CLASS 4	10.00	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	5276.00	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	2629.00	LNFT
617123112	CONDUCTOR-COPPER AWG12-600V	781.00	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	16.00	EACH
617303300	HIGH EFFICACY LUMINAIRE LED	16.00	EACH
617333105	ELEC SERV ASSEMBLY	1.00	EACH
618030005	TRAFFIC CONTROL DEVICES CB	400000.00	UNIT
619010090	SIGNS-ALUM REFL SHEET XI	232.00	SQFT
619010200	RESET SIGNS	1.00	EACH
619010230	REMOVE SIGN	21.00	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	1426.00	LB
619010480	POLES-TREATED WOOD 4 IN	84.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	16.00	LNFT
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	7.00	EACH
619011010	DELINEATOR DES A	16.00	EACH
619011179	DELINEATOR-FLEX SURF MTD WH	8.00	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	16.00	EACH
620010301	CURB MARKING-YELLOW EPOXY	26.00	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.00	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	12.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	3.00	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	15.00	GAL
620012955	TEMPORARY STRIPING	10519.00	LNFT
620013000	STRIPING-WHITE PAINT	28.00	GAL
620013960	STRIPING-WHITE EPOXY	37.00	GAL
620014000	STRIPING-YELLOW PAINT	36.00	GAL

620014960	STRIPING-YELLOW EPOXY	48.00	GAL
622010075	GEOGRID - BIAXIAL	49769.00	SQYD
622011022	SUBSURFACE DRAIN FILTER-HIGH SURV	1924.00	SQYD
622011043	PERM EROSION CONTROL-HIGH SURV	76.00	SQYD
622011084	GEOTEXTILE STABILIZATION	30642.00	SQYD
622011087	SEPARATION GEOTEXTILE - MOD	7345.00	SQYD
623000155	MAILBOX	1.00	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.  
 Uniform No. 9383001

**202                    BOWMAN'S CORNER - NORTHEAST NH 24-3(71)109 &                    CONTRACT NO. 03R23**  
**AUGUSTA - SOUTHEAST STPP 9-1(25)21**

NH 24-3(71)109 - Resurfacing, seal & cover, and pavement markings on the Bowman's Corner - Northeast project located in Lewis and Clark County. This project is on Route MT 200 (NH 24) beginning at RP 109.1 extending to RP 116.8 on the east leg of the intersection with Hwy 287 and extends northeast 7.8 miles to the Cascade County line.

STPP 9-1(25)21 - scrub seal with new pavement markings on the Augusta - Southeast project located in Lewis and Clark County This project is on US-287 starting south of Augusta and ending northeast of Augusta from reference post (RP) 21+0.406 - Accumulated Miles (A.M.) 21.693 to RP 39+0.467 - A.M. 39.511.

INVOLVING  
 -----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & COVER			
104030010	MISCELLANEOUS WORK	30000.00	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.00	LS
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
402020320	EMULSIFIED ASPHALT-FOG SEAL	38229.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	316.00	TON
402020377	SCRUB SEAL EMULSION	587.00	TON
403010255	CRACK SEALING	15686.00	LB
409000010	COVER-TYPE 1	509310.00	SQYD
552010160	BRIDGE DECK CRACK SEAL	1196.00	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	210000.00	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	4.00	EACH
620010301	CURB MARKING-YELLOW EPOXY	18.00	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	15.00	GAL
620013000	STRIPING-WHITE PAINT	1269.00	GAL
620013960	STRIPING-WHITE EPOXY	1692.00	GAL
620014000	STRIPING-YELLOW PAINT	616.00	GAL
620014960	STRIPING-YELLOW EPOXY	820.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the

Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.

Uniform No. 9954000, 10244000

**203 DODSON - SOUTH STPS 204-1(6)0 & CONTRACT NO. 08R23  
DODSON SOUTH CANAL - 1M S DODSON STPB 204-1(4)1**

STPS 204-1(6)0 The Dodson-South project is a 1.6-mile-long mill, overlay, and seal & cover project on Montana Secondary Highway 204 (Stage Rd.) in Phillips County. This project begins at RP 1.6, just south of the intersection of S-204 and S Wagner Rd and ends at RP 0.0, at the intersection of US 2 (N-1) and S-204.

STPB 204-1(4)1 The Dodson South Canal - 1M S Dodson project is the replacement of the existing bridge over Dodson Canal on Secondary Highway 204 (Stage Road) with a concrete box culvert. The existing bridge, crossing the Dodson South Canal, in Phillips County, is approximately 1.5 miles south of Dodson. The work will also include reconstruction of the roadway approaching the new structure.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RESURFACING - ASPHALT, SIGNING, BRIDGE REPLACEMENT WITH CULVERT			
104030010	MISCELLANEOUS WORK	20000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
202020041	REMOVE STRUCTURE	1.00	LS
203020375	EMBANKMENT IN PLACE	2144.00	CUYD
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
208010486	STREAMBED MATERIAL	73.00	CUYD
210020000	GRADER-MOTOR	5.00	HOURL
210020170	TEST TRAILER-TRANSPORT, SETUP	280.00	MILE
301020340	CRUSHED AGGREGATE COURSE	132.00	CUYD
301020450	SPECIAL BACKFILL	878.00	CUYD
401020122	COMMERCIAL MIX-PG 58V-34	2623.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1384.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	41.00	TON
409000000	FINAL SWEEP AND BROOM	1.00	CRMI
409000010	COVER-TYPE 1	23296.00	SQYD
411010000	COLD MILLING	24248.00	SQYD
552010041	REVISE JOINT	53.00	LNFT
552010140	TRANSVERSE DECK GROOVING	588.00	SQYD
552011120	JOINT SEALS-POLYURETHANE	56.00	LNFT
557010505	REVISE BRIDGE RAIL-THRIE BEAM	493.00	LNFT
561010525	EXPANSION JOINT-PRECOMPRESSED	56.00	LNFT
561020110	BRIDGE DECK MILLING	639.00	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.00	SQYD
563000010	CONCRETE-CLASS OVERLAY	639.00	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.00	UNIT
603000050	GRANULAR BEDDING MATERIAL	88.00	CUYD
603000060	FOUNDATION MATERIAL	176.00	CUYD
603013415	REIN CONC BOX 14 X 10 DBL	70.00	LNFT
604000100	ADJUST MANHOLE	2.00	EACH
606010037	MASH BOX BEAM TERMINAL - MBEAT	4.00	EACH
606010041	GUARDRAIL-BOX BEAM/8 FT POST	72.00	LNFT
606010140	GUARDRAIL END SECTION WIDENING	4.00	EACH
606010325	GRD RL-BOX BEAM TO W-BEAM TRANS	4.00	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.00	EACH
606010385	REMOVE GUARDRAIL	226.00	LNFT
610100559	REVEGETATION	1.00	LS
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT



618030080	TRAFFIC CONTROL-LS	1.00	LS
619010062	SIGNS-ALUM SHEET INCR XI	39.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	286.00	SQFT
619010230	REMOVE SIGN	30.00	EACH
619010240	REMOVE SIGN-GUIDE	1.00	EACH
619010310	POSTS-STEEL U SIGN	20.00	LB
619010480	POLES-TREATED WOOD 4 IN	362.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	176.00	LNFT
619011010	DELINEATOR DES A	45.00	EACH
619011040	DELINEATOR DES D	12.00	EACH
619011060	DELINEATOR DES F	7.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	3.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.00	GAL
620012955	TEMPORARY STRIPING	8983.00	LNFT
620013000	STRIPING-WHITE PAINT	58.00	GAL
620013960	STRIPING-WHITE EPOXY	78.00	GAL
620014000	STRIPING-YELLOW PAINT	100.00	GAL
620014960	STRIPING-YELLOW EPOXY	106.00	GAL
622011084	GEOTEXTILE STABILIZATION	560.00	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.  
Uniform No. 9553001, 10226000

**204 D1 BRIDGE PRESERVATION NHPB-STPB STWD(773) CONTRACT NO. 07R23**

This project involves a mix of Class A bridge deck repair, bridge deck crack seal, mastic crack fill, and/or joint replacement on various bridge decks located in the MDT Missoula District. Individual bridge decks may involve only one of the repair items or multiple items in any combination. The bridges are located on NHS Non-Interstate and Secondary routes in Missoula and Ravalli Counties.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	- MISSOULA DISTRICT BRIDGE PRESERVATION		
104030010	MISCELLANEOUS WORK	50000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
403010257	CRACK FILLING-MASTIC	13877.00	LB
552010160	BRIDGE DECK CRACK SEAL	34511.00	SQYD
561010525	EXPANSION JOINT-PRECOMPRESSED	280.00	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	80.00	SQYD
606011503	RESET TEMP IMPACT ATTENUATOR	6.00	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	6.00	EACH
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
618100000	SINGLE USE SIGNS	168.00	SQFT
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.00	EACH
618190100	TEMPORARY BARRIER RAIL	642.00	LNFT
618190110	RESET TEMP BARRIER RAIL	642.00	LNFT
620010301	CURB MARKING-YELLOW EPOXY	3.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.00	GAL

620011265	WORDS AND SYMBOLS-YELLOW EPOXY	8.00	GAL
620013960	STRIPING-WHITE EPOXY	59.00	GAL
620014960	STRIPING-YELLOW EPOXY	59.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
Uniform No. 9820000

INVITATION FOR BIDS  
LETTING OF NOVEMBER 16, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on . All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION  
Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

STPP 51-3(14)38 - The Lambert - West project is located along Montana Highway 200 in Richland County beginning approximately 1/4 mile west of the intersection with County Road 126 at reference post 38.4 and extending east for 10.8 miles ending near the intersection with County Road 328, northwest of Lambert at reference post 49.3. This project includes pulverizing and reconstructing the existing surfacing, widening the roadway to include 2-foot shoulders, replacement of drainage structures in poor condition, slope flattening, shoulder rumble strips, seal and cover (chip seal), new signing and pavement markings.

STPP 51-3(16)49 - The Lambert - East project is a seal and cover (chip seal) project on MT 200 in Richland County beginning near Lambert at the intersection with County Road 328 at RP 49.2 and extending east 21.7 miles ending just west of the MT 16 roundabout intersection south of Sidney at RP 70.9. This project will include a chip seal treatment of the pavement.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO.	0001 - SEAL & COVER		
103000000	TRAINING PROGRAM	1000.00	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.00	LS
104030010	MISCELLANEOUS WORK	50000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
203020100	EXCAVATION-UNCLASSIFIED	437605.00	CUYD
203020310	SPECIAL BORROW-NEAT LINE	20624.00	CUYD
203020380	SPECIAL EMBANKMENT	6066.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	77765.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	130.00	MILE
301020268	TRAFFIC GRAVEL	2500.00	CUYD
301020340	CRUSHED AGGREGATE COURSE	55462.00	CUYD
301020416	SHOULDER GRAVEL	23803.00	CUYD
301020450	SPECIAL BACKFILL	11180.00	CUYD
301020625	AGGREGATE TREATMENT	202640.00	SQYD
302000000	PAVEMENT PULVERIZATION	191050.00	SQYD
401020045	PLANT MIX SURF-3/4 IN	36544.00	TON
401020046	PLANT MIX BIT SURF-MISC	979.00	TON
401020300	HYDRATED LIME	525.00	TON
402020192	ASPHALT CEMENT PG 58V-34	2027.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	20491.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	937.00	TON
409000000	FINAL SWEEP AND BROOM	32.00	CRMI
409000010	COVER-TYPE 1	524046.00	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	10.00	MILE
411011135	RUMBLE STRIPS	21.00	MILE
551020030	CONCRETE-CLASS GENERAL	101.00	CUYD
603000050	GRANULAR BEDDING MATERIAL	993.00	CUYD
603000060	FOUNDATION MATERIAL	2250.00	CUYD
603012530	RCP 18 IN	1590.00	LNFT
603012555	RCP 24 IN	44.00	LNFT
603012625	RCP 30 IN	568.00	LNFT
603012660	RCP 36 IN	488.00	LNFT
603012670	RCP 42 IN	134.00	LNFT
603012705	RCP 48 IN	172.00	LNFT
603012741	RCP 60 IN	418.00	LNFT
603013226	RCPA 42 IN EQ DIA	86.00	LNFT
603013235	RCPA 48 IN EQ DIA	50.00	LNFT
603013255	RCPA 72 IN EQ DIA	72.00	LNFT
603013346	REIN CONC BOX 20 X 6	150.00	LNFT
603013348	REIN CONC BOX 12 X 7	238.00	LNFT
603013361	REIN CONC BOX 8 X 6	156.00	LNFT
603013378	REIN CONC BOX 14 X 8	158.00	LNFT
603013407	REIN CONC BOX 12 X 10 DBL	6.00	LNFT
603013410	REIN CONC BOX 16 X 12	104.00	LNFT

603016150	RELAY PIPE CULVERT	18.00	LNFT
603587020	REMOVE PIPE CULVERT	3918.00	LNFT
607100147	FARM FENCE-TYPE F2M-32 IN WW	2118.00	LNFT
607100229	FARM FENCE-TYPE F4W	5248.00	LNFT
607100252	FARM FENCE-TYPE F4M	88328.00	LNFT
607100362	FARM FENCE-PANEL/SINGLE FM	138.00	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	176.00	EACH
607100430	FARM GATE-WIRE-TYPE G-2	1224.00	LNFT
607100551	FENCE-TEMPORARY	1459.00	LNFT
607100720	DEADMAN	144.00	EACH
607150131	RESET GATE	5.00	EACH
610100101	SEEDING AREA NO 1	185.00	ACRE
610100103	SEEDING AREA NO 3	38.00	ACRE
610100326	FERTILIZING AREA NO 1	185.00	ACRE
610100490	TURF REINF MAT-NATURAL FIBER	34163.00	SQYD
610100555	CONDITION SEEDBED SURFACE	224.00	ACRE
610220120	COMPOST	1.00	ACRE
611010300	RESET CATTLE GUARD	1.00	EACH
613100030	RIPRAP-CLASS 1 RANDOM	381.00	CUYD
613100040	RIPRAP-CLASS 2 RANDOM	428.00	CUYD
613100085	OUTLET APRON	211.00	SQYD
613520010	VEGETATED CONCRETE BLOCK MAT	8652.00	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	900000.00	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.00	EACH
619010090	SIGNS-ALUM REFL SHEET XI	75.00	SQFT
619010200	RESET SIGNS	1.00	EACH
619010230	REMOVE SIGN	17.00	EACH
619010240	REMOVE SIGN-GUIDE	2.00	EACH
619010310	POSTS-STEEL U SIGN	220.00	LB
619010480	POLES-TREATED WOOD 4 IN	84.00	LNFT
619011010	DELINEATOR DES A	307.00	EACH
619011040	DELINEATOR DES D	14.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	20.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	20.00	GAL
620012955	TEMPORARY STRIPING	189566.00	LNFT
620013000	STRIPING-WHITE PAINT	1518.00	GAL
620013960	STRIPING-WHITE EPOXY	1568.00	GAL
620014000	STRIPING-YELLOW PAINT	948.00	GAL
620014960	STRIPING-YELLOW EPOXY	980.00	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	117.00	SQYD
622011084	GEOTEXTILE STABILIZATION	60849.00	SQYD
623000180	MAILBOX-LARGE	2.00	EACH
699010025	ROAD WEATHER INFORMATION SYSTEM	1.00	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.  
Uniform No. 8715000, 10224000

**102 RESERVE - EAST STPS-HSIP 258-1(10)1**

**CONTRACT NO. 05B23**

Reconstruction, PMS overlay, rumble strips, and shoulder widening on the Reserve - East project located in Sheridan County. The project is located on Secondary Highway 258, east of Reserve, Montana beginning east of the Big Muddy Creek Overflow bridge at RP 0.8 and extending east approximately 10.5 miles to RP 11.32.

INVOLVING

-----

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
----------	-------------	----------	-------

-----

SECTION NO. 0001 - MAJOR REHAB			
103500005	ESCROW OF BID DOCUMENTS	1.00	LS
104030010	MISCELLANEOUS WORK	50000.00	UNIT
109200005	MOBILIZATION	1.00	LS
202020362	ABANDON WELL	1.00	LS
203020100	EXCAVATION-UNCLASSIFIED	169320.00	CUYD
203020200	EXCAVATION-UNCLASS BORROW	35048.00	CUYD
203020310	SPECIAL BORROW-NEAT LINE	50062.00	CUYD
203020380	SPECIAL EMBANKMENT	10689.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	43038.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	188.00	MILE
301020268	TRAFFIC GRAVEL	1000.00	CUYD
301020340	CRUSHED AGGREGATE COURSE	60262.00	CUYD
301020450	SPECIAL BACKFILL	2026.00	CUYD
301020625	AGGREGATE TREATMENT	202437.00	SQYD
302000000	PAVEMENT PULVERIZATION	90626.00	SQYD
401020045	PLANT MIX SURF-3/4 IN	42214.00	TON
401020046	PLANT MIX BIT SURF-MISC	1192.00	TON
401020300	HYDRATED LIME	608.00	TON
402020192	ASPHALT CEMENT PG 58V-34	2352.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	20212.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	312.00	TON
409000000	FINAL SWEEP AND BROOM	10.00	CRMI
409000010	COVER-TYPE 1	173700.00	SQYD
411011135	RUMBLE STRIPS	21.00	MILE
551020030	CONCRETE-CLASS GENERAL	24.00	CUYD
603000050	GRANULAR BEDDING MATERIAL	237.00	CUYD
603000060	FOUNDATION MATERIAL	358.00	CUYD
603010040	DRAINAGE PIPE 18 IN	2718.00	LNFT
603010048	DRAINAGE PIPE 24 IN	1082.00	LNFT
603010056	DRAINAGE PIPE 30 IN	490.00	LNFT
603010066	DRAINAGE PIPE 36 IN	220.00	LNFT
603010068	DRAINAGE PIPE 48 IN	90.00	LNFT
603012625	RCP 30 IN	82.00	LNFT
603012660	RCP 36 IN	172.00	LNFT
603012769	RCP 72 IN	172.00	LNFT
603013235	RCPA 48 IN EQ DIA	172.00	LNFT
603013358	REIN CONC BOX 14 X 6	116.00	LNFT
603014244	RESET VALVE BOX	2.00	EACH
603587020	REMOVE PIPE CULVERT	2248.00	LNFT
607100229	FARM FENCE-TYPE F4W	13332.00	LNFT
607100252	FARM FENCE-TYPE F4M	7155.00	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	28.00	EACH
607100362	FARM FENCE-PANEL/SINGLE FM	14.00	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	6.00	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	12.00	EACH
607100430	FARM GATE-WIRE-TYPE G-2	256.00	LNFT
607100720	DEADMAN	7.00	EACH
610100101	SEEDING AREA NO 1	111.00	ACRE
610100103	SEEDING AREA NO 3	39.00	ACRE
610100326	FERTILIZING AREA NO 1	111.00	ACRE
610100490	TURF REINF MAT-NATURAL FIBER	6213.00	SQYD
610100555	CONDITION SEEDBED SURFACE	150.00	ACRE
610100565	EROSION CONTROL BLANKET-HIGH-PERFORM	6133.00	SQYD
617673200	SIG STANDARD TYPE 1-200	2.00	EACH
618030005	TRAFFIC CONTROL DEVICES CB	75000.00	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.00	EACH
619010062	SIGNS-ALUM SHEET INCR XI	87.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	270.00	SQFT
619010230	REMOVE SIGN	36.00	EACH
619010240	REMOVE SIGN-GUIDE	3.00	EACH
619010310	POSTS-STEEL U SIGN	211.00	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	840.00	LB
619010480	POLES-TREATED WOOD 4 IN	370.00	LNFT

619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.00	EACH
619010730	FRANG SIGN POST BKWY-W8 X 18	2.00	EACH
619011010	DELINEATOR DES A	296.00	EACH
619011040	DELINEATOR DES D	52.00	EACH
619011060	DELINEATOR DES F	19.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	2.00	GAL
620013000	STRIPING-WHITE PAINT	716.00	GAL
620013960	STRIPING-WHITE EPOXY	478.00	GAL
620014000	STRIPING-YELLOW PAINT	414.00	GAL
620014960	STRIPING-YELLOW EPOXY	278.00	GAL
622011084	GEOTEXTILE STABILIZATION	273048.00	SQYD
623000155	MAILBOX	3.00	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.  
Uniform No. 8897000

**103 MILES CITY - NORTH NH 18-1(15)0**

**CONTRACT NO. 03B23**

The Miles City - North project is located along Montana Highway 59. It begins at the intersection with Main Street in Miles City, extends north for approximately 2.2 miles, and ends just north of the intersection with Secondary Highway 489 (Kinsey Road). The project includes reconstruction of the street south of the Yellowstone River Bridge, widening the shoulders north of the bridge, upgrades to existing sidewalks and curb ramps, new rumble strips north of the bridge and upgraded pavement markings, signing and guardrail. The purpose of this project is to rehabilitate the existing roadway to provide a safer, smoother roadway and reduce maintenance costs.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MAJOR REHAB			
103000000	TRAINING PROGRAM	500.00	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.00	LS
104030010	MISCELLANEOUS WORK	50000.00	UNIT
104030011	MISCELLANEOUS ITEMS-LS	1.00	LS
104030037	MISCELLANEOUS ITEMS-SQYD	782.00	SQYD
104030065	MISCELLANEOUS ITEMS A-LNFT	102.00	LNFT
108000000	CRITICAL PATH SCHEDULE	1.00	LS
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
201311000	REMOVE TREES	4.00	EACH
202020539	REMOVE MISCELLANEOUS ITEMS	2.00	EACH
203020100	EXCAVATION-UNCLASSIFIED	64036.00	CUYD
203020225	EXCAVATION-STREET	21635.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	7222.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
301020340	CRUSHED AGGREGATE COURSE	19811.00	CUYD
301020416	SHOULDER GRAVEL	68.00	CUYD
301020450	SPECIAL BACKFILL	800.00	CUYD
301020625	AGGREGATE TREATMENT	29035.00	SQYD
401020046	PLANT MIX BIT SURF-MISC	2185.00	TON
401020065	PLANT MIX SURF-3/8 IN	12073.00	TON
401020300	HYDRATED LIME	200.00	TON

402020192	ASPHALT CEMENT PG 58V-34	926.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	7074.00	GAL
411010000	COLD MILLING	636.00	SQYD
411011135	RUMBLE STRIPS	1.00	MILE
601012050	WATER SERVICE 1 IN	1555.00	LNFT
603000071	DRAIN-SPECIAL DESIGN	1.00	EACH
603000080	REMOVE WATER VALVE BOX	9.00	EACH
603000085	ADJUST WATER MAIN	7.00	EACH
603010020	FILL AND ABANDON PIPE	21.00	CUYD
603010025	PLUG ENDS AND ABANDON PIPE	58.00	EACH
603010040	DRAINAGE PIPE 18 IN	68.00	LNFT
603010048	DRAINAGE PIPE 24 IN	372.00	LNFT
603012521	RCP 15 IN	1542.00	LNFT
603012625	RCP 30 IN	12.00	LNFT
603012670	RCP 42 IN	50.00	LNFT
603012705	RCP 48 IN	202.00	LNFT
603013202	RCPA 24 IN EQ DIA	88.00	LNFT
603013400	PIPE-SW-POLYETHYLENE 30 IN	236.00	LNFT
603013457	PIPE-PVC 8 IN	146.00	LNFT
603013458	PIPE-PVC 4 IN SANITARY	362.00	LNFT
603013459	PIPE-PVC 4 IN	30.00	LNFT
603013460	PIPE-PVC 6 IN SANITARY	1063.00	LNFT
603013462	PIPE-PVC 6 IN	850.00	LNFT
603013464	PIPE-PVC 8 IN SANITARY	142.00	LNFT
603013470	PIPE-PVC 10 IN	4618.00	LNFT
603013471	PIPE-PVC 10 IN SANITARY	82.00	LNFT
603013539	CONNECT TO MAIN-10 IN	2.00	EACH
603013545	WATER SERVICE CONNECTION	49.00	EACH
603013549	CONNECT TO EXISTING PIPE	29.00	EACH
603013550	SEWER SERVICE CONNECTION	12.00	EACH
603013560	CONNECT WATER LINE-4 IN	10.00	EACH
603013562	CONNECT WATER LINE-6 IN	5.00	EACH
603013564	CONNECT WATER LINE-8 IN	3.00	EACH
603013700	DUCTILE IRON PIPE 10 IN	206.00	LNFT
603013828	DUCTILE IRON FITTINGS	11059.00	LB
603014242	ADJUST VALVE BOX	1.00	EACH
603014492	HYDRANT ASSEMBLY	10.00	EACH
603016003	SPECIAL INSTALLATION OF PIPE	562.00	LNFT
603016045	STEEL CASING 24 IN	102.00	LNFT
603016050	STEEL CASING 30 IN	452.00	LNFT
603016060	STEEL CASING 42 IN	218.00	LNFT
603017022	BYPASS PUMPING	1.00	LS
603587020	REMOVE PIPE CULVERT	536.00	LNFT
603587030	REMOVE STORM DRAIN	1592.00	LNFT
604000120	REMOVE FIRE HYDRANT	6.00	EACH
604000140	REMOVE DROP INLET	24.00	EACH
604010172	REMOVE MANHOLE	14.00	EACH
604010184	CONCRETE APRON	5.00	EACH
604010301	INLET STRUCTURE BASE 32 IN (810 MM)	1.00	EACH
604010302	MANHOLE STRUCTURE BASE 48 IN (1220 MM)	38.00	EACH
604010304	MANHOLE STRUCTURE BASE 60 IN	6.00	EACH
604010352	ADDITIONAL BARREL 48 IN	24.00	LNFT
604010354	ADDITIONAL BARREL 60 IN	23.00	LNFT
604010660	MANHOLE LID AND FRAME	20.00	EACH
604010662	DROP INLET FRAME AND GRATE	25.00	EACH
604100020	AIR RELEASE VALVE ASSEMBLY	21.00	EACH
606010370	RESET GUARDRAIL	587.00	LNFT
606010385	REMOVE GUARDRAIL	1218.00	LNFT
606011288	RESET BRIDGE APPROACH SECTION	4.00	EACH
606011300	RESET OPTIONAL TERMINAL SECT	4.00	EACH
607100252	FARM FENCE-TYPE F4M	915.00	LNFT
607100385	FARM FENCE-PANEL/DOUBLE FM	12.00	EACH
607100720	DEADMAN	2.00	EACH
608000020	SIDEWALK DRAIN	1.00	EACH
608010050	SIDEWALK-CONCRETE 6 IN	3893.00	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	42.00	SQYD



609010112	CURB 4 IN-CONCRETE	54.00	LNFT
609010160	GUTTER-CONC VALLEY	8.00	SQYD
609010200	CURB AND GUTTER-CONC	3484.00	LNFT
610100101	SEEDING AREA NO 1	26.00	ACRE
610100102	SEEDING AREA NO 2	0.00	ACRE
610100103	SEEDING AREA NO 3	5.00	ACRE
610100126	SEEDING-LAWN	0.00	ACRE
610100323	FERTILIZER-LAWN	0.00	ACRE
610100326	FERTILIZING AREA NO 1	26.00	ACRE
610100327	FERTILIZING AREA NO 2	0.00	ACRE
610100490	TURF REINF MAT-NATURAL FIBER	1920.00	SQYD
610100555	CONDITION SEEDBED SURFACE	32.00	ACRE
610220050	MULCH-COMPOST	0.00	ACRE
613100030	RIPRAP-CLASS 1 RANDOM	30.00	CUYD
615010731	VALVE-GATE 4 IN	1.00	EACH
615010737	VALVE-GATE 6 IN W/BOX	11.00	EACH
615010741	VALVE-GATE 8 IN W/BOX	3.00	EACH
615010743	VALVE-GATE 10 IN	27.00	EACH
616343914	CONDUIT-PLASTIC 1 1/2 IN	10.00	LNFT
616343920	CONDUIT-PLASTIC 2 IN	280.00	LNFT
616343924	CONDUIT-PLASTIC 2 1/2 IN	100.00	LNFT
616343930	CONDUIT-PLASTIC 3 IN	390.00	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	5.00	EACH
616783008	PULL BOX-COMPOSITE TYPE 3	3.00	EACH
617000000	FOUNDATION-CONCRETE	21.00	CUYD
617033114	CABLE-COPPER 2AWG14-600V	1350.00	LNFT
617033314	CABLE-COPPER 5AWG14-600V	500.00	LNFT
617033414	CABLE-COPPER 7AWG14-600V	350.00	LNFT
617033514	CABLE-COPPER 9AWG14-600V	500.00	LNFT
617033614	CABLE-COPPER 12AWG14-600V	140.00	LNFT
617086919	CABLE-COPPER 6 PAIR AWG 19 COM	550.00	LNFT
617090050	CABLE-COPPER COAXIAL 50 OHM 3/8 IN	130.00	LNFT
617123106	CONDUCTOR-COPPER AWG6-600V	870.00	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	1140.00	LNFT
617233030	CONTROLLER-CAB PEDESTAL TYPE P	1.00	EACH
617553020	SIG-PEDESTRIAN TYPE 2	8.00	EACH
617605040	CONTRLR/TRAF-ACTUATOR	1.00	EACH
617673080	SIG STANDARD TYPE 1-80	4.00	EACH
617673100	SIG STANDARD TYPE 1-100	4.00	EACH
617693502	SIG STANDARD TYPE 2-A-500-2	1.00	EACH
617693503	SIG STANDARD TYPE 2-A-500-3	1.00	EACH
617693504	SIG STANDARD TYPE 2-A-500-4	1.00	EACH
617713095	SIG STANDARD TYPE 3-A-900-5	3.00	EACH
617763500	DETECTOR-RADAR/PRESENCE	4.00	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.00	LS
617783030	REMOVE AND RESET MISC ELECTRICAL	1.00	LS
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	8.00	EACH
618030005	TRAFFIC CONTROL DEVICES CB	75000.00	UNIT
618100008	TRAFFIC ACTUATED TEMPORARY SIGNALS	1.00	LS
619010062	SIGNS-ALUM SHEET INCR XI	131.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	538.00	SQFT
619010200	RESET SIGNS	6.00	EACH
619010230	REMOVE SIGN	97.00	EACH
619010240	REMOVE SIGN-GUIDE	6.00	EACH
619010300	POSTS-TUBULAR STEEL	100.00	LB
619010310	POSTS-STEEL U SIGN	38.00	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	521.00	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	2773.00	LB
619010480	POLES-TREATED WOOD 4 IN	480.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	32.00	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.00	EACH
619010724	FRANG SIGN POST BKWY-S5 X 10	3.00	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD	1.00	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	12.00	EACH
619011010	DELINEATOR DES A	38.00	EACH
619011040	DELINEATOR DES D	12.00	EACH

620010301	CURB MARKING-YELLOW EPOXY	20.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	37.00	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	8.00	GAL
620013960	STRIPING-WHITE EPOXY	107.00	GAL
620014960	STRIPING-YELLOW EPOXY	90.00	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	77.00	SQYD
622011084	GEOTEXTILE STABILIZATION	29979.00	SQYD
623000155	MAILBOX	8.00	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.  
 Uniform No. 8710000

**104                    SHELBY - SWEETGRASS GUARDRAIL IM-NHPB 15-8(70)354                    CONTRACT NO. 16823R**

The proposed project is located on Interstate 15 (I-15) in Toole County between RP 354.3 and RP 397.9. The project will replace guardrail and bridge rail, repair and seal bridge decks and upgrade signing. The project passes through the city limits of Shelby and Sunburst. Designated interchange ramps and crossroads will also receive guardrail and bridge treatments.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	- GUARDRAIL		
104030010	MISCELLANEOUS WORK	50000.00	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.00	LS
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
409000000	FINAL SWEEP AND BROOM	2.00	CRMI
551020107	CONCRETE-CLASS DECK	19.00	CUYD
552010160	BRIDGE DECK CRACK SEAL	19353.00	SQYD
552011010	EXPANSION JOINT STRIP SEAL	148.00	LNFT
552011120	JOINT SEALS-POLYURETHANE	164.00	LNFT
555010200	REINFORCING STEEL-EPOXY COATED	1304.00	LB
561010525	EXPANSION JOINT-PRECOMPRESSED	318.00	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	151.00	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	74.00	SQYD
603010040	DRAINAGE PIPE 18 IN	74.00	LNFT
605000040	REVISE CONCRETE BARRIER RAIL-BR	6457.00	LNFT
606010012	GUARDRAIL-STIFFENED	137.00	LNFT
606010037	MASH BOX BEAM TERMINAL - MBEAT	10.00	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	4861.00	LNFT
606010117	HIGH-TENSION CABLE RAIL	256.00	LNFT
606010140	GUARDRAIL END SECTION WIDENING	26.00	EACH
606010230	GUARDRAIL-STL/BR APPR-TY 3	11.00	EACH
606010325	GRD RL-BOX BEAM TO W-BEAM TRANS	11.00	EACH
606010330	MGS GUARDRAIL	14424.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	51.00	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	26.00	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	24.00	EACH
606010385	REMOVE GUARDRAIL	22449.00	LNFT
606010670	BOX BEAM DEPART TERM SEC	1.00	EACH
606011503	RESET TEMP IMPACT ATTENUATOR	18.00	EACH

606011518	TEMPORARY IMPACT ATTENUATOR	18.00	EACH
609010010	CURB-CONCRETE	1533.00	LNFT
609010203	REMOVE CURB	1567.00	LNFT
618030005	TRAFFIC CONTROL DEVICES CB	400000.00	UNIT
618030180	TRAFFIC CONTROL-CROSSOVER	2.00	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	2.00	MILE
618030215	WIDE LOAD MARSHALLING	1.00	LS
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	2.00	EACH
618030280	CROSSOVER RECLAMATION	2.00	EACH
618100000	SINGLE USE SIGNS	283.00	SQFT
618190100	TEMPORARY BARRIER RAIL	5620.00	LNFT
618190110	RESET TEMP BARRIER RAIL	5620.00	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	254.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1371.00	SQFT
619010230	REMOVE SIGN	112.00	EACH
619010300	POSTS-TUBULAR STEEL	825.00	LB
619010310	POSTS-STEEL U SIGN	38.00	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1362.00	LB
619010480	POLES-TREATED WOOD 4 IN	74.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	1006.00	LNFT
619010730	FRANG SIGN POST BKWY-W8 X 18	2.00	EACH
619010732	FRANG SIGN POST BKWY-W8 X 24	2.00	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD	2.00	EACH
620013960	STRIPING-WHITE EPOXY	60.00	GAL
620014960	STRIPING-YELLOW EPOXY	48.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 9966000

**105 SF 179 S OF LIBBY CURVE SFTY HSIP 1-1(107)39**

**CONTRACT NO. 01B23**

This project is located on highway 2 south of Libby, beginning at RP 38.5 and continuing North to RP 39.0. This will improve roadside safety on the west side of the roadway by widening the shoulder, flattening roadside slopes, replacing guardrail, and installing shoulder rumble strips in the new shoulder. The existing signing and delineation will be replaced on the west side and new curve warning signing will also be installed.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO.	0001 - ROADWAY SAFETY IMPROVEMENTS		
104030010	MISCELLANEOUS WORK	15000.00	UNIT
104030015	REMOVE AND RESET MISC ITEMS	1.00	LS
109200005	MOBILIZATION	1.00	LS
201130005	CLEARING AND GRUBBING	0.00	ACRE
203020375	EMBANKMENT IN PLACE	3864.00	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	823.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
301020340	CRUSHED AGGREGATE COURSE	1038.00	CUYD
401020162	COMMERCIAL MIX-1/2 IN-PG 58V-34	288.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	175.00	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	560.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	13.00	TON
409000020	COVER-TYPE 2	7515.00	SQYD

411011135	RUMBLE STRIPS	0.00	MILE
603000015	18 INCH - LINER PIPE	119.00	LNFT
603000060	FOUNDATION MATERIAL	38.00	CUYD
603010040	DRAINAGE PIPE 18 IN	38.00	LNFT
603012530	RCP 18 IN	44.00	LNFT
603587020	REMOVE PIPE CULVERT	5.00	LNFT
606010330	MGS GUARDRAIL	200.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	2.00	EACH
606010385	REMOVE GUARDRAIL	287.00	LNFT
610100101	SEEDING AREA NO 1	0.00	ACRE
610100103	SEEDING AREA NO 3	0.00	ACRE
610100326	FERTILIZING AREA NO 1	0.00	ACRE
610100555	CONDITION SEEDBED SURFACE	1.00	ACRE
618030005	TRAFFIC CONTROL DEVICES CB	200000.00	UNIT
619010090	SIGNS-ALUM REFL SHEET XI	42.00	SQFT
619010230	REMOVE SIGN	3.00	EACH
619010480	POLES-TREATED WOOD 4 IN	70.00	LNFT
619011010	DELINEATOR DES A	22.00	EACH
619011040	DELINEATOR DES D	2.00	EACH
620012955	TEMPORARY STRIPING	2334.00	LNFT
620013000	STRIPING-WHITE PAINT	19.00	GAL
620013960	STRIPING-WHITE EPOXY	25.00	GAL
620014000	STRIPING-YELLOW PAINT	17.00	GAL
620014960	STRIPING-YELLOW EPOXY	23.00	GAL
622011084	GEOTEXTILE STABILIZATION	94.00	SQYD
623000180	MAILBOX-LARGE	5.00	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
Uniform No. 9637000

INVITATION FOR BIDS  
LETTING OF DECEMBER 7, 2023  
-----

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on . All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration  
-----

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION  
Loran Frazier, Chairperson  
Montana Transportation Commission

Malcolm "Mack" Long  
Director of Transportation

Mill & fill, resurfacing, guardrail, rumble strips, signage replacement, and pavement markings on the Columbus - East project located in Stillwater County. The project begins west of the Columbus Interchange at RP 408.0 and extends approximately 8.7 miles east along I-90 to RP 417.0. Signing replacement on the project will begin at RP 408.0 and extend approximately 18.6 miles east along I-90 to the west bridge end of the Park City Interchange at RP 426.6.

## INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	- BRIDGE RESURFACING, MILL & FILL, GUARDRAIL AND RUMBLE STRIPS		
103000000	TRAINING PROGRAM	500.00	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.00	LS
104030010	MISCELLANEOUS WORK	50000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020000	GRADER-MOTOR	7.00	HOURL
210020170	TEST TRAILER-TRANSPORT, SETUP	80.00	MILE
301020340	CRUSHED AGGREGATE COURSE	175.00	CUYD
401020045	PLANT MIX SURF-3/4 IN	59514.00	TON
401020046	PLANT MIX BIT SURF-MISC	246.00	TON
401020300	HYDRATED LIME	837.00	TON
402020095	ASPHALT CEMENT PG 70-28	2924.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	23191.00	GAL
402020368	EMULSIFIED ASPHALT CRS-2P	791.00	TON
402020375	EMULSIFIED ASPHALT CHFRS-2P	724.00	TON
409000000	FINAL SWEEP AND BROOM	17.00	CRMI
409000010	COVER-TYPE 1	442984.00	SQYD
409000020	COVER-TYPE 2	407276.00	SQYD
411010000	COLD MILLING	430355.00	SQYD
411011135	RUMBLE STRIPS	34.00	MILE
552010160	BRIDGE DECK CRACK SEAL	2753.00	SQYD
552011120	JOINT SEALS-POLYURETHANE	158.00	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	4.00	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	3.00	SQYD
605000045	REVISE CONC BARRIER RAIL END-BR	8.00	EACH
606010330	MGS GUARDRAIL	19187.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	52.00	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.00	EACH
606010385	REMOVE GUARDRAIL	20825.00	LNFT
609010112	CURB 4 IN-CONCRETE	225.00	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
618030180	TRAFFIC CONTROL-CROSSOVER	6.00	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	17.00	MILE
618030215	WIDE LOAD MARSHALLING	1.00	LS
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	3.00	EACH
618030280	CROSSOVER RECLAMATION	3.00	EACH
618100000	SINGLE USE SIGNS	188.00	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	2159.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1385.00	SQFT
619010230	REMOVE SIGN	133.00	EACH
619010240	REMOVE SIGN-GUIDE	29.00	EACH
619010300	POSTS-TUBULAR STEEL	491.00	LB
619010310	POSTS-STEEL U SIGN	1461.00	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	2343.00	LB
619010480	POLES-TREATED WOOD 4 IN	132.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	72.00	LNFT
619010724	FRANG SIGN POST BKWY-S5 X 10	2.00	EACH
619010734	FRANG SIGN POST BKWY-W12 X 30	2.00	EACH
619010740	FRANG SIGN POST BKWY-3 IN RD	1.00	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD	2.00	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD	1.00	EACH

619011010	DELINEATOR DES A	621.00	EACH
619011020	DELINEATOR DES B	74.00	EACH
619011040	DELINEATOR DES D	16.00	EACH
619011070	DELINEATOR DES G	91.00	EACH
619011080	DELINEATOR DES H	560.00	EACH
619011085	DELINEATOR DES BJ	69.00	EACH
619011087	DELINEATOR DES GJ	44.00	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	2.00	EACH
619011160	TOP MTD BARRIER DELIN-SGL FACE-YELLOW	6.00	EACH
619011161	TOP MTD BARRIER DELIN-SGL FACE-WHITE	6.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	4.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	5.00	GAL
620012955	TEMPORARY STRIPING	104900.00	LNFT
620013000	STRIPING-WHITE PAINT	451.00	GAL
620013960	STRIPING-WHITE EPOXY	601.00	GAL
620014000	STRIPING-YELLOW PAINT	364.00	GAL
620014960	STRIPING-YELLOW EPOXY	486.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.  
Uniform No. 9859000

**102 ROSEBUD INTERCHANGE - EAST IM 94-3(82)104**

**CONTRACT NO. 18R23**

Mill/overlay, seal & cover rumble strips, guardrail, signing, pavement markings, and ADA upgrades on the Rosebud Interchange - East located in Rosebud County. This project begins at exit 103 - Rosebud creek road interchange (RP 103.9) at the west end of the interchange bridge and extends to east of the Hathaway rest area (RP 115.5).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO.	0001 - MILL/OVERLAY, SEAL & COVER, RUMBLE STRIPS		
104030010	MISCELLANEOUS WORK	20000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
202020058	REMOVE GUARD ANGLE	338.00	LNFT
202020095	REMOVE BRIDGE APPROACH SLAB	672.00	SQYD
203020278	EXCAVATION-DIGOUTS	5214.00	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	60.00	MILE
301020340	CRUSHED AGGREGATE COURSE	240.00	CUYD
401020045	PLANT MIX SURF-3/4 IN	42618.00	TON
401020300	HYDRATED LIME	597.00	TON
402020095	ASPHALT CEMENT PG 70-28	2008.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	16719.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	505.00	TON
409000000	FINAL SWEEP AND BROOM	12.00	CRMI
409000020	COVER-TYPE 2	284773.00	SQYD
411010000	COLD MILLING	303094.00	SQYD
411011135	RUMBLE STRIPS	22.00	MILE
552010140	TRANSVERSE DECK GROOVING	542.00	SQYD
552010160	BRIDGE DECK CRACK SEAL	1803.00	SQYD
561020110	BRIDGE DECK MILLING	572.00	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	83.00	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.00	SQYD

563000010	CONCRETE-CLASS OVERLAY	572.00	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.00	UNIT
605000040	REVISE CONCRETE BARRIER RAIL-BR	1046.00	LNFT
606010020	GUARDRAIL-TEMPORARY	75.00	LNFT
606010021	TEMP GD RAIL-STL/BR APPR-TY 1	3.00	EACH
606010024	TEMP OPTIONAL TERM SECT	3.00	EACH
606010037	MASH BOX BEAM TERMINAL - MBEAT	34.00	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	17676.00	LNFT
606010150	GUARDRAIL-STL/BR APPR-TY 1	8.00	EACH
606010268	GRD RL-BOX BEAM/BR APP-SEC-TYPE 3	17.00	EACH
606010330	MGS GUARDRAIL	1550.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	25.00	EACH
606010385	REMOVE GUARDRAIL	19019.00	LNFT
606010670	BOX BEAM DEPART TERM SEC	1.00	EACH
608010020	SIDEWALK-CONCRETE 4 IN	69.00	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	1.00	SQYD
609010200	CURB AND GUTTER-CONC	80.00	LNFT
611010200	REMOVE CATTLE GUARD	4.00	EACH
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
618030180	TRAFFIC CONTROL-CROSSOVER	4.00	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	12.00	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	2.00	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	2.00	EACH
618030280	CROSSOVER RECLAMATION	4.00	EACH
619010062	SIGNS-ALUM SHEET INCR XI	980.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	728.00	SQFT
619010200	RESET SIGNS	1.00	EACH
619010230	REMOVE SIGN	78.00	EACH
619010240	REMOVE SIGN-GUIDE	17.00	EACH
619010300	POSTS-TUBULAR STEEL	218.00	LB
619010310	POSTS-STEEL U SIGN	498.00	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	148.00	LB
619010480	POLES-TREATED WOOD 4 IN	146.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	204.00	LNFT
619011010	DELINEATOR DES A	173.00	EACH
619011020	DELINEATOR DES B	17.00	EACH
619011040	DELINEATOR DES D	8.00	EACH
619011070	DELINEATOR DES G	56.00	EACH
619011080	DELINEATOR DES H	153.00	EACH
619011085	DELINEATOR DES BJ	50.00	EACH
619011087	DELINEATOR DES GJ	33.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	6.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.00	GAL
620013000	STRIPING-WHITE PAINT	630.00	GAL
620013960	STRIPING-WHITE EPOXY	420.00	GAL
620014000	STRIPING-YELLOW PAINT	470.00	GAL
620014960	STRIPING-YELLOW EPOXY	315.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.

Uniform No. 9403000



The Lame Deer - East project is a 12.4-mile-long resurfacing project on US Highway 212 on the Northern Cheyenne Indian Reservation in Rosebud County beginning just east of the junction with MT 39 at reference post 42.3 and extending 12.4 miles east ending at reference post 54.7. This project will include an overlay and chip seal.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RESURFACING			
104030010	MISCELLANEOUS WORK	30000.00	UNIT
109200005	MOBILIZATION	1.00	LS
202020140	REMOVE BITUMINOUS PAVEMENT	6871.00	SQYD
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020000	GRADER-MOTOR	20.00	HOURL
210020170	TEST TRAILER-TRANSPORT, SETUP	216.00	MILE
301020416	SHOULDER GRAVEL	1664.00	CUYD
401020045	PLANT MIX SURF-3/4 IN	46635.00	TON
401020046	PLANT MIX BIT SURF-MISC	374.00	TON
401020300	HYDRATED LIME	658.00	TON
402020095	ASPHALT CEMENT PG 70-28	2722.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	34103.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	513.00	TON
409000000	FINAL SWEEP AND BROOM	12.00	CRMI
409000010	COVER-TYPE 1	288506.00	SQYD
411010000	COLD MILLING	6342.00	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	12.00	MILE
411011135	RUMBLE STRIPS	24.00	MILE
563000050	HIGH FRICTION SURFACE TREATMENT	4869.00	SQYD
606010037	MASH BOX BEAM TERMINAL - MBEAT	42.00	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	1512.00	LNFT
606010370	RESET GUARDRAIL	16776.00	LNFT
606010385	REMOVE GUARDRAIL	2024.00	LNFT
609010203	REMOVE CURB	11604.00	LNFT
617000110	REVISE WEATHER MONITORING SYSTEM	1.00	LS
618030005	TRAFFIC CONTROL DEVICES CB	750000.00	UNIT
618100005	PORTABLE VARIABLE MESSAGE SIGN	7.00	EACH
619010062	SIGNS-ALUM SHEET INCR XI	283.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	398.00	SQFT
619010200	RESET SIGNS	9.00	EACH
619010230	REMOVE SIGN	57.00	EACH
619010240	REMOVE SIGN-GUIDE	12.00	EACH
619010310	POSTS-STEEL U SIGN	240.00	LB
619010480	POLES-TREATED WOOD 4 IN	434.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	168.00	LNFT
619011010	DELINEATOR DES A	189.00	EACH
619011040	DELINEATOR DES D	88.00	EACH
619011060	DELINEATOR DES F	270.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	16.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	10.00	GAL
620012955	TEMPORARY STRIPING	65472.00	LNFT
620013000	STRIPING-WHITE PAINT	958.00	GAL
620013960	STRIPING-WHITE EPOXY	639.00	GAL
620014000	STRIPING-YELLOW PAINT	604.00	GAL
620014960	STRIPING-YELLOW EPOXY	403.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%. All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator. Uniform No. 9936000

104 SAINT REGIS - PARADISE STPP STWD(903)

CONTRACT NO. 20R23

The Saint Regis - Paradise project will perform the following work in Mineral and Sanders Counties: Overlay the existing pavement with new pavement, followed by a chip seal and fog seal on MT-200 (P-6) from reference post 82.4 to 85.4. Other work will include pavement markings, bridge deck crack seal, guardrail, shoulder and centerline rumble strips and revegetation. Chip seal and fog seal (no fog seal for 0.8-miles within the Town of St. Regis) the existing pavement on MT-135 (P-35) from reference post 0.0 to 11.1. Other work will include pavement markings, new drainage (sump), guardrail and revegetation. Crack seal, chip seal and fog seal the existing pavement on Cold Creek Road (X-31006) from reference post 0.0 to 0.3. Other work will include pavement markings. All work on Cold Creek Road is 100% state-funded.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 -	PMS OVERLAY, SEAL & COVER, & FOG SEAL		
104030010	MISCELLANEOUS WORK	15000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
203020100	EXCAVATION-UNCLASSIFIED	60.00	CUYD
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010005	PAR BMP ADMINISTRATION-LS	1.00	LS
208010015	AQUATIC RESOURCE MONITOR	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020000	GRADER-MOTOR	8.00	HOURL
210020170	TEST TRAILER-TRANSPORT, SETUP	140.00	MILE
301020416	SHOULDER GRAVEL	407.00	CUYD
401020046	PLANT MIX BIT SURF-MISC	162.00	TON
401020048	PLANT MIX SURF-1/2 IN	7899.00	TON
401020300	HYDRATED LIME	112.00	TON
402020192	ASPHALT CEMENT PG 58V-34	456.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	3243.00	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	18577.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	463.00	TON
403010255	CRACK SEALING	300.00	LB
409000000	FINAL SWEEP AND BROOM	0.00	CRMI
409000010	COVER-TYPE 1	259799.00	SQYD
411010000	COLD MILLING	9701.00	SQYD
411011135	RUMBLE STRIPS	4.00	MILE
411011145	SINUSOIDAL RUMBLE STRIPS	2.00	MILE
552010160	BRIDGE DECK CRACK SEAL	6951.00	SQYD
604010662	DROP INLET FRAME AND GRATE	1.00	EACH
606010140	GUARDRAIL END SECTION WIDENING	10.00	EACH
606010150	GUARDRAIL-STL/BR APPR-TY 1	8.00	EACH
606010330	MGS GUARDRAIL	2812.00	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	10.00	EACH
606010386	REMOVE AND SALVAGE GUARDRAIL	3477.00	LNFT
610100559	REVEGETATION	1.00	LS
618030005	TRAFFIC CONTROL DEVICES CB	175000.00	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	4.00	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	4.00	EACH
620010301	CURB MARKING-YELLOW EPOXY	13.00	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	14.00	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	10.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	12.00	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	7.00	GAL
620012955	TEMPORARY STRIPING	14551.00	LNFT
620013000	STRIPING-WHITE PAINT	1151.00	GAL
620013960	STRIPING-WHITE EPOXY	1171.00	GAL
620014000	STRIPING-YELLOW PAINT	827.00	GAL
620014960	STRIPING-YELLOW EPOXY	833.00	GAL
699010230	SUMP	1.00	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.  
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:  
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
 Uniform No. 10235000

**105 DODSON - SOUTH STPS 204-1(6)0 CONTRACT NO. 08R23R**  
**DODSON SOUTH CANAL - 1M S DODSON STPB 204-1(4)1**

STPS 204-1(6)0 The Dodson-South project is a 1.6-mile-long mill, overlay, and seal & cover project on Montana Secondary Highway 204 (Stage Rd.) in Phillips County. This project begins at RP 1.6, just south of the intersection of S-204 and S Wagner Rd and ends at RP 0.0, at the intersection of US 2 (N-1) and S-204.

STPB 204-1(4)1 The Dodson South Canal - 1M S Dodson project is the replacement of the existing bridge over Dodson Canal on Secondary Highway 204 (Stage Road) with a concrete box culvert. The existing bridge, crossing the Dodson South Canal, in Phillips County, is approximately 1.5 miles south of Dodson. The work will also include reconstruction of the roadway approaching the new structure.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO.	0001 - RESURFACING - ASPHALT, SIGNING		
104030010	MISCELLANEOUS WORK	20000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
202020041	REMOVE STRUCTURE	1.00	LS
203020375	EMBANKMENT IN PLACE	2144.00	CUYD
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
208010486	STREAMBED MATERIAL	73.00	CUYD
210020000	GRADER-MOTOR	5.00	HOUR
210020170	TEST TRAILER-TRANSPORT, SETUP	280.00	MILE
301020340	CRUSHED AGGREGATE COURSE	132.00	CUYD
301020450	SPECIAL BACKFILL	878.00	CUYD
401020122	COMMERCIAL MIX-PG 58V-34	2623.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1384.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	41.00	TON
409000000	FINAL SWEEP AND BROOM	1.00	CRMI
409000010	COVER-TYPE 1	23296.00	SQYD
411010000	COLD MILLING	24248.00	SQYD
552010041	REVISE JOINT	53.00	LNFT
552010140	TRANSVERSE DECK GROOVING	588.00	SQYD
552011120	JOINT SEALS-POLYURETHANE	56.00	LNFT
557010505	REVISE BRIDGE RAIL-THRIE BEAM	493.00	LNFT
561010525	EXPANSION JOINT-PRECOMPRESSED	56.00	LNFT
561020110	BRIDGE DECK MILLING	639.00	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.00	SQYD
563000010	CONCRETE-CLASS OVERLAY	639.00	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.00	UNIT
603000050	GRANULAR BEDDING MATERIAL	88.00	CUYD
603000060	FOUNDATION MATERIAL	176.00	CUYD
603013415	REIN CONC BOX 14 X 10 DBL	70.00	LNFT
604000100	ADJUST MANHOLE	2.00	EACH
606010037	MASH BOX BEAM TERMINAL - MBEAT	4.00	EACH
606010041	GUARDRAIL-BOX BEAM/8 FT POST	72.00	LNFT
606010140	GUARDRAIL END SECTION WIDENING	4.00	EACH
606010325	GRD RL-BOX BEAM TO W-BEAM TRANS	4.00	EACH

606010342	MASH THRIE BEAM BR APPRCH SECTION	4.00	EACH
606010385	REMOVE GUARDRAIL	226.00	LNFT
610100559	REVEGETATION	1.00	LS
618030015	TRAFFIC CONTROL-FIXED	500.00	UNIT
618030080	TRAFFIC CONTROL-LS	1.00	LS
619010062	SIGNS-ALUM SHEET INCR XI	39.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	286.00	SQFT
619010230	REMOVE SIGN	30.00	EACH
619010240	REMOVE SIGN-GUIDE	1.00	EACH
619010310	POSTS-STEEL U SIGN	20.00	LB
619010480	POLES-TREATED WOOD 4 IN	362.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	176.00	LNFT
619011010	DELINEATOR DES A	45.00	EACH
619011040	DELINEATOR DES D	12.00	EACH
619011060	DELINEATOR DES F	7.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	3.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	4.00	GAL
620012955	TEMPORARY STRIPING	8983.00	LNFT
620013000	STRIPING-WHITE PAINT	58.00	GAL
620013960	STRIPING-WHITE EPOXY	78.00	GAL
620014000	STRIPING-YELLOW PAINT	100.00	GAL
620014960	STRIPING-YELLOW EPOXY	106.00	GAL
622011084	GEOTEXTILE STABILIZATION	560.00	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.

Uniform No. 9553001, 10226000

**106 STILLWATER RIVER - NORTH NH 5-3(161)118**

**CONTRACT NO. 16R23**

This project on National Highway Route 5\US 93 consists of resurfacing of the existing roadway includes mill, plant-mix overlay, and seal and cover. This project is located in Flathead County starting just north of the intersection of Reserve Drive and US 93 North in Kalispell going north for 1.6 miles from reference point 117.7 to 119.3.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
-----			
SECTION NO. 0001	PAVEMENT SEAL AND COVER		
104030010	MISCELLANEOUS WORK	15000.00	UNIT
108000010	STRUCTURE ANALYSIS	1.00	LS
109200005	MOBILIZATION	1.00	LS
208010000	BMP ADMINISTRATION-LS	1.00	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.00	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	15.00	MILE
401020048	PLANT MIX SURF-1/2 IN	7078.00	TON
401020300	HYDRATED LIME	99.00	TON
402020095	ASPHALT CEMENT PG 70-28	354.00	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	2732.00	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	5804.00	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	137.00	TON
409000020	COVER-TYPE 2	77226.00	SQYD
411010000	COLD MILLING	56051.00	SQYD
411011145	SINUSOIDAL RUMBLE STRIPS	4.00	MILE
552010160	BRIDGE DECK CRACK SEAL	1110.00	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	2.00	SQYD
606011503	RESET TEMP IMPACT ATTENUATOR	1.00	EACH

606011518	TEMPORARY IMPACT ATTENUATOR	1.00	EACH
618030005	TRAFFIC CONTROL DEVICES CB	150000.00	UNIT
618100000	SINGLE USE SIGNS	84.00	SQFT
618100001	MOTORCYCLE ADVISORY SIGN	2.00	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.00	EACH
618190100	TEMPORARY BARRIER RAIL	170.00	LNFT
618190110	RESET TEMP BARRIER RAIL	170.00	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	114.00	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	155.00	SQFT
619010200	RESET SIGNS	2.00	EACH
619010230	REMOVE SIGN	20.00	EACH
619010240	REMOVE SIGN-GUIDE	4.00	EACH
619010300	POSTS-TUBULAR STEEL	406.00	LB
619010310	POSTS-STEEL U SIGN	88.00	LB
619010480	POLES-TREATED WOOD 4 IN	152.00	LNFT
619010490	POLES-TREATED WOOD 5 IN	114.00	LNFT
619010742	FRANG SIGN POST BKWY-3.5 IN RD	4.00	EACH
619011010	DELINEATOR DES A	36.00	EACH
619011040	DELINEATOR DES D	42.00	EACH
619011080	DELINEATOR DES H	42.00	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	61.00	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	39.00	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	67.00	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	43.00	GAL
620012955	TEMPORARY STRIPING	17018.00	LNFT
620013000	STRIPING-WHITE PAINT	1149.00	GAL
620013960	STRIPING-WHITE EPOXY	575.00	GAL
620014000	STRIPING-YELLOW PAINT	923.00	GAL
620014960	STRIPING-YELLOW EPOXY	446.00	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.  
Uniform No. 10233000