

July

**619.03.8 Delineators**

Furnish and install new delineators at the locations specified and marked by the Project Manager. Remove delineators conflicting with new construction as specified. Furnish and install snow poles, if required, in accordance with the Detailed Drawings.

Removed delineators are the Contractor's property.

**619.04.4 Delineators**

Delineators of each type specified are measured by the unit and include the reflector, mounting hardware, post, and snow pole, if applicable, complete in place.

Removal of existing delineators is not measured for payment.

Deleted: and