

INVITATION FOR BIDS

LETTING OF MARCH 27, 2008

Sealed bids on the following projects will be received by the Montana Department of Transportation-Highways Division, Contract Plans Bureau, Room 101, 2701 Prospect, Helena, Montana until 9:00 a.m. on March 27, 2008 the bids being publicly opened and read thereafter at 10:00 a.m. in the Department's auditorium.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans if available, and full instructions to bidders are on file for examination and may be obtained from the Contract Plans Bureau. These documents may be requested by FAX (406)444-7236, (see enclosed order form) by mail or by calling (406)444-6216, 6212, 6215 or TTY 444-7696

All bid documents are available for downloading and/or printing at no charge at the following web site: http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link. Additional bid letting information is also available on this web site.

Cost for hard copies of these documents vary with each project and is quoted in the project information contained herein. There will be no refund allowance for documents ordered and returned. Do not send cash. Please make all checks payable to the Montana Department of Transportation. Please do not send payment until billed.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor.

On Federal-aid projects, contractors must register prior to executing a contract.

On State-funded projects, bidders must be registered prior to submitting a bid.

For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

Nancy Espy, Chairperson
Montana Transportation Commission

Jim Lynch
Director of Transportation

1 **STILLWATER RIVER - NORTH**

CBI 5-3(64)118

Grading, gravel, plant mix bituminous surfacing, drainage, fencing, guardrail, pavement markings and the construction of two (2) prestressed concrete beam Type M72 bridges for southbound and northbound US 93 over Church Drive on the Stillwater River-North project located in Flathead County. The project is located approximately 5 kilometers north of Kalispell on National Highway Route 5/US 93 between RP 117.7 and RP 119.3. The length of the project is approximately 2.7 kilometers and is being reconstructed from a 2-lane to a 4-lane highway.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	GRADE, GRAVEL, PMS OVERLAY, DRAINAGE, FENCING, GUARDRAIL, S		
104100000	MISCELLANEOUS WORK	40,000.000	UNIT
104230000	DETOUR-CONST MAINTAIN AND REM	1.000	LSUM
105100200	FINISH GRADE CONTROL	17.560	CRKM
105200000	BRIDGE SURVEY	1.000	LSUM
109200000	MOBILIZATION	1.000	LSUM
203100000	EXCAVATION-UNCLASSIFIED	124,058.000	M3
203200000	EXCAVATION-UNCLASS BORROW	9,210.000	M3
203220000	SPECIAL BORROW-NEAT LINE	55,440.000	M3
203500000	TOPSOIL-SALVAGING AND PLACING	16,895.000	M3
203500100	TOPSOIL-PLACE	5,392.000	M3
207300000	BEDDING MATERIAL	56.000	M3
207320000	FILTER MATERIAL	1,005.200	M3
208106000	MPDES PERMIT FEES	900.000	UNIT
208106050	TEMPORARY EROSION CONTROL - LS	1.000	LSUM
210300000	TEST TRAILER-TRANSPORT,SETUP	8.000	KM
301270000	CRUSHED AGGREGATE COURSE	31,590.000	M3
301440010	COVER - TYPE 1	70,339.000	M2
301700000	TRAFFIC GRAVEL	2,500.000	M3
301750000	BRIDGE END BACKFILL	1,314.000	M3
401080000	PLANT MIX BIT SURF GR S - 19 MM	20,828.000	MT
401100000	DUST PALLIATIVE	142.700	MT
401200000	HYDRATED LIME	292.000	MT
401320000	PAVEMENT PULVERIZATION	15,317.000	M2
402097000	ASPHALT CEMENT PG 70-28	1,250.000	MT
402200000	EMULSIFIED ASPHALT SS-1	18,081.000	L
402225000	EMULSIFIED ASPHALT CRS-2P	129.100	MT
551175000	CONCRETE-CLASS DD	229.600	M3
551410000	CONCRETE-CLASS SD	274.600	M3
552150000	TRANSVERSE DECK GROOVING	886.000	M2
552600000	ELASTOMERIC BEARING DEVICES	24.000	EACH
553040000	PRESTRESSED BEAM-TYPE M-72	516.000	M
555100000	REINFORCING STEEL	16,194.000	KG
555200000	REINFORCING STEEL-EPOXY COATED	38,392.000	KG
559233630	FURN STL PILE HP 360 X 152 MM	704.000	M
559333630	DR STL PILE HP 360 X 152 MM	688.000	M
559556000	PILE DRIVING POINT	32.000	EACH
559640000	DYNAMIC LOAD TEST	4.000	EACH
602010000	REMOVE PIPE CULVERTS	139.000	M
602050000	PLUG AND ABANDON	87.000	M
603004500	DRAINAGE PIPE 450 MM	483.000	M
603006000	DRAINAGE PIPE 600 MM	189.000	M
603008900	DRAINAGE PIPE 900 MM	70.000	M
603100451	CSP 450 MM X 1.63 MM	7.000	M
603100920	CSP 900 MM X 2.01 MM	56.000	M
603101220	CSP 1200 MM X 2.01 MM	16.500	M
603444530	RCP IRR 450 MM CL 3	85.300	M
603446030	RCP IRR 600 MM CL 3	161.200	M
603640150	CORR PLAST PIPE 150 MM PERF	1,489.000	M
603806030	CONNECT TO EXIST MANHOLE	1.000	EACH
603814500	STEEL CASING 450 MM	110.000	M

604011200	MANHOLE-1200 MM-TYPE 1	1.000	EACH
604240000	INLET-DROP-TYPE 4	2.000	EACH
604320000	INLET-CURB-TYPE 2	3.000	EACH
604510000	INLET-MEDIAN-TYPE 1	2.000	EACH
604520000	INLET-MEDIAN-TYPE 2	4.000	EACH
604801000	OIL/WATER SEPARATOR	1.000	LSUM
606000000	GUARD RAIL-STEEL	363.860	M
606110000	GUARD RAIL-STL/BR APPR-TY 1	8.000	EACH
606190000	ONE-WAY DEPART TERM SECTION	4.000	EACH
606250000	GUARD RAIL-OPTIONAL TERM SECT	4.000	EACH
606800000	REMOVE GUARD RAIL	91.300	M
606900000	TEMP METAL GUARDRAIL	45.720	M
606940000	TEMP GD RAIL-STL/BR APPR-TY 1	2.000	EACH
606950000	TEMP OPTIONAL TERM END SECTION	2.000	EACH
607204000	FARM FENCE-TYPE F4W	2,108.100	M
607211000	FARM FENCE-PANEL/SINGLE FW	30.000	EACH
607212000	FARM FENCE-PANEL/DOUBLE FW	18.000	EACH
607300200	FARM GATE-WIRE-TYPE G-2	4.800	M
607300300	FARM GATE-METAL-TYPE G-3	39.600	M
607490000	DEADMAN	22.000	EACH
607602813	FARM FENCE-TYPE F2W-813 MM WW	141.700	M
607700000	REMOVE FENCE	4.800	M
608100000	SIDEWALK-CONCRETE 100 MM	461.700	M2
608150000	SIDEWALK-CONCRETE 150 MM	11.000	M2
608290100	TRUNCATED DOMES	2.000	M2
609000000	CURB AND GUTTER-CONCRETE	309.600	M
610110000	SEEDING AREA NO 1	11.600	HA
610130000	SEEDING AREA NO 3	5.100	HA
610210000	FERTILIZING AREA NO 1	11.600	HA
610400000	CONDITION SEEDBED SURFACE	16.700	HA
610405010	NOXIOUS WEED CONTROL	750.000	UNIT
613010000	RIPRAP-CLASS 1 RANDOM	4.000	M3
613200000	SLOPE PROTECTION-CONCRETE	729.000	M2
618010000	TRAFFIC CONTROL-DEVICES CB	400,000.000	UNIT
618030000	TEMPORARY PAVEMENT MARKINGS	6.000	KM
618140000	SINGLE USE SIGNS	9.200	M2
619023000	SIGNS-SHEET ALUM INCR-SHT I	8.400	M2
619033000	SIGNS-SHEET ALUM REFL SHT I	3.880	M2
619034010	SIGNS-SHEET ALUM REFL SHT IV	17.050	M2
619110000	POSTS-TUBULAR STEEL	59.400	KG
619120000	POSTS-STEEL U SIGN	37.200	KG
619234000	POLES-TRD TMBR-BARN 100 MM	108.000	M
619235500	POLES-TRD TMBR-BARN 130 MM	61.300	M
619340000	FRANG SIGN POST BKWY 102 MM RD	1.000	EACH
619511000	DELINEATOR-DES A	42.000	EACH
619512000	DELINEATOR-DES B	23.000	EACH
619513000	DELINEATOR-DES C	30.000	EACH
619514000	DELINEATOR-DES D	4.000	EACH
619560200	DELINEATOR-FLEX DRIVABLE YLW	35.000	EACH
619700000	REMOVE SIGNS	28.000	EACH
619720000	RESET SIGNS	5.000	EACH
620010000	STRIPING-WHITE PAINT	942.000	L
620020000	STRIPING-YELLOW PAINT	660.000	L
620030000	WORDS AND SYMBOLS-WHITE PAINT	31.000	L
620110000	STRIPING-WHITE EPOXY	847.000	L
620120000	STRIPING-YELLOW EPOXY	645.000	L
620130000	WORDS/SYMBOLS-WHITE EPOXY	19.000	L
620710000	REMOVE PAVEMENT MARKINGS	300.000	M
621030000	REMOVE DROP INLETS	1.000	EACH
622020000	SUBSURFACE DRAIN FILTER-HIGH SURV	5,137.000	M2
622220000	GEOTEXTILE STABILIZATION	2,500.000	M2
622520020	GEOTECH-MISCELLANEOUS WORK	1.000	LSUM
800020000	CRITICAL PATH SCHEDULE	1.000	LSUM
800060000	MAILBOX	5.000	EACH
800080000	RUMBLE STRIPS	8.100	KM
800315000	MISCELLANEOUS ITEMS - INSTALL	103,012.000	M2

Contract to be completed in 200 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of plans and proposal \$15.00. Cross-sections \$7.00.

Large plans \$27.00. Dirt Runs \$10.00. Erosion Control Plans \$3.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the MISSOULA District Administrator.
Contract No. 13308 Uniform No. C061

**2 HARDIN - EAST, STPS-HSIP 384-1(18)0
ST. XAVIER - N & S, SFCS 313-1(18)22
HARDIN - SOUTH, SFCS 313-1(19)0**

STPS-HSIP 384-1(18)0 - Mill and fill, seal and cover and fencing on the Hardin-East project located in Bighorn County. The project is located on State Secondary 384 beginning at RP 0.0 extending east 11.7 miles ending at RP 12.6.

SFCS 313-1(18)22 - Overlay, seal and cover and replace culverts on the St. Xavier-N & S project located in Bighorn County. The project is located on State Secondary 313 beginning at RP 22.0 extending east and north 7.0 miles ending at RP 29.0.

SFCS 313-1(19)0 - Mill and fill, seal and cover and ADA improvements on the Hardin-South project located in Bighorn County. The project is located on State Secondary 313 beginning at RP 0.0 extending north and east 1.4 miles ending at RP 1.4.

MANDATORY PRE-BID CONFERENCE

A pre-bid conference will be held at the following time and location:

Monday, March 3, 2008, 10:00am, Montana Dept. of Transportation, Billings Office - Conference Room, 424 Morey Street, Billings Montana. Representatives of MDT and the Apsaalooke Nation Tribe will be present to describe the project and answer questions.

The pre-bid conference will have a formal sign-in process that will become the official record of attendance for the purposes of determining eligible bidders.

Attendance at this conference is mandatory for any contractor to submit a bid as a prime. Contractors who bid as a prime bidder on this project must have at least one full time, permanent employee present. No proxy representatives, such as subcontractors or consultants, meet this requirement. In the event a bidder tenders a bid but did not attend the pre-bid conference, the bid will be returned unopened.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	MILL & FILL, SEAL & COVER		
050110010	TRAINING PROGRAM	500.000	HOURL
104030010	MISCELLANEOUS WORK	40,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
207010200	BEDDING MATERIAL	330.000	CUYD
210020000	GRADER-MOTOR	40.000	HOURL
210020170	TEST TRAILER-TRANSPORT, SETUP	126.000	MILE
301020340	CRUSHED AGGREGATE COURSE	201.000	CUYD
301020718	COVER - TYPE 1	325,456.000	SQYD
301020735	COVER - TYPE 2	26,401.000	SQYD
401020045	PLANT MIX BIT SURF GR S - 3/4 IN	58,029.000	TON
401020300	HYDRATED LIME	812.000	TON
402020092	ASPHALT CEMENT PG 64-28	3,133.000	TON
402020305	EMULSIFIED ASPHALT SS-1	14.000	GAL
402020368	EMULS ASPHALT CRS-2P	598.300	TON
402020478	TRANSVERSE CRACK SEALING	22,530.000	LNFT
411010000	COLD MILLING	39,707.000	SQYD

551020030	CONCRETE-CLASS DD	12.400	CUYD
551020126	FLOWABLE FILL	652.000	CUYD
557010542	REV BRIDGE RAIL-CONC BARRIER	370.000	LNFT
561010454	RESEAL EXISTING JOINTS	52.000	LNFT
602010010	REMOVE PIPE CULVERTS	987.000	LNFT
602010030	RELAY PIPE CULVERT	8.000	LNFT
603010692	CSP 84 IN 0.079	210.000	LNFT
603012530	RCP 18 IN CLASS 2	80.000	LNFT
603012555	RCP 24 IN CLASS 2	268.000	LNFT
603012610	RCP 30 IN CLASS 2	201.000	LNFT
603012645	RCP 36 IN CLASS 2	211.000	LNFT
606010030	GUARD RAIL-STEEL	275.000	LNFT
606010047	GD RAIL-STL INT RDWY TERM SECT	62.500	LNFT
606010150	GUARD RAIL-STL/BR APPR-TY 1	4.000	EACH
606010230	GUARD RAIL-STL/BR APPR-TY 3	4.000	EACH
606010385	REMOVE GUARD RAIL	837.500	LNFT
606010642	GUARD RAIL-OPTIONAL TERM SECT	7.000	EACH
607100252	FARM FENCE-TYPE F4M	72,568.200	LNFT
607100281	FARM FENCE-TYPE F5M	36,162.300	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	200.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	78.000	EACH
607100430	FARM GATE-WIRE TYPE G-2	398.000	LNFT
607100720	DEADMAN	41.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	192.100	SQYD
608010125	TRUNCATED DOMES	19.700	SQYD
611010016	CATTLE GUARD 16 FT	12.000	EACH
611010024	CATTLE GUARD 24 FT	2.000	EACH
611010200	REMOVE CATTLE GUARD	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	380,000.000	UNIT
618100000	SINGLE USE SIGNS	187.000	SQFT
619011010	DELINEATOR DES A	178.000	EACH
619011030	DELINEATOR DES C	36.000	EACH
619011060	DELINEATOR DES F	34.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	49.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	42.000	GAL
620011260	WORDS/SYMBOLS-WHITE EPOXY	28.000	GAL
620013000	STRIPING-WHITE PAINT	1,652.000	GAL
620013960	STRIPING-WHITE EPOXY	1,061.000	GAL
620014000	STRIPING-YELLOW PAINT	858.000	GAL
620014960	STRIPING-YELLOW EPOXY	555.000	GAL
620017000	TEMPORARY PAVEMENT MARKINGS	21.900	MILE

Contract to be completed in 110 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of plans and proposal, including cross sections \$15.00. Large plans \$27.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the BILLINGS District Administrator.

Contract No. 05108

Uniform Nos. 5204, 5894000, 6247000

3 JCT US 212 - SOUTH, SFCS 484-1(10)0 ASHLAND - WEST, NH 37-2(29)55

SFCS 484-1(10)0 - Plant mix overlay, seal and cover and other improvements. The project is located on State Secondary Route 484 beginning approximately 4 miles east of Ashland at the intersection of US 212/Secondary 484 at RP 0.0 and extending south 19.8 miles to RP 19.8 in Powder River County.

NH 37-2(29)55 - Milling, plant mix bituminous surfacing, seal and cover and guardrail improvements. The project is located on US 212 (National Highway Route 37) beginning west of Ashland at RP 54.77 and extends east 8.1 miles to RP 62.79. The project is located in Rosebud County and partially within the Northern Cheyenne Indian Reservation.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PMS OVERLAY, S & C - SFCS FUNDS - 100% STATE FUNDS			
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
208010207	MPDES PERMIT FEES	4,500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	236.000	MILE
301020415	SHOULDER GRAVEL	9,498.000	TON
301020718	COVER - TYPE 1	424,806.000	SQYD
401020045	PLANT MIX BIT SURF GR S - 3/4 IN	52,101.000	TON
401020300	HYDRATED LIME	731.000	TON
402020092	ASPHALT CEMENT PG 64-28	2,812.000	TON
402020368	EMULS ASPHALT CRS-2P	719.900	TON
411010000	COLD MILLING	26,888.000	SQYD
561020210	SILANE SEALER	888.000	SQYD
606010030	GUARD RAIL-STEEL	575.000	LNFT
606010047	GD RAIL-STL INT RDWY TERM SECT	37.500	LNFT
606010190	GUARD RAIL-STL/BR APPR-TY 2	4.000	EACH
606010230	GUARD RAIL-STL/BR APPR-TY 3	4.000	EACH
606010385	REMOVE GUARD RAIL	1,155.000	LNFT
606010642	GUARD RAIL-OPTIONAL TERM SECT	7.000	EACH
610100557	REVEGETATION	14.800	ACRE
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
618100000	SINGLE USE SIGNS	187.000	SQFT
619010075	SIGNS-ALUM REFL SHEET (I)	32.800	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	108.500	SQFT
619010200	RESET SIGNS	1.000	EACH
619010230	REMOVE SIGNS	33.000	EACH
619010310	POSTS-STEEL U SIGN	160.000	LB
619010480	POLES-TREATED TIMBER-BARN 4 IN	204.000	LNFT
619010490	POLES-TREATED TIMBER-BARN 5 IN	16.000	LNFT
619011010	DELINEATOR DES A	254.000	EACH
619011040	DELINEATOR DES D	6.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	14.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	10.000	GAL
620011260	WORDS/SYMBOLS-WHITE EPOXY	9.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	5.000	GAL
620013000	STRIPING-WHITE PAINT	2,018.000	GAL
620013960	STRIPING-WHITE EPOXY	388.000	GAL
620014000	STRIPING-YELLOW PAINT	1,400.000	GAL
620014960	STRIPING-YELLOW EPOXY	305.000	GAL
620017000	TEMPORARY PAVEMENT MARKINGS	53.200	MILE

Contract to be completed in 75 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of proposal only \$15.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the GLENDIVE District Administrator.

Contract No. 05407

Uniform Nos. 5162000, 6240000

4 HEBGEN LAKE - EAST & WEST STPP 87-1(9)0

Plant mix overlay, seal & cover with an option for Cold In-Place recycling on the Hebgen Lake-East & West project in Madison and Gallatin Counties. The 22.4 mile project is located on US 287 (P-87) and begins in Madison County with seal and cover only between RP 0.0 and RP 6.7 (County Line). The plant mix surfacing portion in Gallatin County is between RP 6.7 and RP 22.4.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BASE BID - PAVE, CRACK SEAL, SEAL & COVER			
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
203020278	EXCAVATION - DIGOUTS	760.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	627.000	CUYD
210020170	TEST TRAILER-TRANSPORT, SETUP	180.000	MILE
301020340	CRUSHED AGGREGATE COURSE	44.000	CUYD
301020718	COVER - TYPE 1	441,157.000	SQYD
402020502	CRACK SEALING	42,564.000	LB
561020080	PREPARE DECK	1,026.200	SQYD
561020150	WATERPROOF MEMBRANE	521.900	SQYD
602010010	REMOVE PIPE CULVERTS	80.000	LNFT
603010040	DRAINAGE PIPE 18 IN	80.000	LNFT
606010030	GUARD RAIL-STEEL	112.500	LNFT
606010385	REMOVE GUARD RAIL	2,750.000	LNFT
606010642	GUARD RAIL-OPTIONAL TERM SECT	55.000	EACH
606011150	REMOVE CONC BARRIER RAIL	11.000	EACH
610100559	REVEGETATION	1.000	LSUM
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
618100000	SINGLE USE SIGNS	102.000	SQFT
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	22.000	GAL
620011260	WORDS/SYMBOLS-WHITE EPOXY	7.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	16.000	GAL
620013000	STRIPING-WHITE PAINT	1,388.000	GAL
620013960	STRIPING-WHITE EPOXY	1,003.000	GAL
620014000	STRIPING-YELLOW PAINT	810.000	GAL
620014960	STRIPING-YELLOW EPOXY	612.000	GAL
620017000	TEMPORARY PAVEMENT MARKINGS	31.000	MILE
622011084	GEOTEXTILE STABILIZATION	1,367.000	SQYD
623000023	TRANSVERSE RUMBLE STRIPS	1.000	LSUM
SECTION NO. 0002 OPTION 1 - CRACK SEAL, PMS, SEAL & COVER (MADISON-2			
401020001	DUST PALLIATIVE	1.900	TON
401020045	PLANT MIX BIT SURF GR S - 3/4 IN	38,550.000	TON
401020300	HYDRATED LIME	540.000	TON
402020092	ASPHALT CEMENT PG 64-28	2,080.900	TON
402020305	EMULSIFIED ASPHALT SS-1	59.000	GAL
402020368	EMULS ASPHALT CRS-2P	754.800	TON
411010000	COLD MILLING	304,318.000	SQYD
SECTION NO. 0003 OPTION 2 - COLD RECYCLE, CRACK SEAL, SEAL & COVER			
301020600	BLOTTER MATERIAL	2,100.000	TON
311010235	QUICK LIME	526.600	TON
401020042	PLANT MIX GR D - COMMERCIAL	989.000	TON
401020325	COLD RECYCLED PLANT MIX	292,984.000	SQYD
402020305	EMULSIFIED ASPHALT SS-1	13,725.000	GAL
402020368	EMULS ASPHALT CRS-2P	752.400	TON
402020476	RECYCLING AGENT CIR-EE	1,127.700	TON
411010000	COLD MILLING	3,797.000	SQYD

Contract to be completed in 85 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of plans and proposal \$15.00. Large plans \$20.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the BUTTE District Administrator.

Contract No. 10308

Uniform No. 5960000

**5 D4-NON-INTERSTATE-STRUCTURE REPLACEMENT
NH 0002(699)**

Grading, gravel, plant mix overlay, structure removals and culvert installations on the D4-Non-Interstate Structure Replacement project in McCone and Phillips Counties. The McCone County portion on N-57 (MT 200) begins approximately 64 km east of Jordan at RP 253.0 (Cemetery Coulee) to RP 261.7 (Beauty Creek), 10 km west of Brockway. The Phillips County portion on N-61 (US 191) begins approximately 61 km southwest of Malta at RP 119.1 (Beaver Creek) and ends 4 km south of Malta at RP 154.2 (N. Fork Taylor Creek).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	STR REPLACEMENT W/CULVERTS (N-57) - MCCONE CO.		
104100000	MISCELLANEOUS WORK	25,000.000	UNIT
104230000	DETOUR-CONST MAINTAIN AND REM	1.000	LSUM
105100200	FINISH GRADE CONTROL	1.100	CRKM
109200000	MOBILIZATION	1.000	LSUM
202011000	REMOVE STRUCTURE	1.000	LSUM
203300000	EMBANKMENT IN PLACE	39,874.000	M3
203500000	TOPSOIL-SALVAGING AND PLACING	6,710.000	M3
207300000	BEDDING MATERIAL	424.000	M3
207310000	FOUNDATION MATERIAL	269.000	M3
208105000	TEMPORARY EROSION CONTROL - CB	35,000.000	UNIT
208106000	MPDES PERMIT FEES	4,500.000	UNIT
301270000	CRUSHED AGGREGATE COURSE	2,257.000	M3
301440010	COVER - TYPE 1	3,226.000	M2
401040500	PLANT MIX GR D - COMMERCIAL	1,015.000	MT
402225000	EMULSIFIED ASPHALT CRS-2P	6.000	MT
551170000	CONCRETE-CLASS DD	12.700	M3
557420050	REVISE BRIDGE RAIL-W740	258.900	M
602010000	REMOVE PIPE CULVERTS	11.800	M
603007500	DRAINAGE PIPE 750 MM	20.500	M
603021000	DRAINAGE PIPE 2100 MM	61.500	M
603100616	CSP 600 MM X 1.63 MM	1.000	M
603100617	CSP 600 MM X 1.63 MM CTD	17.000	M
603122421	CSPA 2400 MM X 2.01 MM CTD	38.500	M
603448920	RCP IRR 900 MM CL 2	39.500	M
606140000	GRD RL-BOX BEAM/BR APP-SEC TYPE 1	20.000	EACH
606242000	GD RL BOX BEAM OPT TERM SEC	20.000	EACH
607204000	FARM FENCE-TYPE F4W	859.800	M
607204100	FARM FENCE-TYPE F4M	737.500	M
607205000	FARM FENCE-TYPE F5W	160.000	M
607205100	FARM FENCE-TYPE F5M	605.600	M
607211000	FARM FENCE-PANEL/SINGLE FW	38.000	EACH
607212000	FARM FENCE-PANEL/DOUBLE FW	38.000	EACH
607300200	FARM GATE-WIRE-TYPE G-2	38.400	M
607400000	FENCE-TEMPORARY	889.600	M
607490000	DEADMAN	3.000	EACH
607602900	FARM FENCE-TYPE F2M-990 MM WW	428.000	M
610110000	SEEDING AREA NO 1	10.500	HA
610120000	SEEDING AREA NO 2	0.500	HA
610210000	FERTILIZING AREA NO 1	10.500	HA
610222000	FERTILIZING AREA NO 2	0.500	HA
610400000	CONDITION SEEDBED SURFACE	10.500	HA
610405010	NOXIOUS WEED CONTROL	1,000.000	UNIT
613010000	RIPRAP-CLASS 1 RANDOM	11.700	M3
618020000	TRAFFIC CONTROL	1.000	LSUM
618030000	TEMPORARY PAVEMENT MARKINGS	0.900	KM
618140000	SINGLE USE SIGNS	18.400	M2
620010000	STRIPING-WHITE PAINT	242.000	L
620020000	STRIPING-YELLOW PAINT	91.000	L
622220000	GEOTEXTILE STABILIZATION	777.000	M2
624010000	STRAW COCONUT BLANKET	3,971.000	M2
800060000	MAILBOX	2.000	EACH

SECTION NO. 0002		ALTERNATE AA1 - BR REPLACEMENT W\RCB (N-61 STA 899+21)	
207300000	BEDDING MATERIAL	38.000	M3
207310000	FOUNDATION MATERIAL	76.000	M3
551170000	CONCRETE-CLASS DD	6.000	M3
603582100	REIN CONC BOX 2100 MM X 1500 MM	24.500	M
622220000	GEOTEXTILE STABILIZATION	163.000	M2
SECTION NO. 0003		ALTERNATE AA2 - BR REPLACEMENT W/CSPA (N-61 STA 899+21)	
207300000	BEDDING MATERIAL	71.000	M3
207310000	FOUNDATION MATERIAL	40.000	M3
551170000	CONCRETE-CLASS DD	6.800	M3
603122421	CSPA 2400 MM X 2.01 MM CTD	23.500	M
622220000	GEOTEXTILE STABILIZATION	146.000	M2
SECTION NO. 0004		ALTERNATE AB1 - BR REPLACEMENT W/RCB DBL (N-61 STA 163+38)	
207300000	BEDDING MATERIAL	172.000	M3
551170000	CONCRETE-CLASS DD	10.200	M3
603584215	REIN CONC BOX 4200 MM X 2100 MM DBL	46.000	M
SECTION NO. 0005		ALTERNATE AB2 - BR REPLACEMENT W/SSPPA (N-61 STA 163+38)	
207300000	BEDDING MATERIAL	445.000	M3
551170000	CONCRETE-CLASS DD	27.600	M3
603337283	SSPPA 3.810 M X 2.82 MM CTD	126.000	M
SECTION NO. 0006		ALTERNATE AC1 - BR REPLACEMENT W/RCB DBL (N-61 STA 172+93)	
207300000	BEDDING MATERIAL	127.000	M3
207310000	FOUNDATION MATERIAL	255.000	M3
551170000	CONCRETE-CLASS DD	9.500	M3
603583522	REIN CONC BX 3350 X 2100 MM DBL	39.500	M
622220000	GEOTEXTILE STABILIZATION	456.000	M2
SECTION NO. 0007		ALTERNATE AC2 - BR REPLACEMENT W/SSPPA (N-61 STA 172+93)	
207300000	BEDDING MATERIAL	274.000	M3
207310000	FOUNDATION MATERIAL	149.000	M3
551170000	CONCRETE-CLASS DD	19.600	M3
603338280	SSPPA 4.040 M X 2.82 MM CTD	60.000	M
622220000	GEOTEXTILE STABILIZATION	406.000	M2
SECTION NO. 0008		ALTERNATE AD1 - BR REPLACEMENT W/CSP (N-61 STA 110+91)	
207300000	BEDDING MATERIAL	54.000	M3
551170000	CONCRETE-CLASS DD	8.200	M3
603582424	REIN CONC BOX 2400 MM X 2400 MM	46.000	M
SECTION NO. 0009		ALTERNATE AD2 - BR REPLACEMENT W/CSP (N-61 STA 110+91)	
207300000	BEDDING MATERIAL	145.000	M3
551170000	CONCRETE-CLASS DD	12.000	M3
603103040	CSP 3000 MM X 3.51 MM CTD	41.000	M

Contract to be completed in/by 150 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of plans and proposal \$16.00. Cross-sections \$15.00.

Large plans \$27.00. Dirt Runs \$0.00. Erosion Control Plans \$3.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the GLENDALE District Administrator.
Contract No. 07308 Uniform No. L457

**6 BELT CR-4 KM N OF JCT S-331
BR 228-1(6)16**

82-meter prestressed concrete girder structure and associated approach roadwork on the Belt Creek - 4 Km N of Jct S-331 project in Cascade/Chouteau Counties. The project is located on the State Secondary Route 228 southwest of Highwood beginning at RP 16.4 and extends 0.37 km to RP 16.6.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 APPROACHES - G, GS, PMS - 51% CASCADE CO/49% CHOUTEAU CO			
104100000	MISCELLANEOUS WORK	20,000.000	UNIT
104230000	DETOUR-CONST MAINTAIN AND REM	1.000	LSUM
105100200	FINISH GRADE CONTROL	0.600	CRKM
105200000	BRIDGE SURVEY	1.000	LSUM
109200000	MOBILIZATION	1.000	LSUM
202011000	REMOVE STRUCTURE	1.000	LSUM
202341000	REMOVE EMBANKMENT PROTECTOR	14.000	M
203100000	EXCAVATION-UNCLASSIFIED	6,329.000	M3
203500000	TOPSOIL-SALVAGING AND PLACING	586.000	M3
208106000	MPDES PERMIT FEES	900.000	UNIT
208106050	TEMPORARY EROSION CONTROL - LS	1.000	LSUM
301270000	CRUSHED AGGREGATE COURSE	1,245.000	M3
301440010	COVER - TYPE 1	2,653.000	M2
401040500	PLANT MIX GR D - COMMERCIAL	675.000	MT
402225000	EMULSIFIED ASPHALT CRS-2P	5.900	MT
551175000	CONCRETE-CLASS DD	140.700	M3
551410000	CONCRETE-CLASS SD	191.200	M3
552150000	TRANSVERSE DECK GROOVING	687.900	M2
552405000	EXPANSION JOINT	10.990	M
552610000	ELASTOMERIC BEARING DEV-TFE	4.000	EACH
552701000	DRILLED SHAFT CONCRETE	175.100	M3
552722900	DRILLED SHAFT-2.29 M	37.300	M
552762290	DRILLED SHAFT CASING - 2.29 M	13.800	M
553040000	PRESTRESSED BEAM-TYPE M-72	324.000	M
555100000	REINFORCING STEEL	24,095.000	KG
555200000	REINFORCING STEEL-EPOXY COATED	21,976.000	KG
557200000	BRIDGE RAIL-T 101	165.040	M
559233110	FURN STL PILE HP 310 X 110 MM	55.200	M
559333110	DR STL PILE HP 310 X 110 MM	51.200	M
559505000	PILE DRILL AND SOCKET	12.800	M
559556000	PILE DRIVING POINT	8.000	EACH
602010000	REMOVE PIPE CULVERTS	13.000	M
603004500	DRAINAGE PIPE 450 MM	34.500	M
606000000	GUARD RAIL-STEEL	22.900	M
606015000	GUARD RAIL-STL INT RDWY TERM SECT	45.700	M
606120000	GUARD RAIL-STL/BR APPR-TY 2	4.000	EACH
606250000	GUARD RAIL-OPTIONAL TERM SECT	2.000	EACH
606440010	WATER FILLED BARRIER	83.000	M
606800000	REMOVE GUARD RAIL	152.400	M
607204000	FARM FENCE-TYPE F4W	213.000	M
607204200	FARM FENCE-TYPE F4W AND F4M	97.000	M
607211000	FARM FENCE-PANEL/SINGLE FW	11.000	EACH
607212000	FARM FENCE-PANEL/DOUBLE FW	5.000	EACH
607400000	FENCE-TEMPORARY	335.000	M
607602991	FARM FENCE-TYPE F2W-990 MM WW	164.000	M
610110000	SEEDING AREA NO 1	0.900	HA
610210000	FERTILIZING AREA NO 1	0.900	HA
610400000	CONDITION SEEDBED SURFACE	0.900	HA
613030000	RIPRAP-CLASS 3 RANDOM	2,155.000	M3
614100000	DESIGN, CONSTRUCT MSE WALLS	91.600	M2
618010000	TRAFFIC CONTROL-DEVICES CB	80,000.000	UNIT
618030000	TEMPORARY PAVEMENT MARKINGS	0.600	KM
618140000	SINGLE USE SIGNS	9.200	M2
619023000	SIGNS-SHEET ALUM INCR-SHT I	1.710	M2
619033000	SIGNS-SHEET ALUM REFL SHT I	0.540	M2
619234000	POLES-TRD TMBR-BARN 100 MM	22.200	M
619700000	REMOVE SIGNS	2.000	EACH
619702000	REMOVE SIGNS-GUIDE	1.000	EACH
620010000	STRIPING-WHITE PAINT	64.000	L
620020000	STRIPING-YELLOW PAINT	64.000	L
620110000	STRIPING-WHITE EPOXY	42.000	L
620120000	STRIPING-YELLOW EPOXY	42.000	L
622120000	PERM. EROSION CONTROL-HIGH SURV	2,715.000	M2

800010000	TRAINING PROGRAM	500.000	HOURL
800060000	MAILBOX	5.000	EACH

Contract to be completed in 140 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of plans and proposal \$15.00. Large plans \$26.00. Dirt Runs \$10.00.

Erosion Control Plans \$3.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the GREAT FALLS District Administrator.
Contract No. 11308 Uniform No. 4867

**7 HAMILTON - SOUTH, NH 7-1(113)44
DARBY - N & S, NH 7-1(109)23
CHARLO - HEIGHTS, NH 7-1(111)39**

NH 7-1(113)44 - Leveling, plant mix surfacing overlay, crushing and stockpiling of cover material, and guardrail improvements. The project is located on US 93 (National Highway Route 7) beginning south of Hamilton at RP 43.7 and extends 2.3 miles north to RP 46.0.

NH 7-1(109)23 - Seal and cover and guardrail improvements. The project is located on US 93 (National Highway Route 7) beginning south of Darby at RP 23.2 and extending north 15.5 miles to RP 38.7.

NH 7-1(111)39 - Seal and cover and guardrail improvements. The project is located on US 93 (National Highway Route 7) beginning south of Hamilton at RP 38.7 and extends north 5.0 miles to RP 43.7. All three projects are located within Ravalli County.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	SEAL & COVER		
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
210020170	TEST TRAILER-TRANSPORT,SETUP	4.000	MILE
301020416	SHOULDER GRAVEL	1,276.000	CUYD
301020718	COVER - TYPE 1	450,815.000	SQYD
301020735	COVER - TYPE 2	24,859.000	SQYD
303050420	CRUSH AND STKPL COVER MATL-TYPE 1	1,330.000	TON
401020049	PLANT MIX SURF GR S NV - 3/4 IN	15,106.000	TON
401020300	HYDRATED LIME	211.000	TON
402020092	ASPHALT CEMENT PG 64-28	815.500	TON
402020305	EMULSIFIED ASPHALT SS-1	356.000	GAL
402020368	EMULS ASPHALT CRS-2P	807.700	TON
411010000	COLD MILLING	11,019.000	SQYD
606010047	GD RAIL-STL INT RDWY TERM SECT	287.500	LNFT
606010370	RESET GUARD RAIL	25.000	LNFT
606010385	REMOVE GUARD RAIL	2,033.000	LNFT
606010642	GUARD RAIL-OPTIONAL TERM SECT	40.000	EACH
610100559	REVEGETATION	1.000	LSUM
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618100000	SINGLE USE SIGNS	102.000	SQFT
620010301	CURB MARKING-YELLOW EPOXY	38.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	27.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	66.000	GAL
620011260	WORDS/SYMBOLS-WHITE EPOXY	15.000	GAL
620013000	STRIPING-WHITE PAINT	919.000	GAL
620013960	STRIPING-WHITE EPOXY	958.000	GAL
620014000	STRIPING-YELLOW PAINT	500.000	GAL
620014960	STRIPING-YELLOW EPOXY	370.000	GAL
620017000	TEMPORARY PAVEMENT MARKINGS	4.200	MILE
623000000	RUMBLE STRIPS	37.000	MILE

Contract to be completed in 50 Working Days.
 The Disadvantaged Business Enterprises' contract goals are 0.0%.
 Cost of proposal only \$15.00.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.
 This project is under the jurisdiction of the MISSOULA District Administrator.
 Contract No. 15308 Uniform Nos. 6194000, 6195000, 6196000

**8 BIG POWDER R-3 KM E POWDERVILLE
 BR 9038(11)**

467-foot prestressed concrete girder structure and associated approach roadwork on the Big Powder R-3 km E Powderville project in Powder River County. The project is located on an off-system local roadway east of Powderville in Section 17, Range 54 East, Township 1 South, approximately 63 miles southeast of Miles City. The total length of the project is 0.34 miles.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	APPROACHES - G, GS		
104030010	MISCELLANEOUS WORK	30,000.000	UNIT
105080115	FINISH GRADE CONTROL	3,600.000	CRFT
105080200	BRIDGE SURVEY	1.000	LSUM
109200005	MOBILIZATION	1.000	LSUM
202020041	REMOVE STRUCTURE	1.000	LSUM
203020375	EMBANKMENT IN PLACE	11,631.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	1,732.000	CUYD
208010150	TEMPORARY EROSION CONTROL - LS	1.000	LSUM
208010207	MPDES PERMIT FEES	900.000	UNIT
301020251	BRIDGE END BACKFILL	2,475.000	CUYD
301020526	TOP SURF 3/4 IN GR 3B	1,218.000	CUYD
501010510	TRANSVERSE DECK GROOVING	1,356.000	SQYD
551020035	CONCRETE-CLASS DD	131.900	CUYD
551020107	CONCRETE-CLASS SD	358.400	CUYD
553010160	PRESTRESSED BEAM-TYPE M-72	1,856.000	LNFT
555010100	REINFORCING STEEL	7,922.000	LB
555010200	REINFORCING STEEL-EPOXY COATED	69,481.000	LB
557010012	BRIDGE RAIL-T 101	938.700	LNFT
559010202	RE-DRIVE TEST PILE	1.000	EACH
559030091	FURN STL PIPE PILE 24 OD X 3/4 IN	524.000	LNFT
559030092	DR STL PIPE PILE 24 X 3/4 IN	348.000	LNFT
559040035	DYNAMIC LOAD TEST	1.000	EACH
559050082	FURN STL PILE HP 14 X 117	344.000	LNFT
559050141	SHEET PILE WALL	1,830.000	SQFT
559050150	ABUTMENT RESTRAINING DEVICE	2.000	EACH
559060085	DR STL PILE HP 14 X 117	332.000	LNFT
559060200	PILE CUTTING SHOE	12.000	EACH
559060300	PILE DRIVING POINT	8.000	EACH
561010500	EXPANSION JOINT	30.500	LNFT
561010600	ELASTOMERIC BEARING DEVICES	8.000	EACH
603010040	DRAINAGE PIPE 18 IN	76.000	LNFT
603010048	DRAINAGE PIPE 24 IN	40.000	LNFT
606010023	ONE-WAY DEPART TERM SECTION	2.000	EACH
606010030	GUARD RAIL-STEEL	100.000	LNFT
606010190	GUARD RAIL-STL/BR APPR-TY 2	4.000	EACH
606010642	GUARD RAIL-OPTIONAL TERM SECT	2.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	591.000	LNFT
607100252	FARM FENCE-TYPE F4M	1,214.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	12.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	16.000	EACH
607100430	FARM GATE-WIRE TYPE G-2	36.000	LNFT

607100720	DEADMAN	2.000	EACH
610100101	SEEDING AREA NO 1	1.800	ACRE
610100102	SEEDING AREA NO 2	0.300	ACRE
610100326	FERTILIZING AREA NO 1	1.800	ACRE
610100327	FERTILIZING AREA NO 2	0.300	ACRE
610100555	CONDITION SEEDBED SURFACE	1.800	ACRE
610100560	RIPRAP REVEGETATION	470.000	SQYD
610100561	EROSION CONTROL BLANKET	842.000	SQYD
613100040	RIPRAP-CLASS 2 RANDOM	595.000	CUYD
618030080	TRAFFIC CONTROL	1.000	LSUM
618100000	SINGLE USE SIGNS	153.000	SQFT
619010075	SIGNS-ALUM REFL SHEET (I)	7.500	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	8.000	SQFT
619010230	REMOVE SIGNS	6.000	EACH
619010480	POLES-TREATED TIMBER-BARN 4 IN	38.000	LNFT
622011043	PERM. EROSION CONTROL-HIGH SURV	695.000	SQYD
624000030	MAILBOX-LARGE	7.000	EACH

Contract to be completed in 160 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of plans and proposal, including cross sections \$15.00. Large plans \$20.00.

Erosion Control Plans \$3.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the GLENDIVE District Administrator.

Contract No. 08308

Uniform No. 5436

9 SCOBIEY - NORTH
STPP-SFCP 32-2(13)52

Cold milling, pms overlay, crush and stockpile, guardrail and signing on the Scobey-North project in Daniels County. The project is located on State Route 13 (P-32), beginning just north of Scobey at the junction with S-248 (RP 51.5) and continuing 14.3 miles north to the Port of Scobey on the US/Canadian Border (RP 65.8).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	PMS OVERLAY, MILL, CRUSH & STKPILE COVER, BR RAIL,		
104030010	MISCELLANEOUS WORK	12,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
210020170	TEST TRAILER-TRANSPORT,SETUP	126.000	MILE
303050420	CRUSH AND STKPL COVER MATL-TYPE 1	3,025.000	TON
401020045	PLANT MIX BIT SURF GR S - 3/4 IN	23,770.000	TON
401020300	HYDRATED LIME	333.000	TON
402020092	ASPHALT CEMENT PG 64-28	1,281.600	TON
411010000	COLD MILLING	9,312.000	SQYD
557010535	REVISE BRIDGE RAIL-W740	101.000	LNFT
606010030	GUARD RAIL-STEEL	12.500	LNFT
606010230	GUARD RAIL-STL/BR APPR-TY 3	8.000	EACH
606010265	GRD RAIL-BOX BEAM/BR APP-SEC TYPE 1	4.000	EACH
606010385	REMOVE GUARD RAIL	800.000	LNFT
606010641	GD RL BOX BEAM OPT TERM SEC	4.000	EACH
606010642	GUARD RAIL-OPTIONAL TERM SECT	8.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	125,000.000	UNIT
618100000	SINGLE USE SIGNS	102.000	SQFT
619010051	SIGNS-ALUM SHEET INCR (I)	14.000	SQFT
619010075	SIGNS-ALUM REFL SHEET (I)	53.200	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	102.100	SQFT
619010210	RESET SIGNS-GUIDE	1.000	EACH
619010230	REMOVE SIGNS	35.000	EACH
619010240	REMOVE SIGNS-GUIDE	1.000	EACH
619010310	POSTS-STEEL U SIGN	252.000	LB

619010480	POLES-TREATED TIMBER-BARN 4 IN	126.000	LNFT
619010490	POLES-TREATED TIMBER-BARN 5 IN	46.000	LNFT
619011010	DELINEATOR DES A	406.000	EACH
619011040	DELINEATOR DES D	24.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	5.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	202.000	GAL
620013000	STRIPING-WHITE PAINT	518.000	GAL
620014000	STRIPING-YELLOW PAINT	404.000	GAL
620017000	TEMPORARY PAVEMENT MARKINGS	14.600	MILE
800320010	MISCELLANEOUS WORK	6.000	EACH

Contract to be completed in 45 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of proposal only \$15.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the GLENDIVE District Administrator.
Contract No. 12308 Uniform No. 6241000

**10 JCT. MT. 16-NORTHWEST
STPS 254-1(23)0**

Cold-in-place recycle plant mix surfacing and seal & cover on 9.4 miles of the Junction Mt 16-Northwest project on Secondary 254 in Dawson County. The project begins approximately 3 miles north of Glendive at the junction of Mt 16 and extends northwest.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
203020278	EXCAVATION - DIGOUTS	77.000	CUYD
208106000	MPDES PERMIT FEES	900.000	UNIT
301020345	CRUSHED AGGREGATE COURSE	6,575.000	TON
301020600	BLOTTER MATERIAL	1,088.000	TON
301020718	COVER - TYPE 1	142,319.000	SQYD
311010235	QUICK LIME	253.600	TON
401020042	PLANT MIX GR D - COMMERCIAL	1,362.000	TON
401020325	COLD RECYCLED PLANT MIX	142,200.000	SQYD
402020305	EMULSIFIED ASPHALT SS-1	6,961.000	GAL
402020368	EMULS ASPHALT CRS-2P	243.800	TON
402020476	RECYCLING AGENT CIR-EE	546.900	TON
610100557	REVEGETATION	2.600	ACRE
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618100000	SINGLE USE SIGNS	102.000	SQFT
619010051	SIGNS-ALUM SHEET INCR (I)	60.000	SQFT
619010075	SIGNS-ALUM REFL SHEET (I)	21.600	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	42.400	SQFT
619010230	REMOVE SIGNS	12.000	EACH
619010240	REMOVE SIGNS-GUIDE	2.000	EACH
619010310	POSTS-STEEL U SIGN	162.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	650.000	LB
619010480	POLES-TREATED TIMBER-BARN 4 IN	64.000	LNFT
619010724	FRANG SIGN POST BKWY - S5 X 10	4.000	EACH
619011010	DELINEATOR DES A	266.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL
620011260	WORDS/SYMBOLS-WHITE EPOXY	1.000	GAL
620013000	STRIPING-WHITE PAINT	680.000	GAL
620013960	STRIPING-WHITE EPOXY	454.000	GAL
620014000	STRIPING-YELLOW PAINT	280.000	GAL
620014960	STRIPING-YELLOW EPOXY	186.000	GAL
620017000	TEMPORARY PAVEMENT MARKINGS	18.800	MILE
622011084	GEOTEXTILE STABILIZATION	200.000	SQYD
624000030	MAILBOX-LARGE	24.000	EACH

Contract to be completed in 70 Calendar Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of proposal only \$15.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the GLENDIVE District Administrator.
Contract No. 04308 Uniform No. 6242000

- 11 **BROADWATER - DIV TO 12TH ST WEST, UPP 1006(10)**
BROADWATER - 28TH TO SHILOH RD, UPP 1006(8)
YELLOWSTONE RIVER - BENCH - IRISTEN, UPP 1027(7)
UPP 1006(10) - Cold milling, PMS overlay, detector loop, seal & cover and pavement markings on the Broadwater-Division to 12th St. West project located in Billings in Yellowstone County. The project begins at RP 3.45, 12th St, and extends approximately 1.5 miles east along Broadwater Avenue to RP 4.94, Division Street.
UPP 1006(8) - Cold milling, PMS overlay, seal & cover and pavement markings on the Broadwater-28th to Shiloh Road project located in Billings in Yellowstone County. The project begins at RP 0.00, Shiloh Road, and extends approximately 1.5 miles east along Broadwater Avenue to RP 1.52, 28th Street West.
UPP 1027(7) - Cold milling, guardrail, PMS overlay, seal & cover and pavement markings on the Yellowstone River-Bench-Iristan project located in Billings in Yellowstone County. The project begins at RP 2.6, Bench Blvd., and extends approximately 1.1 miles northeast along Yellowstone River Road to RP 3.7, Iristan Lane.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 COLD MILLING, PMS OVERLAY, SEAL & COVER AND PAVEMENT MARKING			
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
210020000	GRADER-MOTOR	8.000	HOURL
301020735	COVER - TYPE 2	99,908.000	SQYD
401020049	PLANT MIX SURF GR S NV - 3/4 IN	9,818.000	TON
401020300	HYDRATED LIME	138.000	TON
402020095	ASPHALT CEMENT PG 70-28	530.600	TON
402020368	EMULS ASPHALT CRS-2P	170.000	TON
411010000	COLD MILLING	81,945.000	SQYD
606010385	REMOVE GUARD RAIL	100.000	LNFT
606010642	GUARD RAIL-OPTIONAL TERM SECT	2.000	EACH
617763101	DETECTOR/LOOP	31.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	200,000.000	UNIT
620010301	CURB MARKING-YELLOW EPOXY	83.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	95.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	12.000	GAL
620011260	WORDS/SYMBOLS-WHITE EPOXY	65.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	6.000	GAL
620013000	STRIPING-WHITE PAINT	324.000	GAL
620013960	STRIPING-WHITE EPOXY	222.000	GAL
620014000	STRIPING-YELLOW PAINT	328.000	GAL
620014960	STRIPING-YELLOW EPOXY	225.000	GAL
620017000	TEMPORARY PAVEMENT MARKINGS	7.200	MILE
621013070	ADJUST MANHOLES	4.000	EACH
621013110	ADJUST VALVE BOXES	5.000	EACH

Contract to be completed in 60 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of proposal only \$15.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the BILLINGS District Administrator.
Contract No. 14308 Uniform Nos. 6273000, 6274000, 6275000

**12 SLIDE-NORTH OF GEORGETOWN LAKE
STPP 19-1(31)28**

Rockfall mitigation consisting of rock scaling, rock bolts, shotcrete, debris flow barrier, wire mesh stabilization, trim blasting and grouting on the Slide - North of Georgetown Lake project in Granite County. The project is located on Montana 1 (P-19) between Georgetown Lake and Phillipsburg, beginning at RP 27.7 (county line) and extending 1.2 kilometers northwest to RP 28.4.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROCKFALL MITIGATION			
104100000	MISCELLANEOUS WORK	30,000.000	UNIT
109200000	MOBILIZATION	1.000	LSUM
203180015	SCALING	784.000	HOURL
203220060	DEBRIS FLOW BARRIER SYSTEM	272.000	M2
203220070	WIRE MESH STABILIZATION	392.000	M2
203610000	DRILL PRESPLITTING HOLES	180.000	M
203620000	ROCK BOLT	466.000	M
203630000	DOWEL	29.000	M
203635000	ROCK NAILS	30.000	M
203650000	BLASTING CONSULTANT	1.000	LSUM
203650010	TRIM BLASTING	379.000	M3
606250000	GUARD RAIL-OPTIONAL TERM SECT	4.000	EACH
606800000	REMOVE GUARD RAIL	45.700	M
614000146	SHOTCRETE	2.000	M3
618020000	TRAFFIC CONTROL	1.000	LSUM
618140000	SINGLE USE SIGNS	9.200	M2
619720000	RESET SIGNS	5.000	EACH
800300000	MISCELLANEOUS WORK	1.000	LSUM

Contract to be completed in 100 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of plans and proposal \$15.00. Large plans \$12.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the BUTTE District Administrator.
Contract No. 09308 Uniform No. 4605

**13 EMIGRANT - SOUTH, NH 11-1(55)24
LIVINGSTON - SOUTH, NH 11-1(57)44**

NH 11-1(55)24 - Seal & cover and pavement markings on the Emigrant-South project located in Park County. The project begins at RP 24.1 and extends northeast approximately 9.9 miles along National Highway Route 11/US 89 to RP 34.0 near Emigrant.

NH 11-1(57)44 - Guardrail, seal & cover and pavement markings on the Livingston-South project located in Park County. The project begins at RP 43.7 and extends approximately 9.3 miles along National Highway Route 11/US 89 to RP 53.0. The Livingston urban limits begin at RP 51.691.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
301020718	COVER - TYPE 1	371,057.000	SQYD
402020368	EMULS ASPHALT CRS-2P	632.500	TON
402020502	CRACK SEALING	13,872.000	LB
606010030	GUARD RAIL-STEEL	625.000	LNFT
606010385	REMOVE GUARD RAIL	825.000	LNFT
606010642	GUARD RAIL-OPTIONAL TERM SECT	3.000	EACH
606011300	RESET OPTIONAL TERMINAL SECT	1.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	100,000.000	UNIT
620010301	CURB MARKING-YELLOW EPOXY	25.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	24.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	6.000	GAL
620011260	WORDS/SYMBOLS-WHITE EPOXY	31.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	8.000	GAL
620013000	STRIPING-WHITE PAINT	704.000	GAL
620013960	STRIPING-WHITE EPOXY	938.000	GAL
620014000	STRIPING-YELLOW PAINT	240.000	GAL
620014960	STRIPING-YELLOW EPOXY	320.000	GAL

Contract to be completed by 10/20/08 Completion Date.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of proposal only \$15.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the BUTTE District Administrator.

Contract No. 06308

Uniform Nos. 6210000, 6211000

14 VIRGINIA CITY - ALDER, STPP 29-1(50)14**ALDER - SHERIDAN, STPP 29-1(52)23****VIRGINIA CITY HILL, STPP 29-1(48)6**

STPP 29-1(50)14 - Seal and cover and pavement markings on the Virginia City - Alder project located in Madison County. The project is located on State Highway 287 beginning at RP 13.9 extending northwest 9.3 miles ending at RP 23.2 (Alder).

STPP 29-1(52)23 - Seal and cover and pavement markings on the Alder - Sheridan project located in Madison County. The project is located on State Highway 287 beginning at RP 23.2 extending northwest 9.0 miles ending at RP 32.2.

STPP 29-1(48)6 - Seal and cover and pavement markings on the Virginia City Hill project located in Madison County. The project is located on State Highway 287 beginning at RP 5.6 extending west 8.3 miles ending at RP 13.9.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
301020718	COVER - TYPE 1	368,364.000	SQYD
402020368	EMULS ASPHALT CRS-2P	623.700	TON
618030005	TRAFFIC CONTROL DEVICES CB	70,000.000	UNIT
618100000	SINGLE USE SIGNS	102.000	SQFT
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS/SYMBOLS-WHITE EPOXY	17.000	GAL
620013000	STRIPING-WHITE PAINT	1,036.000	GAL
620013960	STRIPING-WHITE EPOXY	1,381.000	GAL
620014000	STRIPING-YELLOW PAINT	666.000	GAL
620014960	STRIPING-YELLOW EPOXY	887.000	GAL

Contract to be completed by 10/20/08 Completion Date.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of proposal only \$15.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the BUTTE District Administrator.

Contract No. 02308

Uniform Nos. 6215000, 6217000, 6218000

**15 2003 - SLOPE FLATTEN - CENTERVILLE
HSIP 227-1(13)6**

Slope flattening on the 2003-Slope Flatten-Centerville project in Cascade County. The project is located approximately 10 miles southeast of Great Falls on Secondary 227 between Centerville and Tracy (RP 6.2 to 6.3).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001	ROADSIDE SAFETY IMP - SLOPE FLATTENING		
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
109200005	MOBILIZATION	1.000	LSUM
203020375	EMBANKMENT IN PLACE	1,484.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	364.000	CUYD
210020000	GRADER-MOTOR	8.000	HOURL
610100101	SEEDING AREA NO 1	0.700	ACRE
610100326	FERTILIZING AREA NO 1	0.700	ACRE
610100555	CONDITION SEEDBED SURFACE	0.700	ACRE
618030080	TRAFFIC CONTROL	1.000	LSUM

Contract to be completed in 30 Working Days.

The Disadvantaged Business Enterprises' contract goals are 0.0%.

Cost of plans and proposal, including cross sections \$15.00. Large plans \$12.00. Dirt Runs \$10.00.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

http://www.mdt.mt.gov/business/contracting/current_letting.shtml under the "Bid Packages" link.

This project is under the jurisdiction of the GREAT FALLS District Administrator.

Contract No. 03308

Uniform No. 5864000