



Memorandum

Suzy Althof,	Supervisor – Contract Plans Bureau
Jim Frank,	Glendive District Engineering Services Supervisor
Gary Neville,	Billings District Engineering Services Supervisor
Joe Olsen,	Butte District Engineering Services Supervisor
Duane Kailey,	Missoula District Engineering Services Supervisor
Steve Prinzing,	Great Falls District Engineering Services Supervisor
Larry Frideres,	Road Plans Checker
Kevin Farry,	Road Plans Checker

Truncated Domes (Initiated 11-29-04)

(Use on all projects.)

Rescind Supplemental Specification 608.03.2.

A. Construction Requirements. Construct and install Truncated Domes as shown in the Plans and Detailed Drawings. Use Red Brick Color Dye in the concrete mix prior to precasting.

B. Method of Measurement.

Rescind the second sentence of 608.04 and replace with the following.

Truncated Domes are measured by the square yard (square meter) to the nearest 0.1 of a square yard (0.1 square meter).

Contracts with sidewalk work not in conjunction with roadway reconstruction: Reinforcing steel, expansion joint material, bond breaker, excavation or embankment, crushed gravel base, and disposal of material associated with the work are not measured for payment.

All other contracts: Reinforcing steel, expansion joint material, bond breaker, disposal of material, and crushed gravel base are not measured for payment. Excavation or embankment associated with the work is measured by the cubic yard (cubic meter).

C. Basis of Payment.

Rescind the second sentence in the paragraph under the Pay Item/Pay Item columns in Section 608.05 and add the following.

Payment for Truncated Domes is by the square yard (square meter).

Contracts with sidewalk work only not in conjunction with roadway reconstruction: Reinforcing steel, expansion joint material, bond breaker, excavation or embankment, crushed gravel base, and disposal of material associated with the work are paid under Sidewalk-Concrete.

All other contracts: Include the cost of reinforcing steel, expansion joint material, bond breaker, disposal of material, and crushed gravel base in the contract unit price bid for Sidewalk-Concrete. Excavation or embankment associated with the work is paid under the specified type of earthwork.