

NOTES:

- ① INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
 - ② USE WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS. AFFIX BLOCKS TO POSTS WITH TWO 16 PENNY GALV. NAILS OR 14 GAUGE WIRE WRAP.
 - ③ ATTACH REFLECTORS TO POSTS EVERY 25 FEET [7.62 m], INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FABRICATE REFLECTORS FROM 0.063" [1.6] THICK ALUMINUM ALLOY PER SECTION 704 OR PLASTIC REFLECTORS WITH A URETHANE HINGE. FASTEN REFLECTOR TO WOOD POST USING TWO 16 PENNY RING-SHANKED GALVANIZED NAILS AND TWO 3/16" [4.8] DIA. WASHERS IN PRE-DRILLED HOLES.
 - ④ ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 27 3/4" [705].
 - ⑤ WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2' - 0" [0.6 m] FROM THE TRAFFIC LANE.
 - ⑥ DO NOT INSTALL W-BEAM GUARDRAIL FOR OBSTACLES WITHIN 5.3' [1.6 m] OF THE FACE OF THE RAIL.
 - ⑦ USE LOWER HOLE ON NEW CONSTRUCTION INSTALLATIONS.
 - ⑧ USE 6' [1830] POSTS FOR STANDARD INSTALLATIONS.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.







UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 704	DWG. NO. 606-05A
METAL GUARDRAIL - WOOD POSTS (MGS)	


--REVISED--
JANUARY 2018

EFFECTIVE: SEPTEMBER 2014

MDT MONTANA DEPARTMENT OF TRANSPORTATION




- NOTES:
- INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
 - USE ROUTED WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS.
 - ATTACH REFLECTORS TO POSTS EVERY 25 FEET [7.62 m], INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FASTEN REFLECTOR TO STEEL POST USING AN APPROVED ADHESIVE. REFLECTORS MAY BE BOLTED TO POSTS PROVIDED HOLES IN POSTS ARE DRILLED BEFORE BEING GALVANIZED.
 - ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 27 3/4" [705].
 - WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2' - 0" [0.6 m] FROM THE TRAFFIC LANE.
 - STEEL POSTS WITH OTHER POST HOLE CONFIGURATIONS MAY BE ACCEPTED, PROVIDED THEY HAVE AT LEAST THE HOLES DETAILED ON THIS DRAWING AND THEY MEET AASHTO'S PUBLICATION, "A GUIDE TO STANDARDIZED HIGHWAY BARRIER HARDWARE" AND "MASH" REQUIREMENTS.
 - DO NOT INSTALL W-BEAM GUARDRAIL FOR OBSTACLES WITHIN 5.3' [1.6 m] OF THE FACE OF THE RAIL.
 - USE LOWER HOLE ON NEW CONSTRUCTION INSTALLATIONS.
 - USE 6" [1830] POSTS FOR STANDARD INSTALLATIONS.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-05B
METAL GUARDRAIL - STEEL POSTS (MGS)	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	


UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

--REVISED--
JANUARY 2018



QUARTER POST SPACING

- NOTES:
- ① SEE DTL. DWG. NO. 606-05A AND 606-05B FOR STANDARD MGS GUARDRAIL AND ASSOCIATED HARDWARE.
 - ② OBSTACLES CLOSER TO THE FACE OF RAIL THAN THE INDICATED LIMITS REQUIRE THE USE OF A RIGID BARRIER SYSTEM WITH LITTLE TO NO DYNAMIC DEFLECTION.
 - ③ LAP ALL RAIL IN THE DIRECTION OF ADJACENT TRAFFIC.
 - ④ ALL POSTS AND BLOCKS ARE STANDARD DIMENSIONS AS PER DETAILED DRAWING NO. 606-05A AND 606-05B.
 - ⑤ RAIL IS RWM08a-b*.
 - ⑥ PAY LIMIT DEFINED BY RAILS CONTAINING A SECTION OF REDUCED POST SPACING. LIMITS SHOWN ARE FOR EXAMPLE ONLY, ACTUAL PAY LIMITS WILL DIFFER DEPENDING UPON SPLICE LOCATIONS.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.








HALF POST SPACING

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-07

STIFFENED GUARDRAIL SECTIONS (MGS)

--REVISED--	EFFECTIVE: SEPTEMBER 2014
JANUARY 2018	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	








- NOTES:
- SEE DTL. DWG. NO. 606-05A AND 606-05B FOR STANDARD MGS GUARDRAIL AND ASSOCIATED HARDWARE.
 - LAP ALL RAIL IN THE DIRECTION OF ADJACENT TRAFFIC.
 - TYPICAL SPLICE LOCATIONS SHOWN, MAY VARY BASED ON ACTUAL RAIL SEGMENTS INSTALLED. PAY LIMITS NOT DEPENDENT ON SPLICE LOCATION.
 - DO NOT INSTALL MGS LONG SPAN GUARDRAIL FOR ABOVE-GRADE OBSTACLES WITHIN 8' [2.4m] OF THE FACE OF THE RAIL.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-09
LONG SPAN GUARDRAIL (MGS)	
--REVISED-- JANUARY 2018	EFFECTIVE: SEPTEMBER 2014
MONTANA DEPARTMENT OF TRANSPORTATION	



NOTES:






- ① INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
 - ② USE WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS. AFFIX BLOCKS TO POSTS WITH TWO 16 PENNY GALV. NAILS OR 14 GAUGE WIRE WRAP.
 - ③ ATTACH REFLECTORS TO POSTS EVERY 25' [7.62 m], INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FABRICATE REFLECTORS FROM 0.063" [1.6] THICK ALUMINUM ALLOY PER SECTION 704 OR PLASTIC REFLECTORS WITH A URETHANE HINGE. FASTEN REFLECTOR TO WOOD POST USING TWO 16 PENNY RING-SHANKED GALVANIZED NAILS AND TWO 3/16" [4.8] DIA. WASHERS IN PRE-DRILLED HOLES.
 - ④ ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 27 3/4" [705].
 - ⑤ DO NOT INSTALL LONG POST W-BEAM GUARDRAIL FOR OBSTACLES WITHIN 5' - 6" [1.65 m] OF THE FACE OF THE RAIL.
 - ⑥ USE LOWER HOLE ON NEW CONSTRUCTION INSTALLATIONS.
 - ⑦ BEGIN INSLOPE BREAK AT CENTER OF POST.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 704	DWG. NO. 606-11A
METAL GUARDRAIL - LONG POSTS - WOOD (MGS)	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	

--REVISED--
JANUARY 2018



- NOTES:
- INSTALL ALL BOLTS WITH HEADS ON TRAFFIC SIDE OF INSTALLATION.
 - USE ROUTED WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS.
 - ATTACH REFLECTORS TO POSTS EVERY 25' [7.62 m], INCLUDING TERMINAL SECTIONS, WITH THE REFLECTORIZED SURFACE FACING ADJACENT TRAFFIC. FASTEN REFLECTOR TO STEEL POST USING AN APPROVED ADHESIVE. REFLECTORS MAY BE BOLTED TO POSTS PROVIDED HOLES IN POSTS ARE DRILLED BEFORE BEING GALVANIZED.
 - ON EXISTING GUARDRAIL INSTALLATIONS, THE MINIMUM RAIL HEIGHT IS 27 3/4" [705].


- DO NOT INSTALL LONG POST W-BEAM GUARDRAIL FOR OBSTACLES WITHIN 5' - 6" [1.65 m] OF THE FACE OF THE RAIL.
 - USE LOWER HOLE ON NEW CONSTRUCTION INSTALLATIONS.
 - LOCATE POST 12" [305] (MAXIMUM) FROM INSLOPE BREAK.
 - STEEL POSTS WITH OTHER POST HOLE CONFIGURATIONS MAY BE ACCEPTED, PROVIDED THEY HAVE AT LEAST THE HOLES DETAILED ON THIS DRAWING AND THEY MEET AASHTO'S PUBLICATION, "A GUIDE TO STANDARDIZED HIGHWAY BARRIER HARDWARE" AND "MASH" REQUIREMENTS.
- *SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-11B
METAL GUARDRAIL - LONG POSTS - STEEL (MGS)	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	

--REVISED--
JANUARY 2018



TRINITY SOFTSTOP ①



ROAD SYSTEMS MSKT WITH 9' - 4 1/2" RAIL PANEL ①






- ① OPTIONAL TERMINAL SECTION SYSTEMS VARY, REFER TO MANUFACTURER'S DETAIL AND ASSEMBLY INSTRUCTIONS.
- ② SEE DTL. DWG. NO. 606-05A AND 606-05B FOR MGS GUARDRAIL. SEE DTL. DWG. NO. 606-20 IF CONNECTING TO EXISTING RAIL THAT IS NOT WITHIN THE MANUFACTURER'S HEIGHT TOLERANCE.
- ③ LENGTH OF NEED POST LOCATION EQUALS STATION LIMITS INDICATED IN THE PLANS.
- ④ 7' - 0" [2.13m] WIDENING DIMENSION ALLOWS FOR OPTIONAL TERMINAL SECTION FLARE AND SYSTEM WIDTH. A MINIMUM WIDENING DISTANCE OF 5' - 0" [1.52m] IS REQUIRED BEHIND POST LOCATION #1.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-13
SECTION 606, 203	

MASH OPTIONAL TERMINAL SECTIONS


EFFECTIVE: JANUARY 2018



UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

NOTE:
 ① SEE DTL. DWG. NO. 606-05A AND 606-05B FOR MGS GUARDRAIL.
 * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-18
ONE-WAY DEPARTURE TERMINAL SECTION (MGS)	
EFFECTIVE: SEPTEMBER 2014	
--REVISED--	
JANUARY 2018	
MONTANA DEPARTMENT OF TRANSPORTATION	






TRANSITION FROM 27 3/4" [705] (OR GREATER) TO 31" [775] GUARDRAIL MOUNTING HEIGHT

NOTES:






- ① THE MGS TO METAL GUARDRAIL TRANSITION IS PAID FOR AS LINEAR FEET OF MGS GUARDRAIL.
- ② SEE DTL. DWG. NO. 606-05A, 606-05B, 606-11A, AND 606-11B FOR MGS GUARDRAIL AND ASSOCIATED HARDWARE.
- ③ LAP ALL W-BEAM RAIL IN THE DIRECTION OF ADJACENT TRAFFIC.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-20
MGS TO METAL GUARDRAIL TRANSITION	
EFFECTIVE: JANUARY 2018	
 MDT MONTANA DEPARTMENT OF TRANSPORTATION	





- NOTES:
- SEE DTL. DWG. NO. 606-05A FOR STANDARD MGS GUARDRAIL AND ASSOCIATED HARDWARE.
 - LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
 - DO NOT FLARE BRIDGE APPROACH SECTIONS.
 - WHERE CURB EXTENDS UPSTREAM OF POST NO. 5, FURNISH 2 NESTED 12-GAUGE W-BEAM RAILS FOR THIS 12'-6" [3810] SECTION. INCLUDE THIS ADDITIONAL RAIL IN THE COST OF THE BRIDGE APPROACH SECTION.
 - A MINIMUM OF 12'-6" [3810] OF W-BEAM RAIL IS REQUIRED BEFORE END TREATMENT.
 - USE WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS. AFFIX BLOCKS TO POSTS WITH TWO 16 PENNY GALV. NAILS OR 14 GAUGE WIRE WRAP.
 - SEE BRIDGE PLANS FOR CONNECTION DETAILS AND BOLT LOCATIONS.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.









UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-23A
MGS THRIE BEAM BRIDGE APPROACH SECTION - WOOD POSTS	
EFFECTIVE: JANUARY 2018	
MONTANA DEPARTMENT OF TRANSPORTATION	




- NOTES:
- SEE DTL. DWG. NO. 606-05A FOR STANDARD MGS GUARDRAIL AND ASSOCIATED HARDWARE.
 - LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
 - DO NOT FLARE BRIDGE APPROACH SECTIONS.
 - WHERE CURB EXTENDS UPSTREAM OF POST NO. 5, FURNISH 2 NESTED 12-GAUGE W-BEAM RAILS FOR THIS 12'-6\"/>
 - A MINIMUM OF 12'-6\"/>
 - USE WOOD BLOCKS OR OTHER "MASH" APPROVED BLOCKS. AFFIX BLOCKS TO POSTS WITH TWO 16 PENNY GALV. NAILS OR 14 GAUGE WIRE WRAP.
 - SEE BRIDGE PLANS FOR CONNECTION DETAILS AND BOLT LOCATIONS.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-23B
MGS THRIE BEAM BRIDGE APPROACH SECTION - STEEL POSTS	
EFFECTIVE: JANUARY 2018	
MONTANA DEPARTMENT OF TRANSPORTATION	




ELEVATION



PLAN

DETAIL "A"



SECTION A-A






PLATE WASHER

- NOTES:
- ① TAPERED CONCRETE CURBS: TYPE 1, SEE DTL. DWG. NO. 606-26 TYPE 3, SEE DTL. DWG. NO. 606-27
 - ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
 - ③ PORTIONS OF GUARDRAIL & BLOCKOUTS ARE OMITTED FOR CLARITY.
 - ④ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE. (SEE DTL. DWG. NO. 606-05A).
 - ⑤ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
 - ⑥ USE WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
 - ⑦ DO NOT FLARE BRIDGE APPROACH SECTIONS.
 - ⑧ SEE DTL. DWG. NO. 606-25A FOR SKEWED BRIDGES.
 - ⑨ SEE DTL. DWG. NO. 606-05A FOR METAL GUARDRAIL (W-BEAM).
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1
(FOR BRIDGES USING CONCRETE BARRIER RAIL)

- ① 9 5/8" x 9 5/8" (MIN.) x 8'-0" [245 x 245 (MIN.) x 2440] POST W/ 11 5/8" x 9 5/8" (MIN.) x 1'-2" [295 x 244.5 (MIN.) x 350] BLOCKOUT
- ② 7 5/8" x 5 5/8" x 7'-0" [195 x 145 x 2135] POST W/ 11 5/8" x 5 5/8" (MIN.) x 1'-2" [295 x 145 (MIN.) x 350] BLOCKOUT
- ③ 7 5/8" x 5 5/8" x 6'-0" [195 x 145 x 1830] POST W/ 7 5/8" x 5 5/8" (MIN.) x 1'-2" [195 x 145 (MIN.) x 350] BLOCKOUT



METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 2
(FOR BRIDGES WITHOUT CURBS)

* GUARDRAIL NOT ATTACHED TO POSTS. BLOCKOUT FASTENED TO POST WITH STANDARD POST BOLT.



METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3
(FOR BRIDGES WITH EXISTING CONCRETE CURBS)

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-24A
SECTION 606	

BRIDGE APPROACH SECTIONS - WOOD POSTS

--REVISED--
JULY 2016


EFFECTIVE: SEPTEMBER 2014





NOTE:
TAPER THE END OF THE CONCRETE BARRIER RAIL AS SHOWN.

ELEVATION



STD. CONC. CURB (WHERE REQUIRED- SEE ROAD PLANS) (WARP AS NECESSARY TO MEET END OF THE TAPERED CONCRETE CURB)

1" DIA. x 3'-0" [25 DIA. x 915] STEEL DOWELS DRIVEN THROUGH PIPE SLEEVES

TYPE 1 7'-0" [2100] TAPERED CONC. CURB
TYPE 3 6'-0" [1800] TAPERED CONC. CURB

3/4" [19] CHAMFER (TYP.)
ϕ PLATE WASHER W/ ROUND HOLE (SEE DETAIL THIS SHEET)

ϕ 7/8" DIA. x 1'-0" [M22 x 305] HIGH STRENGTH BOLTS (FBX22b*) W/ 1 PLATE WASHER AND 1 HEX NUT (FNX22b*)

RWE02a-b (SEE DTL. DWG. NO. 606-88)

1" [25.4] DIA. HOLE FOR 7/8" [M22] DIA. BOLT

1" [25] x 2" [50] GALV. METAL PLATE

1 1/2" [38] x 1 1/2" [38] GALV. METAL PLATE

1/4" [6 mm] GALV. METAL PLATE

W8 x 21 [W203 x 31 kg/m] (MIN.) STEEL POST


11 5/8" x 5 5/8" [295 x 145] (MIN.) BLOCKOUT

6:1 SLOPE


WIDEN WITH BITUMINOUS SURFACE AS DIRECTED

SECTION A-A


- NOTES:
- TAPERED CONCRETE CURBS: TYPE 1, SEE DTL. DWG. NO. 606-26; TYPE 3, SEE DTL. DWG. NO. 606-27
 - TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
 - PORTIONS OF GUARDRAIL & BLOCKOUTS ARE OMITTED FOR CLARITY.
 - LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE. (SEE DTL. DWG. NO. 606-05B).
 - LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
 - USE ROUTED WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
 - DO NOT FLARE BRIDGE APPROACH SECTIONS.
 - SEE DTL. DWG. NO. 606-25B FOR SKEWED BRIDGES.
 - SEE DTL. DWG. NO. 606-05B FOR METAL GUARDRAIL (W-BEAM).
- *SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.



METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1 (FOR BRIDGES USING CONCRETE BARRIER RAIL)



METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 2 (FOR BRIDGES WITHOUT CURBS)





METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3 (FOR BRIDGES WITH EXISTING CONCRETE CURBS)

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE	DWG. NO.
STANDARD SPEC.	606-24B
SECTION 606	
BRIDGE APPROACH SECTIONS - STEEL POSTS	

--REVISED-- EFFECTIVE: SEPTEMBER 2014
JULY 2016





METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1
(FOR SKEWED BRIDGES USING CONCRETE BARRIER RAIL)




METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3
(FOR SKEWED BRIDGES WITH EXISTING CONCRETE CURBS)

NOTES:


- ① TAPERED CONCRETE CURBS:
TYPE 1, SEE DTL. DWG. NO. 606-26
TYPE 3, SEE DTL. DWG. NO. 606-27
- ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
- ③ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE. (SEE DTL. DWG. NO. 606-05A).
- ④ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
- ⑤ USE WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
- ⑥ DO NOT FLARE BRIDGE APPROACH SECTIONS.
- ⑦ SEE DTL. DWG. NO. 606-24A FOR ADDITIONAL INFORMATION.
- ⑧ SEE DTL. DWG. NO. 606-05A FOR METAL GUARDRAIL (W-BEAM).

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-25A
SKEWED BRIDGE APPROACH SECTIONS - WOOD POSTS	
EFFECTIVE: SEPTEMBER 2014	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	



METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 1
(FOR SKEWED BRIDGES USING CONCRETE BARRIER RAIL)





METAL GUARDRAIL-BRIDGE APPROACH SECTION TYPE 3
(FOR SKEWED BRIDGES WITH EXISTING CONCRETE CURBS)

NOTES:


- ① TAPERED CONCRETE CURBS:
TYPE 1, SEE DTL. DWG. NO. 606-26
TYPE 3, SEE DTL. DWG. NO. 606-27
- ② TAPERED CONCRETE CURBS ARE ALSO REQUIRED ON CONCRETE APPROACH SLABS.
- ③ LAP GUARDRAIL IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE. (SEE DTL. DWG. NO. 606-05B).
- ④ LAP W-BEAM TERMINAL CONNECTOR (RWE02a-b) IN THE DIRECTION OF THE ADJACENT TRAFFIC LANE.
- ⑤ USE WOOD BLOCKS OR OTHER NCHRP 350 APPROVED BLOCKS FOR BLOCKOUTS.
- ⑥ DO NOT FLARE BRIDGE APPROACH SECTIONS.
- ⑦ SEE DTL. DWG. NO. 606-24B FOR ADDITIONAL INFORMATION.
- ⑧ SEE DTL. DWG. NO. 606-05B FOR METAL GUARDRAIL (W-BEAM).

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-25B
SKEWED BRIDGE APPROACH SECTIONS - STEEL POSTS	
EFFECTIVE: SEPTEMBER 2014	
 MONTANA DEPARTMENT OF TRANSPORTATION	




PLAN




VIEW A-A



VIEW B-B



WIRE ROPE DETAIL




SECTION C-C

NOTES:

- ① TAPERED CONCRETE CURB IS USED WITH BRIDGE APPROACH SECTION TYPE 1 (SEE DTL. DWG. NO. 606-24A AND 606-24B).
- ② FURNISH WIRE ROPE MEETING SECTION 705.
- ③ FURNISH GRADE 60 [420] REINFORCING STEEL MEETING SECTION 711.
- ④ ALL CONCRETE IS CLASS GENERAL.
TOTAL CONCRETE PER 7' [2100 mm] TAPERED CURB EST. = 0.2 C. Y. [0.17 m³]
TOTAL REBAR WEIGHT PER 7' [2100 mm] TAPERED CURB EST. = 34 LB [15.1 kg].


BILL OF REINFORCING STEEL (ONE SECTION ONLY)



BENT BARS (ALL DIMENSIONS ARE OUT TO OUT)

MARK	SIZE	NO.	TYPE	LENGTH	A	B	C	D	E
C1	#4	1	1	4'-8"	11"	1'-4"	1'-1"	9"	3 1/2"
C2				4'-2"	9 1/2"	1'-2"	11 1/2"	8"	
C3				3'-9"	8 1/2"	1'-1/2"	10"	7"	
C4				3'-3"	7"	10 1/2"	8"	6 1/2"	
C5				2'-11"	6"	9"	7"	6"	
C6				2'-4"	4"	7"	5"	5"	
C7				2'-0"	3 1/2"	5 1/2"	3 1/2"	4 1/2"	3 1/2"
C8		1	1	1'-6"	2"	3 1/2"	2"	3 1/2"	1 1/2"
B1	#4	4	STRAIGHT	6'-9"	~	~	~	~	~

METRIC BILL OF REINFORCING STEEL (ONE SECTION ONLY)



BENT BARS (ALL DIMENSIONS ARE OUT TO OUT IN mm)


MARK	SIZE	NO.	TYPE	LENGTH	A	B	C	D	E
C1	#13	1	1	1360	270	395	330	205	80
C2				1225	240	350	290	185	
C3				1090	205	310	255	160	
C4				955	175	265	215	140	
C5				820	145	220	175	120	
C6				695	115	180	140	100	
C7				555	80	135	100	80	80
C8		1	1	415	50	90	60	55	40
B1	#13	4	STRAIGHT	2020	~	~	~	~	~

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-26

TAPERED CONCRETE CURB DETAIL


EFFECTIVE: SEPTEMBER 2014



PLAN



ELEVATION



END VIEW

NOTES:

- ① REMOVE THE EXISTING SURFACE UNDER THE NEW TAPERED CONCRETE CURB AS APPROVED BY THE PROJECT MANAGER. EMBED THE TAPERED CONCRETE CURB A MINIMUM OF 4" [100] BELOW THE GRADE MEASURED AT THE INSIDE FACE OF THE TAPER.
- ② FURNISH GRADE 60 [420] REINFORCING STEEL MEETING SECTION 555 AND 711.
- ③ ALL CONCRETE IS CLASS GENERAL.
TOTAL CONCRETE PER 6' [1800] TAPERED CURB EST. = 0.2 C.Y. [0.16 m³]
TOTAL REBAR WEIGHT PER 6' [1800] TAPERED CURB EST. = 27 LB. [11.7 kg]
- ④ TAPERED CONCRETE CURB IS USED WITH BRIDGE APPROACH SECTION TYPE 3 (SEE DTL. DWG. NO. 606-24A AND 606-24B).
- ⑤ ADJUST DIMENSION TO MATCH EXISTING CURB.

BILL OF REINFORCING STEEL (ONE SECTION ONLY)						
 TYPE I						
BENT BARS (ALL DIMENSIONS ARE OUT TO OUT)						
MARK	SIZE	NO.	TYPE	LENGTH	A	B
C1	#4	1	1	1' - 4"	6"	4"
C2	↑	↑	↑	1' - 8"	7"	6"
C3	↑	↑	↑	1' - 11"	8"	7"
C4	↑	↑	↑	2' - 3"	9"	9"
C5	↑	↑	↑	2' - 6"	10"	10"
C6	↑	1	1	2' - 10"	11"	1' - 0"
B1	↓	4	STRAIGHT	5' - 8"	~	~
B2	#4	2	STRAIGHT	2' - 0"	~	~


METRIC BILL OF REINFORCING STEEL (ONE SECTION ONLY)						
 TYPE I						
BENT BARS (ALL DIMENSIONS ARE OUT TO OUT)						
MARK	SIZE	NO.	TYPE	LENGTH (mm)	A (mm)	B (mm)
C1	#13	1	1	390	150	90
C2	↑	↑	↑	480	175	130
C3	↑	↑	↑	570	200	170
C4	↑	↑	↑	665	225	215
C5	↑	↑	↑	755	250	255
C6	↑	1	1	845	270	295
B1	↓	4	STRAIGHT	1720	~	~
B2	#13	2	STRAIGHT	600	~	~

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-27



TAPERED CONCRETE CURB DETAIL

--REVISED--	EFFECTIVE: SEPTEMBER 2014
JULY 2016	




- ① QUADGUARD CARTRIDGE
 - ② DIAPHRAGM
 - ③ FENDER PANEL
 - ④ MONORAIL
 - ⑤ NOSE ASSEMBLY
 - ⑥ BACK UP
- NOT INCLUDED IN MODEL NUMBER, ORDER SEPARATELY

UNIDIRECTIONAL TRAFFIC



PLAN



MONORAIL ASSEMBLY (TYPICAL 6 BAY ASSEMBLY)




TABLE 1:

BAYS	24" [610] WIDTH MODEL NO.	30" [760] WIDTH MODEL NO.	36" [915] WIDTH MODEL NO.	SYSTEM LENGTH	METRIC SYSTEM LENGTH (m)	EFFECTIVE LENGTH	METRIC EFFECTIVE LENGTH (m)	PAD LENGTH	METRIC PAD LENGTH (m)	MAX DESIGN SPEED (M. P. H.)	METRIC MAX DESIGN SPEED (km/hr)	NO. OF CARTRIDGES	
												TYPE I	TYPE II
1	QS2401*	QS3001*	QS3601*	7' - 1"	2.16	5' - 8"	1.73	9' - 0"	2.74	25	40	2	0
2	QS2402*	QS3002*	QS3602*	10' - 1"	3.08	8' - 8"	2.64	9' - 0"	2.74	37	60	2	1
3	QS2403*	QS3003*	QS3603*	13' - 1"	4.00	11' - 8"	3.56	12' - 0"	3.66	44	70	3	1
4	QS2404*	QS3004*	QS3604*	16' - 1"	4.91	14' - 8"	4.47	15' - 0"	4.57	50	80	3	2
5	QS2405*	QS3005*	QS3605*	19' - 1"	5.83	17' - 8"	5.38	18' - 0"	5.49	56	90	4	2
6	QS2406*	QS3006*	QS3606*	22' - 1"	6.74	20' - 8"	6.30	21' - 0"	6.40	62	100	4	3
7	QS2407*	QS3007*	QS3607*	25' - 1"	7.65	23' - 8"	7.21	24' - 0"	7.32	65	105	4	4
8	QS2408*	QS3008*	QS3608*	28' - 1"	8.57	26' - 8"	8.13	27' - 0"	8.23	68	110	4	5
9	QS2409*	QS3009*	QS3609*	31' - 1"	9.49	29' - 8"	9.04	30' - 0"	9.14	71	115	4	6
10	QS2410*	QS3010*	QS3610*	34' - 1"	10.40	32' - 8"	9.96	33' - 0"	10.06	75	120	5	6
11	QS2411*	QS3011*	QS3611*	37' - 1"	11.32	35' - 8"	10.87	36' - 0"	10.97	75	120	5	7
12	QS2412*	QS3012*	QS3612*	40' - 1"	12.23	38' - 8"	11.79	39' - 0"	11.89	75	120	5	8

* G = GREY OR Y = YELLOW

NOTES:

- ① ATTACHMENT SHOWN IS TO SHAPES WITH RECTANGULAR CROSS SECTIONS SUCH AS: PIERS, PARAPETS AND MODIFIED CONCRETE BARRIER RAIL. TRAFFIC FLOW IS UNIDIRECTIONAL. ATTACHMENTS AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BIDIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE FROM THE MANUFACTURER.
- ② THE SYSTEM SHOWN INCLUDES THE TENSION STRUT BACKUP ASSEMBLY AND THE CONCRETE PAD AS DETAILED. SEE THE MANUFACTURER FOR DRAWINGS DETAILING THE REINFORCING STEEL FOR THE CONCRETE PAD AND FOR OTHER BACKUP & CONCRETE PAD OPTIONS.
- ③ PROVIDE ADEQUATE CLEARANCE FOR THE DISTANCE SHOWN TO ALLOW FENDER PANELS TO SLIDE REARWARD UPON IMPACT.
- ④ SEE MANUFACTURER FOR MORE INFORMATION ON SPECIFIC DESIGNS, INSTALLATION AND MAINTENANCE OF THE QUADGUARD SYSTEM.

TABLE 2:

ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	2760051-0000	MONORAIL, ONE BAY	MONORAIL, ONE BAY	#
2	2760061-0000	MONORAIL, TWO BAYS	MONORAIL, TWO BAYS	#
3	2760071-0000	MONORAIL, THREE BAYS	MONORAIL, THREE BAYS	#
4	2760041-0000	MONORAIL END CAP	MONORAIL END CAP	1
5	3525300-0000	ANCHOR KIT	ANCHOR KIT	#
6	2699571-0000	5/8" DIA. x 3 1/2" HEX BOLT	M16 x 89 HEX BOLT	1
7	2704141-0000	5/8" DIA. HEX NUT	M16 HEX NUT	1
8	2708231-0000	5/8" DIA. LOCK WASHER	M16 LOCK WASHER	1

- SEE TABLE 3 BELOW

TABLE 3:

ASSEMBLY NO.	TOTAL RAIL LENGTH	METRIC TOTAL RAIL LENGTH (mm)	# ITEM 1	# ITEM 2	# ITEM 3	# ITEM 5	NO. OF BAYS
3540060-0100	0"	0	0	0	0	0	1
3540060-0200	36.0"	915	1	0	0	2	2
3540060-0300	72.0"	1 830	0	1	0	3	3
3540060-0400	108.1"	2 745	0	0	1	4	4
3540060-0500	144.1"	3 660	1	0	1	5	5
3540060-0600	180.1"	4 575	0	1	1	6	6
3540060-0700	216.1"	5 490	0	0	2	7	7
3540060-0800	252.1"	6 405	1	0	2	8	8
3540060-0900	288.2"	7 320	0	1	2	9	9
3540060-1000	324.2"	8 235	0	0	3	10	10
3540060-1100	360.2"	9 150	1	0	3	12	11
3540060-1200	396.2"	10 065	0	1	3	13	12

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING

REFERENCE DWG. NO. STANDARD SPEC. SECTION 606 606-30A

IMPACT ATTENUATOR - QUADGUARD


EFFECTIVE: SEPTEMBER 2014

MDT MONTANA DEPARTMENT OF TRANSPORTATION



① UNIDIRECTIONAL TRAFFIC →

PLAN




PLASTIC NOSEPIECE (6532B)

FOR NOSEPIECE ATTACHMENT REMOVE EXISTING 5/8" DIA. BOLTS (4 TOTAL) AND RE-INSERT THROUGH NOSEPIECE.

ELEVATION

TRACC BILL OF MATERIAL		
PART NUMBER	QTY	DESCRIPTION
*25980A	1	TRACC UNIT (FULLY ASSEMBLED **)
3310G	4	5/8" DIA. LOCKWASHER
4451G	4	5/8" DIA. x 6" WEDGE EXP. ANCHOR
6825B	4	REFLECTIVE TAPE
6532B	1	PLASTIC NOSEPIECE
ANCHOR HARDWARE (FULL CONCRETE BASE)		
5204G	26	5/8" DIA. x 7 1/16" ANCHOR STUD
3310G	26	5/8" DIA. LOCKWASHER
3361G	26	5/8" DIA. HEX NUT
3300G	26	5/8" DIA. FLAT WASHER
5206B	3	ADHESIVE HIT HY 150(CARTRIDGE)
ANCHOR HARDWARE (ASPHALT BASE)		
6380G	26	5/8" DIA. x 18" ALL THREADED ROD
3310G	26	5/8" DIA. LOCKWASHER
3361G	26	5/8" DIA. HEX NUT
3300G	26	5/8" DIA. FLAT WASHER
5206B	5	ADHESIVE HIT HY 150(CARTRIDGE)


* SEE DET. DWG. NO. 606-31B
 ** EACH UNIT SHIPS 100% ASSEMBLED (PLASTIC NOSE INSTALLED AFTER PLACEMENT)



NOTES:


- ① ATTACHMENT SHOWN IS TO SHAPES WITH RECTANGULAR CROSS SECTIONS SUCH AS: PIERS, PARAPETS, AND MODIFIED CONCRETE BARRIER RAIL. TRAFFIC FLOW IS UNIDIRECTIONAL. ATTACHMENTS AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BIDIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE FROM THE MANUFACTURER.
- ② A 6" REINFORCED CONCRETE PAD IS SHOWN. OTHER FOUNDATION OPTIONS ARE:
 - a) 8" THICK UNREINFORCED CONCRETE
 - b) 8" THICK ASPHALT
 - c) 3" THICK ASPHALT OVER 3" THICK CONCRETE
 - d) 6" THICK ASPHALT OVER 6" THICK COMPACTED SUBBASE
 REINFORCEMENT DRAWINGS FOR THE REINFORCED CONCRETE PAD SHOWN ARE AVAILABLE FROM THE MANUFACTURER.
- ③ SEE MANUFACTURER FOR MORE INFORMATION ON SPECIFIC DESIGNS, PRODUCT OPTIONS, INSTALLATION AND MAINTENANCE OF THE TRACC SYSTEM.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-30B
IMPACT ATTENUATOR - TRACC	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	



PLAN

① UNIDIRECTIONAL TRAFFIC




ELEVATION

FOR NOSEPIECE ATTACHMENT REMOVE EXISTING M16 BOLTS (4 TOTAL) AND RE-INSERT THROUGH NOSEPIECE.

TRACC BILL OF MATERIAL		
PART NUMBER	QTY	DESCRIPTION
*25980A	1	TRACC UNIT (FULLY ASSEMBLED **)
3310G	4	M16 LOCKWASHER
4451G	4	M16 x 152 WEDGE EXP. ANCHOR
6825B	4	REFLECTIVE TAPE
6532B	1	PLASTIC NOSEPIECE
ANCHOR HARDWARE (FULL CONCRETE BASE)		
5204G	26	M16 x 179 ANCHOR STUD
3310G	26	M16 LOCKWASHER
3361G	26	M16 HEX NUT
3300G	26	M16 FLAT WASHER
5206B	3	ADHESIVE HIT HY 150(CARTRIDGE)
ANCHOR HARDWARE (ASPHALT BASE)		
6380G	26	M16 x 457 ALL THREADED ROD
3310G	26	M16 LOCKWASHER
3361G	26	M16 HEX NUT
3300G	26	M16 FLAT WASHER
5206B	5	ADHESIVE HIT HY 150(CARTRIDGE)

* SEE DET. DWG. NO. 606-31B
 ** EACH UNIT SHIPS 100% ASSEMBLED (PLASTIC NOSE INSTALLED AFTER PLACEMENT)




SECTION A-A

NOTES:


- ① ATTACHMENT SHOWN IS TO SHAPES WITH RECTANGULAR CROSS SECTIONS SUCH AS: PIERS, PARAPETS, AND MODIFIED CONCRETE BARRIER RAIL. TRAFFIC FLOW IS UNIDIRECTIONAL. ATTACHMENTS AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BIDIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE FROM THE MANUFACTURER.
- ② A 150 mm REINFORCED CONCRETE PAD IS SHOWN. OTHER FOUNDATION OPTIONS ARE:
 - a) 200 mm THICK UNREINFORCED CONCRETE
 - b) 200 mm THICK ASPHALT
 - c) 75 mm THICK ASPHALT OVER 75 mm THICK CONCRETE
 - d) 150 mm THICK ASPHALT OVER 150 mm THICK COMPACTED SUBBASE
- REINFORCEMENT DRAWINGS FOR THE REINFORCED CONCRETE PAD SHOWN ARE AVAILABLE FROM THE MANUFACTURER.
- ③ SEE MANUFACTURER FOR MORE INFORMATION ON SPECIFIC DESIGNS, PRODUCT OPTIONS, INSTALLATION AND MAINTENANCE OF THE TRACC SYSTEM.

ALL DIMENSIONS ARE MILLIMETERS (mm) UNLESS OTHERWISE NOTED.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-30B
IMPACT ATTENUATOR - TRACC (METRIC)	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	




- NOTES:
- Ⓐ ATTACHMENT SHOWN IS TO SHAPES WITH RECTANGULAR CROSS SECTIONS SUCH AS: PIERS, PARAPETS, AND MODIFIED CONCRETE BARRIER RAIL. TRAFFIC FLOW IS UNIDIRECTIONAL. ATTACHMENTS AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BIDIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE FROM THE MANUFACTURER.
 - Ⓑ PROVIDE ADEQUATE CLEARANCE (5'-0" MIN.) TO ALLOW REAR RAILS TO SLIDE REARWARD UPON IMPACT.
 - Ⓒ A 6" REINFORCED CONCRETE PAD IS SHOWN. OTHER FOUNDATION OPTIONS ARE:
 - a) 8" THICK UNREINFORCED CONCRETE
 - b) 8" THICK ASPHALT
 - c) 3" THICK ASPHALT OVER 3" THICK CONCRETE
 - d) 6" THICK ASPHALT OVER 6" THICK COMPACTED SUBBASE
 - e) 7" THICK REINFORCED DECK STRUCTURE
- SEE MANUFACTURER FOR REINFORCEMENT DRAWINGS AND ANCHORAGE REQUIREMENTS FOR ALL FOUNDATION OPTIONS.
- Ⓓ SEE MANUFACTURER FOR MORE INFORMATION ON SPECIFIC DESIGNS, INSTALLATION AND MAINTENANCE OF THE QUEST SYSTEM.




PARTS LIST			
ITEM	STOCK NO.	DESCRIPTION	QTY.
1	3562003-0000	24" BACKUP ASSEMBLY	1
2	3562002-0000	BAY 1 24" SUPPORT FRAME ASSEMBLY	1
3	2762015-0000	FRONT ANCHOR	2
4	3562005-0000	BAY 3 24" DIAPHRAGM ASSEMBLY	1
5	3562001-0000	TRIGGER ASSEMBLY	1
6	3562004-0000	BAY 2 24" BRIDGE	1
7	2762026-0000	NOSE	1
8	2762024-0000	RT. NOSE TRANSITION	1
9	2762025-0000	LT. NOSE TRANSITION	1
10	276200L-0000	LT. SHAPER RAIL	1
11	276200R-0000	RT. SHAPER RAIL	1
12	2762022-0000	DIAPHRAGM PANEL BRACKET	2
13	2762023-0000	REAR RAIL	2
14	2762007-0000	TRIGGER STRAP	2
15	2762013-0000	BAY 2 PANEL	2
16	2762014-0000	BAY 3 PANEL	2
17	2762033-0000	BAY 1 PANEL	2




DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-30C
IMPACT ATTENUATOR - QUEST	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	



- NOTES:
- Ⓐ ATTACHMENT SHOWN IS TO SHAPES WITH RECTANGULAR CROSS SECTIONS SUCH AS: PIERS, PARAPETS, AND MODIFIED CONCRETE BARRIER RAIL. TRAFFIC FLOW IS UNIDIRECTIONAL. ATTACHMENTS AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BIDIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE FROM THE MANUFACTURER.
 - Ⓑ PROVIDE ADEQUATE CLEARANCE (1.5 m MIN.) TO ALLOW REAR RAILS TO SLIDE REARWARD UPON IMPACT.
 - Ⓒ A 150 mm REINFORCED CONCRETE PAD IS SHOWN. OTHER FOUNDATION OPTIONS ARE:
 - a) 200 mm THICK UNREINFORCED CONCRETE
 - b) 200 mm THICK ASPHALT
 - c) 75 mm THICK ASPHALT OVER 75 mm THICK CONCRETE
 - d) 150 mm THICK ASPHALT OVER 150 mm THICK COMPACTED SUBBASE
 - e) 180 mm THICK REINFORCED DECK STRUCTURE
 - SEE MANUFACTURER FOR REINFORCEMENT DRAWINGS AND ANCHORAGE REQUIREMENTS FOR ALL FOUNDATION OPTIONS.
 - Ⓓ SEE MANUFACTURER FOR MORE INFORMATION ON SPECIFIC DESIGNS, INSTALLATION AND MAINTENANCE OF THE QUEST SYSTEM.




PARTS LIST			
ITEM	STOCK NO.	DESCRIPTION	QTY.
1	3562003-0000	610 mm BACKUP ASSEMBLY	1
2	3562002-0000	BAY 1 610 mm SUPPORT FRAME ASSEMBLY	1
3	2762015-0000	FRONT ANCHOR	2
4	3562005-0000	BAY 3 610 mm DIAPHRAGM ASSEMBLY	1
5	3562001-0000	TRIGGER ASSEMBLY	1
6	3562004-0000	BAY 2 610 mm BRIDGE	1
7	2762026-0000	NOSE	1
8	2762024-0000	RT. NOSE TRANSITION	1
9	2762025-0000	LT. NOSE TRANSITION	1
10	276200L-0000	LT. SHAPER RAIL	1
11	276200R-0000	RT. SHAPER RAIL	1
12	2762022-0000	DIAPHRAGM PANEL BRACKET	2
13	2762023-0000	REAR RAIL	2
14	2762007-0000	TRIGGER STRAP	2
15	2762013-0000	BAY 2 PANEL	2
16	2762014-0000	BAY 3 PANEL	2
17	2762033-0000	BAY 1 PANEL	2



ALL DIMENSIONS ARE MILLIMETERS (mm) UNLESS OTHERWISE NOTED.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-30C
IMPACT ATTENUATOR - QUEST (METRIC)	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	



PLAN

- A QUADGUARD CARTRIDGE
- B DIAPHRAGM
- C FENDER PANEL
- D MONORAIL
- E NOSE ASSEMBLY NOT INCLUDED IN MODEL NUMBER, ORDER SEPARATELY
- F BACK UP

UNIDIRECTIONAL TRAFFIC




ELEVATION

TABLE 1:


BAYS	24" [610] WIDTH MODEL NO.	30" [760] WIDTH MODEL NO.	36" [915] WIDTH MODEL NO.	SYSTEM LENGTH	METRIC SYSTEM LENGTH (m)	EFFECTIVE LENGTH	METRIC EFFECTIVE LENGTH (m)	PAD LENGTH	METRIC PAD LENGTH (m)	MAX DESIGN SPEED (M. P. H.)	METRIC MAX DESIGN SPEED (km/hr)	NO. OF CARTRIDGES	
												TYPE I	TYPE II
1	OG24024	OG24030	OG24036	7'-0"	2.13	5'-8"	1.73	9'-0"	2.74	25	40	2	0
2	OG27024	OG27030	OG27036	10'-0"	3.05	8'-8"	2.64	9'-0"	2.74	43	70	2	1
3	OG28024	OG28030	OG28036	13'-0"	3.96	11'-8"	3.56	12'-0"	3.66	50	80	2	2
4	OG29024	OG29030	OG29036	16'-0"	4.87	14'-8"	4.47	15'-0"	4.57	56	90	3	2
5	OG210024	OG210030	OG210036	19'-0"	5.79	17'-8"	5.38	18'-0"	5.49	62	100	3	3
6	OG210524	OG210530	OG210536	22'-0"	6.71	20'-8"	6.30	21'-0"	6.40	65	105	4	3
7	OG212024	OG211030	OG211036	25'-0"	7.63	23'-8"	7.21	24'-0"	7.32	68	110	4	4
8	OG211524	OG211530	OG211536	28'-0"	8.53	26'-8"	8.13	27'-0"	8.23	71	115	4	5
9	OG212024	OG212030	OG212036	31'-0"	9.45	29'-8"	9.04	30'-0"	9.14	75	120	4	6

NOTES:

- 1 ATTACHMENT SHOWN IS TO SHAPES WITH RECTANGULAR CROSS SECTIONS SUCH AS: PIERS, PARAPETS AND MODIFIED CONCRETE BARRIER RAIL. TRAFFIC FLOW IS UNIDIRECTIONAL. ATTACHMENTS AND TRANSITIONS TO OTHER SHAPES, BARRIERS, RAILINGS AND BIDIRECTIONAL TRAFFIC FLOWS ARE AVAILABLE FROM THE MANUFACTURER.
- 2 THE SYSTEM SHOWN INCLUDES THE TENSION STRUT BACKUP ASSEMBLY AND THE CONCRETE PAD AS DETAILED. SEE THE MANUFACTURER FOR DRAWINGS DETAILING THE REINFORCING STEEL FOR THE CONCRETE PAD AND FOR OTHER BACKUP & CONCRETE PAD OPTIONS.
- 3 PROVIDE ADEQUATE CLEARANCE FOR THE DISTANCE SHOWN TO ALLOW FENDER PANELS TO SLIDE REARWARD UPON IMPACT.
- 4 SEE MANUFACTURER FOR MORE INFORMATION ON SPECIFIC DESIGNS, INSTALLATION AND MAINTENANCE OF THE QUADGUARD II SYSTEM.



PLAN



ELEVATION

MONORAIL ASSEMBLY (TYPICAL 5 BAY ASSEMBLY)




TABLE 2:

ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	2760051-0000	MONORAIL, ONE BAY	MONORAIL, ONE BAY	#
2	2760061-0000	MONORAIL, TWO BAYS	MONORAIL, TWO BAYS	#
3	2760071-0000	MONORAIL, THREE BAYS	MONORAIL, THREE BAYS	#
4	2760041-0000	MONORAIL END CAP	MONORAIL END CAP	1
5	3525300-0000	ANCHOR KIT	ANCHOR KIT	#
6	2699571-0000	5/8" DIA. x 3 1/2" HEX BOLT	M16 x 89 HEX BOLT	1
7	2704141-0000	5/8" DIA. HEX NUT	M16 HEX NUT	1
8	2708231-0000	5/8" DIA. LOCK WASHER	M16 LOCK WASHER	1

- SEE TABLE 3 BELOW

TABLE 3:

ASSEMBLY NO.	TOTAL RAIL LENGTH	METRIC TOTAL RAIL LENGTH (mm)	# ITEM 1	# ITEM 2	# ITEM 3	# ITEM 5	NO. OF BAYS
3540060-0100	0"	0	0	0	0	0	1
3540060-0200	36.0"	915	1	0	0	2	2
3540060-0300	72.0"	1 830	0	1	0	3	3
3540060-0400	108.1"	2 745	0	0	1	4	4
3540060-0500	144.1"	3 660	1	0	1	5	5
3540060-0600	180.1"	4 575	0	1	1	6	6
3540060-0700	216.1"	5 490	0	0	2	7	7
3540060-0800	252.1"	6 405	1	0	2	8	8
3540060-0900	288.2"	7 320	0	1	2	9	9


UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING
 REFERENCE DWG. NO. STANDARD SPEC. 606-30D SECTION 606
 IMPACT ATTENUATOR - QUADGUARD II
 EFFECTIVE: SEPTEMBER 2014
 MDT MONTANA DEPARTMENT OF TRANSPORTATION

ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	SEE TABLE A	DIAPHRAGM	DIAPHRAGM	1
8	2760091-0000	MONORAIL GUIDE	MONORAIL GUIDE	2
9	2704341-0000	3/4" DIA. HEX NUT	M20 HEX NUT	4
10	2699121-0000	3/4" DIA. x 2" HEX BOLT	M20 x 51 HEX BOLT	4
11	2708201-0000	3/4" DIA. LOCK WASHER	M20 LOCK WASHER	4
12	2760292-0000	CARTRIDGE SUPPORT BRACKET	CARTRIDGE SUPPORT BRACKET	2

TABLE A:


ASSEMBLY NO.	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION
3540071-0000	2761011-0000	24" WIDE DIAPHRAGM	610 WIDE DIAPHRAGM
3540072-0000	2761021-0000	30" WIDE DIAPHRAGM	760 WIDE DIAPHRAGM
3540073-0000	2761031-0000	36" WIDE DIAPHRAGM	915 WIDE DIAPHRAGM



DIAPHRAGM ASSEMBLY


ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	3540130-0*00	NOSE, W/ SUPPORT BRACKET	NOSE, W/ SUPPORT BRACKET	1
2	2699341-0000	5/8" DIA. x 2" RAIL BOLT	M16 x 51 RAIL BOLT	6
3	2704191-0000	5/8" DIA. HEX NUT	M16 HEX NUT	6
4	2708871-0000	WASHER (BAR 1/8" x 1 1/4" x 2", W/ 5/8" DIA. HOLE)	WASHER (BAR 3.2 x 32 x 51, W/ M16 HOLE)	6
5	2760251-0000	PULL-OUT BRACKET	PULL-OUT BRACKET	2

* 0 INDICATES GRAY
* 1 INDICATES YELLOW



NOSE ASSEMBLY

ASSEMBLY NO. 3540050-0100 (YELLOW)
ASSEMBLY NO. 3540050-0000 (GRAY)




ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	2760081-0000	FENDER PANEL	FENDER PANEL	1
2	2699341-0000	5/8" DIA. x 2" RAIL BOLT	M16 x 51 RAIL BOLT	2
3	2704191-0000	5/8" DIA. HEX NUT	M16 HEX NUT	2
4	2708841-0000	CAST MUSHROOM WASHER	CAST MUSHROOM WASHER	1
5	2706604-0000	5/8" DIA. x 5" SCREW	M16 x 127 SCREW	1
6	2704141-0000	5/8" DIA. HEX NUT	M16 HEX NUT	1
*7	2708291-0000	5/8" DIA. WASHER	M16 WASHER	2
*8	2021611-0000	ELASTOMERIC BUSHING	ELASTOMERIC BUSHING	1
#7	2708291-0000	5/8" DIA. WASHER	M16 WASHER	1
#8	2021611-0000	5/8" x 1 1/4" O.D. x 1 1/2" DIE SPRING	M16 x 32 O.D. x 38 DIE SPRING	1

* OLDER OPTION
NEWER OPTION

NOTE:

- ① UNDERLYING PANEL IS EITHER ANOTHER FENDER PANEL OR, IN THE CASE OF THE LAST FENDER PANEL IT COULD BE A BACKUP SIDE PANEL, EXTENSION PANEL OR TRANSITION PANEL.
- ② TWO FENDER PANEL ASSEMBLIES ARE REQUIRED PER BAY.



FENDER PANEL ASSEMBLY
ASSEMBLY NO. 3540040-0000

ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	SEE TABLE A	TENSION BACKUP	TENSION BACKUP	1
2	2760141-0000	SIDE PANEL	SIDE PANEL	2
9	3525300-0000	ANCHOR KIT	ANCHOR KIT	3
10	2704191-0000	5/8" DIA. HEX NUT	M16 HEX NUT	4
11	2699341-0000	5/8" DIA. x 2" RAIL BOLT	M16 x 51 RAIL BOLT	4
12	2760293-0000	CARTRIDGE SUPPORT BRACKET	CARTRIDGE SUPPORT BRACKET	1
13	2760294-0000	CARTRIDGE SUPPORT LOCKING BAR	CARTRIDGE SUPPORT LOCKING BAR	1


TABLE A:

ASSEMBLY NO.	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION
3540031-0000	2760011-0000	24" WIDE TENSION BACKUP	610 WIDE TENSION BACKUP
3540032-0000	2760021-0000	30" WIDE TENSION BACKUP	760 WIDE TENSION BACKUP
3540033-0000	2760031-0000	36" WIDE TENSION BACKUP	915 WIDE TENSION BACKUP

NOTE:


- ③ WHEN TRANSITIONING THE QUADGUARD SYSTEM TO EXISTING BARRIERS, SEE MANUFACTURER FOR PROPER USE OF SIDE PANEL (ITEM 2).

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.



BACKUP ASSEMBLY




DETAILED DRAWING
REFERENCE DWG. NO. STANDARD SPEC. 606-31A SECTION 606
IMPACT ATTENUATOR - QUADGUARD ASSEMBLY DETAILS
EFFECTIVE: SEPTEMBER 2014
MDT MONTANA DEPARTMENT OF TRANSPORTATION



BILL OF MATERIAL		
PART NUMBER	QTY	DESCRIPTION
TRACC (25980A)		
19737G	12	1/4" x 3" x 2 1/4" TRACC WASHER
25970A	1	SLED WELDMENT
25971A	8	FRAME WELDMENT
25972A	1	BACKUP FRAME WELDMENT
25973A	16	TWO-BAY FENDER PANEL
25974A	4	ONE-BAY FENDER PANEL
25975A	2	SHREDDER ASSEMBLY
25976A	32	SLOT PLATE
25981A	1	ASSEMBLED BASE (SEE NOTE 2)
TRACC BASE (25981A)		
3256G	48	3/8" DIA. SHOULDER NUT
3361G	40	5/8" DIA. HEAVY HEX NUT
3391G	40	5/8" DIA. x 1 3/4" HEX HEAD BOLT
4252G	180	3/8" DIA. HEX NUT
4258G	180	3/8" DIA. LOCK WASHER
6340G	178	3/8" DIA. x 1 1/2" SHOULDER STUD
6365G	50	3/8" DIA. x 2" HEX FLANGE HD BOLT
25954A	1	END SHOE, RIGHT
25955A	1	END SHOE, LEFT
25956A	1	FRONT ANCHOR WELDMENT
25957A	3	CROSS TIE
25958G	2	RIP PLATE, STAGE 1 (SHIPPING PL.)
25960G	16	DOUBLERS
25961G	2	EXTENSION PLATE, REAR
25962G	48	NUT HOLDER (NUT RETAINER PLATE)
25963G	2	RIP PLATE, STAGE 2
25964G	2	RIP PLATE, STAGE 3, BOTTOM
25965G	2	RIP PLATE, STAGE 3, MIDDLE
25966G	2	RIP PLATE, STAGE 3, TOP
25982A	3	BASE MODULE ASSEMBLY
SHOP HARDWARE		
3253G	2	HITCH PIN CLIP
3340G	32	5/8" DIA. HGR NUT
3361G	46	5/8" DIA. HEX NUT
3391G	32	5/8" DIA. x 1 3/4" HEX HEAD BOLT
3400G	12	5/8" DIA. x 2" HGR BOLT
3435G	20	5/8" DIA. x 3 1/2" HGR BOLT
4372G	88	5/8" DIA. FLAT WASHER
4425G	2	3/4" DIA. x 2" CLEVIS PIN
5306G	14	5/8" DIA. x 2 1/4" HEX HEAD BOLT
6827B	2	TRACC PATENT LABEL

SECTION D-D

SECTION E-E



- NOTES:
- SHIPPING PLATES MAINTAIN SLED POSITION DURING SHIPPING. IT IS NOT NECESSARY TO REMOVE SHIPPING PLATES AFTER INSTALLATION OR REPLACE AFTER REPAIRING DAMAGE TO TRACC UNIT.
 - SEE MANUFACTURER FOR ADDITIONAL DETAILS AND DRAWINGS SHOWING COMPLETE ASSEMBLY OF ALL BASE COMPONENTS.


DETAILED DRAWING

REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-31B
--------------------------------------	------------------

IMPACT ATTENUATOR TRACC ASSEMBLY DETAILS

EFFECTIVE: SEPTEMBER 2014

MDT MONTANA DEPARTMENT OF TRANSPORTATION



BILL OF MATERIAL		
PART NUMBER	QTY	DESCRIPTION
TRACC (25980A)		
19737G	12	6 x 76 x 57 TRACC WASHER
25970A	1	SLED WELDMENT
25971A	8	FRAME WELDMENT
25972A	1	BACKUP FRAME WELDMENT
25973A	16	TWO-BAY FENDER PANEL
25974A	4	ONE-BAY FENDER PANEL
25975A	2	SHREDDER ASSEMBLY
25976A	32	SLOT PLATE
25981A	1	ASSEMBLED BASE (SEE NOTE 2)
TRACC BASE (25981A)		
3256G	48	M10 SHOULDER NUT
3361G	40	M16 HEAVY HEX NUT
3391G	40	M16 x 44 HEX HEAD BOLT
4252G	180	M10 HEX NUT
4258G	180	M10 LOCK WASHER
6340G	178	M10 x 38 SHOULDER STUD
6365G	50	M10 x 51 HEX FLANGE HD BOLT
25954A	1	END SHOE, RIGHT
25955A	1	END SHOE, LEFT
25956A	1	FRONT ANCHOR WELDMENT
25957A	3	CROSS TIE
25958G	2	RIP PLATE, STAGE 1 (SHIPPING PL.)
25960G	16	DOUBLERS
25961G	2	EXTENSION PLATE, REAR
25962G	48	NUT HOLDER (NUT RETAINER PLATE)
25963G	2	RIP PLATE, STAGE 2
25964G	2	RIP PLATE, STAGE 3, BOTTOM
25965G	2	RIP PLATE, STAGE 3, MIDDLE
25966G	2	RIP PLATE, STAGE 3, TOP
25982A	3	BASE MODULE ASSEMBLY
SHOP HARDWARE		
3253G	2	HITCH PIN CLIP
3340G	32	M16 HGR NUT
3361G	46	M16 HEX NUT
3391G	32	M16 x 44 HEX HEAD BOLT
3400G	12	M16 x 51 HGR BOLT
3435G	20	M16 x 89 HGR BOLT
4372G	88	M16 FLAT WASHER
4425G	2	M20 x 51 CLEVIS PIN
5306G	14	M16 x 57 HEX HEAD BOLT
6827B	2	TRACC PATENT LABEL


NOTES:

① SHIPPING PLATES MAINTAIN SLED POSITION DURING SHIPPING. IT IS NOT NECESSARY TO REMOVE SHIPPING PLATES AFTER INSTALLATION OR REPLACE AFTER REPAIRING DAMAGE TO TRACC UNIT.


② SEE MANUFACTURER FOR ADDITIONAL DETAILS AND DRAWINGS SHOWING COMPLETE ASSEMBLY OF ALL BASE COMPONENTS.

ALL DIMENSIONS ARE MILLIMETERS (mm) UNLESS OTHERWISE NOTED.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-31B
IMPACT ATTENUATOR - TRACC ASSEMBLY DETAILS (METRIC)	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	




QUEST SYSTEM ASSEMBLY




DIAPHRAGM ASSEMBLY
(ITEM 4)




TRIGGER ASSEMBLY
(ITEM 5)



SUPPORT FRAME ASSEMBLY
(ITEM 2)




BRIDGE
(ITEM 6)




BACKUP ASSEMBLY
(ITEM 1)

PARTS LIST			
ITEM	STOCK NO.	DESCRIPTION	QTY.
1	3562003-0000	BACKUP ASSEMBLY	1
2	3562002-0000	BAY 1 SUPPORT FRAME ASSEMBLY	1
3	2762015-0000	FRONT ANCHOR	2
4	3562005-0000	BAY 3 DIAPHRAGM ASSEMBLY	1
5	3562001-0000	TRIGGER ASSEMBLY	1
6	3562004-0000	BAY 2 BRIDGE ASSEMBLY	1
7	2762026-0000	NOSE	1
8	2762024-0000	RT. NOSE TRANSITION	1
9	2762025-0000	LT. NOSE TRANSITION	1
10	276200L-0000	LT. SHAPER RAIL	1
11	276200R-0000	RT. SHAPER RAIL	1
12	2762022-0000	DIAPHRAGM PANEL BRACKET	2
13	2762023-0000	REAR RAIL	2
14	2762007-0000	TRIGGER STRAP	2
15	2762013-0000	BAY 2 PANEL	2
16	2762014-0000	BAY 3 PANEL	2
17	2762033-0000	BAY 1 PANEL	2
18	2699251-0000	3/4" DIA. x 3 1/2" HEX BOLT	16
19	2701014-0000	1" DIA. x 5" HEX BOLT	4
20	2701811-0000	5/8" DIA. x 1 1/4" RAIL BOLT	40
21	2701931-0000	3/4" DIA. x 1 1/2" HEX BOLT	4
22	2704191-0000	5/8" DIA. HEX NUT	40
23	2704091-0000	3/4" DIA. HEX NUT	20
24	2704161-0000	1" DIA. HEX NUT	2
25	2708161-0000	2" x 2" x 1/4" BAR WASHER	2
26	2708871-1000	1 1/4" x 2" x 1/8" ROUNDED BAR WASHER	8
27	2700031-0000	INSTALL INSTRUCTIONS	1
28	2735831-3500	MATERIAL SAFETY INFO NOTICE	1
29	2708081-0000	3/4" DIA. (2" O.D.) HVY. FLAT WASHER	16
TRIGGER ASSEMBLY (ITEM 5)			
30	2762008-0000	TRIGGER FRAME	1
31	2762011-0000	RT. TRIGGER ANCHOR	1
32	2762012-0000	LT. TRIGGER ANCHOR	1
33	2699034-0000	1/2" DIA. x 13 1/2" THREADED ROD	2
34	2704911-0000	1/2" DIA. HEX NUT	12
SUPPORT FRAME ASSEMBLY (ITEM 2)			
35	2762010-0000	BAY 1 SUPPORT FRAME	1
36	2762003-0000	DIAPHRAGM RAIL GUIDE	2
37	2699251-0000	3/4" DIA. x 3 1/2" HEX BOLT	6
38	2704091-0000	3/4" DIA. HEX NUT	6
39	2762021-0000	BAY 1 FRAME PANEL BRACKET	2
BRIDGE (ITEM 6)			
40	2762016-0000	BRIDGE	1
41	2762003-0000	DIAPHRAGM RAIL GUIDE	2
42	2704091-0000	3/4" DIA. HEX NUT	2
43	2701931-0000	3/4" DIA. x 1 1/2" HEX BOLT	2
DIAPHRAGM ASSEMBLY (ITEM 4)			
44	2762018-0000	BAY 3 DIAPHRAGM	1
45	2762003-0000	DIAPHRAGM RAIL GUIDE	2
46	2699251-0000	3/4" DIA. x 3 1/2" HEX BOLT	2
47	2704091-0000	3/4" DIA. HEX NUT	2
BACKUP ASSEMBLY (ITEM 1)			
48	2762020-0000	BACKUP	1
49	2762017-0000	BACKUP SHAPER	2
50	2704091-0000	3/4" DIA. HEX NUT	2
51	2699251-0000	3/4" DIA. x 3 1/2" HEX BOLT	2
52	2735711-0000	CAUTION DECAL	1
53	2735712-3500	PRODUCT DECAL	1
54	2705121-0000	3/16" DIA. x 1/2" SD68BS ST. RIVET	1


DETAILED DRAWING
 REFERENCE DWG. NO.
 STANDARD SPEC. 606-31C
 SECTION 606
 IMPACT ATTENUATOR -
 QUEST
 ASSEMBLY DETAILS
 EFFECTIVE: SEPTEMBER 2014
MDT MONTANA DEPARTMENT
 OF TRANSPORTATION




QUEST SYSTEM ASSEMBLY




DIAPHRAGM ASSEMBLY
(ITEM 4)




TRIGGER ASSEMBLY
(ITEM 5)



SUPPORT FRAME ASSEMBLY
(ITEM 2)



BRIDGE
(ITEM 6)



BACKUP ASSEMBLY
(ITEM 1)

PARTS LIST			
ITEM	STOCK NO.	DESCRIPTION	QTY.
1	3562003-0000	BACKUP ASSEMBLY	1
2	3562002-0000	BAY 1 SUPPORT FRAME ASSEMBLY	1
3	2762015-0000	FRONT ANCHOR	2
4	3562005-0000	BAY 3 DIAPHRAGM ASSEMBLY	1
5	3562001-0000	TRIGGER ASSEMBLY	1
6	3562004-0000	BAY 2 BRIDGE ASSEMBLY	1
7	2762026-0000	NOSE	1
8	2762024-0000	RT. NOSE TRANSITION	1
9	2762025-0000	LT. NOSE TRANSITION	1
10	276200L-0000	LT. SHAPER RAIL	1
11	276200R-0000	RT. SHAPER RAIL	1
12	2762022-0000	DIAPHRAGM PANEL BRACKET	2
13	2762023-0000	REAR RAIL	2
14	2762007-0000	TRIGGER STRAP	2
15	2762013-0000	BAY 2 PANEL	2
16	2762014-0000	BAY 3 PANEL	2
17	2762033-0000	BAY 1 PANEL	2
18	2699251-0000	M20 x 89 HEX BOLT	16
19	2701014-0000	M24 x 127 HEX BOLT	4
20	2701811-0000	M16 x 32 RAIL BOLT	40
21	2701931-0000	M20 x 38 HEX BOLT	4
22	2704191-0000	M16 HEX NUT	40
23	2704091-0000	M20 HEX NUT	20
24	2704161-0000	M24 HEX NUT	2
25	2708161-0000	51 x 51 x 6 BAR WASHER	2
26	2708871-1000	32 x 51 x 3 ROUNDED BAR WASHER	8
27	2700031-0000	INSTALL INSTRUCTIONS	1
28	2735831-3500	MATERIAL SAFETY INFO NOTICE	1
29	2708081-0000	M20 (51 O.D.) HVY. FLAT WASHER	16
TRIGGER ASSEMBLY (ITEM 5)			
30	2762008-0000	TRIGGER FRAME	1
31	2762011-0000	RT. TRIGGER ANCHOR	1
32	2762012-0000	LT. TRIGGER ANCHOR	1
33	2699034-0000	13 DIA. x 343 THREADED ROD	2
34	2704911-0000	M12 HEX NUT	12
SUPPORT FRAME ASSEMBLY (ITEM 2)			
35	2762010-0000	BAY 1 SUPPORT FRAME	1
36	2762003-0000	DIAPHRAGM RAIL GUIDE	2
37	2699251-0000	M20 x 89 HEX BOLT	6
38	2704091-0000	M20 HEX NUT	6
39	2762021-0000	BAY 1 FRAME PANEL BRACKET	2
BRIDGE (ITEM 6)			
40	2762016-0000	BRIDGE	1
41	2762003-0000	DIAPHRAGM RAIL GUIDE	2
42	2704091-0000	M20 HEX BOLT	2
43	2701931-0000	M20 x 38 HEX BOLT	2
DIAPHRAGM ASSEMBLY (ITEM 4)			
44	2762018-0000	BAY 3 DIAPHRAGM	1
45	2762003-0000	DIAPHRAGM RAIL GUIDE	2
46	2699251-0000	M20 x 89 HEX BOLT	2
47	2704091-0000	M20 HEX BOLT	2
BACKUP ASSEMBLY (ITEM 1)			
48	2762020-0000	BACKUP	1
49	2762017-0000	BACKUP SHAPER	2
50	2704091-0000	M20 HEX NUT	2
51	2699251-0000	M20 x 89 HEX BOLT	2
52	2735711-0000	CAUTION DECAL	1
53	2735712-3500	PRODUCT DECAL	1
54	2705121-0000	4.8 DIA. x 12.7 SD68BS ST. RIVET	1


DETAILED DRAWING
 REFERENCE DWG. NO.
 STANDARD SPEC. 606-31C
 SECTION 606
 IMPACT ATTENUATOR -
 QUEST
 ASSEMBLY DETAILS (METRIC)
 EFFECTIVE: SEPTEMBER 2014
MDT MONTANA DEPARTMENT
 OF TRANSPORTATION

ALL DIMENSIONS ARE MILLIMETERS
(mm) UNLESS OTHERWISE NOTED.

ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	SEE TABLE A	DIAPHRAGM	DIAPHRAGM	1
8	2760091-0000	MONORAIL GUIDE	MONORAIL GUIDE	2
9	2704341-0000	3/4" DIA. HEX NUT	M20 HEX NUT	4
10	2699121-0000	3/4" DIA. x 2" HEX BOLT	M20 x 51 HEX BOLT	4
11	2708201-0000	3/4" DIA. LOCK WASHER	M20 LOCK WASHER	4
12	2760292-0000	CARTRIDGE SUPPORT BRACKET	CARTRIDGE SUPPORT BRACKET	2

TABLE A:


ASSEMBLY NO.	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION
3540071-0000	2761011-0000	24" WIDE DIAPHRAGM	610 WIDE DIAPHRAGM
3540072-0000	2761021-0000	30" WIDE DIAPHRAGM	760 WIDE DIAPHRAGM
3540073-0000	2761031-0000	36" WIDE DIAPHRAGM	915 WIDE DIAPHRAGM



DIAPHRAGM ASSEMBLY

ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	2760072-0*00	NARROW LT. NOSE	NARROW LT. NOSE	1
2	2760073-0*00	NARROW RT. NOSE	NARROW RT. NOSE	1
3	2760076-0000	NOSE CART. SUPPORT BRACKET	NOSE CART. SUPPORT BRACKET	1
4	2760297-0000	NOSE BAY CART. SUPPORT BRACKET	NOSE BAY CART. SUPPORT BRACKET	1
5	2699065-0000	1/4" DIA. x 3/4" HEX BOLT	M6 x 19 HEX BOLT	1
6	2699841-0000	5/8" DIA. x 1 1/4" HEX BOLT	M16 x 32 HEX BOLT	6
7	2700501-0000	5/8" DIA. x 2" HEX BOLT	M16 x 51 HEX BOLT	6
8	2704151-0000	1/4" DIA. HEX NUT	M6 HEX NUT	6
9	2704191-0000	5/8" DIA. RAIL HEX NUT	M16 RAIL HEX NUT	6
10	2704851-0000	5/8" DIA. x 2" O.D. x 11" HEX NUT COUPLING	M16 x 51 O.D. x 279 HEX NUT COUPLING	6
11	2708281-0000	1/4" DIA. LOCK WASHER	M6 LOCK WASHER	6
12	2708291-0000	5/8" DIA. x 1 3/4" O.D. WASHER	M16 x 44 O.D. WASHER	6


* 1 INDICATES YELLOW
* 2 INDICATES BLACK



NOSE ASSEMBLY

ASSEMBLY NO. 3540042-0100 (YELLOW)
ASSEMBLY NO. 3540042-0200 (BLACK)

ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	2760081-0000	FENDER PANEL	FENDER PANEL	1
2	2699341-0000	5/8" DIA. x 2" RAIL BOLT	M16 x 51 RAIL BOLT	2
3	2704191-0000	5/8" DIA. HEX NUT	M16 HEX NUT	2
4	2708841-0000	CAST MUSHROOM WASHER	CAST MUSHROOM WASHER	1
5	2706604-0000	5/8" DIA. x 5" SCREW	M16 x 127 SCREW	1
6	2704141-0000	5/8" DIA. HEX NUT	M16 HEX NUT	1
7	2708291-0000	5/8" DIA. WASHER	M16 WASHER	1
8	2021611-0000	5/8" DIA. x 1 1/4" O.D. x 1 1/2" DIE SPRING	M16 x 32 O.D. x 38 DIE SPRING	1



FENDER PANEL ASSEMBLY
ASSEMBLY NO. 3540040-0000


NOTE:
① UNDERLYING PANEL IS EITHER ANOTHER FENDER PANEL OR, IN THE CASE OF THE LAST FENDER PANEL IT COULD BE A BACKUP SIDE PANEL, EXTENSION PANEL OR TRANSITION PANEL.
② TWO FENDER PANEL ASSEMBLIES ARE REQUIRED PER BAY.

ITEM	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION	REQ'D
1	SEE TABLE A	TENSION BACKUP	TENSION BACKUP	1
2	2760141-0000	SIDE PANEL	SIDE PANEL	2
9	3525300-0000	ANCHOR KIT	ANCHOR KIT	3
10	2704191-0000	5/8" DIA. HEX NUT	M16 HEX NUT	4
11	2699341-0000	5/8" DIA. x 2" RAIL BOLT	M16 x 51 RAIL BOLT	4
12	2760293-0000	CARTRIDGE SUPPORT BRACKET	CARTRIDGE SUPPORT BRACKET	1
13	2760294-0000	CARTRIDGE SUPPORT LOCKING BAR	CARTRIDGE SUPPORT LOCKING BAR	1

TABLE A:

ASSEMBLY NO.	STOCK NO.	DESCRIPTION	METRIC DESCRIPTION
3540031-0000	2760011-0000	24" WIDE TENSION BACKUP	610 WIDE TENSION BACKUP
3540032-0000	2760021-0000	30" WIDE TENSION BACKUP	760 WIDE TENSION BACKUP
3540033-0000	2760031-0000	36" WIDE TENSION BACKUP	915 WIDE TENSION BACKUP


NOTE:
③ WHEN TRANSITIONING THE QUADGUARD II SYSTEM TO EXISTING BARRIERS, SEE MANUFACTURER FOR PROPER USE OF SIDE PANEL (ITEM 2).




BACKUP ASSEMBLY

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING
REFERENCE DWG. NO. STANDARD SPEC. SECTION 606 606-31D
IMPACT ATTENUATOR - QUADGUARD II ASSEMBLY DETAILS
EFFECTIVE: SEPTEMBER 2014
MDT MONTANA DEPARTMENT OF TRANSPORTATION




- NOTES:
- FOR CABLE GUARDRAIL RUNS OF:
 - 1044 FT. [318.42 m] OR LESS: USE COMPENSATING CABLE END ASSEMBLY (RCE01*) ON ONE END AND TURNBUCKLE CABLE END ASSEMBLY * ON THE OTHER END OF EACH CABLE.
 - GREATER THAN 1044 FT. [318.42 m], UP TO 2052 FT. [625.86 m] MAXIMUM: USE COMPENSATING CABLE END ASSEMBLY (RCE01*) ON BOTH ENDS OF EACH CABLE.
 - LINE POST SPACING:
 - TANGENTS AND CURVES WITH RADIUS 700 FT. [220 m] AND GREATER: 16 FT. [4880 mm].
 - CURVES WITH RADIUS LESS THAN 700 FT. [220 m] DOWN TO 440 FT. [135 m]: 12 FT. [3660 mm].
 - NOTE: DO NOT INSTALL CABLE GUARDRAIL ON THE INSIDE SHOULDER OF ANY CURVE.
 - UNIFORMLY TENSION ALL CABLES TO COMPRESS SPRINGS BY 3 1/2" [90 mm].
 - DO NOT INSTALL CABLE GUARDRAIL FOR OBSTACLES WITHIN 12 FT. [3.7 m] OF THE INSTALLATION LINE.
 - DO NOT USE CABLE GUARDRAIL WITH FILL SLOPES STEEPER THAN 2:1, UNLESS THE DISTANCE BETWEEN THE BACK OF THE POSTS AND THE BREAK IN THE FILL SLOPE IS AT LEAST 8 FT. [2.5 m].
 - ATTACH REFLECTORS TO EVERY OTHER LINE POST (32 FT. [9.76 m] TYP.), BEGINNING AT POST P3. DO NOT ATTACH REFLECTORS TO POSTS P1 AND P2.
 - WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" [0.6 m] FROM THE TRAFFIC LANE.
 - GUIDANCE FOR TENSIONING CABLES USING THE TURNBUCKLES IS GIVEN IN CABLE TENSIONING TABLES. CABLE TENSIONING - NCHRP 230 TESTS HR 22-4 (1986) METRIC CABLE TENSIONING - NYDOT STD. M606-1R1 (1996)
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




TYPICAL LAYOUT FOR MULTIPLE RUNS OF CABLE GUARDRAIL
EACH RUN OF CABLE GUARDRAIL CONTAINS TWO TERMINAL SECTIONS WITH ANCHOR ASSEMBLIES.




CABLE SPLICE
SPLICE CABLE USING A COUPLING DEVICE AS SHOWN, OR AN ALTERNATE METHOD APPROVED BY THE PROJECT MANAGER




REFLECTOR ALT. "B"



TYPICAL INSTALLATION DETAIL
LINE POST & POST P3



TYPICAL INSTALLATION DETAIL
POST P2



REFLECTOR ALT. "A"



NOTE:
REFLECTORS ARE TO BE 14 GAUGE [1.9 mm THK.] ALUMINUM ALLOY

CABLE TENSIONING		METRIC CABLE TENSIONING	
TEMPERATURE (°F)	COMPR. # (INCHES)	TEMPERATURE (°C)	COMPR. # (mm)
120 TO 110	1.00"	50 TO 43	25
109 TO 100	1.25"	42 TO 38	32
99 TO 90	1.50"	37 TO 32	38
89 TO 80	1.75"	31 TO 27	45
79 TO 70	2.00"	26 TO 21	50
69 TO 60	2.25"	20 TO 16	57
59 TO 50	2.50"	15 TO 10	64
49 TO 40	2.75"	9 TO 5	70
39 TO 30	3.00"	4 TO -1	75
29 TO 20	3.25"	-2 TO -7	83
19 TO 10	3.50"	-8 TO -12	89
9 TO 0	3.75"	-13 TO -18	95
-1 TO -10	4.00"	-19 TO -23	100
-11 TO -20	4.25"	-24 TO -29	108



- SPRING COMPRESSION FROM UNLOADED POSITION

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING
REFERENCE DWG. NO. STANDARD SPEC. SECTION 606 606-40
LOW-TENSION CABLE GUARDRAIL
--REVISED--
JANUARY 2018
EFFECTIVE: SEPTEMBER 2014
MDT MONTANA DEPARTMENT OF TRANSPORTATION



ANCHOR UNIT & REBAR INSTALLATION DETAILS



ANCHOR POST DETAIL



CABLE END ASSEMBLY TO ANCHOR BRACKET DETAIL

NOTE:
INSTALL ONE WASHER UNDER HEAD, ONE BETWEEN PLATES & ONE UNDER NUT. AN ADDITIONAL WASHER MAY BE PLACED BETWEEN PLATES TO PLUMB THE ANCHOR POST.

NOTES:
① INSTALL THE CONCRETE ANCHOR INTO THE EXCAVATION, AS DETAILED, SO THAT THE BOTTOM OF THE ANCHOR HAS A FULL AND EVEN BEARING ON THE SURFACE UNDER IT. BACKFILL AROUND THE CONCRETE ANCHOR PER SECTION 203.


② THE CONCRETE ANCHOR CAN BE PLACED AS ONE OR TWO PIECES. THIS DETAIL PRIMARILY SHOWS A TWO PIECE INSTALLATION. FOR ONE PIECE INSTALLATIONS, USE ALL THE SAME DIMENSIONS, LESS THE TAPERED KEYWAY AND THE ADDITIONAL REBAR, AS SHOWN.

③ IF LIFTING DEVICES ARE EMBEDDED INTO THE CONCRETE ANCHORS, ENSURE THAT THEY HAVE A SAFE WORKING LOAD OF 4 TONS [3.6 METRIC TONS] FOR THE ONE PIECE ANCHOR AND 2 TONS [1.8 METRIC TONS] EACH FOR EACH OF THE HALVES OF THE TWO PIECE ANCHOR UNIT.


④ USE CLASS GENERAL CONCRETE TO CONSTRUCT ANCHOR.
SEE DTL. DWG. NO. 606-80 FOR SCHEDULE * OF GUARDRAIL HARDWARE.

NOTE:
DIMENSIONS FOR LEFT AND RIGHT HAND ANCHOR UNITS ARE THE SAME, WITH THE POSITION OF THE ANCHOR POST AND ANCHOR BRACKET BEING THE ONLY DIFFERENCE.


TAPERED KEYWAY DETAIL (TWO PIECE INSTALLATION)



PLAN (RIGHT HAND ANCHOR UNIT)



PLAN (LEFT HAND ANCHOR UNIT)



ELEVATION (LEFT HAND ANCHOR UNIT)

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-41
LOW-TENSION CABLE GUARDRAIL TERMINAL ANCHOR ASSEMBLY	










--REVISED--
JANUARY 2018

EFFECTIVE: SEPTEMBER 2014

MDT MONTANA DEPARTMENT OF TRANSPORTATION

RADIUS TABLE			
RADIUS	LENGTH OF BENT RAIL	L	W
8'	12.5'	25'	15'
16'	25.0'	30'	15'
24'	37.5'	40'	20'
32'	50.0'	50'	20'

METRIC RADIUS TABLE			
RADIUS	LENGTH OF BENT RAIL	L	W
2450 mm	3.81 m	7.6 m	4.6 m
4850 mm	7.62 m	9.1 m	4.6 m
7300 mm	11.43 m	12.2 m	6.1 m
9700 mm	15.24 m	15.2 m	6.1 m




- NOTES:
- DO NOT INSTALL ON SLOPES STEEPER THAN 2:1.
 - DO NOT OMIT OR SHORTEN ANCHOR SECTION.
 - SEE DTL. DWG. NO. 606-05A FOR GUARDRAIL WIDENING REQUIREMENTS.
- *SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING

REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-46
INTERSECTING ROADWAY TERMINAL SECTION (MGS)	
EFFECTIVE: SEPTEMBER 2014	

MDT MONTANA DEPARTMENT OF TRANSPORTATION




1/2" [12.7] DIA. HOLES FOR 3/8" DIA. x 7 1/2" [M10 x 191] HEX BOLT (FBX10a*) AND NUT (FNX10a*) WITH 2 FLAT WASHERS (FWC10a*) (1 WASHER ON POSTS WITH REFLECTIVE TAB)

EXPANSION JOINT


ELEVATION

SPLICE DETAIL



SECTION A-A


- NOTES:**
- USE BOX BEAM RAIL IN MINIMUM NOMINAL LENGTHS OF 18 FT. [5.49 m] UNLESS APPROVED BY THE PROJECT MANAGER.
 - INSTALL EXPANSION JOINTS ON ALL BOX BEAM GUARDRAIL INSTALLATIONS GREATER THAN 300 FT. [90 m] IN LENGTH AT INTERVALS NOT TO EXCEED 500 FT. [150 m].
 - ATTACH REFLECTIVE TABS TO EVERY FOURTH POST (24 FT. [7.32 m] TYP.). ANGLE TABS SLIGHTLY TOWARDS TRAFFIC. DO NOT USE REFLECTIVE TABS ON WY-BET TERMINALS. WY-BET TERMINALS RECEIVE REFLECTIVE CHANNELS.
 - DO NOT INSTALL BOX BEAM GUARDRAIL FOR OBSTACLES WITHIN 5.8' [1.8 m] OF THE FACE OF THE RAIL.
 - WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" [0.6 m] FROM THE TRAFFIC LANE.
 - PROVIDE SHOP BENT BOX BEAM RAIL FOR ROADWAY CURVATURE WITH RADIUS OF LESS THAN 715 FEET [218 m].
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.




REFLECTIVE TAB

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-50
BOX BEAM GUARDRAIL	
EFFECTIVE: SEPTEMBER 2014	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	



1/2" [12.7] DIA. HOLES FOR
 3/8" DIA. x 7 1/2" [M10 x 191]
 HEX BOLT (FBX10α*)
 AND NUT (FNX10α*) WITH
 2 FLAT WASHERS (FWC10α*)




NOTES:

① SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.


* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-52
BOX BEAM ONE-WAY DEPARTURE TERMINAL SECTION	
EFFECTIVE: SEPTEMBER 2014	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	




ELEVATION




BOX BEAM - BRIDGE APPROACH SECTION TYPE 1




BOX BEAM - BRIDGE APPROACH SECTION TYPE 2




TS6 x 2 [TS152 x 51] RAIL CONNECTION DETAIL




SECTION A-A
(TYP. AT POSTS P1 THRU P6)



SECTION B-B
(TYP. AT POSTS P7 & P8)



SECTION C-C
(POST P9)






GUARDRAIL WIDENING DETAIL
(TYP AT POST P1 THRU P9)

- NOTES:
- ① WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" [0.6 m] FROM THE TRAFFIC LANE.
 - ② SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.
 - * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.
 - ** SEE BRIDGE PLANS.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-53
BOX BEAM BRIDGE APPROACH SECTION - TYPES 1 & 2	
EFFECTIVE: SEPTEMBER 2014	




- NOTES:**
- ① INCLUDE COST OF ENTIRE ANCHOR RAIL SECTION, ALONG WITH ALL HARDWARE NECESSARY FOR ATTACHMENT TO CONCRETE BRIDGE RAIL, IN COST OF BRIDGE APPROACH SECTION.
 - ② THE LENGTHS OF CONCRETE ANCHOR BOLTS, TYPE OF RUB RAIL ANCHOR BRACKET AND THE NEED FOR THE 1/4" [6.4] SHIM PLATE IS DEPENDENT UPON THE SHAPE AND THE THICKNESS OF THE CONCRETE BRIDGE RAIL.
 - ③ WIDENING IS REQUIRED IF FINISHED SHOULDER IS LESS THAN 2'-0" [0.6 m] FROM THE TRAFFIC LANE.
 - ④ SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.
 - * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.
 - ** SEE BRIDGE PLANS.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-53A
BOX BEAM BRIDGE APPROACH SECTION-TYPE 3	
EFFECTIVE: SEPTEMBER 2014	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	

1" [25.4] DIA. HOLES IN BOX BEAM RAIL FOR 3/4" DIA. x 8" [M20 x 203] HIGH STRENGTH HEX BOLT (FBX20b*) AND NUT (FNX20b*) WITH TWO HARDENED FLAT WASHERS (FWC20b*)

CONNECTION SLEEVE ATTACHED TO BRIDGE RAIL (TYP.)** (1/4" [6.4] THICK STEEL FORM FIT TUBE TO RECEIVE TS6 x 6 x 3/16 [TS152 x 152 x 4.8] BOX BEAM RAIL)



PLAN



ELEVATION

NOTES:


① SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.


② USE ON EXIT END OF ONE-WAY TRAFFIC BRIDGES ONLY.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.


** SEE BRIDGE PLANS FOR MORE DETAILED INFORMATION ON BRIDGE RAIL AND CONNECTION DETAILS.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-54
BOX BEAM ONE-WAY BRIDGE DEPARTURE SECTION	
EFFECTIVE: SEPTEMBER 2014	
 MONTANA DEPARTMENT OF TRANSPORTATION	



PLAN



ELEVATION



GUARDRAIL WIDENING


NOTES:

- ① PLACE A SELF-ADHESIVE OBJECT MARKER ON THE FACE OF THE NOSE ASSEMBLY, HAVING ALTERNATING RETRO-REFLECTIVE BLACK AND YELLOW STRIPES SLOPED DOWNWARD AT AN ANGLE OF 45° TOWARDS THE SIDE ON WHICH TRAFFIC IS TO PASS.
- ② FLARE THE END SECTION AWAY FROM TRAFFIC AT A RATE OF 50:1 FOR 50 FEET [15.24 m] (ILLUSTRATED). FLARES OF 50:1 FOR 100 FEET [30.48 m] MAY ALSO BE USED. THE FLARE MAY BE OMITTED ON ROADS WITH SHOULDERS GREATER THAN 2 FEET [0.6 m] IN WIDTH.
- ③ OBTAIN PROJECT MANAGER'S APPROVAL OF MANUFACTURER INSTALLATION OPTIONS WHEN SITE CONDITIONS PREVENT THE USE OF THE OPTION SHOWN ON THIS DETAIL.
- ④ SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.
- ⑤ USE WOOD OR OTHER NCHRP 350/MASH APPROVED BLOCKS.


UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

--REVISED--
JULY 2016


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-55A
OPTIONAL BOX BEAM TERMINAL SECTION - WY-BET	
EFFECTIVE: SEPTEMBER 2014	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	



PLAN



ELEVATION




GUARDRAIL WIDENING

NOTES:


- ① PLACE A SELF-ADHESIVE OBJECT MARKER ON THE FACE OF THE NOSE ASSEMBLY, HAVING ALTERNATING RETRO-REFLECTIVE BLACK AND YELLOW STRIPES SLOPED DOWNWARD AT AN ANGLE OF 45° TOWARDS THE SIDE ON WHICH TRAFFIC IS TO PASS.
- ② FLARE THE END SECTION AWAY FROM TRAFFIC AT A RATE OF 50:1 FOR 50 FEET [15.24 m] (ILLUSTRATED). FLARES OF 50:1 FOR 100 FEET [30.48 m] MAY ALSO BE USED. THE FLARE MAY BE OMITTED ON ROADS WITH SHOULDERS GREATER THAN 2 FEET [0.6 m] IN WIDTH.
- ③ OBTAIN PROJECT MANAGER'S APPROVAL OF MANUFACTURER INSTALLATION OPTIONS WHEN SITE CONDITIONS PREVENT THE USE OF THE OPTION SHOWN ON THIS DETAIL.
- ④ SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-55B
OPTIONAL BOX BEAM TERMINAL SECTION - BEAT	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	




POST ATTACHMENT DETAIL
(TYP. AT POSTS P6, P7 AND P8)




POST ATTACHMENT DETAIL
(POST P5)



POST ATTACHMENT DETAIL
(TYP. AT POSTS P2, P3 AND P4)



END ANCHORAGE ASSEMBLY




SECTION A-A

BILL OF MATERIAL			
PC	QTY	DESCRIPTION	METRIC DESCRIPTION (mm)
706G	1	PIPE SLEEVE, 2" DIA. x 6"	PIPE SLEEVE, 50 DIA. x 150
721G	1	PLATE WASHER, 3" x 4" x 3/8"	PLATE WASHER, 75 x 100 x 10
722G	1	NOSE RESTRAINT CABLE BRACKET	NOSE RESTRAINT CABLE BRACKET
736G	2	STEEL TUBE, 6" x 8" x 5'-0"	STEEL TUBE, 152 x 203 x 1525
766G	2	SOIL PLATE, 18" x 24" x 1/4"	SOIL PLATE, 460 x 610 x 6
774A	1	SLOTTED BEARING PLATE	SLOTTED BEARING PLATE
3000G	1	CABLE ASSEMBLY	CABLE ASSEMBLY
3148G	2	1/4" DIA. x 2" LAG SCREW	6 DIA. x 51 LAG SCREW
3240G	3	5/16" DIA. ROUND WASHER	M8 ROUND WASHER
3245G	3	5/16" DIA. HEX NUT	M8 HEX NUT
3254G	3	3/8" DIA. x 1 1/2" LAG SCREW	10 DIA. x 38 LAG SCREW
3255G	5	3/8" DIA. ROUND WASHER	M10 ROUND WASHER
3264G	2	3/8" DIA. x 5" LAG SCREW	10 DIA. x 127 LAG SCREW
3350G	4	5/8" DIA. HEX NUT	M16 HEX NUT
3478G	4	5/8" DIA. x 7 1/2" HEX BOLT	M16 x 191 HEX BOLT
3700G	4	3/4" DIA. ROUND WASHER	M20 ROUND WASHER
3710G	2	3/4" DIA. HEX NUT	M20 HEX NUT
4044G	4	1 1/4" DIA. HEX NUT	32 DIA. HEX NUT
4066B	1	WOOD POST, 6" x 8" x 3'-6 1/2"	WOOD POST, 150 x 200 x 1080
4106B	3		RUBBER PAD, 38.1 x 88.9 x 101.6
4192G	4	1/4" CABLE CLAMP	6.4 CABLE CLAMP
4300G	18	1/2" DIA. ROUND WASHER	M12 ROUND WASHER
4303G	9	1/2" DIA. HEX NUT	M12 HEX NUT
4308G	9	1/2" DIA. x 1 1/2" HEX BOLT	M12 x 38 HEX BOLT
4719G	2	3/4" DIA. x 10" HEX BOLT	M20 x 254 HEX BOLT
4902G	2	1" DIA. ROUND WASHER	M24 ROUND WASHER
4903G	4	1" DIA. HEX NUT	M24 HEX NUT
5044G	1	AIRCRAFT CABLE, 1/4" DIA. x 6'-10"	AIRCRAFT CABLE, 6.4 DIA. x 2080
5092G	2	1/4" AIRCRAFT CABLE THIMBLE	6.4 AIRCRAFT CABLE THIMBLE
5188G	3	5/16" DIA. x 7 1/2" HEX BOLT	M8 x 191 HEX BOLT
5423G	1	1 1/4" DIA. x 36" ALL THREAD ROD	32 DIA. x 915 ALL THREAD ROD
9640G	3	POST ANGLE, 5" x 3 1/2" x 3/8" x 4 1/2"	POST ANGLE, 127 x 89 x 9.5 x 115
9641G	3	SHELF ANGLE, 4 1/2" x 1/8" x 1'-7 1/8"	SHELF ANGLE, 115 x 3.2 x 486
9642G	1	SHELF ANGLE, 4 1/2" x 1/8" x 11 1/8"	SHELF ANGLE, 115 x 3.2 x 283
9852A	1	STRUT AND YOKE ASSEMBLY	STRUT AND YOKE ASSEMBLY
14959A	1	5'-4" STEEL POST	1625 STEEL POST
32300A	1	WY-BET NOSE ASSEMBLY	WY-BET NOSE ASSEMBLY
32301A	1	HSS 6" x 6" x 3/16" INTERMEDIATE SPACER	HSS 152 x 152 x 250 INTERMEDIATE SPACER
32305A	1	BREAKAWAY TENSILE CONNECTOR	BREAKAWAY TENSILE CONNECTOR
32306A	1	HSS 6" x 6" x 3/16" TELESCOPING SECTION	HSS 152 x 152 x 4.8 TELESCOPING SECTION
32307A	1	OUTER TUBE	OUTER TUBE
32309B	1	6" O.D. x 1/4" x 12'-7 7/8" COMPOSITE TUBE	152.4 O.D. x 6.4 x 3860 COMPOSITE TUBE
32310B	1	6" O.D. x 1/8" x 5'-11 7/8" COMPOSITE TUBE	152.4 O.D. x 3.2 x 1830 COMPOSITE TUBE
32312G	3	REFLECTOR CHANNEL	REFLECTOR CHANNEL
32515A	6	5'-4" STEEL POST	1625 STEEL POST


UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-56A
WY-BET BOX BEAM TERMINAL SECTION DETAILS	


EFFECTIVE: SEPTEMBER 2014



BOX BEAM HEAD DETAIL



FIRST RAIL TIE DETAIL

















SECTION "A-A"

BILL OF MATERIAL			
ITEM	QTY	DESCRIPTION	METRIC DESCRIPTION
A	1	LOWER FIRST POST, W6x15, 8'-0" LG.	LOWER FIRST POST, W152 x 22.3 kg/m, 2440 LG.
B	1	UPPER FIRST POST, W6x9, 1'-9 1/2" LG.	UPPER FIRST POST, W152 x 13.4 kg/m, 546 LG.
C	1	SUPPORT BRACKET, 10 GAUGE BENT PLATE	SUPPORT BRACKET, 10 GA. (3.5 THK.) BENT PLATE
D	1	POST BREAKER	POST BREAKER
E	1	END TUBE RAIL, TS 6" x 6" x 1/8" x 12'-0"	END TUBE RAIL, TS 152 x 152 x 3.2 x 3660
F	1	CABLE ASSEMBLY	CABLE ASSEMBLY
G	1	BEARING PLATE	BEARING PLATE
H	1	BOX BEAM HEAD	BOX BEAM HEAD
I	1	RAIL SUPPORT BRACKET, L 5" x 3 1/2" x 3/8" x 4 1/2"	RAIL SUPPORT BRACKET, L 127 x 89 x 9.5 x 115
J	1	BOX BEAM POST W/ SOIL PLATE	BOX BEAM POST W/ SOIL PLATE
K	2	END TUBE SECTION TIE PLATE	END TUBE SECTION TIE PLATE
a	2	5/16" DIA. x 7 1/2" HEX BOLT (GRADE 5)	M8 x 191 HEX BOLT (GRADE 5)
b	1	1/4" DIA. x 3" HEX BOLT (GRADE 2)	M6 x 76 HEX BOLT (GRADE 2)
c	2	1/2" DIA. x 2" HEX BOLT (GRADE 2)	M12 x 51 HEX BOLT (GRADE 2)
d	8	5/8" DIA. x 2" HEX BOLT (GRADE 5)	M16 x 51 HEX BOLT (GRADE 5)
e	1	5/8" DIA. x 8" HEX BOLT (GRADE 5)	M16 x 203 HEX BOLT (GRADE 5)
f	1	5/8" DIA. x 3" HEX BOLT (GRADE 5)	M16 x 76 HEX BOLT (GRADE 5)
g	2	5/16" DIA. HEX NUT	M8 HEX NUT
h	1	1/4" DIA. HEX NUT	M6 HEX NUT
j	2	1/2" DIA. HEX NUT	M12 HEX NUT
k	14	5/8" DIA. HEX NUT	M16 HEX NUT
n	2	1" DIA. ANCHOR CABLE HEX NUT	M24 ANCHOR CABLE HEX NUT
p	4	5/16" DIA. WASHER	M8 WASHER
q	1	1/4" DIA. WASHER	M6 WASHER
r	3	1/2" DIA. WASHER	M12 WASHER
s	10	5/8" DIA. WASHER	M16 WASHER
u	2	1" DIA. ANCHOR CABLE WASHER	M24 ANCHOR CABLE WASHER

- NOTES:
- ① BEAT TERMINAL SECTION TO INCLUDE 36'-0" [10.98 m] OF BOX BEAM GUARDRAIL AS SHOWN ON DTL. DWG. NO. 606-55B.
 - ② PLACE POST BREAKER ON TRAFFIC SIDE OF FIRST POST.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-56B
BEAT BOX BEAM TERMINAL SECTION DETAILS	




- NOTES:
- SEE DTL. DWG. NO. 606-50 FOR STANDARD BOX BEAM GUARDRAIL AND ASSOCIATED DETAILS.
 - SEE DTL. DWG. NO. 606-05A AND 606-05B FOR STANDARD MGS GUARDRAIL AND ASSOCIATED DETAILS. SEE DTL. DWG. NO. 606-20 FOR HEIGHT AND SPLICE TRANSITION DETAILS.
 - MANUFACTURE ANCHOR ANGLES USING AASHTO M 270 [270] GRADE 36 [250] STEEL MEETING SECTION 711. WELD PER SECTION 711.
 - GALVANIZE ANCHOR ANGLES PER SECTION 711. NO PUNCHING, DRILLING, WELDING OR CUTTING IS PERMITTED ON COMPONENTS AFTER GALVANIZING.
 - USE CLASS GENERAL CONCRETE TO CONSTRUCT ANCHOR.
 - PAINT ANY AREAS WHERE GALVANIZING IS BROKEN OR METAL IS BARE ON W-BEAM OR BOX BEAM RAIL WITH ONE COAT OF ZINC RICH PAINT AND TWO COATS OF ALUMINUM PAINT PER SECTION 710.
 - LAP ALL W-BEAM SPLICES IN THE DIRECTION OF ADJACENT TRAFFIC.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 710, 711	DWG. NO. 606-58
BOX BEAM TO MGS TRANSITION SECTION	
--REVISED--	
JANUARY 2018	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	


UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

GUARDRAIL HARDWARE




HEX BOLTS

BOLT SIZE	DESIGNATION *	L	T (MIN.)
REGULAR HEX BOLTS			
3/8" DIA.	FBX10a	3 1/2"	1 1/2"
3/8" DIA.	FBX10a	7 1/2"	1 1/2"
1/2" DIA.	FBX12a	1 1/2"	FULL
1/2" DIA.	FBX12a	2 1/2"	1 3/4"
9/16" DIA.	FBX14a	8"	2"
5/8" DIA.	FBX16a	1 1/2"	FULL
3/4" DIA.	FBX20a	8"	2"
3/4" DIA.	FBX20a	9 1/2"	2"
HIGH STRENGTH HEX BOLTS			
3/4" DIA.	FBX20b	2"	1 1/2"
3/4" DIA.	FBX20b	4"	2"
3/4" DIA.	FBX20b	8"	2"
7/8" DIA.	FBX22b	1'-0"	AS REQUIRED
1" DIA.	FBX24b	AS REQUIRED	AS REQUIRED




HEX NUT

NUT SIZE	DESIGNATION *
REGULAR HEX NUTS	
5/16" DIA.	FNX08a
3/8" DIA.	FNX10a
1/2" DIA.	FNX12a
9/16" DIA.	FNX14a
5/8" DIA.	FNX16a
3/4" DIA.	FNX20a
1" DIA.	FNX24a
HIGH STRENGTH HEX NUTS	
3/4" DIA.	FNX20b
7/8" DIA.	FNX22b
1" DIA.	FNX24b




FLAT WASHERS


WASHER SIZE	DESIGNATION *
REGULAR FLAT WASHERS	
3/8" DIA.	FWC10a
1/2" DIA.	FWC12a
9/16" DIA.	FWC14a
5/8" DIA.	FWC16a
3/4" DIA.	FWC20a
1" DIA.	FWC24a
HARDENED FLAT WASHERS	
3/4" DIA.	FWC20b




5/8" DIA. GUARDRAIL BOLT & RECESSED NUT
FBB01-05*



DESIGNATION *	L	T (MIN.)
FBB01	1 1/4"	1 1/8"
FBB02	2"	1 3/4"
FBB03	10"	4"
FBB04	1'-6"	4"
FBB05	2'-1"	4"




3/4" DIA. SQUARE NUT
FNS20*



3/4" DIA. HOOKED ANCHOR ROD
FRH20a*


- NOTES:
- FURNISH BOLTS AND ANCHOR RODS MEETING THE REQUIREMENTS OF SUBSECTION 705.01.1.
 - FURNISH HIGH STRENGTH BOLTS MEETING THE REQUIREMENTS OF SUBSECTION 711.06.
 - GALVANIZE BOLTS, NUTS AND WASHERS IN ACCORDANCE WITH SUBSECTION 705.01.1.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

METRIC GUARDRAIL HARDWARE




HEX BOLTS

BOLT SIZE	DESIGNATION *	L	T (MIN.)
REGULAR HEX BOLTS			
M10	FBX10a	89	38
M10	FBX10a	191	38
M12	FBX12a	38	FULL
M12	FBX12a	63	44
M14	FBX14a	203	51
M16	FBX16a	38	FULL
M20	FBX20a	203	51
M20	FBX20a	241	51
HIGH STRENGTH HEX BOLTS			
M20	FBX20b	51	38
M20	FBX20b	102	51
M20	FBX20b	203	51
M22	FBX22b	305	AS REQUIRED
M24	FBX24b	AS REQUIRED	AS REQUIRED




HEX NUT

NUT SIZE	DESIGNATION *
REGULAR HEX NUTS	
M8	FNX08a
M10	FNX10a
M12	FNX12a
M14	FNX14a
M16	FNX16a
M20	FNX20a
M24	FNX24a
HIGH STRENGTH HEX NUTS	
M20	FNX20b
M22	FNX22b
M24	FNX24b




FLAT WASHERS


WASHER SIZE	DESIGNATION *
REGULAR FLAT WASHERS	
M10	FWC10a
M12	FWC12a
M14	FWC14a
M16	FWC16a
M20	FWC20a
M24	FWC24a
HARDENED FLAT WASHERS	
M20	FWC20b




M16 GUARDRAIL BOLT & RECESSED NUT
FBB01-05*



DESIGNATION *	L	T (MIN.)
FBB01	32	29
FBB02	51	44
FBB03	254	102
FBB04	457	102
FBB05	635	102



M20 SQUARE NUT
FNS20*




M20 HOOKED ANCHOR ROD
FRH20a*

- NOTES:
- FURNISH BOLTS AND ANCHOR RODS MEETING THE REQUIREMENTS OF SUBSECTION 705.01.1.
 - FURNISH HIGH STRENGTH BOLTS MEETING THE REQUIREMENTS OF SUBSECTION 711.06.
 - GALVANIZE BOLTS, NUTS AND WASHERS IN ACCORDANCE WITH SUBSECTION 705.01.1.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

ALL DIMENSIONS ARE MILLIMETERS (mm) UNLESS OTHERWISE NOTED.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 705, 711	DWG. NO. 606-82
GUARDRAIL HARDWARE	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	




NOTES:

- ① FOR RELATED FASTENER HARDWARE SEE FWC24a*, FNX24a* AND FPA01*.
- ② MACHINE THE SWAGED FITTING FROM HOT-ROLLED CARBON STEEL CONFORMING TO THE REQUIREMENTS OF ASTM A576 [A576 M], GRADE 1035, AND ANNEAL SUITABLE FOR COLD SWAGING. GALVANIZE THE SWAGED FITTING IN ACCORDANCE WITH SUBSECTION 711.08 BEFORE SWAGING. DRILL A LOCK PIN HOLE TO ACCOMMODATE A 1/4" [6.4 mm], PLATED SPRING STEEL PIN THROUGH THE HEAD OF THE SWAGED FITTING TO RETAIN THE STUD IN THE PROPER POSITION.
- ③ THE SWAGED FITTING, STUD AND NUT (FNX24a*) MUST DEVELOP THE BREAKING STRENGTH OF THE WIRE ROPE.
- ④ WIRE ROPE IS TO CONFORM TO THE REQUIREMENTS OF AASHTO M30 [M30M] AND BE 3/4" [19.1 mm] PREFORMED, 6 x 19, WIRE STRAND CORE OR INDEPENDENT WIRE CORE (IWRC), GALVANIZED, RIGHT REGULAR LAY, MANUFACTURED OF IMPROVED PLOW STEEL WITH A MINIMUM BREAKING STRENGTH OF 42,800 POUNDS [190.4 kN].
- ⑤ THE STUD IS TO CONFORM TO THE REQUIREMENTS OF ASTM F568 [F568M] CLASS 8.8 AND BE GALVANIZED IN ACCORDANCE WITH AASHTO M232 [M232M] (ASTM A153 [153M]). PRIOR TO GALVANIZING, MILL A 3/8" [9.5 mm] SLOT INTO THE STUD END FOR THE LOCKING PIN.

CABLE ASSEMBLY

FCA01*




ANCHOR BRACKET & END PLATE

FPA01*

POST SLEEVE

FMM02*



RECTANGULAR PLATE WASHER

FWR03*

NOTES:

- ⑥ ANCHOR BRACKETS, END PLATES AND RECTANGULAR PLATE WASHERS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M270 [M270M] (ASTM A709 [A709M]) GRADE 36 [250] STEEL PLATE. POST SLEEVES ARE TO CONFORM TO THE REQUIREMENTS OF ASTM A53 [A53M] GRADE B.
- ⑦ GALVANIZE FABRICATED PARTS IN ACCORDANCE WITH SUBSECTION 711.08. DO NOT PUNCH, DRILL, OR CUT AFTER GALVANIZING.


* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 711	DWG. NO. 606-84

W-BEAM METAL GUARDRAIL HARDWARE


EFFECTIVE: SEPTEMBER 2014



- NOTES:
- ① ALL HOLES ARE 3/8" [9.5] DIA. EXCEPT AS NOTED.
 - ② MANUFACTURE POSTS AND SOIL PLATES USING AASHTO M 270 [270M] (ASTM A 709 [A709M]) GRADE 36 [250] STEEL. ALL WELDING IS TO CONFORM TO THE APPLICABLE AWS CODE.
 - ③ HOOK BOLTS ARE TO CONFORM TO THE REQUIREMENTS OF ASTM 568 [568M] CLASS 4.6. NUTS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M 291 [291M] (ASTM A 563 [A563M]) CLASS 5.
 - ④ GALVANIZE FABRICATED PARTS IN ACCORDANCE WITH SUBSECTION 711.08. GALVANIZE HOOK BOLTS AND NUTS IN ACCORDANCE WITH AASHTO M 232 [232M] (ASTM A 153 [A153M]). DO NOT PUNCH, DRILL, OR CUT AFTER GALVANIZING.
 - ⑤ NUTS ARE OF THE HEAVY HEX TYPES. INSTALL BOLTS TO DEVELOP AN ULTIMATE PULL OPEN STRENGTH FROM 500 LB. TO 1000 LB. [2225 N TO 4450 N] APPLIED IN A DIRECTION NORMAL TO THE LONGITUDINAL AXIS OF THE POST.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.


CABLE GUARDRAIL POST AND SOIL PLATE

PSE01* AND PLS01*



5/16" DIA. [M8] HOOK BOLT

FBH01*




ALTERNATE 5/16" DIA. [M8] HOOK BOLT

FBH02*


UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-92
LOW-TENSION CABLE GUARDRAIL HARDWARE	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	


--REVISED--
JANUARY 2018



COMPENSATING CABLE END ASSEMBLY
RCE01*





TURNBUCKLE CABLE END ASSEMBLY




CABLE END ASSEMBLY
RCE03*


R. H. = RIGHT HAND
L. H. = LEFT HAND



CABLE WEDGE
FMM01*



CAST STEEL
OR MALL IRON



3/4" [19.1] DIA. - 3 x 7 WIRE ROPE

3/4" [19.1] DIA. CABLE
RCM01*

NOTES:




- ① WIRE ROPE AND CONNECTING HARDWARE ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M30 [M30M] TYPE 1 CLASS A, 3/4" [19.1] ROPE. CONNECTING HARDWARE MUST DEVELOP THE FULL STRENGTH OF A SINGLE CABLE (25,000 LB [111.2 kN]). CAST STEEL COMPONENTS ARE TO CONFORM TO THE REQUIREMENTS OF AASHTO M103 [M103M] (ASTM A27 [A27M]). MALLEABLE IRON CASTINGS ARE TO CONFORM TO THE REQUIREMENTS OF ASTM A47 [A47M].
- ② AT ALL LOCATIONS WHERE THE CABLE IS CONNECTED TO A CABLE SOCKET WITH A WEDGE TYPE CONNECTION, CRIMP ONE WIRE OF THE CABLE OVER THE BASE OF THE WEDGE TO HOLD IT FIRMLY IN PLACE.
- ③ COMPENSATING DEVICES ARE TO HAVE SPRING CONSTANTS OF 450 POUNDS PER INCH [78.8 N/mm], PLUS OR MINUS 50 POUNDS PER INCH [8.8 N/mm], AND PERMIT A TRAVEL OF 6 INCHES [150] PLUS OR MINUS 1 INCH [25].
- ④ DESIGN SOCKET BASKETS FOR USE WITH THE WEDGE DETAILED IN THIS DRAWING.
- ⑤ ALTERNATE HARDWARE DESIGNS WILL BE CONSIDERED FOR APPROVAL PROVIDED THEIR CONNECTION DETAILS, FOR THE PURPOSE OF MAINTENANCE SUBSTITUTIONS, ARE COMPATIBLE WITH THE DETAILS OF THIS DRAWING AND THEIR OPERATING CHARACTERISTICS ARE SIMILAR TO THOSE OF THE HARDWARE IN THIS DRAWING.

* SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.


UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-94
LOW-TENSION CABLE GUARDRAIL HARDWARE	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	


--REVISED--
JANUARY 2018




INTERNAL STIFFENER




EXTERNAL STIFFENER




CABLE ANCHOR BRACKET
FPA02*




SLIP IMPACT BASE
(KEEPER PLATE NOT SHOWN)



KEEPER PLATE



CABLE SUPPORT DETAIL



CABLE GUARDRAIL ANCHOR POST

PSE06*

NOTES:

- MANUFACTURE ANCHOR POSTS AND BRACKETS USING AASHTO M 270 [270M] (ASTM A709 [A709M]) GRADE 36 [250] STEEL. ALL WELDING IS TO CONFORM TO THE APPLICABLE AWS CODE.
 - GALVANIZE FABRICATED PARTS IN ACCORDANCE WITH SUBSECTION 711.08. DO NOT PUNCH, DRILL, OR CUT AFTER GALVANIZING.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.


DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-95

LOW-TENSION CABLE
GUARDRAIL HARDWARE


EFFECTIVE: SEPTEMBER 2014

MDT MONTANA DEPARTMENT OF TRANSPORTATION


--REVISED--
JANUARY 2018




TYPE A BOX BEAM POST AND SOIL PLATE
PSE08* AND PLS01*




TYPE B BOX BEAM POST AND SOIL PLATE
PLS01*




TYPE D BOX BEAM POST AND SOIL PLATE
PSE05* AND PLS01*



TRANSITION POST



BOX BEAM SUPPORT BRACKET
FPP01*



SUPPORT BRACKET W/BLOCKOUT













NOTES:

- ① MANUFACTURE POSTS USING STEEL CONFORMING TO AASHTO M 183 [183M] (ASTM A 36 [36M]). MANUFACTURE SOIL PLATES, SUPPORT BRACKETS AND MISC. COMPONENTS USING AASHTO M 270 [270M] (ASTM A 709 [709M]) GRADE 36 [250] STEEL. ALL WELDING IS TO CONFORM TO THE APPLICABLE AWS CODE.
 - ② MANUFACTURE BLOCKOUTS FROM EITHER ASTM A 500 GRADE B COLD-ROLLED TUBING, ASTM A 501 HOT-ROLLED TUBING OR AUTOMOTIVE ROLLOVER PROTECTIVE STEEL (ROPS). WHEN ASTM A 500 GRADE B STEEL IS USED, TEST THE MATERIAL PER ASTM E 436.
 - ③ GALVANIZE FABRICATED POSTS, BLOCKOUTS, BRACKETS AND MISC. COMPONENTS IN ACCORDANCE WITH SUBSECTION 711.08. DO NOT PUNCH, DRILL, OR CUT AFTER GALVANIZING.
 - ④ SEE DTL. DWG. NO. 606-53 (BOX BEAM BR. APP. SECT.) FOR REQUIRED LOCATION OF LOWER HOLES IN TYPE A AND B POSTS.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

- ** 1/8" [3 mm] x 2'-10" [51-254 mm]
1/8" [3 mm] x 2'-10" [51-254 mm]
- *** 1/8" [3 mm] x 3 1/2" [89 mm]

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.







DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606	DWG. NO. 606-97
BOX BEAM GUARDRAIL HARDWARE	
EFFECTIVE: SEPTEMBER 2014	
MDT MONTANA DEPARTMENT OF TRANSPORTATION	




- NOTES:
- MANUFACTURE BOX BEAM RAIL ELEMENTS FROM EITHER ASTM A 500 GRADE B COLD ROLLED TUBING, ASTM A 501 HOT-ROLLED TUBING OR AUTOMOTIVE ROLLOVER PROTECTIVE STEEL (ROPS). WHEN ASTM A 500 GRADE B STEEL IS USED, TEST THE MATERIAL PER ASTM E 436.
 - FABRICATE SPLICE PLATES AND CONNECTION SLEEVES FROM AASHTO M 270 [270M] (ASTM A 709 [709M]) GRADE 36 [250] STEEL PLATE. THE NUTS ARE TO BE PLAIN UN-COATED 3/4" DIA. [M20] HIGH STRENGTH HEX NUTS. WELD THE NUTS TO THE PLATES IN ACCORDANCE WITH THE APPLICABLE AWS CODE.
 - GALVANIZE FABRICATED RAIL, CONNECTION SLEEVES, AND SPLICE PLATES IN ACCORDANCE WITH SUBSECTION 711.08. DO NOT PUNCH, DRILL, OR CUT AFTER GALVANIZING.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 711	DWG. NO. 606-98
BOX BEAM GUARDRAIL HARDWARE	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	



NOTE:
ALL ANCHOR BRACKET COMPONENTS ARE FABRICATED FROM 1/4\"/>



- NOTES:
- MANUFACTURE BOX BEAM RAIL ELEMENTS FROM EITHER ASTM A 500 GRADE B COLD ROLLED TUBING, ASTM A 501 HOT-ROLLED TUBING OR AUTOMOTIVE ROLLOVER PROTECTIVE STEEL (ROPS). WHEN ASTM A 500 GRADE B STEEL IS USED, TEST THE MATERIAL PER ASTM E 436.
 - FABRICATE ANCHOR BRACKET AND RUB RAIL CONNECTION COMPONENTS FROM AASHTO M 270 [270M] (ASTM A 709 [709M]) GRADE 36 [250] STEEL PLATE.
 - GALVANIZE FABRICATED RAIL, ANCHOR BRACKET, AND RUB RAIL IN ACCORDANCE WITH SUBSECTION 711.08, DO NOT PUNCH, DRILL, WELD OR CUT AFTER GALVANIZING.
- * SEE DTL. DWG. NO. 606-80 FOR SCHEDULE OF GUARDRAIL HARDWARE.

UNITS SHOWN IN BRACKETS [] ARE METRIC AND ARE IN MILLIMETERS (mm) UNLESS OTHER UNITS ARE SHOWN.

DETAILED DRAWING	
REFERENCE STANDARD SPEC. SECTION 606, 711	DWG. NO. 606-99
BOX BEAM GUARDRAIL HARDWARE	
EFFECTIVE: SEPTEMBER 2014	
MONTANA DEPARTMENT OF TRANSPORTATION	