

SUMMARY

SURFACING										
STATION		linear feet				FOR	AGGREGATE	BITUMINOUS MATERIAL	REMARKS	
		GROSS	NET	+	-		sq. yards	tons		
FROM	TO									COVER TYPE II
NORTHBOUND										
21+73.00	148+49.76	12,676.76	12,676.76				53,496	95.1	TYPICAL SECTION NO. 1	
148+49.76	164+33.33	1,583.57	1,583.57				8,805	15.7	TYPICAL SECTION NO. 2	
164+33.33	172+67.25	833.92			833.92	BRIDGE			SEP BOULDER AVE - RR BRIDGE	
172+67.25	185+48.88	1,281.63	1,281.63				5,408	9.6	TYPICAL SECTION NO. 2	
185+48.88										
233+76.70	300+00.00				6,623.30	EQUATION				
	418+80.14	23,331.26	16,707.96				70,508	125.3	TYPICAL SECTION NO. 1	
418+80.14	419+29.98	49.84			49.84	BRIDGE			TENMILE CREEK BRIDGE	
419+29.98	463+67.71	4,437.73	4,437.73				18,727	33.3		
463+67.71	464+86.64	118.93			118.93	BRIDGE			SIERRA RD . BRIDGE	
464+86.64	635+10.37	17,023.73	17,023.73				71,840	127.7	TYPICAL SECTION NO. 1	
SUBTOTAL		61,337.37	53,711.38		7,625.99		228,784	406.7		
SOUTHBOUND										
21+73.00	149+25.00	12,752.00	12,752.00				53,813	95.6	TYPICAL SECTION NO. 1	
149+25.00	164+59.07	1,534.07	1,534.07				8,529	15.2	TYPICAL SECTION NO. 2	
164+59.07	172+93.22	834.15			834.15	BRIDGE			SEP BOULDER AVE - RR BRIDGE	
172+93.22	189+36.25	1,643.03	1,643.03				6,934	12.3	TYPICAL SECTION NO. 2	
189+36.25										
233+76.70	300+00.00				6,623.30	EQUATION				
	418+84.82	22,948.57	16,325.27				68,893	122.4	TYPICAL SECTION NO. 1	
418+84.82	419+35.90	51.08			51.08	BRIDGE			TENMILE CREEK BRIDGE	
419+35.90	463+72.95	4,437.05	4,437.05				18,724	33.3		
463+72.95	464+92.67	119.72			119.72	BRIDGE			SIERRA RD . BRIDGE	
464+92.67	635+18.53	17,025.86	17,025.86				71,849	127.7	TYPICAL SECTION NO. 1	
SUBTOTAL		61,345.53	53,717.28		7,625.25		228,742	406.5		
ADDITIONAL SURFACING										
							93,070	162.6		
TOTAL		~	~	~	~		550,596	975.8		

BRIDGE QUANTITIES					
MDT STRUCTURE ID	NBI STRUCTURE ID	FEATURE CROSSING	sq. yards		REMARKS
			DECK CRACK SEAL		
01178	000000000001178	BOULDER AVE - RR		5,383	
01179	000000000001179	BOULDER AVE - RR		5,343	
01181	100015196+01921	TEN MILE CREEK		218	
01182	100015196+01922	TEN MILE CREEK		218	
01183	100015197+00391	SIERRA ROAD		509	
01184	100015197+00392	SIERRA ROAD		509	
TOTAL		~	~	12,180	

PAVEMENT MARKINGS				
ITEM	UNIT	INTERIM APPLICATION #	FINAL APPLICATION	TOTAL
STRIPING - WHITE PAINT	gallon	625		625
STRIPING - YELLOW PAINT	gallon	458		458
WORDS & SYMBOLS - WHITE PAINT	gallon	166		166
STRIPING - WHITE EPOXY	gallon		830	830
STRIPING - YELLOW EPOXY	gallon		609	609
WORDS & SYMBOLS - WHITE EPOXY	gallon		220	220
CURB MARKING - YELLOW EPOXY	gallon		59	59
FINAL SWEEP AND BROOM	course mile			26.1

BASED ON 1 APPLICATION.

PROJECT NAME
HELENA - NORTH

COUNTY
LEWIS & CLARK

PROJECT ID
IM 15-3(116)190

UPN
10238000

CHECKED BY
T. JOHNSON

REVIEWED BY
R. SNYDER

DESIGNED BY
C. BASZLER

10238000RD\SUM001.DWG



ROAD PLANS