

INVITATION FOR BIDS
LETTING OF January 12, 2023

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on January 12, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson
Montana Transportation Commission

Malcolm "Mack" Long
Director of Transportation

NHFP 90-4(82)211 - Pavement Preservation project to mill and fill full width the I-90 eastbound and westbound lanes, interchange ramps, crossroads at the Gregson Interchange, Ramsay Interchange and Nissler Junction to a depth of 0.20ft. and replaced with 0.20 ft. plant mix surfacing.

This project will also include a seal and cover, bridge work, MASH compliant guardrail, rumble strips, new cattleguards, pavement markings and updated signing.

The project is located 4.2 miles west of Butte on I-90. The project begins west of the Fairmont Interchange (RP 211.5) and proceeds 8.5 miles east to the Nissler Interchange (219.2).

HSIP STWD (657) - Nissler Interchange - NB to WB loop ramp (121.6 to 121.95): replace existing speed advisory sign with solar powered radar speed feedback sign, install linear delineation on barrier in curve. WB to SB ramp: install chevrons and shoulder rumble strips through curve.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PAVE PRES, MILL FILL			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020140	REMOVE BITUMINOUS PAVEMENT	1,922.000	SQYD
203020278	EXCAVATION-DIGOUTS	4,261.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	3,040.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	23.000	MILE
301020340	CRUSHED AGGREGATE COURSE	780.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	61,685.000	TON
401020300	HYDRATED LIME	864.000	TON
402020095	ASPHALT CEMENT PG 70-28	3,889.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	28,378.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	804.300	TON
409000000	FINAL SWEEP AND BROOM	17.000	CRMI
409000020	COVER-TYPE 2	451,779.000	SQYD
411010000	COLD MILLING	482,374.000	SQYD
411011135	RUMBLE STRIPS	34.290	MILE
501010210	PORT CEM CONC PAVE 10 IN	3,760.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	5,536.000	SQYD
552011140	RESEAL EXISTING JOINTS	32.800	LNFT
557010606	REMOVE BRIDGE RAIL	1,087.900	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	58.500	SQYD
605000000	CONCRETE BARRIER RAIL TRANSITION	1.000	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	1,190.200	LNFT
605000045	REVISE CONC BARRIER RAIL END-BR	8.000	EACH
605000070	REMOVE CONCRETE BARRIER RAIL	169.000	EACH
605000080	TALL CONCRETE BARRIER RAIL	128.000	EACH
605000090	CONCRETE BARRIER RAIL	37.000	EACH
606010140	GUARDRAIL END SECTION WIDENING	30.000	EACH
606010330	MGS GUARDRAIL	22,253.100	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	30.000	EACH
606010339	MGS GRDL STIFF 1/4 POST SPACING	150.000	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	11.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	23.000	EACH
606010385	REMOVE GUARDRAIL	24,225.000	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	8.000	EACH
606011510	REMOVE IMPACT ATTENUATOR	1.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	8.000	EACH
606011520	IMPACT ATTENUATOR	1.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	850.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	5.000	EACH

607100380	FARM FENCE-PANEL/DOUBLE FW	11.000	EACH
609010112	CURB 4 IN-CONCRETE	180.000	LNFT
609010203	REMOVE CURB	30.000	LNFT
611010025	CATTLE GUARD 24 FT-HEAVY DUTY	8.000	EACH
611010200	REMOVE CATTLE GUARD	8.000	EACH
617000000	FOUNDATION-CONCRETE	0.500	CUYD
617673200	SIG STANDARD TYPE 1-200	1.000	EACH
617903461	VEHICLE SPEED FEEDBACK SIGN-SOLAR	1.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	450,000.000	UNIT
618100000	SINGLE USE SIGNS	200.000	SQFT
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	30.000	DAY
618190100	TEMPORARY BARRIER RAIL	2,970.000	LNFT
618190110	RESET TEMP BARRIER RAIL	2,620.000	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	4,198.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1,106.500	SQFT
619010230	REMOVE SIGN	99.000	EACH
619010240	REMOVE SIGN-GUIDE	40.000	EACH
619010300	POSTS-TUBULAR STEEL	1,147.000	LB
619010310	POSTS-STEEL U SIGN	722.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,173.000	LB
619010480	POLES-TREATED WOOD 4 IN	216.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	525.000	LNFT
619010720	FRANG SIGN POST BKWY-S3 X 5.7	2.000	EACH
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD	4.000	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD	4.000	EACH
619010800	PANEL DELINEATOR DESIGN A	13.000	EACH
619010830	PANEL DELINEATOR DESIGN H	13.000	EACH
619011010	DELINEATOR DES A	329.000	EACH
619011020	DELINEATOR DES B	37.000	EACH
619011040	DELINEATOR DES D	16.000	EACH
619011070	DELINEATOR DES G	84.000	EACH
619011085	DELINEATOR DES BJ	67.000	EACH
619011087	DELINEATOR DES GJ	37.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	8.000	GAL
620012955	TEMPORARY STRIPING	64,889.000	LNFT
620013000	STRIPING-WHITE PAINT	852.000	GAL
620013960	STRIPING-WHITE EPOXY	680.000	GAL
620014000	STRIPING-YELLOW PAINT	712.000	GAL
620014960	STRIPING-YELLOW EPOXY	475.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	3,760.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

Uniform No. 9465000, 9652000

102 MALTA - SOUTH NH

61-4 (26) 147

CONTRACT NO. 03B22

The Malta - South project is the major rehabilitation of 9.6 miles of US Highway 191 (N-61) in Phillips County. The project begins approximately 9.5 miles south of Malta at Reference Post 147.4, just south of S Alkali Creek Road and extends north for 9.6 miles to the intersection of US 191 and 9th Street at Reference Post 157.0. The roadway surface will be rehabilitated or reconstructed to current design standards, including centerline and shoulder rumble strips, new and lengthened drainage structures, signing, and pavement markings

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
----------	-------------	----------	-------

SECTION NO. 0001 - RD REHAB/RECONST, DRAINAGE, RUMBLE STRIPS, SIGNING,
PAVEMENT MARKINGS

103000000	TRAINING PROGRAM	1,000.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
107000060	NOXIOUS WEED CONTROL	10,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020358	ABANDON WELL	2.000	EACH
203020100	EXCAVATION-UNCLASSIFIED	572,900.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	10,516.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	61,785.000	CUYD
204010185	BLASTING CONSULTANT	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	2,000.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	240.000	MILE
301020254	BRIDGE END BACKFILL-TYPE 3	990.000	CUYD
301020450	SPECIAL BACKFILL	4,159.000	CUYD
301020465	LOW PERMEABILITY BACKFILL	235.000	CUYD
302000000	PAVEMENT PULVERIZATION	70,085.000	SQYD
409000000	FINAL SWEEP AND BROOM	9.800	CRMI
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	9.100	MILE
411011135	RUMBLE STRIPS	18.400	MILE
551020030	CONCRETE-CLASS GENERAL	66.800	CUYD
551020126	CONTROLLED LOW STRENGTH MATL	2.000	CUYD
552010160	BRIDGE DECK CRACK SEAL	1,132.000	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	10.000	SQYD
601010770	ADJUST WATER SERVICE LINE	1.000	EACH
601011920	INSULATION	144.000	SQFT
603000050	GRANULAR BEDDING MATERIAL	1,018.000	CUYD
603000060	FOUNDATION MATERIAL	1,033.000	CUYD
603010040	DRAINAGE PIPE 18 IN	1,938.000	LNFT
603010048	DRAINAGE PIPE 24 IN	1,234.000	LNFT
603010056	DRAINAGE PIPE 30 IN	794.000	LNFT
603010064	DRAINAGE PIPE 42 IN	228.000	LNFT
603010066	DRAINAGE PIPE 36 IN	802.000	LNFT
603010068	DRAINAGE PIPE 48 IN	388.000	LNFT
603010072	DRAINAGE PIPE 54 IN	126.000	LNFT
603010076	DRAINAGE PIPE 60 IN	148.000	LNFT
603010080	DRAINAGE PIPE 66 IN	164.000	LNFT
603010084	DRAINAGE PIPE 72 IN	302.000	LNFT
603010088	DRAINAGE PIPE 78 IN	384.000	LNFT
603010714	CSP 96 IN	60.000	LNFT
603010730	CSP 120 IN	90.000	LNFT
603012530	RCP 18 IN	216.000	LNFT
603012555	RCP 24 IN	198.000	LNFT
603012625	RCP 30 IN	278.000	LNFT
603012660	RCP 36 IN	138.000	LNFT
603013212	RCPA 30 IN EQ DIA	124.000	LNFT
603013216	RCPA 36 IN EQ DIA	174.000	LNFT
603013235	RCPA 48 IN EQ DIA	98.000	LNFT
603013263	RCPA 84 IN EQ DIA	32.000	LNFT
603014242	ADJUST VALVE BOX	2.000	EACH
603016050	STEEL CASING 30 IN	88.000	LNFT
603016150	RELAY PIPE CULVERT	30.000	LNFT
603017070	STORM DRAIN PIPE-30 IN	351.600	LNFT
603017085	STORM DRAIN PIPE-42 IN	191.200	LNFT
603587020	REMOVE PIPE CULVERT	3,719.900	LNFT
604000100	ADJUST MANHOLE	3.000	EACH
604000200	RESET FIRE HYDRANT	2.000	EACH
604010306	MANHOLE STRUCTURE BASE 72 IN	1.000	EACH
604010308	MANHOLE STRUCTURE BASE 84 IN (2100 MM)	1.000	EACH
604010358	ADDITIONAL BARREL 84 IN	2.000	LNFT
604010660	MANHOLE LID AND FRAME	2.000	EACH
605000045	REVISE CONC BARRIER RAIL END-BR	4.000	EACH
606010190	GUARDRAIL-STL/BR APPR-TY 2	4.000	EACH

606010330	MGS GUARDRAIL	637.400	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	7.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	4.000	EACH
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	40.000	LNFT
606010385	REMOVE GUARDRAIL	1,306.400	LNFT
606011518	TEMPORARY IMPACT ATTENUATOR	4.000	EACH
607000030	FENCE-CHAIN LINK 4 FT	126.000	LNFT
607100010	FENCE-WILDLIFE FRIENDLY FW/FM	21,131.000	LNFT
607100114	FARM FENCE-TYPE F2W-32 IN WW	1,303.000	LNFT
607100147	FARM FENCE-TYPE F2M-32 IN WW	1,436.000	LNFT
607100229	FARM FENCE-TYPE F4W	702.000	LNFT
607100252	FARM FENCE-TYPE F4M	51,785.000	LNFT
607100293	FARM FENCE-TYPE F6M	1,685.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	12.000	EACH
607100362	FARM FENCE-PANEL/SINGLE FM	104.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	8.000	EACH
607100385	FARM FENCE-PANEL/DOUBLE FM	231.000	EACH
607100430	FARM GATE-WIRE-TYPE G-2	724.000	LNFT
607100440	FARM GATE-METAL-TYPE G-3	16.000	LNFT
607100551	FENCE-TEMPORARY	3,202.000	LNFT
607100720	DEADMAN	55.000	EACH
607150131	RESET GATE	3.000	EACH
608000020	SIDEWALK DRAIN	2.000	EACH
608010050	SIDEWALK-CONCRETE 6 IN	494.500	SQYD
608010067	REMOVE SIDEWALK	150.700	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	20.200	SQYD
609010030	CURB-CONC MEDIAN TYPE A	97.000	LNFT
609010160	GUTTER-CONC VALLEY	22.500	SQYD
609010200	CURB AND GUTTER-CONC	710.600	LNFT
609010305	REMOVE CURB AND GUTTER	367.300	LNFT
610100101	SEEDING AREA NO 1	170.500	ACRE
610100103	SEEDING AREA NO 3	16.900	ACRE
610100326	FERTILIZING AREA NO 1	170.500	ACRE
610100470	SODDING	318.000	SQYD
610100490	TURF REINF MAT-NATURAL FIBER	34,110.000	SQYD
610100555	CONDITION SEEDBED SURFACE	170.500	ACRE
610100560	RIPRAP REVEGETATION	541.000	SQYD
611010016	CATTLE GUARD 16 FT-LIGHT DUTY	3.000	EACH
611010025	CATTLE GUARD 24 FT-HEAVY DUTY	1.000	EACH
611010200	REMOVE CATTLE GUARD	4.000	EACH
613100030	RIPRAP-CLASS 1 RANDOM	365.900	CUYD
613100040	RIPRAP-CLASS 2 RANDOM	159.400	CUYD
614010009	RETAINING WALL	13.000	SQYD
615010580	TRASH GUARD	3.000	EACH
617000000	FOUNDATION-CONCRETE	1.000	CUYD
617573070	RECTANGULAR RAPID FLASHING BEACON	2.000	EACH
617673200	SIG STANDARD TYPE 1-200	2.000	EACH
617903255	PUSH BUTTON-PEDESTRIAN-TACTILE	2.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	750,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618190100	TEMPORARY BARRIER RAIL	530.000	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	182.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	491.100	SQFT
619010180	HISTORICAL MARKER	1.000	EACH
619010230	REMOVE SIGN	76.000	EACH
619010240	REMOVE SIGN-GUIDE	6.000	EACH
619010310	POSTS-STEEL U SIGN	160.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	850.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	399.000	LB
619010480	POLES-TREATED WOOD 4 IN	816.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	64.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	6.000	EACH
619010724	FRANG SIGN POST BKWY-S5 X 10	2.000	EACH
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	2.000	EACH
619011010	DELINEATOR DES A	305.000	EACH
619011040	DELINEATOR DES D	20.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	2.000	GAL

620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	15.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	8.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	10.000	GAL
620012955	TEMPORARY STRIPING	57,546.000	LNFT
620013000	STRIPING-WHITE PAINT	712.000	GAL
620013960	STRIPING-WHITE EPOXY	475.000	GAL
620014000	STRIPING-YELLOW PAINT	319.000	GAL
620014960	STRIPING-YELLOW EPOXY	254.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	541.000	SQYD
622011084	GEOTEXTILE STABILIZATION	19,992.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	161,837.000	SQYD
623000155	MAILBOX	9.000	EACH
SECTION NO. 0002 - ALTERNATE AA1- CRUSHED AGG BASE SURFACING			
301020268	TRAFFIC GRAVEL	9,000.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	124,652.000	CUYD
301020625	AGGREGATE TREATMENT	234,458.000	SQYD
401020045	PLANT MIX SURF GR S-3/4 IN	56,433.000	TON
401020046	PLANT MIX BIT SURF GR S -MISC	2,948.000	TON
401020300	HYDRATED LIME	831.000	TON
402020092	ASPHALT CEMENT PG 64-28	2,886.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	23,854.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	443.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	367.800	TON
409000010	COVER-TYPE 1	207,030.000	SQYD
SECTION NO. 0003 - ALTERNATE AA2 - CEMENT TREATED BASE SURFACING			
301020268	TRAFFIC GRAVEL	9,000.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	69,370.000	CUYD
301020625	AGGREGATE TREATMENT	95,005.000	SQYD
304010002	BLOTTER MATERIAL	143,851.000	SQYD
304010005	BASE-CEMENT TREATED	33,130.000	CUYD
401020045	PLANT MIX SURF GR S-3/4 IN	57,166.000	TON
401020046	PLANT MIX BIT SURF GR S -MISC	2,948.000	TON
401020300	HYDRATED LIME	842.000	TON
402020092	ASPHALT CEMENT PG 64-28	2,922.300	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	24,365.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	443.000	GAL
402020360	EMULSIFIED ASPHALT CRS-2	124.400	TON
402020375	EMULSIFIED ASPHALT CHFRS-2P	367.800	TON
409000010	COVER-TYPE 1	207,030.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator. Uniform No. 7951000

103 POWER - N&S

IM 15-6(46)301

CONTRACT NO. 01123

The Power - N& S project is in Teton County on Interstate 15 (I-15) beginning at RP 301.4, the Cascade/Teton County line, and continuing north 7.8 miles to RP 309.2, approximately 3 miles south of the Dutton Interchange. Mainline will be milled and overlaid full width and new shoulder rumble strips will be cut. The Power Interchange ramps and crossroad will be crack sealed. Everything will be chip sealed.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, OVERLAY, SEAL & COVER			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS

109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	46.000	MILE
401020045	PLANT MIX SURF GR S-3/4 IN	45,242.000	TON
401020300	HYDRATED LIME	633.000	TON
402020095	ASPHALT CEMENT PG 70-28	2,266.400	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	18,002.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	636.600	TON
403010255	CRACK SEALING	466.000	LB
409000000	FINAL SWEEP AND BROOM	16.200	CRMI
409000020	COVER-TYPE 2	356,025.000	SQYD
411010000	COLD MILLING	364,880.000	SQYD
411011135	RUMBLE STRIPS	30.400	MILE
552010160	BRIDGE DECK CRACK SEAL	2,734.700	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	90.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	2.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	200,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	2.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	1.000	GAL
620012955	TEMPORARY STRIPING	20,592.000	LNFT
620013000	STRIPING-WHITE PAINT	766.000	GAL
620013960	STRIPING-WHITE EPOXY	516.000	GAL
620014000	STRIPING-YELLOW PAINT	598.000	GAL
620014960	STRIPING-YELLOW EPOXY	401.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator. Uniform No. 9948000

104 FALLON - SOUTHWEST

CRSII-IM 94-5(46)178

CONTRACT NO. 10R22

Mill & overlay, seal & cover, rumble strips, bridge deck repair, bridge rail, guardrail, signing, & pavement markings on the Fallon - Southwest project.

This project is located on I-94 east bound lanes the project begins at RP 178.0, 1.5± miles east of Terry Exit 176 and ends at to 184.5, 1.0± miles west of Fallon Exit 185.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL & OVERLAY, SEAL & COVER			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	171.600	LNFT
202020139	REMOVE ASPHALT FROM DECK	153.700	SQYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	30.000	MILE
401020045	PLANT MIX SURF GR S-3/4 IN	18,920.000	TON
401020300	HYDRATED LIME	260.000	TON
402020095	ASPHALT CEMENT PG 70-28	948.300	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	7,398.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	248.800	TON
409000000	FINAL SWEEP AND BROOM	6.500	CRMI
409000010	COVER-TYPE 1	139,213.000	SQYD

411010000	COLD MILLING	149,824.000	SQYD
411011135	RUMBLE STRIPS	12.800	MILE
552010041	REVISE JOINT	182.000	LNFT
552010140	TRANSVERSE DECK GROOVING	2,198.800	SQYD
561010525	EXPANSION JOINT-PRECOMPRESSED	305.900	LNFT
561020110	BRIDGE DECK MILLING	2,292.500	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	32.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.000	SQYD
563000010	CONCRETE-CLASS OVERLAY	2,292.500	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.000	UNIT
563000040	POLYMER OVERLAY	1,271.100	SQYD
563000045	POLYMER OVERLAY PRIMER	1,271.100	SQYD
563000100	PREPARE DECK	1,271.100	SQYD
605000040	REVISE CONCRETE BARRIER RAIL-BR	1,557.000	LNFT
606010037	MASH BOX BEAM TERMINAL - MBEAT	22.000	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	3,312.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	10.000	EACH
606010190	GUARDRAIL-STL/BR APPR-TY 2	3.000	EACH
606010325	GRD RL-BOX BEAM TO W-BEAM TRANS	6.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	6.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	8.000	EACH
606010385	REMOVE GUARDRAIL	3,951.000	LNFT
609010203	REMOVE CURB	1,600.000	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	2.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	6.500	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	1.000	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	1.000	EACH
618030280	CROSSOVER RECLAMATION	2.000	EACH
619010058	SIGNS-ALUM SHEET INCR IV	142.300	SQFT
619010086	SIGNS-ALUM REFL SHEET IV	113.300	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	94.000	SQFT
619010230	REMOVE SIGN	25.000	EACH
619010240	REMOVE SIGN-GUIDE	3.000	EACH
619010310	POSTS-STEEL U SIGN	504.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	74.000	LB
619011010	DELINEATOR DES A	168.000	EACH
619011020	DELINEATOR DES B	12.000	EACH
619011080	DELINEATOR DES H	168.000	EACH
620012955	TEMPORARY STRIPING	67,253.000	LNFT
620013000	STRIPING-WHITE PAINT	295.000	GAL
620013955	REMOVE PAVEMENT MARKINGS	34,848.000	LNFT
620013960	STRIPING-WHITE EPOXY	417.000	GAL
620014000	STRIPING-YELLOW PAINT	236.000	GAL
620014960	STRIPING-YELLOW EPOXY	314.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 9404000

105 I-94 FARM FENCE - RP 0-78 (D5) IM 94-1 (84) 0 CONTRACT NO. 07123

Installation of farm and wildlife fencing and cattle guards on the I-94 Farm Fence - RP 0-78 (D5) project in Yellowstone and Treasure Counties. The project begins near Billings on Interstate 94 at the Pinehill Interchange (RP 0.1) and extends northeast 78.3 miles to the Rosebud County line. Cattle Guard replacements are at the Pompey's Pillar Interchange (RP 23.3) and the Sarpy Creek Interchange (RP 72.0).

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - INTERSTATE FENCING, CATTLE GUARDS			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
606010370	RESET GUARDRAIL	250.000	LNFT
607100012	FENCE - WILDLIFE FRIENDLY FM	186,332.000	LNFT
607100152	FARM FENCE-TYPE F3M-32 IN WW	85,314.000	LNFT
607100281	FARM FENCE-TYPE F5M	103,891.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	188.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	75.000	EACH
607100390	FENCE-PANEL/SNGL-SPECIAL DESIGN	854.000	EACH
607100395	FENCE-PANEL/DBL-SPECIAL DESIGN	555.000	EACH
607100720	DEADMAN	340.000	EACH
610100559	REVEGETATION	1.000	LS
611010030	CATTLE GUARD 30 FT-HEAVY DUTY	7.000	EACH
611010040	CATTLE GUARD 40 FT-HEAVY DUTY	1.000	EACH
611010210	REMOVE AND SALVAGE CATTLE GUARD	8.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator. Uniform No. 8131003

106 **DEARBORN - N & S** **IM 15-4(172)229** **CONTRACT NO. 28R22**

Crack Seal and Seal & Cover on I-15 in Lewis and Clark and Cascade Counties, beginning at RP 236.8, approximately 0.5 miles north of NBI I00015236+02121 bridge over the Missouri River and extends north 11.1 miles to RP 247.9 approximately 0.5 miles north of the Hardy Creek Interchange. Interchange ramps and crossroads will be included.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & COVER			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
402020375	EMULSIFIED ASPHALT CHFRS-2P	910.800	TON
403010255	CRACK SEALING	69,093.000	LB
409000000	FINAL SWEEP AND BROOM	24.700	CRMI
409000020	COVER-TYPE 2	511,968.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	185,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
620010300	CURB MARKING-YELLOW PAINT	12.000	GAL
620010301	CURB MARKING-YELLOW EPOXY	16.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	115.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	153.000	GAL
620013000	STRIPING-WHITE PAINT	538.000	GAL
620013960	STRIPING-WHITE EPOXY	718.000	GAL
620014000	STRIPING-YELLOW PAINT	491.000	GAL

620014960 STRIPING-YELLOW EPOXY

655.000 GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.
This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9946000

INVITATION FOR BIDS
LETTING OF February 23, 2023

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on February 23, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson
Montana Transportation Commission

Malcolm "Mack" Long
Director of Transportation

NHPB STWD(730) - The I-15 Bridge Rehab - Clancy Area project is a bridge repair and resurfacing project on 9 bridges on I-15 located in the vicinity of Clancy and Montana City. The project involves spot repair, overlays, or replacement of bridge decks. In addition, the bridges will have railing systems updated to meet current bridge railing safety standards and other minor bridge repairs will be included. Crossover construction, guardrail, and surfacing.

NHPB 15-1(128)180 - The I-15 Bridge Rehab - Jefferson City project is a bridge repair and resurfacing project on 3 bridges on I-15 located in the vicinity of Jefferson City. The project involves spot repair and patching at various locations of two stream crossing bridges, and complete replacement of the deck at the Jefferson City Interchange. In addition, the bridges will have railing systems updated to meet current bridge railing safety standards and other minor bridge repairs will be included.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - BRIDGE REHABILITATION			
104030010	MISCELLANEOUS WORK	150,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	319.800	LNFT
202020115	REMOVE DECK	2,108.200	SQYD
203020100	EXCAVATION-UNCLASSIFIED	2,532.000	CUYD
203020185	TEMPORARY CHANNEL DIVERSION	1.000	LS
203020278	EXCAVATION-DIGOUTS	137.000	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
209010160	TEMPORARY SHORING	1.000	LS
301020252	BRIDGE END BACKFILL-TYPE 1	69.000	CUYD
301020340	CRUSHED AGGREGATE COURSE	2,148.000	CUYD
301020625	AGGREGATE TREATMENT	3,346.000	SQYD
401020021	COMMERCIAL MIX-PG 70-28	2,072.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	458.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	14.800	TON
409000000	FINAL SWEEP AND BROOM	0.600	CRMI
409000020	COVER-TYPE 2	8,104.000	SQYD
411010000	COLD MILLING	5,772.000	SQYD
411011135	RUMBLE STRIPS	0.600	MILE
501010401	CONCRETE-SHALLOW REPAIR	1.600	SQYD
551020036	CONCRETE-CLASS STRUCTURE LOW SLUMP	502.900	CUYD
552010043	FRP REINFORCEMENT	98.400	SQFT
552010059	EPOXY INJECTION	34.800	LNFT
552010060	REPAIR STRUCTURE	1.000	LS
552010140	TRANSVERSE DECK GROOVING	3,831.800	SQYD
552011010	EXPANSION JOINT STRIP SEAL	34.600	LNFT
552011030	EXPANSION JOINT-ASPHALT PLUG	175.600	LNFT
552011120	JOINT SEALS-POLYURETHANE	247.300	LNFT
555010200	REINFORCING STEEL-EPOXY COATED	127,396.000	LB
556000100	PAINT EXISTING STRUCTURAL STEEL	0.400	SQYD
561020110	BRIDGE DECK MILLING	2,113.800	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	9.400	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	8.000	SQYD
563000010	CONCRETE-CLASS OVERLAY	2,113.800	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.000	UNIT
563000040	POLYMER OVERLAY	665.000	SQYD
563000045	POLYMER OVERLAY PRIMER	665.000	SQYD
563000100	PREPARE DECK	665.000	SQYD
563000110	WATERPROOF MEMBRANE	34.800	SQYD
603013413	PIPE-CORR POLYETHYLENE DR 8 IN	133.000	LNFT
603015270	EMBANKMENT PROTECTOR 18 IN	528.000	LNFT
603587010	REMOVE EMBANKMENT PROTECTOR	280.000	LNFT

604000270	ADJUST MEDIAN INLET	1.000	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	1,493.400	LNFT
605000093	36 IN SS CONCRETE BARRIER RAIL-BR-CSC	1,117.500	LNFT
606010117	HIGH-TENSION CABLE RAIL	2,161.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	21.000	EACH
606010150	GUARDRAIL-STL/BR APPR-TY 1	6.000	EACH
606010330	MGS GUARDRAIL	2,927.300	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	21.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	38.000	EACH
606010386	REMOVE AND SALVAGE GUARDRAIL	2,880.600	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	8.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	8.000	EACH
607150125	RESET FENCE	40.000	LNFT
609010112	CURB 4 IN-CONCRETE	1,506.300	LNFT
609010200	CURB AND GUTTER-CONC	24.000	LNFT
609010203	REMOVE CURB	1,374.300	LNFT
610100559	REVEGETATION	1.000	LS
610100560	RIPRAP REVEGETATION	6.000	SQYD
613100040	RIPRAP-CLASS 2 RANDOM	39.000	CUYD
613300050	BANK PROTECTION-TYPE 3	21.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	40,000.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	5.000	EACH
618030280	CROSSOVER RECLAMATION	5.000	EACH
618100000	SINGLE USE SIGNS	377.000	SQFT
618190100	TEMPORARY BARRIER RAIL	1,400.000	LNFT
618190110	RESET TEMP BARRIER RAIL	1,400.000	LNFT
620013000	STRIPING-WHITE PAINT	32.000	GAL
620013955	REMOVE PAVEMENT MARKINGS	132,280.000	LNFT
620013960	STRIPING-WHITE EPOXY	353.000	GAL
620014000	STRIPING-YELLOW PAINT	30.000	GAL
620014960	STRIPING-YELLOW EPOXY	285.000	GAL
622011043	PERM EROSION CONTROL-HIGH SURV	74.000	SQYD
622011084	GEOTEXTILE STABILIZATION	192.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	4,220.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

Uniform No. 9783000, 9782000

202 CARTER - NORTH & SOUTH

CRSII-NH 10-3(22)20

CONTRACT NO. 06123

Milling, PMS overlay, seal and cover, signing and pavement markings on the Carter - North & South project located in Chouteau County. The project begins at RP 20.06 and proceeds northeast along US-87 (N-10) for approximately 9.7 miles traversing through the Town of Carter and ending at RP 29.73.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - COLD MILLING & PMS OVERLAY			
104030010	MISCELLANEOUS WORK	25,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	48.000	MILE
401020045	PLANT MIX SURF-3/4 IN	25,168.000	TON

401020300	HYDRATED LIME	352.000	TON
402020192	ASPHALT CEMENT PG 58V-34	1,433.100	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	20,524.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	338.600	TON
409000000	FINAL SWEEP AND BROOM	9.700	CRMI
409000010	COVER-TYPE 1	188,401.000	SQYD
411010000	COLD MILLING	203,271.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	9.700	MILE
411011135	RUMBLE STRIPS	19.400	MILE
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	182.500	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	264.900	SQFT
619010230	REMOVE SIGN	44.000	EACH
619010240	REMOVE SIGN-GUIDE	8.000	EACH
619010310	POSTS-STEEL U SIGN	180.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	167.000	LB
619010480	POLES-TREATED WOOD 4 IN	532.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	102.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	8.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	18.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	5.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	12.000	GAL
620012955	TEMPORARY STRIPING	102,708.000	LNFT
620013000	STRIPING-WHITE PAINT	724.000	GAL
620013960	STRIPING-WHITE EPOXY	482.000	GAL
620014000	STRIPING-YELLOW PAINT	372.000	GAL
620014960	STRIPING-YELLOW EPOXY	249.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9845000

203 CYR BR REHAB - 3M W ALBERTON STPB 31170(2) CONTRACT NO. 05123

The Cyr Bridge Rehab - 3M W Alberton project will rehabilitate the existing Cyr bridge, replace the bridge rail, install new approach guardrail, reconstruct the roadway (200 ft. from the west bridge end and 150 ft. from the east bridge end), and construct a historical turnout with a historical marker on the northeast corner of the bridge. The project is located on Fish Creek Rd/Old MT-10 (X-31170) in Mineral County, approximately 3 miles west of Alberton from RP 0.0 to 0.2.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - MAJOR BRIDGE REHAB			
103000000	TRAINING PROGRAM	500.000	HOURL
104030010	MISCELLANEOUS WORK	35,000.000	UNIT
104030035	MISCELLANEOUS ITEMS-REPAIR	1.000	LS
104030037	MISCELLANEOUS ITEMS-SQYD	78.000	SQYD
104030040	MISCELLANEOUS ITEMS-SQFT	25.000	SQFT
104030045	MISCELLANEOUS ITEMS-EACH	1.000	EACH
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020115	REMOVE DECK	28.800	SQYD
203020100	EXCAVATION-UNCLASSIFIED	748.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS

208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	272.000	CUYD
301020625	AGGREGATE TREATMENT	1,155.000	SQYD
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	345.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	174.000	GAL
551020035	CONCRETE-CLASS STRUCTURE	7.100	CUYD
552010060	REPAIR STRUCTURE	1.000	LS
552011010	EXPANSION JOINT STRIP SEAL	52.000	LNFT
555010100	REINFORCING STEEL	236.000	LB
555010200	REINFORCING STEEL-EPOXY COATED	5,402.000	LB
556000110	PAINT STRUCTURE	1.000	LS
556010010	STRUCTURAL STEEL - MISC	1.000	LS
557010110	HAND RAIL	1,062.800	LNFT
557010537	REVISE BRIDGE RAIL-W830	1,074.300	LNFT
557010606	REMOVE BRIDGE RAIL	1,060.700	LNFT
561010525	EXPANSION JOINT-PRECOMPRESSED	57.500	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	50.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	20.000	SQYD
563000040	POLYMER OVERLAY	1,381.300	SQYD
563000045	POLYMER OVERLAY PRIMER	1,381.300	SQYD
563000100	PREPARE DECK	1,381.300	SQYD
606010037	MASH BOX BEAM TERMINAL - MBEAT	4.000	EACH
606010040	GUARDRAIL-STEEL BOX BEAM	54.000	LNFT
606010266	GRD RL-BOX BEAM/BR APP-SEC TYPE 2	4.000	EACH
607100149	FARM FENCE-TYPE F3W-32 IN WW	117.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	1.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	1.000	EACH
610100559	REVEGETATION	1.000	LS
613100030	RIPRAP-CLASS 1 RANDOM	2.000	CUYD
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618100005	PORTABLE VARIABLE MESSAGE SIGN	4.000	EACH
619010090	SIGNS-ALUM REFL SHEET XI	16.400	SQFT
619010180	HISTORICAL MARKER	1.000	EACH
619010230	REMOVE SIGN	8.000	EACH
619010480	POLES-TREATED WOOD 4 IN	32.000	LNFT
620013000	STRIPING-WHITE PAINT	2.000	GAL
620013960	STRIPING-WHITE EPOXY	3.000	GAL
620014000	STRIPING-YELLOW PAINT	2.000	GAL
620014960	STRIPING-YELLOW EPOXY	3.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	1,139.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9524000

204 SOUTH OF LIVINGSTON - SOUTH NH 11-1(94)24 CONTRACT NO. 01223
Scrub seal and cover, new pavement markings, and upgrades to existing guardrail on the South of Livingston - South project located in Park County. The project begins at RP 23.7 and extends approximately 25.9 miles northeast along National Highway Route 11/US-89 to RP 49.7.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - SCRUB SEAL & COVER, GUARDRAIL			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS

208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
402020377	SCRUB SEAL EMULSION	901.700	TON
409000000	FINAL SWEEP AND BROOM	25.600	CRMI
409000010	COVER-TYPE 1	501,543.000	SQYD
606010140	GUARDRAIL END SECTION WIDENING	34.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	34.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	28,562.500	LNFT
606010346	MGS INTERSECTING RDWAY TERMINAL SECTION	375.000	LNFT
606010385	REMOVE GUARDRAIL	29,362.500	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
620011105	WORDS AND SYMBOLS-WHITE PAINT	11.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	24.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	13.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	32.000	GAL
620013000	STRIPING-WHITE PAINT	959.000	GAL
620013960	STRIPING-WHITE EPOXY	1,278.000	GAL
620014000	STRIPING-YELLOW PAINT	430.000	GAL
620014960	STRIPING-YELLOW EPOXY	573.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
 Uniform No. 9476000

205 BOULDER HILL - GUARDRAIL IM 15-3(97)167 CONTRACT NO. 03123

The Boulder Hill - Guardrail project is located in Jefferson County on Interstate 15. The project begins approximately 3 miles north of the Boulder Interchange (Exit 164) at RP 167.0 and extends north to RP 175.1, near the Jefferson City Interchange (Exit 176). The project will replace guardrail including terminal sections, bridge approach sections and one-way departure terminal sections. The project will also include roadway delineation.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS

SECTION NO. 0001 - GUARDRAIL SAFETY IMPROVEMENTS			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
552011120	JOINT SEALS-POLYURETHANE	122.000	LNFT
605000040	REVISE CONCRETE BARRIER RAIL-BR	803.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	19.000	EACH
606010330	MGS GUARDRAIL	46,700.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	19.000	EACH
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	19.000	EACH
606010385	REMOVE GUARDRAIL	48,337.500	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	4.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	4.000	EACH
609010112	CURB 4 IN-CONCRETE	24,153.000	LNFT
609010203	REMOVE CURB	24,153.000	LNFT
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618190100	TEMPORARY BARRIER RAIL	2,000.000	LNFT
618190110	RESET TEMP BARRIER RAIL	2,000.000	LNFT

619011010	DELINEATOR DES A	359.000	EACH
619011020	DELINEATOR DES B	12.000	EACH
619011080	DELINEATOR DES H	326.000	EACH
619011138	DELINEATION-LINEAR-WHITE-W-BEAM	4,610.000	EACH
619011139	DELINEATION-LINEAR-YELLOW-W-BEAM	3,082.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 9245000

INVITATION FOR BIDS
LETTING OF March 9, 2023

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on March 9, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson
Montana Transportation Commission

Malcolm "Mack" Long
Director of Transportation

NHFP 90-4(82)211 - Pavement Preservation project to mill and fill full width the I-90 eastbound and westbound lanes, interchange ramps, crossroads at the Gregson Interchange, Ramsay Interchange and Nissler Junction to a depth of 0.20ft. and replaced with 0.20 ft. plant mix surfacing.

This project will also include a seal and cover, bridge work, MASH compliant guardrail, rumble strips, new cattleguards, pavement markings and updated signing. The project is located 4.2 miles west of Butte on I-90. The project begins west of the Fairmont Interchange (RP 211.1) and proceeds 8.5 miles east to the Nissler Interchange (219.2).

HSIP STWD (657) - Nissler Interchange - NB to WB loop ramp (121.6 to 121.95): replace existing speed advisory sign with solar powered radar speed feedback sign, install linear delineation on barrier in curve. WB to SB ramp: install chevrons and shoulder rumble strips through curve.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - PAVE PRES, MILL FILL			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020278	EXCAVATION-DIGOUTS	2,407.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	1,602.000	CUYD
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	23.000	MILE
301020340	CRUSHED AGGREGATE COURSE	401.000	CUYD
301020416	SHOULDER GRAVEL	53.000	CUYD
401020045	PLANT MIX SURF-3/4 IN	61,528.000	TON
401020300	HYDRATED LIME	861.000	TON
402020095	ASPHALT CEMENT PG 70-28	3,889.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	25,174.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	802.600	TON
409000000	FINAL SWEEP AND BROOM	17.000	CRMI
409000020	COVER-TYPE 2	450,513.000	SQYD
411010000	COLD MILLING	482,374.000	SQYD
411011135	RUMBLE STRIPS	34.290	MILE
501010210	PORT CEM CONC PAVE 10 IN	1,266.000	SQYD
552010160	BRIDGE DECK CRACK SEAL	5,536.000	SQYD
552011140	RESEAL EXISTING JOINTS	32.800	LNFT
557010606	REMOVE BRIDGE RAIL	1,087.900	LNFT
562000020	CLASS A BRIDGE DECK REPAIR	58.500	SQYD
605000000	CONCRETE BARRIER RAIL TRANSITION	1.000	EACH
605000040	REVISE CONCRETE BARRIER RAIL-BR	1,199.200	LNFT
605000045	REVISE CONC BARRIER RAIL END-BR	8.000	EACH
605000070	REMOVE CONCRETE BARRIER RAIL	169.000	EACH
605000080	TALL CONCRETE BARRIER RAIL	128.000	EACH
605000090	CONCRETE BARRIER RAIL	37.000	EACH
606010140	GUARDRAIL END SECTION WIDENING	30.000	EACH
606010330	MGS GUARDRAIL	22,253.100	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	30.000	EACH
606010339	MGS GRDL STIFF 1/4 POST SPACING	150.000	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	11.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	23.000	EACH
606010385	REMOVE GUARDRAIL	24,225.000	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	9.000	EACH
606011510	REMOVE IMPACT ATTENUATOR	1.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	9.000	EACH
606011520	IMPACT ATTENUATOR	1.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	850.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	5.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	11.000	EACH
609010112	CURB 4 IN-CONCRETE	180.000	LNFT

609010203	REMOVE CURB	30.000	LNFT
610100559	REVEGETATION	1.000	LS
611010025	CATTLE GUARD 24 FT-HEAVY DUTY	8.000	EACH
611010200	REMOVE CATTLE GUARD	8.000	EACH
617000000	FOUNDATION-CONCRETE	0.500	CUYD
617673200	SIG STANDARD TYPE 1-200	1.000	EACH
617903461	VEHICLE SPEED FEEDBACK SIGN-SOLAR	1.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	700,000.000	UNIT
618100000	SINGLE USE SIGNS	200.000	SQFT
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	50.000	DAY
618190100	TEMPORARY BARRIER RAIL	3,540.000	LNFT
618190110	RESET TEMP BARRIER RAIL	3,120.000	LNFT
619010062	SIGNS-ALUM SHEET INCR XI	4,198.600	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	1,106.500	SQFT
619010230	REMOVE SIGN	99.000	EACH
619010240	REMOVE SIGN-GUIDE	40.000	EACH
619010300	POSTS-TUBULAR STEEL	1,147.000	LB
619010310	POSTS-STEEL U SIGN	722.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	1,173.000	LB
619010480	POLES-TREATED WOOD 4 IN	216.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	525.000	LNFT
619010720	FRANG SIGN POST BKWY-S3 X 5.7	2.000	EACH
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
619010742	FRANG SIGN POST BKWY-3.5 IN RD	4.000	EACH
619010744	FRANG SIGN POST BKWY-4 IN RD	4.000	EACH
619010800	PANEL DELINEATOR DESIGN A	13.000	EACH
619010830	PANEL DELINEATOR DESIGN H	13.000	EACH
619011010	DELINEATOR DES A	329.000	EACH
619011020	DELINEATOR DES B	37.000	EACH
619011040	DELINEATOR DES D	16.000	EACH
619011070	DELINEATOR DES G	84.000	EACH
619011085	DELINEATOR DES BJ	67.000	EACH
619011087	DELINEATOR DES GJ	37.000	EACH
619011205	DELINEATION-LINEAR-BARRIER-YELLOW	232.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	8.000	GAL
620012955	TEMPORARY STRIPING	64,889.000	LNFT
620013000	STRIPING-WHITE PAINT	852.000	GAL
620013960	STRIPING-WHITE EPOXY	680.000	GAL
620014000	STRIPING-YELLOW PAINT	712.000	GAL
620014960	STRIPING-YELLOW EPOXY	475.000	GAL
622011086	SEPARATION GEOTEXTILE - HIGH	1,746.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

Uniform No. 9465000, 9652000

102 SF 139 - RACETRACK BRIDGE REMOVAL IM-HSIP 90-4(70)196 CONTRACT NO. 03323

Remove Structures, grading, gravel, plant mix surfacing, seal & cover, pavement markings and updated signing on the SF 139 - Racetrack Bridge Removal located in Deer Lodge and Powell counties.

The project is located on Interstate Route 90 south of the Racetrack Interchange between Deer Lodge and Warm Springs. The project begins at RP-195.35 and extends east to RP-196.2. The project length is 0.6 miles. The project Reference Posts and stationing run from north to south.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - STRUCTURE REMOVAL			
103000000	TRAINING PROGRAM	500.000	HOURL
103500005	ESCROW OF BID DOCUMENTS	1.000	LS
104030010	MISCELLANEOUS WORK	75,000.000	UNIT
108000000	CRITICAL PATH SCHEDULE	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020041	REMOVE STRUCTURE	1.000	LS
203020100	EXCAVATION-UNCLASSIFIED	266,475.000	CUYD
203020310	SPECIAL BORROW-NEAT LINE	45,054.000	CUYD
203080100	TOPSOIL-SALVAGING AND PLACING	7,089.000	CUYD
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT, SETUP	56.000	MILE
301020340	CRUSHED AGGREGATE COURSE	15,757.000	CUYD
301020450	SPECIAL BACKFILL	20,667.000	CUYD
301020625	AGGREGATE TREATMENT	46,471.000	SQYD
401020045	PLANT MIX SURF-3/4 IN	16,363.000	TON
401020300	HYDRATED LIME	229.000	TON
402020095	ASPHALT CEMENT PG 70-28	850.700	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	6,976.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	68.200	TON
409000000	FINAL SWEEP AND BROOM	1.700	CRMI
409000020	COVER-TYPE 2	38,336.000	SQYD
411011135	RUMBLE STRIPS	3.200	MILE
551020030	CONCRETE-CLASS GENERAL	19.600	CUYD
603000050	GRANULAR BEDDING MATERIAL	549.000	CUYD
603000060	FOUNDATION MATERIAL	704.000	CUYD
603012725	RCP 54 IN	564.000	LNFT
603013361	REIN CONC BOX 8 X 6	318.000	LNFT
603587020	REMOVE PIPE CULVERT	1,387.400	LNFT
606010020	GUARDRAIL-TEMPORARY	1,450.000	LNFT
606010021	TEMP GD RAIL-STL/BR APPR-TY 1	2.000	EACH
606010024	TEMP OPTIONAL TERM SECT	2.000	EACH
606010117	HIGH-TENSION CABLE RAIL	400.000	LNFT
606010330	MGS GUARDRAIL	400.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	2.000	EACH
606010385	REMOVE GUARDRAIL	5,387.500	LNFT
606011300	RESET OPTIONAL TERMINAL SECT	1.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	9,468.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	21.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	24.000	EACH
607100720	DEADMAN	2.000	EACH
610010100	TOPSOIL	2,000.000	CUYD
610100101	SEEDING AREA NO 1	17.700	ACRE
610100103	SEEDING AREA NO 3	6.200	ACRE
610100326	FERTILIZING AREA NO 1	17.700	ACRE
610100555	CONDITION SEEDBED SURFACE	23.900	ACRE
618030015	TRAFFIC CONTROL-FIXED	50,000.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	4.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	4.000	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	1.000	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	1.000	EACH
618030280	CROSSOVER RECLAMATION	2.000	EACH
618100000	SINGLE USE SIGNS	200.000	SQFT
619010062	SIGNS-ALUM SHEET INCR XI	151.400	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	98.300	SQFT
619010200	RESET SIGNS	1.000	EACH
619010230	REMOVE SIGN	6.000	EACH
619010240	REMOVE SIGN-GUIDE	2.000	EACH
619010300	POSTS-TUBULAR STEEL	501.000	LB
619010310	POSTS-STEEL U SIGN	72.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	880.000	LB

619010490	POLES-TREATED WOOD 5 IN	16.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	2.000	EACH
619010730	FRANG SIGN POST BKWY-W8 X 18	2.000	EACH
619011010	DELINEATOR DES A	24.000	EACH
619011070	DELINEATOR DES G	8.000	EACH
619011080	DELINEATOR DES H	28.000	EACH
620012955	TEMPORARY STRIPING	26,944.000	LNFT
620013000	STRIPING-WHITE PAINT	76.000	GAL
620013960	STRIPING-WHITE EPOXY	51.000	GAL
620014000	STRIPING-YELLOW PAINT	62.000	GAL
620014960	STRIPING-YELLOW EPOXY	41.000	GAL
622011084	GEOTEXTILE STABILIZATION	2,503.000	SQYD
622011086	SEPARATION GEOTEXTILE - HIGH	72,839.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.

Uniform No. 8613000

**103 W BROADWAY - OLD HWY 10 (MSLA) NH 132-1(2)0 CONTRACT NO. 09R22
PATH PRESERVATION - MISSOULA TA 8199(165)**

NH 132-1(2)0 - This resurfacing project on W. Broadway (Old Hwy 10) in Missoula County begins on the south side of the S-474/US Hwy 10 W. intersection and extends southeasterly 5.6 miles to the west side of the Reserve Street interchange. The pavement will be milled and overlaid with new asphalt. Other work includes chip seal, fog seal, guardrail upgrades, inlet adjustment, new signing, and pavement markings.

TA 8199(165) - Crack filling, dig out (tree root removal), surfacing, and fog seal over the entire length of the path. The project is located on the Northside Greenway Path that runs parallel to the railroad tracks on the northside of Missoula.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - OVERLAY, CHIP SEAL, GUARDRAIL, SIGNING, PAVEMENT MARKINGS, & PATH PRESERVATION			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
203020278	EXCAVATION-DIGOUTS	459.000	CUYD
203020375	EMBANKMENT IN PLACE	305.000	CUYD
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010015	AQUATIC RESOURCE MONITOR	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	126.000	CUYD
301020416	SHOULDER GRAVEL	80.000	CUYD
401020048	PLANT MIX SURF-1/2 IN	25,962.000	TON
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	76.000	TON
401020300	HYDRATED LIME	363.000	TON
402020192	ASPHALT CEMENT PG 58V-34	1,505.500	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	10,272.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	16,095.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	377.700	TON
403010255	CRACK SEALING	314.000	LB
409000020	COVER-TYPE 2	211,518.000	SQYD
411010000	COLD MILLING	205,234.000	SQYD
603014242	ADJUST VALVE BOX	12.000	EACH
604000100	ADJUST MANHOLE	1.000	EACH

604000260	ADJUST DROP INLET	8.000	EACH
605000070	REMOVE CONCRETE BARRIER RAIL	18.000	EACH
605000090	CONCRETE BARRIER RAIL	12.000	EACH
606010150	GUARDRAIL-STL/BR APPR-TY 1	4.000	EACH
606010330	MGS GUARDRAIL	665.500	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	5.000	EACH
606010385	REMOVE GUARDRAIL	528.100	LNFT
609010010	CURB-CONCRETE	72.000	LNFT
610100559	REVEGETATION	1.000	LS
617533000	SIG-TRAF-BACKPLATE-REFLECTIVE	34.000	EACH
617763510	DETECTOR-RADAR/ADVANCE	3.000	EACH
618030005	TRAFFIC CONTROL DEVICES CB	275,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	684.900	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	911.700	SQFT
619010230	REMOVE SIGN	79.000	EACH
619010240	REMOVE SIGN-GUIDE	30.000	EACH
619010310	POSTS-STEEL U SIGN	134.000	LB
619010320	POSTS-STEEL STRUCTURAL SIGN	2,169.000	LB
619010480	POLES-TREATED WOOD 4 IN	482.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	462.000	LNFT
619010722	FRANG SIGN POST BKWY-S4 X 7.7	14.000	EACH
619010724	FRANG SIGN POST BKWY-S5 X 10	4.000	EACH
619011010	DELINEATOR DES A	124.000	EACH
619011040	DELINEATOR DES D	48.000	EACH
619011180	DELINEATOR-FLEX SURF MTD YLW	14.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	24.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	78.000	GAL
620011110	WORDS AND SYMBOLS-YELLOW PAINT	44.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	51.000	GAL
620011265	WORDS AND SYMBOLS-YELLOW EPOXY	30.000	GAL
620012955	TEMPORARY STRIPING	118,014.000	LNFT
620013000	STRIPING-WHITE PAINT	880.000	GAL
620013960	STRIPING-WHITE EPOXY	586.000	GAL
620014000	STRIPING-YELLOW PAINT	560.000	GAL
620014960	STRIPING-YELLOW EPOXY	373.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

[http://www.mdt.mt.gov/business/contracting/under the "Advertised Bid Packages" link.](http://www.mdt.mt.gov/business/contracting/under%20the%20Advertised%20Bid%20Packages%20link)

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9863000, 10086000

104 THOMPSON FALLS - URBAN STPP 6-1(172)50 CONTRACT NO. 01323

Milling and overlay and seal and cover on the Thompson Falls - Urban project located in Sanders County. Additional work will include approach chip sealing, new pavement markings, signing, delineation, luminaire replacements, and ADA upgrades. The project begins at RP 50.2 and extends southeasterly through the town of Thompson Falls for approximately 1.3 miles ending at RP 51.5.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL & FILL, SEAL & COVER, ADA UPGRADES			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS

208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	216.000	MILE
301020340	CRUSHED AGGREGATE COURSE	84.000	CUYD
301020625	AGGREGATE TREATMENT	1,530.000	SQYD
401020064	COMMERCIAL PLANT MIX-MISC	307.000	TON
401020162	COMMERCIAL MIX-1/2 IN-PG 58V-34	2,653.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	1,132.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	76.000	TON
409000000	FINAL SWEEP AND BROOM	1.300	CRMI
409000030	COVER-TYPE 3	34,387.000	SQYD
411010000	COLD MILLING	20,749.000	SQYD
603014242	ADJUST VALVE BOX	11.000	EACH
604000260	ADJUST DROP INLET	12.000	EACH
608010020	SIDEWALK-CONCRETE 4 IN	1,111.000	SQYD
608010050	SIDEWALK-CONCRETE 6 IN	433.900	SQYD
608010125	DETEC WARNING DEVICES-TYPE 1	52.600	SQYD
609010200	CURB AND GUTTER-CONC	2,169.200	LNFT
610100559	REVEGETATION	1.000	LS
616343914	CONDUIT-PLASTIC 1 1/2 IN	95.000	LNFT
616782999	ADJUST PULL BOX	3.000	EACH
616783006	PULL BOX-COMPOSITE TYPE 1	3.000	EACH
617000000	FOUNDATION-CONCRETE	1.160	CUYD
617123106	CONDUCTOR-COPPER AWG6-600V	172.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	273.000	LNFT
617183056	STANDARD-STL TYPE 10-A-500-6	2.000	EACH
617303800	RESET LUMINAIRE ASSEMBLY	1.000	LS
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
619010090	SIGNS-ALUM REFL SHEET XI	512.800	SQFT
619010230	REMOVE SIGN	58.000	EACH
619010340	POSTS-TUBULAR STEEL-SQ-PERF	2,455.300	LB
619010480	POLES-TREATED WOOD 4 IN	88.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	64.000	LNFT
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	4.000	EACH
619011010	DELINEATOR DES A	19.000	EACH
619011040	DELINEATOR DES D	10.000	EACH
620010301	CURB MARKING-YELLOW EPOXY	24.000	GAL
620010310	CURB MARKING-BLUE PAINT	2.000	GAL
620011105	WORDS AND SYMBOLS-WHITE PAINT	30.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	22.000	GAL
620012955	TEMPORARY STRIPING	11,272.000	LNFT
620013000	STRIPING-WHITE PAINT	78.000	GAL
620013960	STRIPING-WHITE EPOXY	69.000	GAL
620014000	STRIPING-YELLOW PAINT	44.000	GAL
620014960	STRIPING-YELLOW EPOXY	39.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9708000

105 SF 189 93 N RUMBLE STRIPS HSIP 5-1(83)7 CONTRACT NO. 02323

SF 189 93 N Rumble Strips project located in Missoula and Lake Counties. Install new rumble strips at various locations on US 93. Install shoulder rumble strips where not currently present from RP 6.5 to RP 45.7 and the curve near RP 70. This project is located entirely within the Flathead Indian Reservation.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RUMBLE STRIPS			
104030010	MISCELLANEOUS WORK	5,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
411011135	RUMBLE STRIPS	20.200	MILE
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
620013960	STRIPING-WHITE EPOXY	1,296.000	GAL
620014960	STRIPING-YELLOW EPOXY	146.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
Uniform No. 9892000

INVITATION FOR BIDS
LETTING OF April 6, 2023

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on April 6, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson
Montana Transportation Commission

Malcolm "Mack" Long
Director of Transportation

Roadside safety enhancements include installations of advance warning signs with flashing beacons, road closure gates, electronic variable message signs (VMS), guardrail to shield the VMS structures, and upgrading wind speed gauge on the I-90 Incident Management project located in Broadwater, Gallatin, Park, Sweet Grass, Stillwater, and Yellowstone Counties.

This project begins just east of the Three Forks Interchange at RP 273.7 and extends 182.3 miles east past the Johnson Lane Interchange near Billings at RP 456.0.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - GUARDRAIL, SIGNING, ELECTRICAL			
Billing District 53% Butte District 47%			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
107000020	CONTAMINATED SOIL	10,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
551020030	CONCRETE-CLASS GENERAL	3.000	CUYD
606010150	GUARDRAIL-STL/BR APPR-TY 1	1.000	EACH
606010330	MGS GUARDRAIL	3,700.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	16.000	EACH
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	16.000	EACH
606010385	REMOVE GUARDRAIL	50.000	LNFT
616323114	CONDUIT-STEEL 1 1/2 IN RIGID	210.000	LNFT
616343914	CONDUIT-PLASTIC 1 1/2 IN	1,450.000	LNFT
616343920	CONDUIT-PLASTIC 2 IN	20,312.000	LNFT
616783007	PULL BOX-COMPOSITE TYPE 2	110.000	EACH
617000000	FOUNDATION-CONCRETE	68.000	CUYD
617000050	POLES-TREATED WOOD CLASS 4	450.000	LNFT
617000060	GATE-ROAD CLOSURE	34.000	EACH
617033214	CABLE-COPPER 3AWG14-600V	628.000	LNFT
617033314	CABLE-COPPER 5AWG14-600V	21,760.000	LNFT
617123104	CONDUCTOR-COPPER AWG4-600V	10,219.000	LNFT
617123108	CONDUCTOR-COPPER AWG8-600V	9,860.000	LNFT
617123110	CONDUCTOR-COPPER AWG10-600V	48,258.000	LNFT
617303300	HIGH EFFICACY LUMINAIRE LED	34.000	EACH
617333000	SERV ASSEMBLY-MODIFY	1.000	EACH
617333100	SERV ASSEMBLY	24.000	EACH
617483110	SIG-TRAF 1 COL-1 WAY 12	37.000	EACH
617523010	SOL SIG-TRAF 1 COLOR-1 WAY 12	48.000	EACH
617673200	SIG STANDARD TYPE 1-200	24.000	EACH
617781000	REMOVE AND SALVAGE MISC ELECTRICAL	1.000	LS
617903459	BLANKOUT SIGN	1.000	EACH
617903475	VARIABLE MESSAGE SIGN COLOR-HALF	5.000	EACH
617903480	VARIABLE MESSAGE SIGN COLOR-FULL	12.000	EACH
618030015	TRAFFIC CONTROL-FIXED	500.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
619010062	SIGNS-ALUM SHEET INCR XI	1,199.700	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	321.400	SQFT
619010320	POSTS-STEEL STRUCTURAL SIGN	11,121.000	LB
619010510	OVERHEAD STRUCTURE/METAL	7.000	EACH
619010521	OVERHEAD STR/METAL-CANTILEVER	6.000	EACH
619010726	FRANG SIGN POST BKWY-W4 X 13	30.000	EACH
619010730	FRANG SIGN POST BKWY-W8 X 18	18.000	EACH

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Billings District Administrator.
Uniform No. 9856000

102 SWAN LAKE STPP 83-2(25)71 CONTRACT NO. 01423

The Swan Lake project is located in Lake County on Highway 83 (P-83) from RP 70.5 to 77.6. The project will include an asphalt mill and overlay, seal and cover, and fog seal. In addition, new pavement markings, signing, delineation, sinusoidal rumble strips, and guardrail upgrades will be included.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL, FILL, SEAL & COVER, GUARDRAIL UPGRADES			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010015	AQUATIC RESOURCE MONITOR	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	80.000	MILE
401020048	PLANT MIX SURF-1/2 IN	12,409.000	TON
401020300	HYDRATED LIME	174.000	TON
402020192	ASPHALT CEMENT PG 58V-34	706.100	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	4,896.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	8,093.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	193.200	TON
409000010	COVER-TYPE 1	107,838.000	SQYD
411010000	COLD MILLING	100,184.000	SQYD
411011145	SINUSOIDAL RUMBLE STRIPS	5.200	MILE
606010140	GUARDRAIL END SECTION WIDENING	21.000	EACH
606010335	MASH W-BEAM TERMINAL SECTION	21.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	15,450.000	LNFT
606010345	MGS ONE-WAY DEPARTURE TERMINAL SECTION	1.000	EACH
606010386	REMOVE AND SALVAGE GUARDRAIL	16,509.700	LNFT
610100559	REVEGETATION	1.000	LS
618030005	TRAFFIC CONTROL DEVICES CB	400,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
618100005	PORTABLE VARIABLE MESSAGE SIGN	2.000	EACH
618100007	TRAFFIC ACTUATED TEMPORARY SIGNALS	80.000	DAY
619010062	SIGNS-ALUM SHEET INCR XI	90.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	753.400	SQFT
619010200	RESET SIGNS	5.000	EACH
619010230	REMOVE SIGN	105.000	EACH
619010240	REMOVE SIGN-GUIDE	4.000	EACH
619010310	POSTS-STEEL U SIGN	379.000	LB
619010340	POSTS-TUBULAR STEEL-SQ-PERF	155.800	LB
619010480	POLES-TREATED WOOD 4 IN	1,066.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	146.000	LNFT
619010770	SQ TUBLR SLIP BASE BKWY-3 IN	2.000	EACH
619011010	DELINEATOR DES A	225.000	EACH
619011030	DELINEATOR DES C	68.000	EACH
619011040	DELINEATOR DES D	4.000	EACH
619011060	DELINEATOR DES F	215.000	EACH
620011105	WORDS AND SYMBOLS-WHITE PAINT	4.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	2.000	GAL
620012955	TEMPORARY STRIPING	67,955.000	LNFT
620013000	STRIPING-WHITE PAINT	528.000	GAL
620013960	STRIPING-WHITE EPOXY	352.000	GAL
620014000	STRIPING-YELLOW PAINT	494.000	GAL
620014960	STRIPING-YELLOW EPOXY	329.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
 Uniform No. 9869000

103 KALISPELL URBAN PAVE PRES UPP 6799(60) CONTRACT NO. 03423

This project is located in Flathead County and includes multiple locations within the Kalispell area. The work on E. Reserve Dr. (RP 0.009 to RP 0.998), W. Evergreen Dr. (RP 0.728 to RP 1.437), Airport Rd. (RP 11.368 to RP 12.115), Conrad Dr. (RP 1.496 to RP 1.554), and Woodland Park Dr. (RP 0.002 to RP 0.410) includes milling out the existing roadway surface, applying a plant mix overlay and finishing with a seal & cover. The work on 7th Ave. E. / Whitefish Stage (RP 0.010 to RP 2.559) and Woodland Ave. (RP 0.005 to RP 1.082) includes a seal and cover only. This project will receive new pavement markings and the manholes and valve boxes that are located within the milling area will receive concrete collars.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - COLD MILL, OVERLAY, SEAL & COVER			
104030010	MISCELLANEOUS WORK	10,000.000	UNIT
105080112	ADJUST MONUMENT BOX	2.000	EACH
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010015	AQUATIC RESOURCE MONITOR	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	2.000	MILE
401020048	PLANT MIX SURF-1/2 IN	5,299.000	TON
401020300	HYDRATED LIME	74.000	TON
620014960	STRIPING-YELLOW EPOXY	268.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.
 All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:
<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Missoula District Administrator.
 Uniform No. 10217000

104 SE OF MILES CITY - SOUTH NH 23-1(38)28 CONTRACT NO. 22R22

Resurfacing, rumble strips, striping, and signing on the SE of Miles City - South project.

This project is located on Montana Highway Route 59 (National Highway Route 23) in Custer County. NH-23 is classified as a principal arterial route. The project begins approximately 27.5 miles south of Miles City, at RP 27.8 and extends 5.4 miles south to RP 33.2.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - RESURFACING			
104030010	MISCELLANEOUS WORK	15,000.000	UNIT
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT

210020170	TEST TRAILER-TRANSPORT, SETUP	1.000	MILE
401020045	PLANT MIX SURF-3/4 IN	14,600.000	TON
401020046	PLANT MIX BIT SURF-MISC	210.000	TON
401020300	HYDRATED LIME	207.000	TON
402020095	ASPHALT CEMENT PG 70-28	712.200	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5,742.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	192.400	TON
409000000	FINAL SWEEP AND BROOM	5.400	CRMI
409000010	COVER-TYPE 1	108,541.000	SQYD
411010000	COLD MILLING	112,325.000	SQYD
411011135	RUMBLE STRIPS	10.800	MILE
618030005	TRAFFIC CONTROL DEVICES CB	250,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010062	SIGNS-ALUM SHEET INCR XI	73.000	SQFT
619010090	SIGNS-ALUM REFL SHEET XI	76.900	SQFT
619010230	REMOVE SIGN	14.000	EACH
619010240	REMOVE SIGN-GUIDE	4.000	EACH
619010310	POSTS-STEEL U SIGN	120.000	LB
619010480	POLES-TREATED WOOD 4 IN	122.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	140.000	LNFT
619011010	DELINEATOR DES A	150.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
620012955	TEMPORARY STRIPING	56,664.000	LNFT
620013000	STRIPING-WHITE PAINT	392.000	GAL
620013960	STRIPING-WHITE EPOXY	261.000	GAL
620014000	STRIPING-YELLOW PAINT	66.000	GAL
620014960	STRIPING-YELLOW EPOXY	44.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Glendive District Administrator.
Uniform No. 9582000

INVITATION FOR BIDS
LETTING OF April 27, 2023

Bids on the following projects will be received by the Montana Department of Transportation, Construction Contracting Bureau, until 9:00 a.m. on April 27, 2023. All bids will then be reviewed for correctness and then publicly read in the Department's assigned room.

Bid proposals, plans, cross-sections, dirt runs & erosion control plans, if available, and full instructions to bidders may be obtained from the Construction Contracting Bureau's website: <http://www.mdt.mt.gov/business/contracting> under the "Bid Package" link. Additional bid letting information is also available on this website.

Persons or firms desiring to qualify or bid on highway construction on the basis of a joint venture must declare their intention by executing a "Declaration of Joint Venture and Power of Attorney." Joint Venture affidavits must be included with the Bid Proposal.

Any contract entered into pursuant to this advertisement is subject to all appropriate state and federal civil rights laws. The prime and subcontractors are required to pay the wage rates set out in the bid proposal.

NOTICE TO BIDDERS

The following projects are funded in whole or in part by funds received from the Federal Highway Administration (FHWA), and their construction is wholly contingent on the state's continued receipt of those federal funds. If the federal funds are reduced or not received, the Department may choose to terminate any or all of the contracts for convenience under the provisions of Subsection 108.10. Any bidder on these projects, by submitting its bid or bids, understands and accepts the possibility of the contracts being terminated in the event federal funds are reduced or not available and by submitting any bid, each bidder waives any claims for costs or damages other than as specifically allowed by Subsection 108.10.2. In particular, bidders understand and accept that no payment will be allowed for any claimed anticipated profit for work not performed.

MDT will not discriminate on the basis of race, color, national origin or sex in the award, performance or administration of any MDT contract or in the administration of its DBE program (49 CFR Part 26). MDT attempts to provide reasonable accommodations for any known disability that may interfere with a person participating in any service, program or activity of the department. Alternate accessible formats of this document will be provided upon request. If reasonable accommodation is needed to participate in MDT bid lettings, call the Civil Rights Bureau at 406-444-6331 or TTY 406-444-7696 [TTY 1-800-335-7592 (toll free)].

Contractor Registration

Effective July 1, 1996, Montana law requires all contractors to register with the Montana Department of Labor. On Federal-aid projects, contractors must register prior to executing a contract. On State-funded projects, bidders must be registered prior to submitting a bid. For information regarding this requirement, contact the Department of Labor at 1-406-444-7734 or TTY 1-406-444-5549

MONTANA DEPARTMENT OF TRANSPORTATION

Loran Frazier, Chairperson
Montana Transportation Commission

Malcolm "Mack" Long
Director of Transportation

The Buxton - North & South project is located on Interstate Route 15 (I-15) in Silver Bow County. The project begins south of the Buxton Interchange at RP 115.9 and proceeds 5 miles north to end at the Rarus Bridge near the I-90 Nissler Interchange at RP 120.9. Works includes seal and cover, culvert replacement, guardrail upgrades, bridge work, cattle guards, and pavement markings.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & COVER, CULVERT REPLACEMENT			
104030010	MISCELLANEOUS WORK	50,000.000	UNIT
104030070	MISCELLANEOUS ITEMS-REMOVAL	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
202020058	REMOVE GUARD ANGLE	166.000	LNFT
202020097	REMOVE BRIDGE APPROACH SLAB	4.000	EACH
202020140	REMOVE BITUMINOUS PAVEMENT	272.000	SQYD
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010150	TEMPORARY EROSION CONTROL-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
301020340	CRUSHED AGGREGATE COURSE	483.000	CUYD
301020450	SPECIAL BACKFILL	6,932.000	CUYD
301020625	AGGREGATE TREATMENT	2,044.000	SQYD
401020021	COMMERCIAL MIX-PG 70-28	1,909.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	797.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	5,879.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	294.100	TON
409000000	FINAL SWEEP AND BROOM	9.800	CRMI
409000020	COVER-TYPE 2	163,610.000	SQYD
411010000	COLD MILLING	4,666.000	SQYD
411011135	RUMBLE STRIPS	0.600	MILE
551020030	CONCRETE-CLASS GENERAL	13.800	CUYD
552010140	TRANSVERSE DECK GROOVING	1,126.400	SQYD
552010160	BRIDGE DECK CRACK SEAL	4,968.100	SQYD
556000100	PAINT EXISTING STRUCTURAL STEEL	364.200	SQYD
561010525	EXPANSION JOINT-PRECOMPRESSED	214.000	LNFT
561020110	BRIDGE DECK MILLING	1,175.800	SQYD
562000020	CLASS A BRIDGE DECK REPAIR	16.000	SQYD
562000030	CLASS B BRIDGE DECK REPAIR	5.000	SQYD
563000010	CONCRETE-CLASS OVERLAY	1,175.800	SQYD
563000012	CONCRETE-CLASS OVERLAY-FIXED	500.000	UNIT
603000050	GRANULAR BEDDING MATERIAL	124.000	CUYD
603000060	FOUNDATION MATERIAL	247.000	CUYD
603013371	REIN CONC BOX 9 X 9	234.000	LNFT
603587020	REMOVE PIPE CULVERT	218.000	LNFT
605000040	REVISE CONCRETE BARRIER RAIL-BR	522.000	LNFT
605000045	REVISE CONC BARRIER RAIL END-BR	8.000	EACH
606010020	GUARDRAIL-TEMPORARY	1,600.000	LNFT
606010022	TEMP GD RAIL-STL/BR APPR-TY 3	5.000	EACH
606010024	TEMP OPTIONAL TERM SECT	16.000	EACH
606010117	HIGH-TENSION CABLE RAIL	1,879.000	LNFT
606010140	GUARDRAIL END SECTION WIDENING	46.000	EACH
606010330	MGS GUARDRAIL	6,100.000	LNFT
606010335	MASH W-BEAM TERMINAL SECTION	33.000	EACH
606010337	MGS GUARDRAIL/LONG POSTS	5,563.000	LNFT
606010342	MASH THRIE BEAM BR APPRCH SECTION	16.000	EACH
606010370	RESET GUARDRAIL	646.000	LNFT
606010385	REMOVE GUARDRAIL	11,130.300	LNFT
606011503	RESET TEMP IMPACT ATTENUATOR	2.000	EACH
606011518	TEMPORARY IMPACT ATTENUATOR	2.000	EACH
607100114	FARM FENCE-TYPE F2W-32 IN WW	1,075.000	LNFT
607100360	FARM FENCE-PANEL/SINGLE FW	20.000	EACH
607100380	FARM FENCE-PANEL/DOUBLE FW	6.000	EACH
609010112	CURB 4 IN-CONCRETE	670.000	LNFT
609010203	REMOVE CURB	520.000	LNFT

610100559	REVEGETATION	1.000	LS
611010022	CATTLE GUARD 20 FT-HEAVY DUTY	1.000	EACH
611010025	CATTLE GUARD 24 FT-HEAVY DUTY	6.000	EACH
611010200	REMOVE CATTLE GUARD	7.000	EACH
618030015	TRAFFIC CONTROL-FIXED	10,000.000	UNIT
618030080	TRAFFIC CONTROL-LS	1.000	LS
618030180	TRAFFIC CONTROL-CROSSOVER	12.000	EACH
618030190	TRAFFIC CONTROL-TWO WAY TRAF	6.000	MILE
618030250	CROSSOVER-CONST, MAINTAIN, REMOVE	2.000	EACH
618030260	CROSSOVER-CONST, MAINTAIN, CLOSE	4.000	EACH
618030280	CROSSOVER RECLAMATION	6.000	EACH
618100000	SINGLE USE SIGNS	240.000	SQFT
618190100	TEMPORARY BARRIER RAIL	300.000	LNFT
618190110	RESET TEMP BARRIER RAIL	300.000	LNFT
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	16.000	GAL
620012955	TEMPORARY STRIPING	15,442.000	LNFT
620013000	STRIPING-WHITE PAINT	282.000	GAL
620013960	STRIPING-WHITE EPOXY	376.000	GAL
620014000	STRIPING-YELLOW PAINT	208.000	GAL
620014960	STRIPING-YELLOW EPOXY	277.000	GAL
622011084	GEOTEXTILE STABILIZATION	310.000	SQYD

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Butte District Administrator.
Uniform No. 9462000

202 JCT S279 - WEST (MT 200) NH 24-3(69)76 CONTRACT NO. 05423
LINCOLN - E&W NH 24-3(73)65

NH 24-3(69)76 - The JCT S-279 West (MT-200) project is in Lewis and Clark County on MT 200 beginning at RP 75+0.751 (accumulated miles 76.486) and ending at RP 83+0.132 (accumulated miles 83.839), approximately 3.5 miles east of the unincorporated town of Lincoln. This project proposes a 0.15' centerline trench mill/fill, full width crack seal and seal and cover with new pavement markings, and bridge deck seal. Centerline rumble strips will be re-milled.

NH 24-3(73)65 - The Lincoln - E&W project is in Lewis and Clark County on MT 200 beginning at RP 65+0.450 (accumulated miles 66.193) and ending at RP 75+0.751 (accumulated miles 76.486). This project proposes a 0.15' centerline trench mill/fill, full width crack seal and seal and cover with new pavement markings. Centerline rumble strips will be re-milled.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - SEAL & COVER, PAVEMENT MARKINGS, RUMBLE STRIPS			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	176.000	MILE
401020155	COMMERCIAL MIX-3/8 IN-PG 58V-34	1,804.000	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	857.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	26,129.000	GAL

402020375	EMULSIFIED ASPHALT CHFRS-2P	629.800	TON
402020450	VOID REDUCING ASPHALT MEMBRANE	85,661.000	LNFT
403010255	CRACK SEALING	39,672.000	LB
409000010	COVER-TYPE 1	353,783.000	SQYD
411010000	COLD MILLING	19,028.000	SQYD
411011125	CENTERLINE RUMBLE STRIPS-TYPE 2	2.300	MILE
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	13.900	MILE
411011135	RUMBLE STRIPS	17.000	MILE
552010160	BRIDGE DECK CRACK SEAL	1,440.000	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	300,000.000	UNIT
620011105	WORDS AND SYMBOLS-WHITE PAINT	12.000	GAL
620011260	WORDS AND SYMBOLS-WHITE EPOXY	7.000	GAL
620012955	TEMPORARY STRIPING	108,640.000	LNFT
620013000	STRIPING-WHITE PAINT	1,282.000	GAL
620013960	STRIPING-WHITE EPOXY	857.000	GAL
620014000	STRIPING-YELLOW PAINT	522.000	GAL
620014960	STRIPING-YELLOW EPOXY	349.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.

Uniform No. 9953000, 9960000

203 DUPUYER - SOUTHEAST

STPP 3-3(37)71

CONTRACT NO. 06423

Full width mill/fill, seal, and cover, signing and pavement markings. Existing rumble strips will be re-milled.

The Dupuyer - Southeast project is in Pondera County on Hwy 89 beginning at RP 70.45 and ending at RP 74.92.

INVOLVING

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 - MILL/FILL, SEAL & COVER, SIGNING, AND PAVEMENT MARKINGS			
104030010	MISCELLANEOUS WORK	20,000.000	UNIT
105070000	CONTRACTOR SURVEY AND LAYOUT	1.000	LS
108000010	STRUCTURE ANALYSIS	1.000	LS
109200005	MOBILIZATION	1.000	LS
208010000	BMP ADMINISTRATION-LS	1.000	LS
208010005	PAR BMP ADMINISTRATION-LS	1.000	LS
208010200	TEMPORARY EROSION CONTROL-FIXED	500.000	UNIT
210020170	TEST TRAILER-TRANSPORT,SETUP	85.000	MILE
401020045	PLANT MIX SURF-3/4 IN	9,837.000	TON
401020300	HYDRATED LIME	138.000	TON
402020192	ASPHALT CEMENT PG 58V-34	510.900	TON
402020315	EMULSIFIED ASPHALT-TACK COAT	5,118.000	GAL
402020320	EMULSIFIED ASPHALT-FOG SEAL	7,428.000	GAL
402020375	EMULSIFIED ASPHALT CHFRS-2P	174.200	TON
409000010	COVER-TYPE 1	97,993.000	SQYD
411010000	COLD MILLING	103,292.000	SQYD
411011130	CENTERLINE RUMBLE STRIPS-TYPE 3	4.400	MILE
411011135	RUMBLE STRIPS	8.800	MILE
552010160	BRIDGE DECK CRACK SEAL	744.200	SQYD
618030005	TRAFFIC CONTROL DEVICES CB	160,000.000	UNIT
618100001	MOTORCYCLE ADVISORY SIGN	2.000	EACH
619010088	SIGNS-ALUM REFL SHEET IX	104.200	SQFT
619010230	REMOVE SIGN	13.000	EACH
619010310	POSTS-STEEL U SIGN	83.000	LB

619010480	POLES-TREATED WOOD 4 IN	48.000	LNFT
619010490	POLES-TREATED WOOD 5 IN	66.000	LNFT
619011010	DELINEATOR DES A	159.000	EACH
619011040	DELINEATOR DES D	2.000	EACH
619011060	DELINEATOR DES F	13.000	EACH
620012955	TEMPORARY STRIPING	46,584.000	LNFT
620013000	STRIPING-WHITE PAINT	330.000	GAL
620013960	STRIPING-WHITE EPOXY	220.000	GAL
620014000	STRIPING-YELLOW PAINT	316.000	GAL
620014960	STRIPING-YELLOW EPOXY	165.000	GAL

Contract to be completed as outlined in the Contract Time special provision found in the proposal.

The Disadvantaged Business Enterprises' contract goals are 0.00%.

All bid documents are available for downloading and/or printing free of charge on the Contractor's System web site at the following address:

<http://www.mdt.mt.gov/business/contracting> under the "Advertised Bid Packages" link.

This project is under the jurisdiction of the Great Falls District Administrator.
Uniform No. 9957000